

Bid Schedule: 2021 Purdy Mesa Flowline Replacement

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	104/108	Water Main (20") (C900 PVC, DR-18)	32,600.	LF	\$ _____	\$ _____
2	104/108	Water Main (6") (C900 PVC, DR-25)	100.	LF	\$ _____	\$ _____
3	104/108	Combination Air Valve and Vault (6")	12.	EA	\$ _____	\$ _____
4	104/108	Gate Valve (6") (MJ)	1.	EA	\$ _____	\$ _____
5	104/108	Check Valve (6") (Tideflex or approved equal)	1.	EA	\$ _____	\$ _____
6	104/108	Tee (20"x6") (Epoxy Coated, MJ x MJ fitting)	1.	EA	\$ _____	\$ _____
7	104/108	Elbow (20" x 11.25 deg) (MJ, Epoxy Coated)	47.	EA	\$ _____	\$ _____
8	104/108	Elbow (20" x 22.5 deg) (MJ, Epoxy Coated)	14.	EA	\$ _____	\$ _____
9	104/108	Elbow (20" x 45 deg) (MJ, Epoxy Coated)	24.	EA	\$ _____	\$ _____
10	104/108	Elbow (6" x 45 deg) (MJ, Epoxy Coated)	2.	EA	\$ _____	\$ _____
11	104/108	Connection to Existing Pressure Control Tower		Lump Sum	---	\$ _____
12	202	Abandon Pipe (Includes cutting and plugging with concrete each end)	8.	EA	\$ _____	\$ _____
13	208	Erosion Control		Lump Sum	---	\$ _____
14	209	Dust Control		Lump Sum	---	\$ _____
15	210	Reset Fence	680.	LF	\$ _____	\$ _____
16	210	Reset Gate	3.	EA	\$ _____	\$ _____
17	212.02	Seeding (Native Dryland)	38.01	AC	\$ _____	\$ _____
18	620	Asphalt Removal (includes Saw Cutting and Milling)	170.	SY	\$ _____	\$ _____
19	401	Hot Bituminous Patching (Grading SX, PG 64-22) (GYR-75) (One 3" Lift Bottom Mat, Includes Emulsified Asphalt Tack Coat and Flow Fill per Mesa County ROW Permit)	170.	SY	\$ _____	\$ _____

Bid Schedule: 2021 Purdy Mesa Flowline Replacement

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
20	401	Hot Bituminous Patching (Grading SX, PG 64-22) (GYR=75) (One 2" Top Mat with T-Top, Includes Emulsified Asphalt Tack Coat)	221.	SY	\$ _____	\$ _____
21	607	Protective fencing at Hookless Cactus locations as called out.	1,000.	LF	\$ _____	\$ _____
22	620	Sanitary Facility		Lump Sum	---	\$ _____
23	625	Construction Surveying		Lump Sum	---	\$ _____
24	626	Mobilization/Demobilization		Lump Sum	---	\$ _____
25	630	Traffic Control		Lump Sum	---	\$ _____
Bid Amount:					\$	_____

Bid Amount:

dollars

Signature

Name

Title

Date

Company