

Bid Schedule: Hogchute (AKA Carson) Reservoir Dam Rehabilitation

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	626 01 22 50	Mobilization		Lump Sum	---	\$ _____
2	208 01 57 19	Erosion Control		Lump Sum	---	\$ _____
3	01 57 60	Construction Dewatering		Lump Sum	---	\$ _____
4	02 41 00	Demolition (intake, outfall, piping, controls, spillway grouted riprap, etc.)		Lump Sum	---	\$ _____
5	03 30 00 31 20 00 31 37 00	Concrete Overflow Spillway (excavation, form, concrete placement, backfill, and riprap, etc.)		Lump Sum	---	\$ _____
6	31 24 00 31 20 00	Embankment Excavation		Lump Sum	---	\$ _____
7	33 41 66	Type I Filter Material	1,000.	CY	\$ _____	\$ _____
8	33 41 66	Type II Filter Material	120.	CY	\$ _____	\$ _____
9	33 41 66 33 42 15	HDPE Perforated Drain Pipe	270.	LF	\$ _____	\$ _____
10	33 41 66 33 42 15	HDPE Solid Drain Pipe		LF		
11	31 24 00 31 20 00 31 23 33	Embankment Backfill (embankment fill, rock shell, restore stockpile areas, etc.)		Lump Sum	---	\$ _____
12	35 22 28 33 42 15	Stainless Steel Slide Gate		Lump Sum	---	\$ _____
13	03 30 00 33 42 15 05 50 00	Concrete Buttress Intake Structure (Concrete buttress, conduit encasement, air vent and hydraulics conduit, steel elbow, etc.)		Lump Sum	---	\$ _____
14	26 05 43 33 42 15	Locking Valve Box		Lump Sum	---	\$ _____
15	05 50 00	Trash Rack		Lump Sum	---	\$ _____
16	32 92 26	Wetland Soil Stockpiling	4,100.	SY	\$ _____	\$ _____
17	31 20 00	Auxiliary Spillway Grading	3,000.	SY	\$ _____	\$ _____
18	31 37 00	Auxiliary Spillway Rock Berms	1,105.	LF	\$ _____	\$ _____
19	33 42 15 03 30 00	30-Inch Steel Pipe	100.	LF	\$ _____	\$ _____

Bid Schedule: Hogchute (AKA Carson) Reservoir Dam Rehabilitation

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
20	33 01 36	CIPP Pipe Lining	300.	LF	\$ _____	\$ _____
21	03 30 00 31 20 00 31 37 00 05 52 04	Impact Basin (excavation, backfill, formwork, concrete, riprap, steel railing, etc.)		Lump Sum	---	\$ _____
22	32 92 26 32 99 10	Site Restoration (placing topsoil, seeding, sodding, planting, mulching, etc.)		Lump Sum	---	\$ _____
23	40 70 10	Early Warning System		Lump Sum	---	\$ _____
24	625	Construction Surveying		Lump Sum	---	\$ _____
Bid Amount:						\$ _____

Bid Amount:

dollars

Signature

Name

Title

Date

Company