

## Bid Schedule (Revised per Addendum No. 8): Hogchute (AKA Carson) Reservoir Dam Rehabilitation

**&project**

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	626 01 22 50	Mobilization		Lump Sum	---	\$ _____
2	208 01 57 19	Erosion Control		Lump Sum	---	\$ _____
3	01 57 60	Construction Dewatering		Lump Sum	---	\$ _____
4	02 41 00	Demolition (intake, outfall, piping, controls, spillway grouted riprap, etc.)		Lump Sum	---	\$ _____
5	03 30 00 31 20 00 31 37 00	Concrete Overflow Spillway (excavation, form, concrete placement, backfill, and riprap, etc.)		Lump Sum	---	\$ _____
6	31 24 00 31 20 00	Embankment Excavation		Lump Sum	---	\$ _____
7	33 41 66	Type I Filter Material	1,000.	CY	\$ _____	\$ _____
8	33 41 66	Type II Filter Material	120.	CY	\$ _____	\$ _____
9	33 41 66 33 42 15	HDPE Perforated Drain Pipe	270.	LF	\$ _____	\$ _____
10	33 41 66 33 42 15	HDPE Solid Drain Pipe	300.	LF	\$ _____	\$ _____
11	31 24 00 31 20 00 31 23 33	Embankment Backfill (embankment fill, rock shell, restore stockpile areas, etc.)		Lump Sum	---	\$ _____
12	35 22 28 33 42 15	Stainless Steel Slide Gate		Lump Sum	---	\$ _____
13	03 30 00 33 42 15 05 50 00	Concrete Buttress Intake Structure (Concrete buttress, conduit encasement, air vent and hydraulics conduit, steel elbow, etc.)		Lump Sum	---	\$ _____
14	26 05 43 33 42 15	Locking Valve Box		Lump Sum	---	\$ _____
15	05 50 00	Trash Rack		Lump Sum	---	\$ _____
16	32 92 26	Wetland Soil Stockpiling	4,100.	SY	\$ _____	\$ _____
17	31 20 00	Auxiliary Spillway Grading	3,000.	SY	\$ _____	\$ _____
18	31 37 00	Auxiliary Spillway Rock Berms	1,105.	LF	\$ _____	\$ _____

## Bid Schedule (Revised per Addendum No. 8): Hogchute (AKA Carson) Reservoir Dam Rehabilitation

**&project**

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
19	33 42 15 03 30 00	30-Inch Steel Pipe	100.	LF	\$ _____	\$ _____
20	33 01 36	CIPP Pipe Lining	300.	LF	\$ _____	\$ _____
21	03 30 00 31 20 00 31 37 00 05 52 04	Impact Basin (excavation, backfill, formwork, concrete, riprap, steel railing, etc.)		Lump Sum	---	\$ _____
22	32 92 26 32 99 10	Site Restoration (placing topsoil, seeding, sodding, planting, mulching, etc.)		Lump Sum	---	\$ _____
23	40 70 10	Early Warning System		Lump Sum	---	\$ _____
24	625	Construction Surveying		Lump Sum	---	\$ _____
<b>Bid Amount:</b>					<b>\$</b>	<b>_____</b>

**Bid Amount:**

**dollars**

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Name

\_\_\_\_\_  
Title

\_\_\_\_\_  
Date

\_\_\_\_\_  
Company