



Purchasing Division

ADDENDUM NO. 1

DATE: April 30, 2021
FROM: City of Grand Junction Purchasing Division
TO: All Offerors
RE: 2021 Curb, Gutter, and Sidewalk Replacement Project IFB-4913-21-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

1. The price bid schedule was left out of the solicitation document. Please see the price bid schedule attached below.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", written in a cursive style.

Duane Hoff Jr., Senior Buyer
City of Grand Junction, Colorado

Bid Schedule: 2021 Curb, Gutter, and Sidewalk Replacement Project

CONTRACTOR: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	202	Saw Cut Concrete	700.	LF	\$ _____	\$ _____
2	202	Remove/Reset Privacy Fence (6" Cedar)	110.	LF	\$ _____	\$ _____
3	207	Restore Landscaping	Lump	SUM	---	\$ _____
4	208	Erosion Control (Complete in Place)	Lump	SUM	---	\$ _____
5	401	Hot Mix Asphalt (Patching)(4" thick) (Grading SX, Binder Grade 64-22) to include 6" of Aggregate Base Course (Class 6).	535.	SY	\$ _____	\$ _____
6	608	Concrete Curb and Gutter (2.5' Wide) To Include 6" of Class 6 Aggregate Base Course	50.	LF	\$ _____	\$ _____
7	608	Monolithic Vertical Curb, Gutter and Sidewalk to include 6" of Aggregate Base Course (Class 6).	130.	SY	\$ _____	\$ _____
8	608	Monolithic Drive Over Curb, Gutter and Sidewalk to include 6" of Aggregate Base Course (Class 6).	400.	SY	\$ _____	\$ _____
9	608	Concrete Sidewalk (4" Thick) to include 6" of Aggregate Base Course (Class 6).	800.	SY	\$ _____	\$ _____
10	608	Concrete Drainage Pan to include 8" of Aggregate Base Course (Class 6).	26.	SY	\$ _____	\$ _____
11	608	Concrete Intersection Corner to include 6" of Aggregate Base Course (Class 6).	275.	SY	\$ _____	\$ _____
12	608	Concrete Driveway Section (6"Thick) to Include 6" of Class 6 Aggregate Base Course	80.	SY	---	\$ _____
13	608	Detectable Warning (Cast Iron, Wet Set)(2' X 2')	18.	EA	\$ _____	\$ _____
14	620	Sanitary Facility	Lump	SUM	---	\$ _____
15	626	Mobilization	Lump	SUM	---	\$ _____
16	630	Traffic Control (Complete In Place) to Include Traffic Control Plan(s)	Lump	SUM	---	\$ _____
17		Sidewalk Trough Drain	6.	LF	\$ _____	\$ _____
MCR		MINOR CONTRACT REVISIONS	---	---	---	\$ <u>15,000.00</u>

Bid Amount: \$ _____

Bid Amount: _____ **dollars**