



Purchasing Division

ADDENDUM NO. 2

DATE: May 13, 2021
FROM: City of Grand Junction Purchasing Division
TO: All Offerors
RE: 2021 Curb, Gutter, and Sidewalk Replacement Project IFB-4913-21-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:


1. Q. 853 Ouray Ave 40' of 5' Sidewalk: Item to remove/reset decorative fencing to place forms, or is this considered restoring landscaping?
 - A. This item will be considered part of Item No. 3 - Restore Landscaping.
2. Q. 2436 Patterson Rd Fisher Liquor Barn entrance: Can entrance be fully closed to remove both ramps and replace? Are there considerations for High early mix? If the entrance/exit can't be closed fully, how is the fillet going to be poured with the tight turn and narrow road?
 - A. For bidding purposes, it should be assumed that the driveway can be closed ½ at a time to allow traffic to flow through the alternating sides.
3. Q. Photos marked tree roots – What is the cities plan?
 - A. The contractor will be responsible for removing tree roots at the City's discretion/direction.
4. Q. Behind 417 Main St (in alley): Can we close this section of alley and block parking spaces? Is there a design for the ramp? 8' seems to narrow and won't be ADA?
 - A. This is intended to be a pass-through area with truncated domes rather than a ramp. There is not a new design for the ramp as it will utilize existing grades.
5. Q. Have the affected home owners of driveways to be replaced been notified and made aware that they won't be able to use their driveways for 1 week?
 - A. Notification and coordination of the driveway closures are the responsibility of the contractor.

6. Q. Privacy fence (Cedar) marked for remove/reset seems to be in poor condition, is there a consideration for the item to be remove/replace? Item is marked on bid sheet as (6" Cedar) should this be 6' instead?
- A. For bidding purposes please bid to remove/reset. Also, the Bid Item No. 2 has been changed to reflect a 6' fence. Please see the updated bid schedule.
7. Q. 2674 Lookout Lane 80'x25' asphalt (220 SY): This is considered patching? If not there is no item for full depth asphalt removal or paving?
- A. This area will be included in Bid Item No. 5 - 4" asphalt patching.
8. Q. No bid item for flagging?
- A. Flagging hours should be incorporated into Bid Item No. 16.
9. Q. 845 Teller Ave up to 9th St: Concrete between sidewalk and retaining walls is to remain & be used to form new sidewalk?
- A. Yes
10. Q. 527 W Main St (Riverside School): Is the Jersey barrier the contractors responsibility to remove?
- A. This will be removed by others.
11. Q. Pg. 24 of the bid documents has the following: 3.3.27 ACI Concrete and Flatwork Finisher and Technician: Hand finishing concrete will be permitted only when performed under the direct supervision of a craftsman holding the following certificate: ACI Concrete Flatwork Finisher and Technician (ACICFFT) or other Flatwork Finisher certification program approved by the City Engineering Manager. Can this be enforced? Can the City have the bidders turn in this certification with the bid to ensure this requirement is being met?
- A. This specification is not evaluated as a pre-qualification to bid, but will be required during the submittal process. Please see the updated Project Submittal Form.
12. See attached updated Project Submittal Form.
13. See attached updated Price Bid Schedule. Contractor shall utilize this Addendum 2 Price Bid Schedule when submitting their bid response.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,



Duane Hoff Jr., Senior Buyer
City of Grand Junction, Colorado

PROJECT SUBMITTAL FORM

PROJECT: **2021 Curb, Gutter, and Sidewalk Replacements**

CONTRACTOR:

PROJECT ENGINEER: Eric Mocko

Description	Date Received	Resubmittal Requested	Resubmittal Received	Date Accepted
-------------	---------------	-----------------------	----------------------	---------------

STREET CONSTRUCTION

Asphalt mix designs				
Base course gradation, Proctor curve				
Concrete Mix Designs				

EROSION CONTROL / STORMWATER MANAGEMENT

Inlet Protection				
Concrete Washout				

PERMITS, PLANS, OTHER

Traffic Control Plan				
CDOT Special Use Permit				
ACI Concrete and Flatwork Finisher and Technician Certification				

Bid Schedule: 2021 Curb, Gutter, and Sidewalk Replacement Project

Addendum #2

CONTRACTOR: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	202	Saw Cut Concrete	700.	LF	\$ _____	\$ _____
2	202	Remove/Reset Privacy Fence (6' Cedar)	110.	LF	\$ _____	\$ _____
3	207	Restore Landscaping	Lump	SUM	---	\$ _____
4	208	Erosion Control (Complete in Place)	Lump	SUM	---	\$ _____
5	401	Hot Mix Asphalt (Patching)(4" thick) (Grading SX, Binder Grade 64-22) to include 6" of Aggregate Base Course (Class 6).	535.	SY	\$ _____	\$ _____
6	608	Concrete Curb and Gutter (2.5' Wide) To Include 6" of Class 6 Aggregate Base Course	50.	LF	\$ _____	\$ _____
7	608	Monolithic Vertical Curb, Gutter and Sidewalk to include 6" of Aggregate Base Course (Class 6).	130.	SY	\$ _____	\$ _____
8	608	Monolithic Drive Over Curb, Gutter and Sidewalk to include 6" of Aggregate Base Course (Class 6).	400.	SY	\$ _____	\$ _____
9	608	Concrete Sidewalk (4" Thick) to include 6" of Aggregate Base Course (Class 6).	800.	SY	\$ _____	\$ _____
10	608	Concrete Drainage Pan to include 8" of Aggregate Base Course (Class 6).	26.	SY	\$ _____	\$ _____
11	608	Concrete Intersection Corner to include 6" of Aggregate Base Course (Class 6).	275.	SY	\$ _____	\$ _____
12	608	Concrete Driveway Section (6"Thick) to Include 6" of Class 6 Aggregate Base Course	80.	SY	---	\$ _____
13	608	Detectable Warning (Cast Iron, Wet Set)(2' X 2')	18.	EA	\$ _____	\$ _____
14	620	Sanitary Facility	Lump	SUM	---	\$ _____
15	626	Mobilization	Lump	SUM	---	\$ _____
16	630	Traffic Control (Complete In Place) to Include Traffic Control Plan(s)	Lump	SUM	---	\$ _____
17		Sidewalk Trough Drain	6.	LF	\$ _____	\$ _____
MCR		MINOR CONTRACT REVISIONS	---	---	---	\$ <u>15,000.00</u>

Bid Amount: \$ _____

Bid Amount:

dollars