



Purchasing Division

ADDENDUM NO. 5

DATE: May 27, 2021
FROM: City of Grand Junction Purchasing Division
TO: All Offerors
RE: Persigo Wastewater Treatment Plant Large Repairs IFB-4910-21-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

1. Q. Contractor Bid Form, Bid Item No. 10 (Address Existing Leaking Cracks): We would request that a unit price per lineal foot be added for this work item since it is not possible to quantify the extent of these repairs prior to the bid.

A. The City has revised the Bid Schedule to update Bid Item 10 (Address Existing Leaking Cracks) to include 100 Linear Feet of Urethane Grout Injection.

2. Q. Contractor Bid Form, Bid Item 5.1 (Coating System at Clarifier Concrete Walls) & Bid Item 5.2 (Coating System at Clarifier Concrete Slab): Please provide specifications for the required concrete coating systems. Addenda No. 2, Item No. 1 indicated that these coatings can be found in Specification Section 09-07-23. Please be advised that Specification Section 09-97-23 has not been included in our PDF copy of the specifications.

A. The contractor is directed to the link on page 26 of the Solicitation for Appendix C (Project Specific Specifications). Clicking this link downloads the entire Specification document. The Section 09 97 23 for Immersion-Grade Concrete Coatings starts on page 198 of the PDF (Page 75 of the Primary Clarifier Repairs Specifications). Subsection 2.2 of this section describes both the base bid and alternate bid coating types.

3. See the attached updated/modified (Base Bid) Price Bid Schedule. Contractor shall utilize this Addendum 5 (Base Bid) Price Bid Schedule when submitting their bid response.

4. See updated/modified [FE Basin Walls Drawings](#) (click link). These drawings show a possible design change that may be required depending upon test results (to be performed by WJE during construction). The change focuses on the new wall base and how it is connected to the existing slab (see sheet 4.6). Contractors should note that an additional construction joint is required, along with waterstop and sealant. The new wall base rebar would not be doweled into the existing slab. This change may be implemented during construction and will be incorporated into the construction scope via a Change Order.

5. See updated/modified specs for the [Sludge Blending Tank](#) to include an optional (Add Alternate, as per Addendum 4) concrete coating. These changes were made due to the results of WJE's ASR investigation.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", written in a cursive style.

Duane Hoff Jr., Senior Buyer
City of Grand Junction, Colorado

Bid Schedule: Persigo WWTP Large Repairs w/ FE Basin Walls (Addendum 5)

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	3-1	Concrete Corner Spall Repair	46.	SF	\$ _____	\$ _____
2	3-2	Concrete Coping Repair	4.	SF	\$ _____	\$ _____
3	3-3	Installation of New Anchors	39.	EA	\$ _____	\$ _____
4	3-5	Sealant Installation	780.	LF	\$ _____	\$ _____
5		North Dividing Wall Demolition/Removal		Lump Sum	---	\$ _____
6		North Dividing Wall Installation		Lump Sum	---	\$ _____
7		South Dividing Wall Demolition/Removal		Lump Sum	---	\$ _____
8		South Dividing Wall Installation		Lump Sum	---	\$ _____
9		Splice of Slab L-Bars at North & South Wall	210.	EA	\$ _____	\$ _____
10		Address Existing Leaking Cracks (Urethane Grout Injection)	100.	LF	\$ _____	\$ _____
11		Install New Catwalk at South Dividing Wall		Lump Sum	---	\$ _____
12	5-1	Installation of Coating System at Walls	15,400.	SF	\$ _____	\$ _____
13		Additional Surface Preparation	7,000.	SF	\$ _____	\$ _____
14	5-3	Removal of Dome and Entrance Extension	2.	EA	\$ _____	\$ _____
15	5-5	Installation of Guardrail	760.	LF	\$ _____	\$ _____
16	5-6	Installation of New Grating	60.	SF	\$ _____	\$ _____
17		Patch Wall at MEP Penetration		Lump Sum	---	\$ _____
18		Concrete Repairs	180.	SF	\$ _____	\$ _____
19		Crack Sealing	1,000.	LF	\$ _____	\$ _____
20	6-1	Installation of Coating System		Lump sum	---	\$ _____
21	6-2	Replacement of Connections at Perimeter Beams (North & West Elev)		Lump sum	---	\$ _____
22	6-4	Replacement of Connections at Main Beams (North and West Elev)		Lump sum	---	\$ _____
23	6-6	Sealant Installation	160.	LF	\$ _____	\$ _____
24	6-3	Replacement of Connections at Perimeter Beams (East Elevation)		Lump sum	---	\$ _____
25	6-5	Replacement of Connections at Main Beams (South & East Elev)		Lump sum	---	\$ _____

Bid Schedule: Persigo WWTP Large Repairs w/ FE Basin Walls (Addendum 5)

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
26		Sanitary Facility	2.	EA	\$ _____	\$ _____
27		Access		Lump sum	---	\$ _____
28		Mobilization		Lump sum	---	\$ _____
29		General Conditions (Protection, Access, Temporary Removal and Reset of Utilities)		Lump sum	---	\$ _____
MCR		Minor Contract Revisions	---	---	---	\$ 235,000.00

Bid Amount: \$ _____

Base Bid Amount:

_____ dollars