



Purchasing Division

## ADDENDUM NO. 3

**DATE:** September 9, 2021  
**FROM:** City of Grand Junction Purchasing Division  
**TO:** All Offerors  
**RE:** Monument Road Left Turn Lane at Frog Pond Subdivision IFB-4945-21-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

1. Q. In regards to the retaining wall detail, without a footer we are concerned the wall will be subject to rotational forces, and will cause the wall to tip with backfill operations, and later with heavy traffic loading. Can the Engineer confirm this wall is to be installed without a footer, or can the detail be revised to include a footer?
  - A. The retaining wall has been revised to address the concern of surcharge loading during and after construction. A footer has been added (see attached revised drawings) to the wall from Station 5+00 to 6+00. This wall shall be constructed per CDOT M-Standard M-601-20 for a design height of 2 ft. The cross-section sheets have also been revised to show the footer. The updated bid schedule is attached. Contractor shall utilize the attached Addendum 3 Price Bid Schedule when submitting their bid response.
2. Addendum 3 Attachments: (CLICK LINKS)
  - [CDOT M-601-20](#)
  - [MON RD LT LN-5](#)
  - [MON RD LT LN-10](#)
  - [MON RD LT LN-11](#)

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", is written over a white background.

Duane Hoff Jr., Senior Buyer  
City of Grand Junction, Colorado

**Bid Schedule: Monument Rd Left Turn Lane at Frog Pond Subdivision (Addendum #3)**

Item No.	Description	Quantity	Units	Unit Price	Total Price
1	202- Removal of Sidewalk 00175	106.	Sq Yd	\$ _____	\$ _____
2	202- Removal of Asphalt Mat 00220	90.	Sq Yd	\$ _____	\$ _____
3	202- Removal of Asphalt Mat (Milling 1 1/2" 00226 Deep)(T-top)	90.	Sq Yd	\$ _____	\$ _____
4	202- Removal of Pavement Marking (Planing) 00250	3,322.	Lin Ft	\$ _____	\$ _____
5	203- Unclassified Excavation 00000	537.	Cu Yd	\$ _____	\$ _____
6	304- Aggregate Base Course (Class 6) 06000	732.	Tons	\$ _____	\$ _____
7	403 Hot Mix Asphalt (5 1/2 inch thick) (Grading SX, 75, Binder Grade PG 64- 22)	230.	Tons	\$ _____	\$ _____
8	504 Concrete Wall (Class D) (Includes associated black Reinforcing Steel and any necessary appurtenances to complete work)	22.	Cu Yd	\$ _____	\$ _____
9	608- Detectable Warnings (Cast Iron) Wet Set 00015 (2' x 2')	10.	Each	\$ _____	\$ _____
10	608- Concrete Bikeway (6" Thick) to include 6" 00040 of Class 6 Aggregate Base Course.	106.	Sq Yd	\$ _____	\$ _____
11	609- Concrete Curb CDOT Type 2 (Sect. B) 6 20010 inch Barrier (Includes 6" of Class 6 ABC)	255.	Lin Ft	\$ _____	\$ _____
12	620- Sanitary Facility 00020	1.	Each	\$ _____	\$ _____
13	625- Construction Surveying 00000	Lump Sum		---	\$ _____
14	626- Mobilization 00000	Lump Sum		---	\$ _____
15	627- Epoxy Pavement Marking 00005	15.	Gallon	\$ _____	\$ _____
16	627- Preformed Thermoplastic Pavement 00070 Marking (Left Turn Symbol)	1.	Each	\$ _____	\$ _____
17	630 Stormwater Management	Lump Sum		---	\$ _____
18	630 Traffic Control (Complete In Place) (Includes Traffic Control Plan)	Lump Sum		---	\$ _____
MCR	MINOR CONTRACT REVISIONS	---	---	---	\$ <u>6,000.00</u>
				<b>Bid Amount:</b>	\$ _____

**Bid Amount:**

**dollars**