



Purchasing Division

ADDENDUM NO. 2

DATE: September 23, 2021
FROM: City of Grand Junction Purchasing Division
TO: All Offerors
RE: 2021 Alley Improvements District Project IFB-4949-21-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

1. Q. Are you expecting highearly?
 - A. No, no concrete additives are being required beyond what is identified in the specifications.
2. Q. Do working hours include weekends?
 - A. Weekend work is permitted with prior authorization from the City if inspection resources are available.
3. Q. Is Xcel placing new material?
 - A. No, it is anticipated that Xcel will backfill with site material.
4. Q. Is there base course planned for under the concrete in the alley?
 - A. No base course is intended to be placed under the concrete. Additional 80 tons of Bid Schedule Item Number 6, Subgrade Stabilization (Class 3 Aggregate Base Course) (Complete in Place) has been added to the revised Bid Schedule (a new total of 160 tons for Item No. 6, Subgrade Stabilization).
5. Q. Concerning City standards for clean-outs, some seem to be solid, some not. Please clarify. Do you want to block it out or use ring?
 - A. Clean-outs should have ring and cover installed per standard specifications in areas where clean-outs are not surrounded by concrete.
6. Q. Will Contractor be required to include cold weather conditions in their bid?

A. Yes, the contractor is required to include cold weather provisions for the placement of concrete as part of the bid.

7. Contractor shall utilize the attached revised Addendum 3 Price Bid Schedule.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", written in a cursive style.

Duane Hoff Jr., Senior Buyer
City of Grand Junction, Colorado

Bid Schedule: 2021 Alley Improvement District (Addendum 2)

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	208	Storm Drain Inlet Box Protection	2.	EA	\$ _____	\$ _____
2	208	Concrete Washout	1.	LS	\$ _____	\$ _____
3	209	Dust Abatement	30.	DAYS	\$ _____	\$ _____
4	210	Adjust Sanitary Sewer Manhole (Includes Structure &/or Frame & Grate)	2.	EA	\$ _____	\$ _____
5	210	Adjust Sanitary Sewer Cleanout	8.	EA	\$ _____	\$ _____
6	304	Subgrade Stabilization (Class 3 Aggregate Base Course) (Complete in Place).	160.	Tons	\$ _____	\$ _____
7	304	Aggregate Base Course (Class 6) (areas on plan between edge of alley and ROW)	55.	Tons	\$ _____	\$ _____
8	412	Concrete Pavement (8" thick) (Class P) (Includes all Pavement Removals and Unclassified Excavation Necessary)	751.	SY	\$ _____	\$ _____
9	420	Geogrid (Standard)	80.	SY	\$ _____	\$ _____
10	620	Sanitary Facility	1.	LS	\$ _____	\$ _____
11	625	Construction Surveying (Includes As-Built Documentation)	1.	LS	\$ _____	\$ _____
12	626	Mobilization	1.	LS	\$ _____	\$ _____
13	630	Traffic Control (Complete in Place)	20.	DAYS	\$ _____	\$ _____
14	630	Traffic Control Plan	1.	LS	\$ _____	\$ _____
15	G-56	Weekly Newsletters	6.	Weeks	\$ _____	\$ _____
MCR		Minor Contract Revisions	---	---	---	\$ 10,000.00

Bid Amount: \$ _____

Bid Amount: _____

dollars