



Purchasing Division

ADDENDUM NO. 2

DATE: October 29, 2021
FROM: City of Grand Junction Purchasing Division
TO: All Interested Parties
RE: Shadow Lake Pump Station Electrical Improvements IFB-4952-22-SH

Bidders responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following:

Question 1. Section 25 05 73 – Please clarify if the contractor is to perform the Short Circuit/Coordination/Arc Flash Study or if that is being taken care of by the the City of Grand Junction’s engineering firm.

Answer: The City’s consultant, Magna IV, will be preforming the short circuit, coordination and arc flash study.

Question 2. The coordination study is supposed to be completed and approved before the new MCC is released to production. This could delay the delivery of the MCC. Please clarify if this is correct.

Answer: The City’s consultant, Magna IV, will be responsible for completing the coordination study. MCC submittal will be reviewed and approved prior to completing the coordination study.

Question 3. Section 25 05 73.3.3 states that there is to be a 4 hour Arc Flash Training provided. Is this the responsibility of the contractor or is this being provided by the City of Grand Junction’s engineering firm?

Answer: The City’s consultant, Magna IV, will conduct the training.

Question 4. The contract drawings state the contractor is to replace the existing PLC cabinet with one that will be provided by the City. Please clarify that the existing PLC Cabinet and PLC are to remain in place and re-used.

Answer: The existing PLC shall remain and existing wiring to the MCC shall be investigated and I/O reused as required. If additional modules are required to accommodate signals in the design beyond existing spare I/O, additional modules shall be identified and procured by the City and installed by the Contractor. PLC programming will be completed by the City.

Question 5. At the pre-bid it was stated that the city would have a recycle dumpster delivered to the site for the MCC to be hauled off in. Please verify that this is still what will happen.

Answer: Yes, the City will provide a recycle dumpster for the Contractor to use.

Question 6. Is the Conduit and Wiring supposed to be demolished and replaced from the Golf Secondary and Residential Primary VFDs?

Answer: Note #2 on Drawing E-2 indicates to intercept and extend existing wiring as required. If Contractor deems replacement is required due to age after demolition of the MCC, then conduits and wiring shall be replaced. All existing in slab conduits shall be reused and above ground shall be reworked as required or provide new conduit and fittings.

A copy of the Sign-In Sheet from the mandatory site visit is attached.

The original solicitation for the project referenced above is amended as noted.

All other conditions of subject remain the same.

Respectfully,



Susan Hyatt, Senior Buyer
City of Grand Junction, Colorado

Solicitation Name:	Shadow Lake Pump Station Electrical Improvements
Solicitation #:	IFB-4952-22-SH
Date:	10/19/2021
Time:	2:00 PM

SIGN-IN SHEET



	Company Name	Representative Name	Phone	Email
1	Sturgeon Electric	Shane Moe	(970) 985-3345	smoe@myrgroup.com
2	Dare Case Contracting	Will Gray	(970) 852-7763	will@darecase.com
3	EC Electric	Jack Payton	970-241-3302	jp@ec-electric.com
4				
5				
6				
7				
8				
9				
0				
1				
2				
3				
4				