

Bid Schedule: 28 1/4 Rd and Hawthorne Ave.

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1		CLEAR AND GRUB	1.	LS	\$ _____	\$ _____
2		REMOVAL TREE	1.	EA	\$ _____	\$ _____
3		REMOVAL OF PIPE	69.	LF	\$ _____	\$ _____
4		REMOVAL OF BOLLARD	4.	EA	\$ _____	\$ _____
5		REMOVAL ASPHALT MAT (FULL DEPTH)	11.56	SY	\$ _____	\$ _____
6		REMOVAL ASPHALT MAT (PLANING) 2" MILL	29.22	SY	\$ _____	\$ _____
7		REMOVAL OF PAVEMENT MARKING	136.	SF	\$ _____	\$ _____
8		REMOVAL GROUND SIGN (RETURN TO TRAFFIC DEPT AT THE CITY SHOPS)	10.	EA	\$ _____	\$ _____
9		SAWING ASPHALT MAT (6 IN)	66.	LF	\$ _____	\$ _____
10		REMOVAL OF FENCE	116.	LF	\$ _____	\$ _____
11		UNCLASSIFIED EXCAVATION	2,417.	CY	\$ _____	\$ _____
12		EROSION CONTROL LOG TYPE 1 (9 IN)	1,150.	LF	\$ _____	\$ _____
13		AGGREGATE BAG	30.	LF	\$ _____	\$ _____
14		CONCRETE WASHOUT	1.	EA	\$ _____	\$ _____
15		STORM DRAIN INLET PROTECTION (TYPE	6.	EA	\$ _____	\$ _____
16		VEHICLE TRACKING PAD	2.	EA	\$ _____	\$ _____
17		RELOCATE WATER VALVE	2.	EA	\$ _____	\$ _____
18		Adjust Manhole	1.	EA	\$ _____	\$ _____
19		SEEDING (NATIVE)	11,300.	SF	\$ _____	\$ _____
20		ROCK MULCH (WEED FREE)	4,020.	SF	\$ _____	\$ _____
21		LANDSCAPE WEED BARRIER FABRIC	446.67	SY	\$ _____	\$ _____
22		ADJUST VALVE BOX	2.	EA	\$ _____	\$ _____
23		ABC (CL 6)	1,844.	TON	\$ _____	\$ _____
24		RECONDITIONING (12" DEPTH)	3,459.22	SY	\$ _____	\$ _____
25		Hot Mix Asphalt (Grading SX) (75) (PG 64-22)	845.	TON	\$ _____	\$ _____
26		Concrete Sidewalk (4 Inch)	462.	SY	\$ _____	\$ _____
27		RIPRAP (9 INCH)	40.89	CY	\$ _____	\$ _____
28		18 Inch Reinforced Concrete Pipe (Complete In Place)	93.	LF	\$ _____	\$ _____
29		18 Inch Reinforced Concrete End Section	1.	EA	\$ _____	\$ _____
30		Manhole Slab Base (5 Foot)	1.	EA	\$ _____	\$ _____
31		16 Foot Gate	1.	EA	\$ _____	\$ _____
32		Concrete Intersection corner	147.	SY	\$ _____	\$ _____
33		Detectable Warnings	16.	SF	\$ _____	\$ _____
34		City Curb with Spill Gutter	576.	LF	\$ _____	\$ _____
35		City Standard Curb and Gutter	647.	LF	\$ _____	\$ _____
36		Monolithic Drive Over Curb, Gutter and Sidewalk (6'-6" wide)	283.	LF	\$ _____	\$ _____
37		Concrete Drainage Pan (6'-0" width)	38.	LF	\$ _____	\$ _____
38		Median Cover Material (Concrete) 6" Thickness	25.	SY	\$ _____	\$ _____
39		Construction Surveying	1.	LS	\$ _____	\$ _____
40		Mobilization	1.	LS	\$ _____	\$ _____
41		Traffic Control (Complete In Place)	1.	LS	\$ _____	\$ _____
MCR		Minor Contract Revisions	---	---	---	\$ 15,000.00

Bid Schedule: 28 1/4 Rd and Hawthorne Ave.

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
----------	-----------------	-------------	----------	-------	------------	-------------

Bid Amount: \$ _____

Bid Amount: _____ **dollars**