



Purchasing Division

ADDENDUM NO. 1

DATE: March 24, 2022
FROM: City of Grand Junction Purchasing Division
TO: All Offerors
RE: Partial Reconstruction of South Rim Drive and Kansas Avenue IFB-5044-22-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

1. Q. I printed out the bid schedule it says " 2020 S Downtown & Elm Ave Waterline Replacement" on it. Is this the correct bid schedule with the wrong name or is it a wrong bid schedule all together?

A. The bid schedule line items are correct, it is only the title that is in correct. Please see the attached corrected price bid schedule.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", written over a horizontal line.

Duane Hoff Jr., Contract Administrator
City of Grand Junction, Colorado

Bid Schedule: Partial Reconstruction of South Rim Drive and Kansas Avenue

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	202	Removal of Asphalt Mat (Full Depth)	14,398.65	SY	\$ _____	\$ _____
2	208	Storm Drain Inlet Protection (Gravel Filter at Curb Inlet) (Includes Maintenance & Removal of Debris, & Removal of Inlet Protection)	2.	Each	\$ _____	\$ _____
3	210	Reset Landscape Ground Cover (Match in Kind) (Contractor shall remove ground cover and underlying weed barrier as needed and stockpile materials. Contractor shall reset these materials and provide additional materials as needed)		Lump Sum	---	\$ _____
4	210	Adjust Manhole Rim to Finished Grade	15.	Each	\$ _____	\$ _____
5	210	Adjust Water Valve Box to Finished Grade	19.	Each	\$ _____	\$ _____
6	210	Reset Stop Sign	1.	Each	\$ _____	\$ _____
7	304	Aggregate Base Course (Class 6) (4" thick) (Shoulder Base)	9.8	Tons	\$ _____	\$ _____
8	304	6" Recondition Existing Base Course	14,348.6	SY	\$ _____	\$ _____
9	401	Hot Bituminous Pavement (5" Thick) (Grading SX, Binder Grade PG 64-22) (One 3" Lift & One 2" Lift)	1,086.35	Tons	\$ _____	\$ _____
10	401	Hot Bituminous Pavement (3" Thick) (Grading SX, Binder Grade PG 64-22) (One 3" Lift)	1,715.71	Tons	\$ _____	\$ _____
11	608	Concrete Gutter (Match in Kind)	40.83	SY	\$ _____	\$ _____
12	630	Traffic Control Plan		Lump Sum	---	\$ _____
13	630	Traffic Control (Complete In Place)		Lump Sum	---	\$ _____
14	630	Flagging		Lump Sum	---	\$ _____
15	620	Sanitary Facility		Lump Sum	---	\$ _____
16	625	Construction Surveying		Lump Sum	---	\$ _____
17	626	Mobilization		Lump Sum	---	\$ _____
MCR		Minor Contract Revisions		---	---	\$ <u>30,000.00</u>

Bid Amount: \$ _____

Bid Amount: _____

dollars