

2022 ASPHALT OVERLAYS – Selected Streets

| Street | From | To |
|------------------|---------------------|-----------------|
| Redlands Parkway | HWY 340 | CO River Bridge |
| 21 ½ Rd | HWY 6&50 | 848 21 ½ Rd |
| 25 ½ Rd | Independent Ave | Patterson Rd |
| Fernwood Ct | Piazza Way | Cul-de-sac |
| 30 Road | D Rd | E Rd |
| E Yucatan Ct | Lanai Dr | Cul-de-sac |
| Eden Ct | E Yucatan Dr | Cul-de-sac |
| Meadow Point Ct | 207 Meadow Point Ct | Cul-de-sac |
| Gold Leaf Ct | Hunter Creek Dr | Cul-de-sac |
| Unawweep Ave | 27 Rd | Lynnwood St |
| 27 Rd | Unawweep Ave | B ¾ Rd |

LOCATION: Redlands Parkway

AREA: 4,000' X Varies

16,250 SY

MAT THICKNESS:

Varies

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|--|--------|----------|
| 1 | 202 | Asphalt Removal (Planing)(Thickness Varies) | / SY | 2,251. |
| 2 | 202 | Asphalt Removal (Planing)(Full Depth) | / SY | 3,119. |
| 3 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 20. |
| 7 | 210 | Adjust Manhole Ring and Cover (Sanitary and Storm Sewer) | / EA | 3. |
| 8 | 210 | Adjust Valve Box (Price to Include adjustment of Survey Monuments) | / EA | 5. |
| 9 | 304 | Aggregate Base Course (Class 6) - Shoulder Edging Gravel | / Tons | 200. |
| 10 | 304 | Aggregate Base Course (Class 6) - Pavement Section (12" Thick) | / Tons | 488. |
| 11 | 401 | Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22) | / Tons | 2,130. |
| 15 | 627-30405 | Preformed Thermoplastic Pavement Marking (Word/Symbol) | / SF | 486. |
| 16 | 627-30410 | Preformed Plastic Pavement Marking (X-Walk/Stopline) | / SF | 500. |
| 18 | 630 | Traffic Control Plan | / EA | 1. |
| 19 | 630 | Flagging | / HR | 1,600. |
| 20 | 203 | Concrete Curb & Gutter Removal | / LF | 225. |
| 21 | 203 | Concrete Sidewalk Removal | / SY | 77. |
| 22 | 210 | Reset Guardrail (| / LF | 1,395. |
| 23 | 401 | Hot Mix Asphalt (3" thick) (Grading SX, Binder Grade 64-22) | / Tons | 78. |
| 24 | 401 | Hot Mix Asphalt (5" thick) (Grading SX, Binder Grade 64-22) | / Tons | 795. |
| 25 | 401 | Hot Mix Asphalt (4" thick) (Grading SX, Binder Grade 64-22) | / Tons | 86. |
| 26 | 304 | Aggregate Base Course (Class 6) - 15" Base Course | / Tons | 2,408. |
| 27 | 304 | Aggregate Base Course (Class 6) - 6" Base Course | / Tons | 126. |
| 28 | 608/304 | Concrete Curb Ramp to include 6" of Class 6 Aggregate Base Course | / SY | 33. |
| 29 | 608 | Detectable Warning (Wet Set)(Cast Iron)(2'x4') | / SF | 40. |
| 30 | 608/304 | Concrete Curb and Gutter (1.5' Wide Spill Curb) To Include 6" of Class 6 Aggregate Base Course | / LF | 755. |
| 31 | 608/304 | Concrete Crosswalk Section (8"Thick) to Include 6" of Class 6 Aggregate Base Course | / SF | 117. |

| | | | | |
|----|---------|---|------|--------|
| 32 | 608/304 | Concrete Median Cover (6" Thick) to Include 6" of Class 6 Aggregate Base Course | / SY | 340. |
| 33 | | SubBase Reconditioning (6" Thick) | / SY | 3,750. |
| 34 | 203 | Excavation and Embankment (Cut) | / CY | 1,288. |
| 35 | 608/304 | Inlet Structure | / EA | 2. |
| 36 | 608/304 | 18" RCP Storm Drain Pipe | / LF | 50. |
| 37 | | Adjust Telephone Ped. (By Others) | / EA | 2. |
| 38 | | Adjust Electrical Ped. (By Others) | / EA | 1. |
| 39 | | Adjust Electical Light (By Others) | / EA | 1. |

COMMENTS:

- 1) Full Width Mill (FWM) from concrete section of HWY 340 roundabout to 200' NE
- 2) FWM from bridge deck of Colorado River Bridge to 200' SW
- 3) 7' Edge Mill at Curb and Gutter, V-Pans, Paved Driveways, and Street Intersections
- 4) Refer to plans for details.

LOCATION: 21 1/2 Rd
 AREA: 4,500 X Varies
 MAT THICKNESS:

Hwy 6 and 50 to 848 21 1/2 Road
 14,783 SY
 2" Overlay

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|--|--------|----------|
| 1 | 202 | Asphalt Removal (Planing)(Thickness Varies) | / SY | 3,238.67 |
| 3 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 4. |
| 7 | 210 | Adjust Manhole Ring and Cover (Sanitary and Storm Sewer) | / EA | 10. |
| 8 | 210 | Adjust Valve Box (Price to Include adjustment of Survey Monuments) | / EA | 16. |
| 9 | 304 | Aggregate Base Course (Class 6) - Shoulder Edging Gravel | / Tons | 160. |
| 11 | 401 | Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22) | / Tons | 1,675. |
| 18 | 630 | Traffic Control Plan | / EA | 1. |
| 19 | 630 | Flagging | / HR | 800. |

COMMENTS:

- 1) Full Width Mill (FWM) from HWY 6 and 50 to 200' N
- 2) FWM from northern terminus (848 21 1/2 Rd) to 200' S.
- 3) FWM 150' N and S of H Road intersection (to include intersection)
- 4) 7' Edge Mill at Curb and Gutter, V-Pans, Paved Driveways, and Street Intersections

LOCATION: 25 1/2 Road
 AREA: 3,915' X Varies
 MAT THICKNESS:

Independent Ave. to Patterson Rd.
 20,085 SY
 2" Overlay

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|--|--------|-----------|
| 1 | 202 | Asphalt Removal (Planing)(Thickness Varies) | / SY | 11,422.22 |
| 3 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 4. |
| 7 | 210 | Adjust Manhole Ring and Cover (Sanitary and Storm Sewer) | / EA | 24. |
| 8 | 210 | Adjust Valve Box (Price to Include adjustment of Survey Monuments) | / EA | 20. |
| 11 | 401 | Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22) | / Tons | 2,250. |
| 18 | 630 | Traffic Control Plan | / EA | 1. |
| 19 | 630 | Flagging | / HR | 800. |

COMMENTS:

- 1) FWM from S. Edge of Patterson Rd. to 200'S
- 2) FWM from N. Edge of Independent Ave. to 200'N
- 3) 7' Edge Mill at Curb and Gutter, Drainage Pans, Paved Driveways, Street Intersections

LOCATION: Fernwood Ct

Piazza Way to end of Cul-de-sac

AREA: 600' X 22'

1,875 SY

MAT THICKNESS:

2" Overlay

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|---|--------|----------|
| 1 | 202 | Asphalt Removal (Planing)(Thickness Varies) | / SY | 1,875. |
| 3 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 2. |
| 11 | 401 | Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22) | / Tons | 210. |
| 18 | 630 | Traffic Control Plan | / EA | 1. |
| 19 | 630 | Flagging | / HR | 160. |

COMMENTS:

- 1) Full width mill entire street and cul-de-sac. Sparrow Ct is **not** included.

LOCATION: 30 Road
 AREA: 4,550' X Varies
 MAT THICKNESS:

D Road to E Road
 23,175 SY
 2" Overlay

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|--|--------|----------|
| AA1-1 | 202 | Asphalt Removal (Planing)(Thickness Varies) | / SY | 18,500. |
| AA1-10 | 401 | Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22) | / Tons | 2,585. |
| AA1-11 | 401 | Hot Mix Asphalt (Patching - Up to 7" thick) (To Include 6" of Class 6 Aggregate Base Course)(Grading SX, Binder Grade 64-22) | / Tons | 500. |
| AA1-12 | 608/304 | Concrete Tie-In to Existing Driveway (6" depth)(max 3' width) to Include 6" of Class 6 Aggregate Base Course | / SY | 530.4 |
| AA1-13 | 608/304 | Concrete Curb Ramp (Standard Concrete Detail C-21) to Include 6" of Class 6 Aggregate Base Course | / SY | 74.8 |
| AA1-14 | 608 | Detectable Warning (Wet Set)(Cast Iron)(2'x4') | / SF | 24. |
| AA1-15 | 609/304 | Concrete Driveway Section (Standard Concrete Detail C-08) to Include 6" of Class 6 Aggregate Base Course | / SY | 1,420. |
| AA1-19 | 627-30405 | Preformed Thermoplastic Pavement Marking (Word/Symbol) | / SF | 492.8 |
| AA1-2 | 202 | Concrete Sidewalk Removal | / SY | 530.4 |
| AA1-20 | 627-30410 | Preformed Plastic Pavement Marking (X-Walk/Stopline) | / SF | 496. |
| AA1-23 | 630 | Flagging | / HR | 200. |
| AA1-3 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 20. |
| AA1-7 | 210 | Adjust Valve Box (Price to Include adjustment of Survey Monuments) | / EA | 36. |
| AA1-8 | 210 | Adjust Manhole Ring and Cover (Sanitary and Storm Sewer) | / EA | 31. |
| AA1-9 | 304 | Subgrade Stabilization (Class 3 Aggregate Base Course - 24" Thick)(Complete in Place) | / Tons | 200. |

COMMENTS:

- 1) Full Width Mill (FWM) from D Rd to 200' N
- 2) FWM from northern terminus (E Rd concrete intersection) to 200' S.
- 3) FWM 150' N and S of D 1/2 Rd intersection (to include intersection)
- 4) 7' Edge Mill at Curb and Gutter, V-Pans, Paved Driveways, and Street Intersections

LOCATION: E Yucatan Ct
 AREA: 1,360' X 25'
 MAT THICKNESS:

Lanai Dr to end of cul-de-sac
 4,180 SY
 2" Overlay

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|--|--------|----------|
| AA2-1 | 202 | Asphalt Removal (Planing)(Thickness Varies) | / SY | 4,180. |
| AA2-13 | 401 | Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22) | / Tons | 460. |
| AA2-14 | 401 | Hot Mix Asphalt (Patching - Up to 4" thick) (To Include 6" of Class 6 Aggregate Base Course)(Grading SX, Binder Grade 64-22) | / Tons | 100. |
| AA2-19 | 630 | Traffic Control Plan | / EA | 1. |
| AA2-20 | 630 | Flagging | / HR | 40. |
| AA2-4 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 2. |
| AA2-8 | 210 | Adjust Manhole Ring and Cover (Sanitary and Storm Sewer) | / EA | 9. |
| AA2-9 | 210 | Adjust Valve Box (Price to Include adjustment of Survey Monuments) | / EA | 4. |

COMMENTS:

- 1) FWM from Lanai Dr to end of cul-de-sac.

LOCATION: Eden Court
 AREA: 515' X 25'
 MAT THICKNESS:

E Yucatan Ct to end of cul-de-sac
 1,830 SY
 2" Overlay

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|--|--------|----------|
| AA2-1 | 202 | Asphalt Removal (Planing)(Thickness Varies) | / SY | 1,830. |
| AA2-13 | 401 | Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22) | / Tons | 210. |
| AA2-14 | 401 | Hot Mix Asphalt (Patching - Up to 4" thick) (To Include 6" of Class 6 Aggregate Base Course)(Grading SX, Binder Grade 64-22) | / Tons | 50. |
| AA2-19 | 630 | Traffic Control Plan | / EA | 1. |
| AA2-20 | 630 | Flagging | / HR | 40. |
| AA2-4 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 2. |
| AA2-8 | 210 | Adjust Manhole Ring and Cover (Sanitary and Storm Sewer) | / EA | 3. |
| AA2-9 | 210 | Adjust Valve Box (Price to Include adjustment of Survey Monuments) | / EA | 3. |

COMMENTS:

- 1) FWM from E Yucatan Ct to end of cul-de-sac

LOCATION: Meadow Point Court

207 Meadow Point Ct to end of cul-de-sac

AREA: 240' X 28'

1,130 SY

MAT THICKNESS:

2" Overlay

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|---|--------|----------|
| AA2-10 | 304 | Aggregate Base Course (Class 6) - Pavement Section (12" Thick) | / Tons | 700. |
| AA2-11 | 304 | Subgrade Stabilization (Class 3 Aggregate Base Course - 24" Thick)(Complete in Place) | / Tons | 200. |
| AA2-12 | 401 | Hot Mix Asphalt (4" thick) (Grading SX, Binder Grade 64-22) | / Tons | 275. |
| AA2-19 | 630 | Traffic Control Plan | / EA | 1. |
| AA2-2 | 202 | Asphalt Removal (Full Depth) | / SY | 1,130. |
| AA2-20 | 630 | Flagging | / HR | 80. |
| AA2-3 | 203 | Excavation and Embankment (Bike Lanes - See SP-2)(Cut) | / CY | 300. |
| AA2-4 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 4. |
| AA2-8 | 210 | Adjust Manhole Ring and Cover (Sanitary and Storm Sewer) | / EA | 3. |

COMMENTS:

- 1) Remove asphalt, recondition base/replace failed base course and repave from 207 Meadow Point Ct to end of cul-de-sac

LOCATION: Gold Leaf Court

Hunter Creek Dr to end of cul-de-sac

AREA: 280' X 28'

2,160 SY

MAT THICKNESS:

2" Overlay

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|--|--------|----------|
| AA2-1 | 202 | Asphalt Removal (Planing)(Thickness Varies) | / SY | 2,160. |
| AA2-13 | 401 | Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22) | / Tons | 240. |
| AA2-14 | 401 | Hot Mix Asphalt (Patching - Up to 4" thick) (To Include 6" of Class 6 Aggregate Base Course)(Grading SX, Binder Grade 64-22) | / Tons | 20. |
| AA2-19 | 630 | Traffic Control Plan | / EA | 1. |
| AA2-20 | 630 | Flagging | / HR | 40. |
| AA2-4 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 2. |

COMMENTS:

- 1) FWM from Hunter Creek Dr to end of cul-de-sac

LOCATION: Unawep Avenue
 AREA: 4,150' X 45'
 MAT THICKNESS:

27 Rd to Lynnwood Dr
 20,578 SY
 2" Overlay

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|--|------------|-----------|
| AA3-1 | 202 | Asphalt Removal (Planing)(Thickness Varies) | / SY | 14,244.44 |
| AA3-10 | 627-30410 | Preformed Plastic Pavement Marking (X-Walk/Stopline) | / SF | 224. |
| AA3-11 | 630 | Traffic Control (Complete In Place) | / Lump Sum | 1. |
| AA3-12 | 630 | Traffic Control Plan | / EA | 1. |
| AA3-13 | 630 | Flagging | / HR | 400. |
| AA3-2 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 8. |
| AA3-3 | 210 | Adjust Valve Box (Price to Include adjustment of Survey Monuments) | / EA | 34. |
| AA3-4 | 210 | Adjust Manhole Ring and Cover (Sanitary and Storm Sewer) | / EA | 13. |
| AA3-5 | 401 | Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22) | / Tons | 2,212.65 |
| AA3-6 | 620 | Sanitary Facility | / Lump Sum | 1. |
| AA3-7 | 625 | Construction Surveying | / Lump Sum | 1. |
| AA3-8 | 626 | Mobilization | / Lump Sum | 1. |
| AA3-9 | 627-30405 | Preformed Thermoplastic Pavement Marking (Word/Symbol) | / SF | 636.3 |

COMMENTS:

- 1) FWM from 27 Rd intersection to 200'E
- 2) FWM from Lynnwood St to 200'W
- 3) 12' Edge Mill at Curb and Gutter, Drainage Pans, Paved Driveways, Street Intersections

LOCATION: 27 Road
 AREA: 1,285' X Varies
 MAT THICKNESS:

27 Rd to B ¾ Road
 4,000 SY
 2" Overlay

| Item No. | CDOT, City Ref. | Description | Price | Quantity |
|----------|-----------------|--|------------|----------|
| AA4-1 | 202 | Asphalt Removal (Planing)(Thickness Varies) | / SY | 1,877.78 |
| AA4-10 | 620 | Sanitary Facility | / Lump Sum | 1. |
| AA4-11 | 625 | Construction Surveying | / Lump Sum | 1. |
| AA4-12 | 626 | Mobilization | / Lump Sum | 1. |
| AA4-13 | 630 | Traffic Control (Complete In Place) | / Lump Sum | 1. |
| AA4-14 | 630 | Traffic Control Plan | / EA | 1. |
| AA4-15 | 630 | Flagging | / HR | 200. |
| AA4-2 | 203 | Front End Loader (End of Day Millings Buck Up) | / HR | 2. |
| AA4-3 | 208 | Erosion Control | / Lump Sum | 1. |
| AA4-4 | 209 | Dust Abatement | / Lump Sum | 1. |
| AA4-5 | 210 | Restore Landscaping | / Lump Sum | 1. |
| AA4-6 | 210 | Adjust Valve Box (Price to Include adjustment of Survey Monuments) | / EA | 2. |
| AA4-7 | 210 | Adjust Manhole Ring and Cover (Sanitary and Storm Sewer) | / EA | 4. |
| AA4-8 | 304 | Aggregate Base Course (Class 6) - Shoulder Edging Gravel | / Tons | 150. |
| AA4-9 | 401 | Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22) | / Tons | 561. |

COMMENTS:

- 1) FWM from 27 Rd to 200'S
- 2) FWM from B ¾ Rd. to 200'N
- 3) 7' Edge Mill at Curb and Gutter, Drainage Pans, Paved Driveways, Street Intersections, does **not** include commercial parking lots