## CHANGE ORDER

## Number 1

Date: September 7, 2021

To: Oldcastle SW Group, Inc. dba United Companies

City of Grand Junction, Department of Public Works and Utilities From:

Project: 2021 Contract Street Maintenance - Asphalt Overlays

2021-00000328 P.O.:

It is agreed to modify the Contract for the Project as follows:

This change order includes the addition of 3 street areas to the overlay project. This includes an addtional 13,585SY of asphalt milling, 59 valve box adjustments, 45 manhole adjustments, 250 tons of Class 6 shouldering material, 3,881 tons of asphalt, and the associated mobilization, traffic control, and flagging costs. This CO will also extend the contract completion date to October 16, 2021 to allow for the added areas and project delays beyond the control of the contractor.

## Summary of Contract price adjustments - itemized on the attached sheet(s):

Original Contract Amount	\$2,085,553.20
Approved Change Orders	0.00
This Change Order	446,154.15
Revised Contract Amount	\$2,531,707.35

## Summary of Contract time adjustments:

Original Contract Time	90.	Cal. Days
Approved Change Orders	0.	
This Change Order	35.	_
Revised Contract Time	125.	Cal. Days

Construction Start Date: June 14, 2021 Contract Completion Date: October 16, 2021

This modification constitutes compensation in full for all costs and mark-ups directly and/or indirectly attributable to the changes ordered herein, for all delays, impacts and disruptions related thereto and for performance of the changes within the Contract Time.

Owner:	City of Grand Junction		
Prepared by:	Docusigned by:  Eric Wocks - Project Engineer, City of Grand Junction	Date:	9/17/2021
	Eric Mocko, Project Engineer		
Recommended	by Trenton Prall - Director, Public Works Engineering - City of Grand Junction	Date:	9/17/2021
	Trent Prall, Public Works Director		
Approved by:	Docusigned by:  Gray Caton - City Manager - City of Grand Junction  OF CHE INFORMATION  OF CHE INFORMATION	Date:	9/17/2021
	Greg Caton, City Manager		
Contractor:	Oldcastle SW Group, Inc. dba United Com	npanies	

Eyle Alpha - General Manager, Oldcastle SW Group, Inc., dba United Companies Signature:

Name and Title:



2273 River Road Grand Junction, CO 81505 (970) 243-4900 3794 County Road 109 Glenwood Springs, CO 81601 (970) 704-4800 13124 6175 Road Montrose, CO 81403 (970) 249-1815

964 CR 63L Telluride, CO 81435 (970) 728-3775

www.united-gj.com

То:	City Of Grand Junction	Contact:	Eric Mocko
Address:	250 North 5th Street	Phone:	970-244-1554
	Grand Junction, CO 81501	Fax:	
Project Name:	2021 CSM City Of Grand Junction	Bid Number:	21078
Project Location:	Grand Junction, CO	Bid Date:	4/30/2021

We are pleased to propose the following:

Item #	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
202	Asphalt Milling	13,585.00	SY	\$1.70	\$23,094.50
210	Adjust Valve Box	59.00	EACH	\$79.00	\$4,661.00
210	Adjust Manhole	45.00	EACH	\$625.00	\$28,125.00
304	Aggregate Base Course	250.00	TON	\$32.00	\$8,000.00
401	Hot Mix Asphalt 2" Thick 64-22	3,881.00	TON	\$86.65	\$336,288.65
620	Sanitary Facility	1.00	LS	\$150.00	\$150.00
626	Mobilization	1.00	LS	\$17,290.00	\$17,290.00
630	Traffic Control	1.00	LS	\$14,580.00	\$14,580.00
630	Flagging	570.00	HR	\$24.50	\$13,965.00

Total Bid Price: \$446,154.15

#### Notes:

- This proposal is to become part of the contract documents.
- If you have any questions regarding this proposal, please contact Justin Vensel at (970) 243-4900. Thank You

#### **Payment Terms:**

Payment due within 30 days of date of invoice, regardless of when payment is made by Owner

ACCEPTED:	CONFIRMED:		
The above prices, specifications and conditions are satisfactory and are hereby accepted.	Oldcastle SW Group, Inc. Dba United Companies		
Buyer:			
Signature:	Authorized Signature:		
Date of Acceptance:	Estimator: Justin Vensel		
	(970) 243-4900 justin.vensel@unitedco.com		

9/2/2021 10:00:13 AM Page 1 of 1



Date:

# **NOTICE TO PROCEED**

Date:	June 8, 2021
Contractor:	Oldcastle SW Group, Inc. dba United Companies
Project:	2021 Contract Street Maintenance – Asphalt Overlays IFB-4908-21-DH
	e with the contract dated May 20, 2021 the Contractor is hereby notified to n the Project on or before June 14, 2021.
The date of fi	nal completion as determined is <u>90 Calendar Days from the start date of</u> <u>Proceed</u> .
CITY OF GF	RAND JUNCTION, COLORADO
Duane Hoff J	r., Senior Buyer
Receipt of thi	s Notice to Proceed is hereby acknowledged:
Contractor:	
Ву:	
Print Name:	
Title:	



## CITY OF GRAND JUNCTION, COLORADO

#### CONTRACT

This CONTRACT made and entered into this <u>20<sup>th</sup></u> day of <u>May, 2021</u> by and between the <u>City of Grand Junction</u>, Colorado, a government entity in the County of Mesa, State of Colorado, hereinafter in the Contract Documents referred to as the "Owner" and <u>Oldcastle SW Group, Inc. dba United Companies</u> hereinafter in the Contract Documents referred to as the "Contractor."

#### WITNESSETH:

WHEREAS, the Owner advertised that sealed Bids would be received for furnishing all labor, tools, supplies, equipment, materials, and everything necessary and required for the Project described by the Contract Documents and known as **2021 Contract Street Maintenance – Asphalt Overlays IFB-4908-21-DH**.

WHEREAS, the Contract has been awarded to the above named Contractor by the Owner, and said Contractor is now ready, willing and able to perform the Work specified in the Notice of Award, in accordance with the Contract Documents;

NOW, THEREFORE, in consideration of the compensation to be paid the Contractor, the mutual covenants hereinafter set forth and subject to the terms hereinafter stated, it is mutually covenanted and agreed as follows:

#### **ARTICLE 1**

<u>Contract Documents</u>: It is agreed by the parties hereto that the following list of instruments, drawings, and documents which are attached hereto, bound herewith, or incorporated herein by reference constitute and shall be referred to either as the "Contract Documents" or the "Contract", and all of said instruments, drawings, and documents taken together as a whole constitute the Contract between the parties hereto, and they are fully a part of this agreement as if they were set out verbatim and in full herein:

The order of contract document governance shall be as follows:

- a. The body of this contract agreement
- b. Solicitation Documents for the Project; 2021 Contract Street Maintenance Asphalt Overlays;
- c. Notice of Award
- d. Contractors Response to the Solicitation

- e. Work Change Requests (directing that changed work be performed);
- f. Field Orders
- g. Change Orders.

## **ARTICLE 2**

<u>Definitions:</u> The clauses provided in the Solicitation apply to the terms used in the Contract and all the Contract Documents.

## **ARTICLE 3**

<u>Contract Work:</u> The Contractor agrees to furnish all labor, tools, supplies, equipment, materials, and all that is necessary and required to complete the tasks associated with the Work described, set forth, shown, and included in the Contract Documents as indicated in the Solicitation Document.

## **ARTICLE 4**

Contract Time and Liquidated Damages: Time is of the essence with respect to this Contract. The Contractor hereby agrees to commence Work under the Contract on or before the date specified in the Solicitation from the Owner, and to achieve Substantial Completion and Final Completion of the Work within the time or times specified in the Solicitation. In the event the Work is not completed in the times set forth and as agreed upon, the Contractor further agrees to pay Liquidated Damages to the Owner as set forth in the Solicitation. The Contractor acknowledges and recognizes the delays, expenses and difficulties involved in proving in a legal proceeding the actual losses suffered by the Owner if the work is not completed on time. Accordingly, instead of requiring any such proof, the Owner and the Contractor agree that as Liquidated Damages for delay, but not as a penalty, the Contractor shall pay to the Owner the amounts specified in the Solicitation.

## **ARTICLE 5**

Contract Price and Payment Procedures: The Contractor shall accept as full and complete compensation for the performance and completion of all of the Work specified in the Contract Documents, the sum of **Two Million Eighty-Five Thousand Five Hundred Fifty-Three and 20/100 Dollars (\$2,085,553.20).** If this Contract contains unit price pay items, the Contract Price shall be adjusted in accordance with the actual quantities of items completed and accepted by the Owner at the unit prices quoted in the Solicitation Response. The amount of the Contract Price is and has heretofore been appropriated by the Grand Junction City Council for the use and benefit of this Project. The Contract Price shall not be modified except by Change Order or other written directive of the Owner. The Owner shall not issue a Change Order or other written directive which requires additional work to be performed, which work causes the aggregate amount payable under this Contract to exceed the amount appropriated for this Project, unless and until the Owner provides Contractor written assurance that lawful appropriations to cover the costs of the additional work have been made.

Unless otherwise provided in the Solicitation, monthly partial payments shall be made as the Work progresses. Applications for partial and Final Payment shall be prepared by the Contractor and approved by the Owner in accordance with the Solicitation.

Upon Final Completion of the Work under the Contract and before the Contractor shall receive final payment, the Owner shall publish at least twice in a newspaper of general circulation published in the County a notice that: 1. the Owner has accepted such Work as completed according to the Contract Documents; 2. the Contractor is entitled to final payment therefore; 3. thirty days after the first publication, specifying the exact date, the Owner shall pay the full balance due under the Contract; and 4. persons having claims for labor, materials, team hire, sustenance, provisions, provender, or other supplies used or consumed by the Contractor or a subcontractor shall file a verified statement of the amount due and unpaid on account of such claim prior to the date specified for such payment. Nothing herein shall be construed as relieving the Contractor and the Sureties on the Contractor's Bonds from any claim or claims for work or labor done or materials or supplies furnished in the execution of the Contract.

## **ARTICLE 6**

<u>Bonds:</u> The Contractor shall furnish currently herewith the Bonds required by the Contract Documents, such Bonds being attached hereto. The Performance Bond shall be in an amount not less than one hundred percent (100%) of the Contract Price set forth in Article 5. The Payment Bond shall be in an amount not less than one hundred (100%) of the Contract Price set forth in Article 5.

## ARTICLE 7

<u>Contract Binding:</u> The Owner and the Contractor each binds itself, its partners, successors, assigns and legal representatives to the other party hereto in respect to all covenants, agreements and obligations contained in the Contract Documents. The Contract Documents constitute the entire agreement between the Owner and Contractor and may only be altered, amended or repealed by a duly executed written instrument. Neither the Owner nor the Contractor shall, without the prior written consent of the other, assign or sublet in whole or in part its interest under any of the Contract Documents and specifically, the Contractor shall not assign any moneys due or to become due without the prior written consent of the Owner.

## **ARTICLE 8**

<u>Severability:</u> If any part, portion or provision of the Contract shall be found or declared null, void or unenforceable for any reason whatsoever by any court of competent jurisdiction or any governmental agency having the authority thereover, only such part, portion or provision shall be effected thereby and all other parts, portions and provisions of the Contract shall remain in full force and effect.

IN WITNESS WHEREOF, City of Grand Junction, Colorado, has caused this Contract to be subscribed and sealed and attested in its behalf; and the Contractor has signed this Contract the day and the year first mentioned herein.

DocuSigned by:

The Contract is executed in two counterparts.

## **CITY OF GRAND JUNCTION, COLORADO**

By: Duane Hoff Jr., Senior Buyer - Lity of Grand Junctions / 2021 | 11:27 MDT

Duane Hoff Jr., Senior Buyer

Date

## Oldcastle SW Group, Inc. dba United Companies

By: 72 ( 5/20/2021 | 19:38 MDT

Kyle Alpha - General Manager, Oldcasthers ManagerIn Dateba United Companies



# **NOTICE OF AWARD**

Date:	May 4, 2021			
Company:	Oldcastle SW Group, Inc. dba United Companies			
Project:	2021 Contract street Maintenance – Asphalt Overlays IFB-4908-21-DH			
	en awarded the City of Grand Junction 2021 Contract street Maintenance – Asphalt -4908-21-DH for a total price of <b>\$2,085,553.20</b> .			
_	Eric, City of Grand Junction Eric Mocko 970-256-4017 for delivery schedule and re- irchasing Division an acknowledged copy of this Notice of Award.	turn		
CITY OF GRA	AND JUNCTION, COLORADO			
Duane Hoff Jr	r., Senior Buyer			
SUPPLIER ACKNOWLEDGEMENT Receipt of this Notice to Award is hereby acknowledged:				
Company:				
Ву:				
Title:				
Date:				



## **Purchasing Division**

## Invitation for Bid

IFB-4908-21-DH 2021 Contract Street Maintenance – Asphalt Overlays

# **Responses Due:**

April 30, 2021 prior to 3:00PM

<u>Accepting Electronic Responses Only</u>

<u>Responses Only Submitted Through the Rocky Mountain E-Purchasing</u>

<u>System (RMEPS)</u>

https://www.rockymountainbidsystem.com/default.asp

(Purchasing Representative does not have access or control of the vendor side of RMEPS. If website or other problems arise during response submission, vendor <u>MUST</u> contact RMEPS to resolve issue prior to the response deadline. 800-835-4603)

NOTE: All City solicitation openings will continue to be held virtually.

## **Purchasing Representative:**

Duane Hoff Jr., Senior Buyer duaneh@gjcity.org 970-244-1545

This document has been developed specifically to solicit competitive responses for this solicitation, and may not be the same as previous City of Grand Junction solicitations. All vendors are urged to thoroughly review this solicitation prior to responding. Submittal by FAX, EMAIL or HARD COPY IS NOT ACCEPTABLE for this solicitation.

# **Invitation for Bids**

# **Table of Contents**

Section 1 Instruction to Bidders

Section 2 General Contract Conditions

Section 3 Statement of Work

Section 4 Contractor's Bid Form

Price Proposal/Bid Schedule Form

**Appendix** 

**Attachments** 

# 1. Instructions to Bidders

1.1. Purpose: The City of Grand Junction is soliciting competitive bids from qualified and interested companies for all labor, equipment, and materials required to complete the project, which includes approximately 55,127 SY of asphalt milling, 10,664 tons of 2-inch overlay Grading SX-75 (64-22) asphalt, 2100 square yards of shoulder widening (H Road Bike Lanes), 230 square yards of monolithic curb, gutter, sidewalk, 1,062 linear feet of curb and gutter, 441, square yards of concrete curb ramps, and 1,469 square yards of concrete driveways. All dimensions and scope of work should be verified by Contractors prior to submission of bids.

## **IFB Questions:**

Duane Hoff Jr., Senior Buyer duaneh@gjcity.org

The City would like to remind all Contractors, Sub-Contractors, Vendors, Suppliers, Manufacturers, Service Providers, etc. that (with the exception of Pre-Bid or Site Visit Meetings) all questions, inquiries, comments, or communication pertaining to any formal solicitation (whether process, specifications, scope, etc.) must be directed (in writing) to the Purchasing Agent assigned to the project, or Purchasing Division. Direct communication with the City assigned Project Managers/Engineers is not appropriate for public procurement, and may result in disqualification.

- 1.2. Mandatory Pre-Bid Meeting: Prospective bidders are required to attend a mandatory pre-bid meeting on April 19, 2021 at 10:00AM. Meeting location shall be in the City Hall Auditorium, located at 250 N. 5<sup>th</sup> Street, Grand Junction, CO. The purpose of this visit will be to inspect and to clarify the contents of this Invitation for Bids (IFB).
- **1.3. The Owner:** The Owner is the City of Grand Junction, Colorado and is referred to throughout this Solicitation. The term Owner means the Owner or his authorized representative.
- **1.4. Procurement Process:** Procurement processes shall be governed by the most current version of the City of Grand Junction <u>Purchasing Policy and Procedure Manual</u>.
- 1.5. Submission: Each bid shall be submitted in electronic format only, and only through the Rocky Mountain E-Purchasing website (https://www.rockymountainbidsystem.com/default.asp). This site offers both "free" and "paying" registration options that allow for full access of the Owner's documents and for electronic submission of proposals. (Note: "free" registration may take up to 24 hours to process. Please Plan accordingly.) Please view our "Electronic Vendor Registration Guide" at <a href="http://www.gicity.org/business-and-economic-development/bids/">http://www.gicity.org/business-and-economic-development/bids/</a> for details. (Purchasing Representative does not have access or control of the vendor side of RMEPS. If website or other problems arise during response submission, vendor MUST contact RMEPS to resolve issue prior to the response deadline. 800-835-4603)

Please join Solicitation Opening, IFB-4908-21-DH, 2021 Contract Street Maintenance - Asphalt Overlays on GoToConnect from your computer using the Chrome browser.

https://my.jive.com/meet/386631277 You can also dial in using your phone. US: (571) 317-3116

Access Code: 386-631-277

**1.6.** Modification and Withdrawal of Bids Before Opening. Bids may be modified or withdrawn by an appropriate document stating such, duly executed and submitted to the place where Bids are to be submitted at any time prior to Bid Opening.

1.7. Printed Form for Price Bid: All Price Bids must be made upon the Price Bid Schedule attached, and should give the amounts both in words and in figures, and must be signed and acknowledged by the bidder.

The Offeror shall specify a unit price in figures for each pay item for which a quantity is given and shall provide the products (in numbers) of the respective unit prices and quantities in the Extended Amount column. The total Bid price shall be equal to the sum of all extended amount prices. When an item in the Price Bid Schedule provides a choice to be made by the Offeror, Offeror's choice shall be indicated in accordance with the specifications for that particular item and thereafter no further choice shall be permitted.

Where the unit of a pay item is lump sum, the lump sum amount shall be shown in the "extended amount" column and included in the summation of the total Bid.

All blank spaces in the Price Bid Schedule must be properly filled out.

Bids by corporations must be executed in the corporate name by the president or vice president or other corporate office accompanied by evidence of authority to sign. The corporate address and state of incorporation shall be shown below the signature.

Bids by partnerships must be executed in the partnership name and signed by a partner whose title must appear under the signature and the official address of the partnership must be shown below the signature.

All names must be typed or printed below the signature.

The Offeror's Bid shall contain an acknowledgement of receipt of all Addenda, the numbers of which shall be filled in on the Contractor's Bid Form.

The contact information to which communications regarding the Bid are to be directed must be shown.

- **1.8. Exclusions:** No oral, telephonic, emailed, or facsimile bid will be considered
- **1.9. Contract Documents:** The complete IFB and bidder's response compose the Contract Documents. Copies of bid documents can be obtained from the City Purchasing website, <a href="http://www.gjcity.org/business-and-economic-development/bids/">http://www.gjcity.org/business-and-economic-development/bids/</a>.

- 1.10. Additional Documents: The July 2010 edition of the "City Standard Contract Documents for Capital Improvements Construction", Plans, Specifications and other Bid Documents are available for review or download on the Public Works & Planning/Engineering page at <a href="www.gjcity.org">www.gjcity.org</a>. Electronic copies may be obtained on a CD format at the Department of Public Works and Planning at City Hall.
- **1.11. Definitions and Terms:** See Article I, Section 3 of the General Contract Conditions in the *Standard Contract Documents for Capital Improvements Construction*.
- 1.12. Examination of Specifications: Bidders shall thoroughly examine and be familiar with the project Statement of Work. The failure or omission of any Offeror to receive or examine any form, addendum, or other document shall in no way relieve any Offeror from any obligation with respect to his bid. The submission of a bid shall be taken as evidence of compliance with this section. Prior to submitting a bid, each Offeror shall, at a minimum:
  - a. Examine the Contract Documents thoroughly;
  - b. Visit the site to familiarize themselves with local conditions that may in any manner affect cost, progress, or performance of the Work;
  - c. Become familiar with federal, state, and local laws, ordinances, rules, and regulations that may in any manner affect cost, progress or performance of the Work;
  - d. Study and carefully correlate Bidder's observations with the *Contract Documents*, and:
  - e. Notify the Purchasing Agent of all conflicts, errors, ambiguities or discrepancies in or among the *Contract Documents* within the designated inquiry period.

On request, the Owner will provide each Offeror access to the site to conduct such investigations and tests as each Bidder deems necessary for submission of a Bid. It shall be the Offeror's responsibility to make or obtain any additional examinations, investigations, explorations, tests and studies and obtain any additional information and data which pertain to the physical conditions (including without limitation, surface, subsurface and underground utilities) at or contiguous to the site or otherwise which may affect cost, progress or performance of the work and which the Offeror deems necessary to determine its Bid for performing the work in accordance with the time, price and other terms and conditions of the Contract Documents. Location of any excavation or boring made by Offeror shall be subject to prior approval of Owner and applicable agencies. Offeror shall fill all holes, restore all pavements to match the existing structural section and shall clean up and restore the site to its former condition upon completion of such exploration. The Owner reserves the right to require the Offeror to execute an access agreement with the Owner prior to accessing the site.

The lands upon which the Work is to be performed, rights of way, and access thereto, and other lands designated for use by Contractor in performing the Work, are identified on the Drawings.

Information and data reflected in the *Contract Documents* with respect to underground utilities at or contiguous to the site are based upon information and data furnished to the Owner and the Engineer by the owners of such underground utilities or others, and the Owner does not assume responsibility for the accuracy or completeness thereof, unless it is expressly provided otherwise in the *Contract Documents*.

By submission of a Bid, the Offeror shall be conclusively presumed to represent that the Offeror has complied with every requirement of these Instructions to Bidders, that the *Contract Documents* are not ambiguous and are sufficient in scope and detail to indicate and convey understanding of all terms and conditions for performance of the Work.

- **1.13.** Questions Regarding Statement of Work: Any information relative to interpretation of Scope of Work or specifications shall be requested of the Purchasing Representative, in writing, in ample time, prior to the inquiry deadline.
- 1.14. Addenda & Interpretations: If it becomes necessary to revise any part of this solicitation, a written addendum will be posted electronically on the City's website at <a href="http://www.gjcity.org/business-and-economic-development/bids/">http://www.gjcity.org/business-and-economic-development/bids/</a>. The Owner is not bound by any oral representations, clarifications, or changes made in the written specifications by Owner, unless such clarification or change is provided in written addendum form from the City Purchasing Representative.
- **1.15. Taxes:** The Owner is exempt from State retail and Federal tax. The bid price must be net, exclusive of taxes.
- **1.16. Sales and Use Taxes:** The Contractor and all Subcontractors are required to obtain exemption certificates from the Colorado Department of Revenue for sales and use taxes in accordance with the provisions of the General Contract Conditions. Bids shall reflect this method of accounting for sales and use taxes on materials, fixtures and equipment.
- **1.17. Offers Binding 60 Days:** Unless additional time is required by the Owner, or otherwise specified, all formal offers submitted shall be binding for sixty (60) calendar days following opening date, unless the Bidder, upon request of the Purchasing Representative, agrees to an extension.
- 1.18. Exceptions and Substitutions: Bidders taking exception to the specifications and/or scope of work shall do so at their own risk. The Owner reserves the right to accept or reject any or all substitutions or alternatives. When offering substitutions and/or alternatives, Bidder must state these exceptions in the section pertaining to that area. Exception/substitution, if accepted, must meet or exceed the stated intent and/or specifications and/or scope of work. The absence of such a list shall indicate that the Bidder has not taken exceptions, and if awarded a contract, shall hold the Bidder responsible to perform in strict accordance with the specifications and/or scope of work contained herein.
- **1.19.** Collusion Clause: Each bidder by submitting a bid certifies that it is not party to any collusive action or any action that may be in violation of the Sherman Antitrust Act. Any

and all bids shall be rejected if there is evidence or reason for believing that collusion exists among bidders. The Owner may, or may not, accept future bids for the same services or commodities from participants in such collusion.

**1.20. Disqualification of Bidders:** A Bid will not be accepted from, nor shall a Contract be awarded to, any person, firm, or corporation that is in arrears to the Owner, upon debt or contract, or that has defaulted, as surety or otherwise, upon any obligation to the Owner, or that is deemed irresponsible or unreliable.

Bidders may be required to submit satisfactory evidence that they are responsible, have a practical knowledge of the project bid upon and that they have the necessary financial and other resources to complete the proposed Work.

Either of the following reasons, without limitation, shall be considered sufficient to disqualify a Bidder and Bid:

- a. More than one Bid is submitted for the same Work from an individual, firm, or corporation under the same or different name; and
- b. Evidence of collusion among Bidders. Any participant in such collusion shall not receive recognition as a Bidder for any future work of the Owner until such participant has been reinstated as a qualified bidder.
- 1.21. Public Disclosure Record: If the bidder has knowledge of their employee(s) or sub-contractors having an immediate family relationship with a City employee or elected official, the bidder must provide the Purchasing Representative with the name(s) of these individuals. These individuals are required to file an acceptable "Public Disclosure Record", a statement of financial interest, before conducting business with the City.

# 2. General Contract Conditions for Construction Projects

- 2.1. The Contract: This Invitation for Bid, submitted documents, and any negotiations, when properly accepted by the City, shall constitute a contract equally binding between the City and Contractor. The contract represents the entire and integrated agreement between the parties hereto and supersedes all prior negotiations, representations, or agreements, either written or oral. The contract may be amended or modified with Change Orders, Field Orders, or Addendums.
- **2.2. The Work:** The term Work includes all labor necessary to produce the construction required by the Contract Documents, and all materials and equipment incorporated or to be incorporated in such construction.
- 2.3. Execution, Correlation, Intent, and Interpretations: The Contract Documents shall be signed by the Owner (City) and Contractor. City will provide the contract. By executing the contract, the Contractor represents that he/she has visited the site, familiarized himself with the local conditions under which the Work is to be performed, and correlated his observations with the requirements of the Contract Documents. The Contract Documents are complementary, and what is required by any one, shall be as

binding as if required by all. The intention of the documents is to include all labor, materials, equipment and other items necessary for the proper execution and completion of the scope of work as defined in the technical specifications and drawings contained herein. All drawings, specifications and copies furnished by the City are, and shall remain, City property. They are not to be used on any other project, and with the exception of one contract set for each party to the contract, are to be returned to the owner on request at the completion of the work.

- 2.4. The Owner: The Owner is the City of Grand Junction, Colorado and is referred to throughout the Contract Documents. The term Owner means the Owner or his authorized representative. The Owner shall, at all times, have access to the work wherever it is in preparation and progress. The Contractor shall provide facilities for such access. The Owner will make periodic visits to the site to familiarize himself generally with the progress and quality of work and to determine, in general, if the work is proceeding in accordance with the contract documents. Based on such observations and the Contractor's Application for Payment, the Owner will determine the amounts owing to the Contractor and will issue Certificates for Payment in such amounts, as provided in the contract. The Owner will have authority to reject work which does not conform to the Contract documents. Whenever, in his reasonable opinion, he considers it necessary or advisable to insure the proper implementation of the intent of the Contract Documents, he will have authority to require the Contractor to stop the work or any portion, or to require special inspection or testing of the work, whether or not such work can be then be fabricated, installed, or completed. The Owner will not be responsible for the acts or omissions of the Contractor, and sub-Contractor, or any of their agents or employees, or any other persons performing any of the work.
- 2.5. Contractor: The Contractor is the person or organization identified as such in the Agreement and is referred to throughout the Contract Documents. The term Contractor means the Contractor or his authorized representative. The Contractor shall carefully study and compare the General Contract Conditions of the Contract, Specification and Drawings, Scope of Work, Addenda and Modifications and shall at once report to the Owner any error, inconsistency or omission he may discover. Contractor shall not be liable to the Owner for any damage resulting from such errors, inconsistencies or omissions. The Contractor shall not commence work without clarifying Drawings, Specifications, or Interpretations.
- **2.6. Sub-Contractors:** A sub-contractor is a person or organization who has a direct contract with the Contractor to perform any of the work at the site. The term sub-contractor is referred to throughout the contract documents and means a sub-contractor or his authorized representative.
- 2.7. Award of Sub-Contractors & Other Contracts for Portions of the Work: Contractor shall submit with their bid response to the Owner, in writing for acceptance, a list of the names of the sub-contractors or other persons or organizations proposed for such portions of the work as may be designated in the proposal requirements, or, if none is so designated, the names of the sub-contractors proposed for the principal portions of the work. Prior to the award of the contract, the Owner shall notify the successful Contractor in writing if, after due investigation, has reasonable objection to any person or organization on such list. If, prior to the award of the contract, the Owner has a

reasonable and substantial objection to any person or organization on such list, and refuses in writing to accept such person or organization, the successful Contractor may, prior to the award, withdraw their proposal without forfeiture of proposal security. If the successful Contractor submits an acceptable substitute with an increase in the proposed price to cover the difference in cost occasioned by the substitution, the Owner may, at their discretion, accept the increased proposal or may disqualify the Contractor. If, after the award, the Owner refuses to accept any person or organization on such list, the Contractor shall submit an acceptable substitute and the contract sum shall be increased or decreased by the difference in cost occasioned by such substitution and an appropriate Change Order shall be issued. However, no increase in the contract sum shall be allowed for any such substitution unless the Contractor has acted promptly and responsively in submitting a name with respect thereto prior to the award.

- 2.8. Quantities of Work and Unit Price: Materials or quantities stated as unit price items in the Bid are supplied only to give an indication of the general scope of the Work, and are as such, estimates only. The Owner does not expressly or by implication agree that the actual amount of Work or material will correspond therewith, and reserves the right after award to increase or decrease the quantity of any unit item of the Work without a change in the unit price except as set forth in Article VIII, Section 70 of the General Contract Conditions. The City also reserves the right to make changes in the Work (including the right to delete any bid item in its entirety or add additional bid items) as set forth in Article VIII, Sections 69 through 71 of the General Contract Conditions.
- 2.9. Substitutions: The materials, products and equipment described in the Solicitation Documents shall be regarded as establishing a standard of required performance. function, dimension, appearance, or quality to be met by any proposed substitution. No substitution will be considered prior to receipt of Bids unless the Offeror submits a written request for approval to the City Purchasing Division at least ten (10) days prior to the date for receipt of Bids. Such requests for approval shall include the name of the material or equipment for which substitution is sought and a complete description of the proposed substitution including drawings, performance and test data, and other information necessary for evaluation, including samples if requested. The Offeror shall set forth changes in other materials, equipment, or other portions of the Work including changes of the work of other contracts, which incorporation of the proposed substitution would require to be included. The Owner's decision of approval or disapproval of a proposed substitution shall be final. If the Owner approves a proposed substitution before receipt of Bids, such approval will be set forth in an Addendum. Offeors shall not rely upon approvals made in any other manner.
- **2.10.** Supervision and Construction Procedures: The Contractor shall supervise and direct the work, using his best skill and attention. He shall be solely responsible for all construction means, methods, techniques, sequences and procedures and for coordinating all portions of the work under the contract.
- 2.11. Warranty: The Contractor warrants to the Owner that all materials and equipment furnished under this contract will be new unless otherwise specified, and that all work will be of good quality, free from faults and defects and in conformance with the Contract Documents. All work not so conforming to these standards may be considered defective. If required by Owner, the Contractor shall furnish satisfactory evidence as to the kind and

quality of materials and equipment. If within ten (10) days after written notice to the Contractor requesting such repairs or replacement, the Contractor should neglect to make or undertake with due diligence to the same, the City may make such repairs or replacements. All indirect and direct costs of such correction or removal or replacement shall be at the Contractor's expense. The Contractor will also bear the expenses of making good all work of others destroyed or damaged by the correction, removal or replacement of his defective work.

- 2.12. Permits, Fees, & Notices: The Contractor shall secure and pay for all permits, governmental fees and licenses necessary for the proper execution and completion of the work. The Contractor shall give all notices and comply with all laws, ordinances, rules, regulations and orders of any public authority bearing on the performance of the work. If the Contractor observes that any of the Contract Documents are at variance in any respect, he shall promptly notify the Owner in writing, and any necessary changes shall be adjusted by approximate modification. If the Contractor performs any work knowing it to be contrary to such laws, ordinances, rules and regulations, and without such notice to the Owner, he shall assume full responsibility and shall bear all costs attributable.
- **2.13.** Responsibility for Those Performing the Work: The Contractor shall be responsible to the Owner for the acts and omissions of all his employees and all sub-contractors, their agents and employees, and all other persons performing any of the work under a contract with the Contractor.
- **2.14. Use of the Site:** The Contractor shall confine operations at the site to areas permitted by law, ordinances, permits and the Contract Documents, and shall not unreasonably encumber the site with any materials or equipment.
- **2.15. Cleanup:** The Contractor at all times shall keep the premises free from accumulation of waste materials or rubbish caused by his operations. At the completion of work he shall remove all his waste materials and rubbish from and about the project, as well as all his tools, construction equipment, machinery and surplus materials.
- **2.16. Insurance:** The Contractor shall secure and maintain such insurance policies as will provide the coverage and contain other provisions specified in the General Contract Conditions, or as modified in the Special Contract Conditions.
  - The Contractor shall file a copy of the policies or Certificates of Insurance acceptable to the City with the Engineer within ten (10) Calendar Days after issuance of the Notice of Award. These Certificates of Insurance shall contain a provision that coverage afforded under the policies shall not be canceled unless at least thirty (30) Calendar Days prior written notice has been given to the City.
- 2.17. Indemnification: The Contractor shall defend, indemnify and save harmless the Owner, and all its officers, employees, insurers, and self-insurance pool, from and against all liability, suits, actions, or other claims of any character, name and description brought for or on account of any injuries or damages received or sustained by any person, persons, or property on account of any negligent act or fault of the Contractor, or of any Contractor's agent, employee, sub-contractor or supplier in the execution of, or

performance under, any contract which may result from proposal award. Contractor shall pay any judgment with cost which may be obtained against the Owner growing out of such injury or damages.

- 2.18. Miscellaneous Conditions: Material Availability: Contractors must accept responsibility for verification of material availability, production schedules, and other pertinent data prior to submission of bid. It is the responsibility of the bidder to notify the Owner immediately if materials specified are discontinued, replaced, or not available for an extended period of time. OSHA Standards: All bidders agree and warrant that services performed in response to this invitation shall conform to the standards declared by the US Department of Labor under the Occupational Safety and Health Act of 1970 (OSHA). In the event the services do not conform to OSHA standards, the Owner may require the services to be redone at no additional expense to the Owner.
- 2.19. Time: Time is of the essence with respect to the time of completion of the Project and any other milestones or deadline which are part of the Contract. It will be necessary for each Bidder to satisfy the City of its ability to complete the Work within the Contract Time set forth in the Contract Documents. The Contract Time is the period of time allotted in the Contract Documents for completion of the work. The date of commencement of the work is the date established in a Notice to Proceed. If there is no Notice to Proceed, it shall be the date of the Contract or such other date as may be established therein, or as established as entered on the Bid Form. The Date of Final Completion of the work is the date certified by the Owner when all construction, and all other work associated to include, but not be limited to: testing, QA/QC, receipt of required reports and/or forms, grant requirements (if applicable), punch list items, clean-up, receipt of drawings and/or as-builts, etc., is fully complete, and in accordance with the Contract Documents.
- **2.20. Progress & Completion:** The Contractor shall begin work on the date of commencement as defined in the Contract, and shall carry the work forward expeditiously with adequate forces and shall complete it within the contract time.
- 2.21. Payment & Completion: The Contract Sum is stated in the Contract and is the total amount payable by the Owner to the Contractor for the performance of the work under the Contract Documents. Upon receipt of written notice that the work is ready for final inspection and acceptance and upon receipt of application for payment, the Owner's Project Manager will promptly make such inspection and, when he finds the work acceptable under the Contract Documents and the Contract fully performed, the Owner shall make payment in the manner provided in the Contract Documents.
- 2.22. Bid Bond: Each Bid shall as a guaranty of good faith on the part of the Bidder be accompanied by a Bid Guaranty consisting of: a certified or cashier's check drawn on an approved national bank or trust company in the state of Colorado, and made payable without condition to the City; or a Bid Bond written by an approved corporate surety in favor of the City. The amount of the Bid Guaranty shall not be less than 5% of the total Bid amount. Once a Bid is accepted and a Contact is awarded, the apparent successful bidder has ten calendar days to enter into a contractor in the form prescribed and to furnish the bonds with a legally responsible and approved surety. Failure to do so will result I forfeiture of the Bid Guaranty to the City as Liquidated Damages.

Each bidder shall guaranty its total bid price for a period of sixty (60) Calendar Days from the date of the bid opening.

- 2.23. Performance & Payment Bonds: Contractor shall furnish a Performance and a Payment Bond, each in an amount at least equal to that specified for the contract amount as security for the faithful performance and payment of all Contractor's obligations under the Contract Documents. These bonds shall remain in effect for the duration of the Warranty Period (as specified in the Special Conditions). Contractor shall also furnish other bonds that may be required by the Special Conditions. All bonds shall be in the forms prescribed by the Contract Documents and be executed by such sureties as (1) are licensed to conduct business in the State of Colorado and (2) are named in the current list of "Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies" as published in Circular 570 (amended) by the Audit Staff, Bureau of Accounts, U.S. Treasury Department. All bonds singed by an agent must be accompanied by a certified copy of the Authority Act. If the surety on any bond furnished by the Contractor is declared bankrupt, or becomes insolvent, or its rights to do business in Colorado are terminated, or it ceases to meet the requirements of clauses (1) and (2) of this section, Contractor shall within five (5) days thereafter substitute another bond and surety, both of which shall be acceptable to the City.
- 2.24. Retention: The Owner will deduct money from the partial payments in amounts considered necessary to protect the interest of the Owner and will retain this money until after completion of the entire contract. The amount to be retained from partial payments will be five (5) percent of the value of the completed work, and not greater than five (5) percent of the amount of the Contract. When the retainage has reached five (5) percent of the amount of the Contract no further retainage will be made and this amount will be retained until such time as final payment is made.
- 2.25. Liquidated Damages for Failure to Enter Into Contract: Should the Successful Bidder fail or refuse to enter into the Contract within ten Calendar Days from the issuance of the Notice of Award, the City shall be entitled to collect the amount of such Bidder's Bid Guaranty as Liquidated Damages, not as a penalty but in consideration of the mutual release by the City and the Successful Bidder of all claims arising from the City's issuance of the Notice of Award and the Successful Bidder's failure to enter into the Contract and the costs to award the Contract to any other Bidder, to readvertise, or otherwise dispose of the Work as the City may determine best serves its interest.
- 2.26. Liquidated Damages for Failure to Meet Project Completion Schedule: If the Contractor does not achieve Final Completion by the required date, whether by neglect, refusal or any other reason, the parties agree and stipulate that the Contractor shall pay liquidated damages to the City for each such day that final completion is late. As provided elsewhere, this provision does not apply for delays caused by the City. The date for Final Completion may be extended in writing by the Owner.

The Contractor agrees that as a part of the consideration for the City's awarding of this Contract liquidated damages in the daily amount of **\$1,500.00** is reasonable and necessary to pay for the actual damages resulting from such delay. The parties agree that the real costs and injury to the City for such delay include hard to quantify items

such as: additional engineering, inspection and oversight by the City and its agents; additional contract administration; inability to apply the efforts of those employees to the other work of the City; perceived inefficiency of the City; citizens having to deal with the construction and the Work, rather than having the benefit of a completed Work, on time; inconvenience to the public; loss of reputation and community standing for the City during times when such things are very important and very difficult to maintain.

The Contractor must complete the Work and achieve final completion included under the Bid Schedule in the number of consecutive calendar days after the City gives is written Notice to Proceed. When the Contractor considers the entire Work ready for its intended use, Contractor shall certify in writing that the Work is fully complete. Final Completion date is the date by which the Contractor shall have fully completed all clean-up, and all items that were identified by the City in the inspection for final completion. Unless otherwise stated in the Special Conditions, for purposes of this liquidated damages clause, the Work shall not be finished and the Contract time shall continue to accrue until the City gives its written Final Acceptance.

If the Contractor shall fail to pay said liquidated damages promptly upon demand thereof after having failed to achieve Final Completion on time, the City shall first look to any retainage or other funds from which to pay said liquidated damages; if retainage or other liquid funds are not available to pay said liquidated damages amounts, the Surety on the Contractor's Performance Bond and Payment Bond shall pay such liquidated damages. In addition, the City may withhold all, or any part of, such liquidated damages from any payment otherwise due the Contractor.

Liquidated damages as provided do not include any sums to reimburse the City for extra costs which the City may become obligated to pay on other contracts which were delayed or extended because of the Contractor's failure to complete the Work within the Contract Time. Should the City incur additional costs because of delays or extensions to other contracts resulting from the Contractor's failure of timely performance, the Contractor agrees to pay these costs that the City incurs because of the Contractor's delay, and these payments are separate from and in addition to any liquidated damages.

The Contractor agrees that the City may use its own forces or hire other parties to obtain Final Completion of the work if the time of completion has elapsed and the Contractor is not diligently pursuing completion. In addition to the Liquidated Damages provided for, the Contractor agrees to reimburse the City for all expenses thus incurred.

2.27. Contingency/Force Account/Minor Contract Revisions: Contingency/Force Account/Minor Contract Revisions work will be authorized by the Owner's Project Manager and is defined as minor expenses to cover miscellaneous or unforeseen expenses related to the project. The expenses are not included in the Drawings, Specifications, or Scope of Work and are necessary to accomplish the scope of this contract. Contingency/Force Account/Minor Contract Revisions Authorization will be directed by the Owner through an approved form. Contingency/Force Account/Minor Contract Revisions funds are the property of the Owner and any Contingency/Force Account/Minor Contract Revisions funds, not required for project completion, shall remain the property of the Owner. Contractor is not entitled to any Contingency/Force Account/Minor Contract Revisions funds, that are not authorized by Owner or Owner's Project Manager.

- 2.28. Protection of Persons & Property: The Contractor shall comply with all applicable laws, ordinances, rules, regulations and orders of any public authority having jurisdiction for the safety of persons or property or to protect them from damage, injury or loss. Contractor shall erect and maintain, as required by existing safeguards for safety and protection, and all reasonable precautions, including posting danger signs or other warnings against hazards promulgating safety regulations and notifying owners and users of adjacent utilities. When or where any direct or indirect damage or injury is done to public or private property by or on account of any act, omission, neglect, or misconduct by the Contractor in the execution of the work, or in consequence of the non-execution thereof by the Contractor, he shall restore, at his own expense, such property to a condition similar or equal to that existing before such damage or injury was done, by repairing, rebuilding, or otherwise restoring as may be directed, or it shall make good such damage or injury in an acceptable manner.
- 2.29. Changes in the Work: The Owner, without invalidating the contract, may order changes in the work within the general scope of the contract consisting of additions, deletions or other revisions, the contract sum and the contract time being adjusted accordingly. All such changes in the work shall be authorized by Change Order and shall be executed under the applicable conditions of the contract documents. A Change Order is a written order to the Contractor signed by the Owner issued after the execution of the contract, authorizing a change in the work or an adjustment in the contract sum or the contract time. The contract sum and the contract time may be changed only by Change Order.
- 2.30. Claims for Additional Cost or Time: If the Contractor wishes to make a claim for an increase in the contract sum or an extension in the contract time, he shall give the Owner written notice thereof within a reasonable time after the occurrence of the event giving rise to such claim. This notice shall be given by the Contractor before proceeding to execute the work, except in an emergency endangering life or property in which case the Contractor shall precede in accordance with the regulations on safety. No such claim shall be valid unless so made. Any change in the contract sum or contract time resulting from such claim shall be authorized by Change Order.
- **2.31. Minor Changes in the Work:** The Owner shall have authority to order minor changes in the work not involving an adjustment in the contract sum or an extension of the contract time and not inconsistent with the intent of the contract documents.
- **2.32. Field Orders:** The Owner may issue written Field Orders which interpret the Contract Documents in accordance with the specifications, or which order minor changes in the work in accordance with the agreement, without change in the contract sum or time. The Contractor shall carry out such Field Orders promptly.
- 2.33. Uncovering & Correction of Work: The Contractor shall promptly correct all work rejected by the Owner as defective or as failing to conform to the contract documents whether observed before or after substantial completion and whether or not fabricated installed or competed. The Contractor shall bear all costs of correcting such rejected work, including the cost of the Owner's additional services thereby made necessary. If within one (1) year after the date of completion or within such longer period of time as may be prescribed by law or by the terms of any applicable special guarantee required

by the contract documents, any of the work found to be defective or not in accordance with the contract documents, the Contractor shall correct it promptly after receipt of a written notice from the Owner to do so unless the Owner has previously given the Contractor a written acceptance of such condition. The Owner shall give such notice promptly after discover of condition. All such defective or non-conforming work under the above paragraphs shall be removed from the site where necessary and the work shall be corrected to comply with the contract documents without cost to the Owner. The Contractor shall bear the cost of making good all work of separate Contractors destroyed or damaged by such removal or correction. If the Owner prefers to accept defective or non-conforming work, he may do so instead of requiring its removal and correction, in which case a Change Order will be issued to reflect an appropriate reduction in the payment or contract sum, or, if the amount is determined after final payment, it shall be paid by the Contractor.

- **2.34. Amendment:** No oral statement of any person shall modify or otherwise change, or affect the terms, conditions or specifications stated in the resulting contract. All amendments to the contract shall be made in writing by the Owner.
- **2.35. Assignment:** The Contractor shall not sell, assign, transfer or convey any contract resulting from this IFB, in whole or in part, without the prior written approval from the Owner.
- 2.36. Compliance with Laws: Bids must comply with all Federal, State, County and local laws governing or covering this type of service and the fulfillment of all ADA (Americans with Disabilities Act) requirements.
- 2.37. Confidentiality: All information disclosed by the Owner to the Contractor for the purpose of the work to be done or information that comes to the attention of the Contractor during the course of performing such work is to be kept strictly confidential.
- **2.38. Conflict of Interest:** No public official and/or City/County employee shall have interest in any contract resulting from this IFB.
- **2.39. Contract Termination**: This contract shall remain in effect until any of the following occurs: (1) contract expires; (2) completion of services; (3) acceptance of services or, (4) for convenience terminated by either party with a written *Notice of Cancellation* stating therein the reasons for such cancellation and the effective date of cancellation.
- **2.40. Employment Discrimination:** During the performance of any services per agreement with the Owner, the Contractor, by submitting a Bid, agrees to the following conditions:
  - 2.40.1. The Contractor shall not discriminate against any employee or applicant for employment because of race, religion, color, sex, age, handicap, or national origin except when such condition is a legitimate occupational qualification reasonably necessary for the normal operations of the Contractor. The Contractor agrees to post in conspicuous places, visible to employees and applicants for employment, notices setting forth the provisions of this nondiscrimination clause.

- 2.40.2. The Contractor, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, shall state that such Contractor is an Equal Opportunity Employer.
- **2.40.3.** Notices, advertisements, and solicitations placed in accordance with federal law, rule, or regulation shall be deemed sufficient for the purpose of meeting the requirements of this section.
- **2.41. Affirmative Action:** In executing a Contract with the City, the Contractor agrees to comply with Affirmative Action and Equal Employment Opportunity regulations presented in the General Contract Conditions.
- 2.42. Immigration Reform and Control Act of 1986 and Immigration Compliance: The Offeror certifies that it does not and will not during the performance of the contract employ illegal alien workers or otherwise violate the provisions of the Federal Immigration Reform and Control Act of 1986 and/or the immigration compliance requirements of State of Colorado C.R.S. § 8-17.5-101, et.seq. (House Bill 06-1343).
- **2.43. Ethics:** The Contractor shall not accept or offer gifts or anything of value nor enter into any business arrangement with any employee, official, or agent of the Owner.
- 2.44. Failure to Deliver: In the event of failure of the Contractor to deliver services in accordance with the contract terms and conditions, the Owner, after due oral or written notice, may procure the services from other sources and hold the Contractor responsible for any costs resulting in additional purchase and administrative services. This remedy shall be in addition to any other remedies that the Owner may have.
- **2.45. Failure to Enforce**: Failure by the Owner at any time to enforce the provisions of the contract shall not be construed as a waiver of any such provisions. Such failure to enforce shall not affect the validity of the contract or any part thereof or the right of the Owner to enforce any provision at any time in accordance with its terms.
- **2.46.** Force Majeure: The Contractor shall not be held responsible for failure to perform the duties and responsibilities imposed by the contract due to legal strikes, fires, riots, rebellions, and acts of God beyond the control of the Contractor, unless otherwise specified in the contract.
- 2.47. Independent Contractor: The Contractor shall be legally considered an Independent Contractor and neither the Contractor nor its employees shall, under any circumstances, be considered servants or agents of the Owner. The Owner shall be at no time legally responsible for any negligence or other wrongdoing by the Contractor, its servants, or agents. The Owner shall not withhold from the contract payments to the Contractor any federal or state unemployment taxes, federal or state income taxes, Social Security Tax or any other amounts for benefits to the Contractor. Further, the Owner shall not provide to the Contractor any insurance coverage or other benefits, including Workers' Compensation, normally provided by the Owner for its employees.
- **2.48. Nonconforming Terms and Conditions:** A bid that includes terms and conditions that do not conform to the terms and conditions of this Invitation for Bid is subject to rejection

as non-responsive. The Owner reserves the right to permit the Contractor to withdraw nonconforming terms and conditions from its bid prior to a determination by the Owner of non-responsiveness based on the submission of nonconforming terms and conditions.

Items for non-responsiveness may include, but not be limited to:

- a. Submission of the Bid on forms other than those supplied by the City;
- Alteration, interlineation, erasure, or partial detachment of any part of the forms which are supplied herein;
- Inclusion of unauthorized additions conditional or alternate Bids or irregularities
  of any kind which may tend to make the Bid incomplete, indefinite, or ambiguous
  as to its meaning;
- d. Failure to acknowledge receipt of any or all issued Addenda;
- e. Failure to provide a unit price or a lump sum price, as appropriate, for each pay item listed except in the case of authorized alternative pay items;
- f. Failure to list the names of Subcontractors used in the Bid preparation as may be required in the Solicitation Documents;
- g. Submission of a Bid that, in the opinion of the Owner, is unbalanced so that each item does not reasonably carry its own proportion of cost or which contains inadequate or unreasonable prices for any item;
- h. Tying of the Bid with any other bid or contract; and
- i. Failure to calculate Bid prices as described herein.

## **2.49.** Evaluation of Bids and Offerors: The Owner reserves the right to:

- reject any and all Bids,
- waive any and all informalities,
- take into account any prompt payment discounts offered by Bidder,
- negotiate final terms with the Successful Bidder,
- take into consideration past performance of previous awards/contracts with the Owner of any Contractor, Vendor, Firm, Supplier, or Service Provider in determining final award. and
- disregard any and all nonconforming, nonresponsive or conditional Bids.

Discrepancies between words and figures will be resolved in favor of words. Discrepancies between Unit Prices and Extended Prices will be resolved in favor of the Unit Prices. Discrepancies between the indicated sum of any column of figures and the correct sum thereof will be resolved in favor of the correct sum. The corrected extensions and totals will be shown in the tabulation of Bids.

The Owner may consider the qualifications and experience of Subcontractors and other persons and organizations (including those who are to furnish the principal items of material or equipment) proposed for those portions of the work as to which the identity of Subcontractors and other persons and organizations must be submitted. Operating costs, maintenance considerations performance data, and guarantees of materials and equipment may also be considered by the Owner.

The Owner will conduct such investigations as deemed necessary to assist in the evaluation of any Bid and to establish the responsibility, qualifications and financial ability of the Offeror, proposed Subcontractors and other persons and organizations to do the Work in accordance with the *Contract Documents* to the City's satisfaction within the Contract Time.

The Offeror shall furnish the Owner all information and data requested by the Owner to determine the ability of the Offeror to perform the Work. The Owner reserves the right to reject the Bid if the evidence submitted by, or investigation of such Offeror fails to satisfy the Owner that such Offeror is properly qualified to carry out the obligations of the Contract and to complete the Work contemplated therein.

By submitting a Bid, each Offeror authorizes the Owner to perform such investigation of the Offeror as the Owner deems necessary to establish the responsibility, qualifications and financial ability of the Offeror and, by its signature thereon, authorizes the Owner to obtain reference information concerning the Offeror and releases the party providing such information and the Owner from any and all liability to the Offeror as a result of such reference information so provided.

The Owner reserves the right to reject the Bid of any Offeror who does not pass any evaluation to the Owner's satisfaction.

If the Contract is to be awarded, it will be awarded to the Offeror who, by evaluation, the Owner determines will best meet the Owner's interests.

The Owner reserves the right to accept or reject the Work contained in any of the Price Bid Schedules or alternates, either in whole or in part.

2.50. Award of Contract: Unless otherwise indicated, a single award will be made for all the bid items in an individual bid schedule. In the event that the Work is contained in more than one Bid Schedule, the City may award Schedules individually or in combination. In the case of two Bid Schedules which are alternative to each other, only one of such alternative Schedules will be awarded. Within forty-five (45) Calendar Days of Bid Opening, the City will issue a Notice of Award to the Successful Bidder which will be accompanied by four (4) unsigned copies of the Contract and the Performance and Payment Bond forms. Within ten (10) Calendar Days thereafter, the Successful Bidder shall sign and deliver four (4) copies of the Contract, Performance Bond, Payment Bond and Certificates of Insurance to the City. Within ten (10) Calendar Days thereafter, the City will deliver two (2) fully executed counterparts of the Contract to the Contractor. No contract shall exist between the Successful Bidder and the City and the Successful Bidder shall have no rights at law or in equity until the Contract has been duly executed by the City.

The Successful Bidder's failure to sign and submit a Contract and other documents set forth in this Paragraph within the prescribed time shall be just cause of annulment of the award, and forfeiture of the Bid Guaranty. The award of Contract may then be made to the next qualified Bidder in the same manner as previously prescribed.

- **2.51.** Ownership: All plans, prints, designs, concepts, etc., shall become the property of the Owner.
- 2.52. Oral Statements: No oral statement of any person shall modify or otherwise affect the terms, conditions, or specifications stated in this document and/or resulting agreement. All modifications to this request and any agreement must be made in writing by the Owner.
- 2.53. Patents/Copyrights: The Contractor agrees to protect the Owner from any claims involving infringements of patents and/or copyrights. In no event shall the Owner be liable to the Contractor for any/all suits arising on the grounds of patent(s)/copyright(s) infringement. Patent/copyright infringement shall null and void any agreement resulting from response to this IFB.
- **2.54. Remedies**: The Contractor and Owner agree that both parties have all rights, duties, and remedies available as stated in the Uniform Commercial Code.
- **2.55. Venue**: Any agreement as a result of responding to this IFB shall be deemed to have been made in, and shall be construed and interpreted in accordance with, the laws of the City of Grand Junction, Mesa County, Colorado.
- **2.56. Expenses:** Expenses incurred in preparation, submission and presentation of this IFB are the responsibility of the company and cannot be charged to the Owner.
- **2.57. Sovereign Immunity:** The Owner specifically reserves its right to sovereign immunity pursuant to Colorado State Law as a defense to any action arising in conjunction to this agreement.
- 2.58. Non-Appropriation of Funds: The contractual obligation of the Owner under this contract is contingent upon the availability of appropriated funds from this fiscal year budget as approved by the City Council or Board of County Commissioners from this fiscal year only. State of Colorado Statutes prohibit obligation of public funds beyond the fiscal year for which the budget was approved. Anticipated expenditures/obligations beyond the end of the current Owner's fiscal year budget shall be subject to budget approval. Any contract will be subject to and must contain a governmental non-appropriation of funds clause.
- 2.59. Cooperative Purchasing: Purchases as a result of this solicitation are primarily for the City/County. Other governmental entities may be extended the opportunity to utilize the resultant contract award with the agreement of the successful provider and the participating agencies. All participating entities will be required to abide by the specifications, terms, conditions and pricings established in this Bid. The quantities furnished in this bid document are for only the City/County. It does not include quantities

for any other jurisdiction. The City or County will be responsible only for the award for its jurisdiction. Other participating entities will place their own awards on their respective Purchase Orders through their purchasing office or use their purchasing card for purchase/payment as authorized or agreed upon between the provider and the individual entity. The City/County accepts no liability for payment of orders placed by other participating jurisdictions that choose to piggy-back on our solicitation. Orders placed by participating jurisdictions under the terms of this solicitation will indicate their specific delivery and invoicing instructions.

2.60. Keep Jobs in Colorado Act: Contractor shall be responsible for ensuring compliance with Article 17 of Title 8, Colorado Revised Statutes requiring 80% Colorado labor to be employed on public works. Contractor shall, upon reasonable notice provided by the Owner, permit the Owner to inspect documentation of identification and residency required by C.R.S. §8-17-101(2)(a). If Contractor claims it is entitled to a waiver pursuant to C.R.S. §8-17-101(1), Contractor shall state that there is insufficient Colorado labor to perform the work such that compliance with Article 17 would create an undue burden that would substantially prevent a project from proceeding to completion, and shall include evidence demonstrating the insufficiency and undue burden in its response.

Unless expressly granted a waiver by the Owner pursuant to C.R.S. §8-17-101(1), Contractor shall be responsible for ensuring compliance with Article 17 of Title 8, Colorado Revised Statutes requiring 80% Colorado labor to be employed on public works. Contractor shall, upon reasonable notice provided by the Owner, permit the Owner to inspect documentation of identification and residency required by C.R.S. §8-17-101(2)(a).

- 2.60.1. "Public project" is defined as:
  - (a) any construction, alteration, repair, demolition, or improvement of any land, building, structure, facility, road, highway, bridge, or other public improvement suitable for and intended for use in the promotion of the public health, welfare, or safety and any maintenance programs for the upkeep of such projects
  - (b) for which appropriate or expenditure of moneys may be reasonably expected to be \$500,000.00 or more in the aggregate for any fiscal year
  - (c) except any project that receives federal moneys.

# 3. Statement of Work

- 3.1. GENERAL: The work request is for improvements to selected roads within the City of Grand Junction. The improvements will include asphalt mill and fill operations, shoulder widening, and concrete removal and replacement.
- 3.2. PROJECT DESCRIPTION: The project includes approximately 55,127 SY of asphalt milling, 10,664 tons of 2-inch overlay Grading SX-75 (64-22) asphalt, 2100 square yards of shoulder widening (H Road Bike Lanes), 230 square yards of monolithic curb, gutter, sidewalk, 1,062 linear feet of curb and gutter, 441, square yards of concrete curb ramps, and 1,469 square yards of concrete driveways. All dimensions and scope of work should be verified by Contractors prior to submission of bids.

#### 3.3. SPECIAL CONDITIONS & PROVISIONS:

3.3.1 Mandatory Pre-Bid Meeting: Prospective bidders are required to attend a mandatory pre-bid meeting on April 19, 2021 at 10:00AM. Meeting location shall be in the City Hall Auditorium, located at 250 N. 5<sup>th</sup> Street, Grand Junction, CO. The purpose of this visit will be to inspect and to clarify the contents of this Invitation for Bids (IFB).

## 3.3.2 QUESTIONS REGUARDING SOLICIATION PROCESS/SCOPE OF WORK:

Duane Hoff Jr., Senior Buyer City of Grand Junction duaneh@gicity.org

3.3.3 Project Manager: The Project Manager for the Project is Eric Mocko, Project Engineer, who can be reached at (970) 256-4017. <u>During Construction</u>, all notices, letters, submittals, and other communications directed to the City shall be addressed and mailed or delivered to:

City of Grand Junction
Department of Public Works – Engineering Division
Attn: Eric Mocko, Project Manager
333 West Avenue, Building C
Grand Junction, CO 81501

- **3.3.4 Affirmative Action:** The Contractor is not required to submit a written Affirmative Action Program for the Project.
- 3.3.5 Pricing: Pricing shall be all inclusive to include but not be limited to: all labor, equipment, supplies, materials, freight (F.O.B. Destination Freight Pre-paid and Allowed to each site), travel, mobilization costs, fuel, set-up and take down costs, and full-time inspection costs, and all other costs related to the successful completion of the project.

The Owner shall not pay nor be liable for any other additional costs including but not limited to: taxes, shipping charges, insurance, interest, penalties, termination payments, attorney fees, liquidated damages, etc.

**3.3.6 Freight/Shipping:** All freight/shipping shall be F.O.B. Destination – Freight Pre-Paid and Allowed to the project site(s), Grand Junction, CO.

Contractor must meet all federal, state, and local rules, regulations, and requirements for providing such services.

3.3.7 Contract: A binding contract shall consist of: (1) the IFB and any amendments thereto, (2) the bidder's response (bid) to the IFB, (3) clarification of the bid, if any, and (4) the City's Purchasing Department's acceptance of the bid by "Notice of Award" or by "Purchase Order". All Exhibits and Attachments included In the IFB shall be incorporated into the contract by reference.

- A. The contract expresses the complete agreement of the parties and, performance shall be governed solely by the specifications and requirements contained therein.
- B. Any change to the contract, whether by modification and/or supplementation, must be accomplished by a formal contract amendment signed and approved by and between the duly authorized representative of the bidder and the City Purchasing Division or by a modified Purchase Order prior to the effective date of such modification. The bidder expressly and explicitly understands and agrees that no other method and/or no other document, including acts and oral communications by or from any person, shall be used or construed as an amendment or modification to the contract.
- **3.3.8 Time of Completion:** The scheduled time of Completion for the Project is <u>90</u> Calendar Days from the starting date specified in the Notice to Proceed.

Completion is achieved when site cleanup and all punch list items (resulting from the final inspection) have been completed. Completion shall have the meaning set forth in Article I, Section 3 (Definitions and Terms) of the General Contract Conditions.

**3.3.9 Working Days and Hours:** The working days and hours shall be as stated in the General Contract Conditions or as mutually agreed upon in the preconstruction meeting with the following exception:

The following streets shall have all work performed between the hours of 8:00PM to 6:00AM:

- High Country Court
- Bogart Lane
- Hoover Drive
- Crossroads Area

No traffic control shall be in place, other than prestaging, prior to 9:00PM and all traffic control shall be removed prior to 6:00AM. In the event that traffic control is not removed by the time set above, the contractor shall be subjected to a \$500/hour penalty.

- **3.3.10 Licenses and Permits:** Contractor is responsible for obtaining all necessary licenses and permits required for Construction, at Contractors expense. See Section 2.12. Contractor shall supply to Owner all copies of finalized permits.
- 3.3.11 Permits: The following permits are required for the Project and will be obtained by the City at no cost to the Contractor:
  None

The following permits are required for the Project and shall be obtained and paid for by the Contractor, with the costs included in the total bid price for the Project:

- CDOT Permit for 20 ½ Rd. (Broadway), 27 Rd. (HWY 50), Hoover Dr. (Frontage Rd.)
- **3.3.12 City Furnished Materials:** The City will furnish the following materials for the Project:
  - Door-hanger notices informing residents of the upcoming milling, overlay, or concrete work, planned dates of the work, and parking restrictions. These shall be hung on doors at least two, but not more than 7 days prior to the work at each location. In the event that door hangers are not distributed as per these special conditions and a vehicle needs to be removed from the project site the Contractor shall be responsible for the costs associated with the relocation of the vehicle.
  - Damaged or outdated manhole ring and covers and Water Valve boxes and lids that need to be replaced. The City will furnish the above mentioned. The Contractor shall be responsible for picking up the materials from Castings Inc.
- 3.3.13 Project Newsletters: A newsletter for the Project will be prepared and distributed by the City as necessary. It will include general information about the Project including interruptions in utility services, street closures, parking restrictions, project schedule, and the names and telephone numbers of the contacts for the City and Contractor. The newsletter will be mailed approximately one week before the Contractor commences work.

The Contractor will be responsible for notifying all businesses and / or residents located adjacent to the work. Door hanger notifications shall be distributed at least two (2) working days prior to the day the milling, overlay, demo, and concrete work is scheduled to begin.

- **3.3.14 Project Sign:** Project signs, if any, will be furnished and installed by the City.
- **3.3.15 Authorized Representatives of the City:** Those authorized to represent the City shall include Purchasing Agent, Engineers, and Inspectors employed by the City, only.
- **3.3.16 Stockpiling Materials and Equipment:** All stockpiling/storage shall be in accordance with General Contract Condition Section 51.
- 3.3.17 Traffic Control: The Contractor shall provide and maintain traffic control in accordance with the approved Traffic Control Plan and the Manual on Uniform Traffic Control Devices. A Traffic Control Plan shall be prepared by the Contractor and reviewed by the City two days prior to the pre-construction meeting. Traffic control will be paid as lump sum and shall include all associated signs, cones, traffic control supervisor, assistant to the traffic control supervisor, set up and tear down.
- 3.3.18 Clean-Up: The Contractor is responsible for cleaning up all loose materials that have been deposited or swept into gutters, and onto sidewalks and driveways as a result of construction operations. The costs for all clean-up work shall be considered incidental and will not be paid for separately.

3.3.19 Quality Control Testing: Supplier shall perform Quality Control (QC) testing on the Asphalt. The Contractor shall provide QC throughout the Contract, with the use of their own QC Technicians or the use of a certified laboratory. In accordance with Section 401.06.3 of the City of Grand Junction Standard Specifications for Road and Bridge Construction, results of all QC tests shall be submitted to the Project Engineer and the City's Quality Assurance (QA) Technician within 4 hours of the time of sampling. Failure to do so may require that paving be suspended until all sampling results have been received, reviewed, and approved. The Contractor shall supply QC Lab personnel for night work for comparison of test data. If lab personnel is not supplied paving operations will be suspended until one is available. QC Field personnel shall remain on site during the duration of the paving operation or until in-place density are met.

The Contractor/Supplier shall perform QC testing on all concrete. The City will perform QA testing for concrete.

The Contractor, at their own discretion, may elect to forgo the soils QC field testing (in-place soils density) for the placement of Embankment and Aggregate Base Course. QA testing for these items will be performed by the City, and laboratory results for submittal purposes shall be provided by the contractor. However, if a sufficient number of failed test results are observed by the City and/or it's QA testing representatives, written notification will be provided to the contractor, and back payment to the City for failed location re-tests will be required.

- **3.3.20 Schedule of Submittals:** Contractor shall deliver these submittals at least two days prior to the pre-construction meeting:
  - Traffic Control Plans
  - Project Schedule
  - Hourly rate tables for Labor and Equipment to be used on this project
  - Asphalt Mix Designs for SX mix.
  - Concrete Mix Designs for Structural Concrete
  - Tack Coat
  - Emulsified Asphalt
- **3.3.21 Uranium Mill Tailings:** It is anticipated that radioactive mill tailings will not be encountered on this Project.
- **3.3.22 Fugitive Petroleum or Other Contamination:** It is anticipated that soil contamination from fugitive petroleum or other contaminants will not be encountered with the Project.
- 3.3.23 Excess Material: All excess materials shall be disposed in accordance with General Contract Condition Section 50. All asphalt millings shall be delivered to the City Storage Yard located adjacent to the City Cemetery at 2620 Legacy Way and become the property of the City of Grand Junction.

- **3.3.24 Existing Utilities and Structures:** Utilities were <u>not</u> potholed during design of this project. The location of existing utilities and structures shown on the Plans is approximate with the information gathered during design. It is the responsibility of the Contractor to pothole/locate and protect all structures and utilities in accordance with General Contract Condition Section 37.
- **3.3.25 Incidental Items:** Any item of work not specifically identified or paid for directly, but which is necessary for the satisfactory completion of any paid items of work, will be considered as incidental to those items, and will be included in the cost of those items.
- **3.3.26 Survey:** The Contractor shall give the City survey crew a minimum of 72 hours' notice prior to milling roadways.
- 3.3.27 Existing Concrete Sidewalks, Pans, Fillets, Curbs and Gutters: The existing sidewalks, pans, fillets, curb and gutter are in good serviceable condition. In most instances the installation of new sidewalk and pavement will be adjacent to existing concrete. The Contractor will need to protect all concrete adjacent to construction. If the concrete is damaged during construction the Contractor will be responsible for its replacement at no cost to the City. The Contractor, the City Project Inspector, and/or the City Project Manager will walk and record any concrete that is deemed to be damaged before construction has started.
- 3.3.28 ACI Concrete and Flatwork Finisher and Technician: Hand finishing concrete will be permitted only when performed under the direct supervision of a craftsman holding the following certificate: ACI Concrete Flatwork Finisher and Technician (ACICFFT) or other Flatwork Finisher certification program approved by the City Engineering Manager.
- **3.3.29 Special Equipment:** Auger extensions shall be used when the screed is extended to a width greater than two feet beyond the auger. The auger extensions shall be installed to ensure a constant head of material.

Asphalt Material Transfer Vehicle: The contractor shall use a materials transfer vehicle in conjunction with belly dumps to reduce irregularities in the paving on the following street sections:

- Crossroads Boulevard
- H Road
- 27 Road (Horizon Dr. to I-70)
- 20 ½ Road
- **3.3.30 Arterial and Collector Streets:** All paving shall be completed a maximum of 7 calendar days after the milling at ALL locations.
- **3.3.31 Asphalt Paper Joints:** The Contractor shall install asphalt paper joints at all locations where milling the roadway creates a vertical edge greater than 1" in height in the direction of travel. The paper joints shall be installed immediately following milling operations. In the event the paper joints are not installed immediately following

- milling operations, the Contractor shall be subjected to a \$500/day penalty at each unprotected joint location. The asphalt used in the paper joint shall be removed prior to placing the overlay. The cost of the paper joints shall be included in the unit price for the asphalt items and will not be measured or paid for separately.
- 3.3.32 Tack Coat: Tack Coat will be required between the existing asphalt and the leveling asphalt, existing asphalt and new overlay, and between leveling asphalt and new overlay asphalt. The tack coat shall meet the requirements of Section 407 of the Standard Specifications for Road and Bridge Construction, as modified, herein. The cost of the tack coat will be considered incidental to the work and will not be paid for separately.
- 3.3.33 Milling at Drainage Inlets: When milling adjacent to inlets that have a concrete edge protruding into the street, it shall be the Contractor's responsibility to provide an approved marker or barricade to protect vehicle tires from damage until the overlay is placed. It shall be the Contractors responsibility to ensure millings, tack coat and/or HMA do not enter the storm drain system.
- 3.3.34 Painted Lane Lines: The Contractor shall be responsible for recording the location of all existing striping and shall place longitudinal paving joints on or immediately adjacent to said striping. Any locations where striping will differ from existing locations are indicated on the project plans, and longitudinal paving joints shall be placed on or immediately adjacent to proposed striping locations.
- 3.3.35 Temporary Pavement Marking Tape: The Contractor shall be responsible for furnishing and placing temporary pavement marking tape in the event that existing stripes were removed during milling operation. The Contractor shall be responsible for furnishing and placing temporary pavement marking tape prior to the final roller pass. Pavement marking tape shall be placed on the seams of the new asphalt as determined by the record of existing striping or new striping locations per provided project plans. The cost of the marking tape and labor to install will be considered incidental to the work and will not be paid for separately.
- **3.3.36 Transverse Milling:** Butt joints (Transverse Milling) shall be placed in all locations where new asphalt will be joined to existing pavement. The location and width of all butt joints will be designated by the Project Engineer or their representative.
- 3.3.37 Pavement Cross Slope: Each paving machine shall be equipped with a 4' carpenters level. On those occasions when the paving foreman determines that an existing street has little or no cross slope, the Contractor shall advise the Engineer of his observations rather than overlaying the street as is. The Engineer or his representative will then determine how best to correct the inadequate cross slope.
- **3.3.38 Payment for Hot Mix Asphalt:** Section 401.07.1 of the City of Grand Junction Standard Specifications for Road and Bridge Construction will be used to determine Pay Factors for calculating the basis of payment for Hot Bituminous Pavement with the following modifications:

The pay factor (PF) should be calculated for mat density (excluding joint density), air voids, and VMA daily. An average daily pay factor (DPF) should then be calculated/weighted in the following proportion:

- Mat Density (excluding joint density) 50%
- Air Voids 25%
- VMA 25%

The incentive payment will then be based on a weighted average project pay factor (PPF). The PPF shall be calculated/weighted per the DPFs and accepted quantities placed for each day's production of each pay item. This PPF will then be applied to the total accepted quantities for each pay item, as applicable.

- 3.3.39 Manholes and Water Valves: It shall be the contractors' responsibility to accurately record and adjust all manholes, valve boxes and survey monuments to final grade. In the event that a utility is paved over it shall be the contractors' responsibility to expose and adjust to final grade within 2 days. In all other cases utilities shall be raised to final grade within 7 days after completion of paving each street segment, and it shall be the contractors' responsibility to expose the affected utility during the event of an emergency.
- **3.3.40 Materials:** In the event that excavation of the manholes grade rings are disturbed or removed and replaced due to damage the Contractor is instructed to follow these guidelines:

The annular area beneath the bottom of the uppermost grade ring shall either be filled with a self-consolidating material, i.e. ¾" screened rock or engineer approved equal or shall be completely filled with Quikrete's Rapid Road Repair or Engineer approved equal. No other means will be considered.

## 3.3.41 Work By Others / Coordination

It is not anticipated that work by others will be necessary prior to or during construction at this time.

#### 3.4. SCOPE OF WORK:

## STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION:

The City of Grand Junction Standard Specifications for Road and Bridge Construction are hereby modified or supplemented for this Project by the following modifications to The Standard Specifications for Road and Bridge Construction, State Department of Highways, Division of Highways, State of Colorado:

## SP-1 SECTION 202 – REMOVAL OF STRUCTURES AND OBSTRUCTIONS

Section 202 of the Standard Specifications is hereby revised for this project as follows:

Section 202.07, shall include the following:

All concrete removal required for installation of new will be considered incidental and will not be measured or paid for separately.

Section 210.10, Adjust Structure, shall include the following:

- (1) The following shall apply to adjusting manhole rings in traveled through lanes:
  - (a) Manholes shall be paved over during the overlay. Sand or paper will be used to prevent the asphalt from adhering to the manhole cover. After paving, the manhole ring shall be adjusted to grade by the use of concrete grade rings. The cut area around the manhole shall then be patched with Grading-SX, Hot Mix Asphalt to the same thickness as the adjacent pavement. When adjusting the manhole ring to match the cross slope of the street, the Contractor shall fill the space between the concrete grade ring and the cast iron ring with Rapid Road Repair or Engineer approve equal. In the event that grade rings are removed and or replaced as part of the adjustment the contractor shall fill the annular area below the uppermost grade ring with a self-consolidating media such as 3/4" washed rock or completely fill the area with Rapid Road Repair or Engineer approved equal.
  - (b) Manhole adjustment tolerance: all manholes adjusted as part of this project shall meet the following criteria: level with the adjacent asphalt or (–)1/8". Manholes set outside of this tolerance will be rejected.
- (2) Valve boxes can be adjusted by the use of cast iron valve box extensions or by digging the valve box out after paving and raising the existing box. After adjusting the height of the valve box, the area around the valve box shall be filled with Grading-SX, Hot Mix Asphalt to the same thickness as the adjacent pavement. Water valve tolerance will be the same as section 1 b with the exception of (–) 1/4"

Subsection 202.12, shall include the following:

Locations of saw cuts shall be determined and directed by the Construction Inspector or the Engineer. Saw cuts shall be incidental to work.

## SP-2 SECTION 203 – EXCAVATION AND EMBANKMENT

Section 203 of the Standard Specifications is hereby revised for this project as follows:

Section 203.03 shall include the following:

Unclassified Excavation shall consist of materials excavated and placed to facilitate the construction of the shoulder widening (new bike lanes) on H Road. All placed embankment material shall be free of trash and organic materials. It is anticipated that the excavated materials will be generally suitable for placement as part of the new embankment sections on this road. Any unsuitable materials identified by the contractor and/or representative of the City shall be brought to the attention of the Project Engineer and once confirmed by the Engineer, will be considered excess materials incidental to this pay item. This item will be paid for as total cubic yards

excavated per plan. The materials placed and compacted per plan will be considered an incidental cost to this item.

Note: The Engineer estimates the materials cut from H Road will include approximately 52 cubic yards (complete-in-place) of embankment fill. This material will be borrowed from the excavated quantity and is anticipated to generate approximately 875 cubic yards of net excess material. The excess materials shall be wasted on adjacent embankment slopes as directed by the Engineer.

Section 203.07 shall be revised, where applicable, to include the following:

Soil embankment materials shall be tested for compaction. Materials classified as AASHTO A-1 through A-4 soils shall be compacted at ± 2 percent of Optimum Moisture Content (OMC) and to at least 95 percent of the maximum dry density determined in accordance with AASHTO T 180. Materials classified as AASHTO A-5 through A-7 Materials shall be compacted at a moisture content ranging from minus 1 percent to plus 3 percent of OMC and to at least 95 percent of the maximum dry density determined in accordance with AASHTHO T 99.

Section 203.14 shall include the following:

Payment for work shall be made under Excavation and Embankment and will be measured by planned cut quantity. Unsuitable material exported from the site will not be measured or paid for separately and will be considered excess materials incidental to this pay item.

Pay Item Pay Unit Excavation and Embankment CY

## SP-3 SECTION 304 – AGGREGATE BASE COURSE

Section 304 of the Standard Specifications is hereby revised for this project as follows:

Subsection 304.01 shall include the following:

In areas of asphalt overlay where there is no curb and gutter and/or a drainage pan, the Contractor shall backfill the shoulder with Class-6 Aggregate Base Course immediately following the overlay. The shoulder shall have a slope of 1:12 or flatter and shall extend a maximum 4' from the edge of asphalt. The aggregate base course shall be brought level to the new pavement surface and compacted. An exception to this will be made in areas where shoulder material would extend into existing yards or landscaping adjacent to the roadway. In these locations, it will be necessary to provide materials that match the existing landscape.

## <u>SP-4 SECTION 401 – PLANT MIX PAVEMENTS - GENERAL</u>

## REVISION OF SECTION 401 PLANT MIX PAVEMENTS

Section 401 if the Standard Specifications are hereby revised for this project as follows:

## 401.01 Description.

Add the following:

This work shall consist of providing a Hot Mix Asphalt (HMA) to be placed as shown on the plans, or as directed by the Owner. The Contractor shall be responsible for Process Control (PC) of the HMA; including the design, and control of the quality of the material incorporated into the project.

## 401.02 Composition of Mixtures.

Delete subparagraph (a) Mix Design and replace with the following:

A Job Mix Formula (JMF) design shall be submitted for each mixture required, at least 10 calendar days prior to placing any mix on the project, for acceptance by the Owner. JMF's previously approved by CDOT within the past six months may be utilized. The JMF design shall be determined using AASHTO T-312 or CP-L 5115 for the Method of Mixture Design. Grading ST, SX, and S shall be designed using 100mm molds. The job mix gradation shall be wholly within the Master Range Table in subsection 703.04 before the tolerances shown in Section 401 are applied.

Designs shall be developed and performed in a materials laboratory that meets the requirements set forth by AASHTO Materials Reference Laboratory (AMRL) for all testing procedures. The design shall be stamped and signed by a Professional Engineer licensed in the State of Colorado. In addition, the Contractor shall submit, as part of the mixture design, laboratory data documents to verify the following:

- Gradation, specific gravity, source and description of individual aggregate and properties, and the final blend.
- Aggregate physical properties.
- Source and Grade of the Performance Graded Binder.
- Proposed Design Job Mix: aggregate and additive blending, final gradation, optimum binder content.
- Mixing and compaction temperatures used.
- Mixture properties shall be determined with a minimum of four binder contents.

The JMF for each mixture shall establish a single percentage of aggregate passing each required sieve size, a single percentage of asphalt cement to be added to the aggregate, and a single temperature for the mixture at the discharge point of the plant.

The Owner reserves the right to verify the asphalt supplier's mix design for each JMF design utilizing materials produced and stockpiled. The asphalt supplier shall provide, at no cost, a sufficient quantity of each aggregate, mineral filler, Recycled Asphalt Pavement (RAP), and additive for the required laboratory tests, as well as all Certificates of Conformance/ Compliance at any time on any material used. The Asphalt Supplier shall provide copies of quality control testing results during the production of HMA used within one business day from the sampling date.

Mixture design of HMA shall meet the requirements of Table 403-1 and Table 403-2 in the Revision to Section 403. For mixes requiring a design gyration of 100 (ESALs greater than 3 million) the Project Special Conditions should be used. This gyration is not recommended for the majority of roads within Mesa County.

Delete subparagraph (b) Mixtures Furnished to the Project and replace with the following:

Production verification shall occur prior to, or during, the start of the project. Volumetric properties of the mix shall be verified by LabCAT Level C Certified Technicians. If the mix was produced for another project within the last 90 days, data from that project can be submitted for verification. All mixtures furnished for the project shall conform within the ranges of tolerance listed in Table 401.02A. The mix verification test reports shall be submitted to the Owner prior to mix placement.

TABLE
401.02A
Production Mix
Tolerances

<u>Property</u>	Tolerance
Asphalt Cement Content	<u>± 0.3%</u>
<u>VMA</u>	<u>± 1.2%</u>
Air Voids	± 1.2%

Verification testing for binder content, gradation and physical properties shall be performed at the frequencies listed in Table 401.23-1.

There shall be no substitutions of materials allowed during production, unless approved in advance by the Owner. All substitutions will require checkpoint verification. If the checkpoint differs from the Job Mix Formula (JMF), a new mix design will be required. Upon request of the Owner, the binder grade may be changed by one available binder grade level without requiring a new mix design.

Should a change in the source of any material used in the production of HMA (aggregate, mineral filler, lime, or performance graded asphalt binder) occur, a one point verification test (at optimum binder content) of the mix must be performed to verify that the applicable criteria shown on Table 403-1 (HMA) and Table 403-2 (VMA) of Revision to Section 403 are still met. If this testing shows noncompliance, the Contractor shall establish a new job mix design and obtain approval by the Owner before the new HMA is used.

## Add the following new subparagraphs:

(c) Reclaimed Asphalt Pavement (RAP). RAP shall be allowed in HMA up to a maximum binder replacement of 23 percent, unless otherwise specified in the contract, and provided that all the specifications for the HMA are met. Fine Aggregate Angularity requirements shall apply only to the virgin fraction of the fine aggregate. RAP shall be of uniform quality and gradation with a maximum size no greater than the nominal aggregate size of the mix. RAP shall not contain clay balls, vegetable matter, or other deleterious substances.

The Contractor shall have an approved mix design for the amount of RAP to be used. The AC content of the RAP utilized in the Contractor RAP mix design shall be the average AC content determined in accordance with 1B or 1C, below, or alternatively, a minimum of five samples of the Contractors RAP stockpile may be sampled and the average AC content of the RAP be determined using AASHTO T-164, Method A or B, or in accordance with 1C below. The Contractor shall determine the total binder replaced by the binder in the RAP pursuant to the following equation:

Total Binder Replaced =  $(A \times B) \times 100/E$ Where:

A = RAP % Binder Content \*

B = RAP % in Mix \*

E = Total Effective Binder Content \*

\* in decimal format (i.e. 2% is 0.02)

The Total Binder Replaced by the binder in the RAP shall not exceed 23 percent of the effective binder content of either the mix design or the produced mix.

The Contractor shall have an approved Quality Control (QC) Plan that details how the RAP will be processed and controlled. The QC plan shall address the following:

- 1. RAP Processing Techniques. This requires a schematic diagram and narrative that explains the processing (crushing, screening, and rejecting) and stockpile operation for this specific project.
- 2. Control of RAP Asphalt Binder Content (AASHTO T-164, Method A or B). RAP Asphalt Binder Content may also be determined in accordance with CP-L 5120, provided an RAP AC content correction factor is determined through correlation testing with AASHTO T-164, Method A or B. The correction factor shall be determined by performing correlation testing on the first five samples of the RAP AC content, then at a frequency of one for every five AC content tests thereafter. The correction factor shall be determined by calculating the average difference in AC content between CP-L 5120 and AASHTO T-164, Method A or B, and applying the correction to the AC content determined in accordance with CP-L 5120:

Frequency: 1 per 1000 tons of processed RAP material (minimum five tests)

3. (Alternate) The Contractor may propose a RAP asphalt content correction factor to be used in conjunction with CP-L 5120. The proposed CP-L 5120 RAP asphalt content correction factor shall be used with all RAP asphalt contents tested for the mixture design and quality control sampling and testing. The methodology of the proposed CP-L 5120 RAP asphalt content correction factor shall be outlined in detail in the approved RAP QC Plan. At a minimum, the proposed CP-L 5120 correction factor shall identify the principal source locations of the RAP aggregate, gradation of the material tested, and specific ignition oven serial number used in all the RAP asphalt content testing. The RAP source locations, material gradation, and specific equipment used shall substantiate the CP-L 5120 asphalt content correction factor used for the testing. The substantiation must be from data

gathered from historical information or specific asphalt content correction data obtained from tests performed on similar virgin aggregate sources, virgin material gradations, and the specific equipment used.

4. Control of RAP Gradation (CP31 or AASHTO T-30):

Frequency: 1 per1000 tons of processed RAP material (minimum three tests, sampling from belt feed and not stockpile)

5. Process Control Charts shall be maintained for binder content and each screen listed in Table 401.2C, during addition of any RAP material to the stockpile. The Contractor shall maintain separate control charts for each RAP stockpile. The control charts shall be displayed and shall be made available, along with RAP AC extraction testing laboratory reports to the Engineer upon request

The processed RAP must be 100 percent passing the 31.5 mm (1½ inch) sieve. The aggregate obtained from the processed RAP shall be 100 percent passing the 25.0 mm (1 inch) sieve. The aggregate and binder obtained from the processed RAP shall be uniform in all the measured parameters in accordance with the following:

Table 401.2C RAP Binder & Aggregate Uniformity Tolerances

Element	StandardDeviation
Binder Content	0.5
% Passing ¾"	4.0
% Passing ½"	4.0
% Passing 3/8"	4.0
%Passing #4	4.0
% Passing #8	4.0
% Passing #30	3.0
% Passing #200	1.5

(d) Warm Mix Asphalt (WMA) Technology. The Contractor may choose to use a WMA Technology that is included on the CDOT approved products list (https://www.codot.gov/business/apl/asphalt-warm-mix.html).

WMA technologies (additive or foaming) used shall be identified on the mix design, indicating usage as a workability additive and/or anti-strip additive. WMA shall be submitted and approved by the Owner for use on a project.

The addition of WMA additives during production, including foaming, shall be controlled by a calibrated metering system interlocked with the plant's controls per the manufacturers' recommendation. Additives may be added at the asphalt terminal at the dosage rate recommended by the WMA technology provider. The foaming process mixes water and binder to create microscopic steam bubbles. Typical water injection rate is  $\leq 2\%$  of binder flow rate or per manufacturers' recommendation.

(e) Anti-Strip Additives. Anti-Strip shall be added into the HMA. Anti-Strip agents may be liquids (added to the binder), lime (added to the aggregates) or other products, and shall be submitted for approval by the Owner.

The minimum value for Tensile Strength Ratio (TSR) tested in accordance with Table 401.21-1 shall be 80% for the mix design and 70% during production.

There are various types of liquid Anti-Strips. Amine and Organo-silane type liquid Anti-Strip additives are physically mixed with the asphalt binder. Liquid Anti-Strip agents shall be added per the manufactures recommendations. Typical product dosages are provided in Table 401.2E-1.

TABLE 401.2E-1 Liquid Anti-Strip Dosage Rates

Туре	Typical Dosage Rate
Amine	0.4% to 0.8%
Organo-silane	0.05% to 0.15%

WMA chemical products which display Anti-Stripping characteristics will be classified, and identified on the mix design, as a liquid Anti-Strip additive.

When a liquid Anti-Strip additive is used, the Contractor shall include the following information with the mix design submission:

- Information on the type of liquid Anti-Strip additive to be supplied, including product name, product manufacturer/supplier
- Additive rate
- TSR values for the treated mixes
- The proposed method for incorporating the additive into the plant produced mix

## 401.03 Aggregates.

Add the following:

The percentage of fractured faces shall be as shown in Table 403.1 of the Revision to Section 403.

Grading ST (3/8" nominal) mixes may be used for leveling, maintenance, bike paths, sidewalks and thin lift overlays. Grading SX (1/2" nominal) mixes shall be used on top and bottom lifts and for patching. Grading S (3/4" nominal) mixes may be used for bottom lifts.

## 401.05 Hydrated Lime.

Add the following:

When used in the HMA, hydrated lime shall be added at the rate of 1% by dry weight of the aggregate and shall be included in the amount of material passing the No. 200 sieve.

## 401.06 Asphalt Cement.

Revise the second paragraph to read as follows:

The asphalt cement shall meet the applicable requirements of subsection 702.01.

## Add the following:

The Contractor shall provide to the Owner acceptable 'Certifications of Compliance' of each applicable asphalt binder grade from the supplier. Should testing or certificate show nonconformance with the specifications, the asphalt binder may be rejected. When production begins, the Contractor shall, upon request, provide to the Owner a one quart can of each specified asphalt binder for analysis. Additionally, the Contractor shall provide the refinery test results that pertain to the asphalt binders used during production.

Based on climatic conditions and reliability, binder grades approved for use in Mesa County are as follows in Table 401.06A-1:

TABLE 401.06A-1 Recommended Performance Graded Binders

Condition	Non-modified Binder	Modified Binder
Free flowing traffic loads and 300,000 to 1 million 18K ESAL	PG 64-22	
Free flowing traffic loads and 300,000 to 1 million 18K ESAL, plus above 6000 elevation	PG 58-28	
Slow moving or standing trucks, major street intersections and/or 10,000,000 18K ESAL		PG 76-28 (top lift only)

Binder grades other than those shown above shall not be used unless the proposed binder and the mix design are approved in writing by the OWNER. The asphalt cement shall meet the requirements of subsection 702.01

## 401.07 Weather Limitations and Placement Temperatures.

## Revise as follows:

Surface temperatures shall be used to determine placement of APM. APM produced with documented WMA will be allowed a reduction in minimum surface temperatures for placement as provided in Table 401.07A-1. Ambient temperatures and other weather conditions shall be considered prior to placement.

TABLE 401.07A-1
Minimum Surface Temperatures for placement of APM

Commonted Larvan	Mini	mum Surface	Temperatur	e (°F)
Compacted Layer Thickness (in.)	Top Layer			s Below
Tillekiless (III.)	Top Layer		the To	p Layer
Product	APM	with WMA	APM	with WMA

<11/2	60	50	50	40
1½ - <3	50	45	40	35
3 or more	45	40	35	35

If the Contractor modifies the placement and compaction processes when ambient temperatures are below minimum surface temperatures in Table 401.07A-1, they shall demonstrate to the Owner the required in-place density has been achieved. APM cooling software such as PaveCool, or MultiCool can be used to determine placement and compaction times available.

## 401.08 Asphalt Mixing Plant.

Delete the last paragraph of the subsection.

## 401.09 Hauling Equipment.

Add the following:

The Owner may reject any HMA which demonstrates it has been contaminated from a petroleum distillate release agent. The Owner may reject any uncovered HMA which demonstrates it has been impacted by contamination and/or weather.

## 401.10 Asphalt Pavers.

Delete the twelve paragraph and replace with the following:

Contractor shall submit for and receive approval of the screed control devices to be utilized on the paver prior to use for placing HMA on the project.

Add the following:

A Material Transfer Vehicle (MTV) or Material Transfer Device (MTD) may be required for placement of the HMA when specified in the contract documents. The MTV shall be a self-propelled unit with on board storage of material. An MTD is a non-self-propelled unit. Both MTV and MTD are capable of receiving material from trucks or from the ground, transferring the material from the unit to a paver hopper insert via a conveyor system.

## 401.11 Tack Coat.

Delete and replace with the following:

A tack coat shall be applied between pavement course and to all existing concrete and asphalt surfaces per Section 407. Tack coat is considered incidental to the cost of the HMA.

## 401.15 Mixing.

Add the following:

If a WMA technology (additive or foaming) is used, the discharge temperatures may be lowered during production at the discretion of the Contractor provided all specifications are achieved. Mix design is to indicate revised allowable discharge temperatures with WMA usage.

## 401.16 Spreading and Finishing.

Revise as follows:

Joints in the top layer of new pavement shall be located on lane lines unless otherwise shown on the plans. Longitudinal joints shall be minimized with wide paving pulls. Transverse joints shall be formed by cutting back on the previous run to expose the full depth of the course. Tack coat material shall be applied to contact surfaces of all joints before additional mixture is placed against the previously compacted material.

## 401.17 Compaction.

Revise as follows:

Equipment used for compaction of the HMA will be at the discretion of the Contractor. The number, weight, and type of rollers furnished shall be sufficient to obtain the required density and surface texture.

All joints shall be compacted to 92% of maximum theoretical specific gravity (Rice), taken six inches offset from the joint. The allowable variance shall be  $\pm 2\%$ . Joint density will be determined using nuclear density equipment.

Delete paragraphs six through eight, and paragraphs eleven to the end of the subsection and replace with the following:

Cores may be used to verify compaction results. The Contractor shall core the pavement, as required by the Owner; in accordance with AASHTO T 230, Method B, or for field calibration of nuclear density equipment in accordance with the ASTM D 2950. At a minimum, cores for nuclear density equipment correlation shall be taken at the beginning of placement of each project or change of mixture materials or gradation, unless otherwise approved by the Engineer. If the correlation cores were produced for another project within the last 90 days, data from that project can be submitted for verification, if no change in materials or gradation has occurred. When cores are used, the Contractor shall provide all labor and equipment for the coring and repair of the holes.

Along forms, curbs, headers, walls, and all other places not accessible to the rollers, the mixture shall meet all project compaction specifications. Any mixture that is defective, shall be corrected to meet the project specifications at the expense of the Contractor.

## 401.20 Surface Smoothness.

Delete and replace with the following:

The finish transverse and longitudinal surface elevation of the pavement shall be measured using a 10-foot straightedge. Surface smoothness shall be verified following the finish roller pass. Surface variation shall not exceed 3/16 inch in 10 feet for full lane width paving. For patching, the variation

shall not exceed 3/8 inch in 10 feet. The final pavement surface shall not vary from the specified cross section by more than one inch at any point. Transverse measurements for variations shall exclude breaks in the crown sections. If the surface tolerance exceeds 3/16" across transverse joints, measured in at least three locations, the Contractor shall make corrections to the joint before proceeding. All corrections shall be made at the Contractor's expense.

The final surface pavement adjacent to curb and gutter shall be finished from 1/8-inch to 3/8- inches above the lip for catch curb and shall not extend above the lip for spill curb.

The Contractor shall adjust all manholes, valve boxes, and survey range boxes 1/8 to 1/4- inch below final grade and adjusted to match the slope of the roadway. Valve boxes and manholes are to be maintained fully accessible at all times for emergency and maintenance operations. The cost of adjusting valve boxes, manholes, and survey range boxes shall be included in the work, unless otherwise specified. The Contractor shall be responsible for any cost incurred by the Owner to provide access to the covered manholes or valve boxes. Final adjustment of all utility access points shall be completed within seven days of from the time the HMA was placed.

Add the following new subsections:

## **401.23 Testing and Inspection**

The Contractor shall assume full responsibility for controlling all operations and processes to meet the Specifications. The Contractor shall perform all tests necessary for process control purposes on all elements at the frequency listed in Table 401.23-1. The Contractor shall maintain a log of all process control testing. Test results that have sampling or testing errors shall not be used. Process control testing shall be performed at the expense of the Contractor.

Laboratories shall be accredited by AASHTO Materials Reference Laboratory (AMRL) for the tests being performed. Technicians obtaining samples and conducting compaction tests must have a LabCAT Level A certification. Technicians conducting tests of asphalt content and gradation must have a LabCAT Level B certification. Technicians performing volumetric testing must have a LabCAT Level C certification. Equivalent NICET certification for all technicians is acceptable.

When requested by the Owner, the Contractor shall submit a quality control plan that addresses production, sampling, testing, and qualifications of testing personnel, timing, and methods for making adjustments to meet the specifications. The Contractor will provide a process or schedule for making corrections for material that was placed but does not meet specifications as well as obtain a follow up sample immediately after corrective actions are taken to assess the adequacy of the corrections. In the event the follow-up process control sample also fails to meet Specification requirements; the Contractor shall cease production of the asphalt mixture until the problem is adequately resolved to the satisfaction of the Owner.

## **TABLE** 401.23-1

## Minimum Materials Sampling and Testing for Process Control and Owners Acceptance

Test	Standard	Minimum Frequency
Sampling	AASHTO T168, ASTM D 979 and ASTM D3665, CP 41	1/1000 tons or fraction thereof (not less than one test per day)
In-Place Density	AASHTO T 166, T 238, T 230, CP 81 (nuclear), CP 44 (coring)	One test for each 250 lineal feet per lane and one test per 1,000 lineal feet of joint per lift
Thickness (Core) (when called for in Project specs.)	ASTM D3549	One test for each 1000 lineal feet per lane
Air Voids & VMA	CP-L 5115 A.I. SP-2	1/1000 tons or fraction thereof (not less than one test per day)
Gradation	AASHTO T 27/T 11, CP 31	1/1000 tons or fraction thereof (not less than one test per day)
Hveem/Marshall Stability As Applicable	CP-L 5016	One per project per mix used
Binder Content	CP-L 5120, AASHTO T 164 or other methods agreed upon between Owner and Contractor	1/1000 tons or fraction thereof (not less than one test per day)
Maximum Theoretical Specific Gravity (Rice)	AASHTO T 209 (Rice), CP-L 51	1/1000 tons or fraction thereof (not less than one test per day)
Lottman Stripping, TSR & Dry Density	CP-L 5109	One per project per mix used.

Field control testing of dense graded asphalt mixes for the above tests shall meet the requirements of Table 403-1 and Table 403-2 in the Revision to Section 403.

## 401.24 Acceptance

If any materials furnished, or work performed, fails to meet the specification requirements, such deficiencies shall be documented and reported to the Owner. Copies of all process control tests shall

be delivered to the Owner within one business day. Test results that cannot be completed within one day shall be provided to the Owner no later than three days after the sample was obtained.

Owners Acceptance (OA) test results, if any, and/or Process Control (PC) test results will be evaluated to determine acceptability. If the Contractor does not meet the project specifications, but acceptable work has been produced, the Owner shall determine the extent of the work to be accepted. If the Owner determines the work is not acceptable, the Contractor shall correct the work, as approved by the Owner, at the expense of the Contractor.

## SP-5 SECTION 403 – HOT MIX ASPHALT

## REVISION OF SECTION 403 HOT MIX ASPHALT

Section 403 of the Standard Specifications is hereby revised for this project as follows:

## 403.02 Materials

Delete and replace with the following:

The materials shall conform to the requirements of subsections 401.2 of the Revised Section 401 above.

The design mix for hot mix asphalt (HMA) shall conform to the following Table 403-1 and Table 403-2:

Table 403-1 Mixture Properties for Hot Mix Asphalt

Property	Test Method	Value
Troperty	1 est Method	
Air Voids, percent at: N (design)	AASHTO T-132, CPL 5115	3.0 – 4.0
Lab Compaction (Revolutions): N (design)	CPL 5115	75
Hveem Stability, (Grading ST, SX & S only)	CPL 5106	28 min.
Aggregate Retained on the 4.75 mm (No. 4) Sieve for S, SX and SG, and on the 2.36mm (No. 8) Sieve for ST and SF with at least 2 Mechanically Induced fractured faces	CP 45	60% min.
Accelerated Moisture Susceptibility Tensile Strength Ratio (Lottman)(for S & SX mixes)	AASHTO T-283 Method B, CPL 5109 Method B	80 min.
Minimum Dry Split Tensile Strength, kPa (psi)	CPL 5109 Method B	205 (30) min.
Voids in the Mineral Aggregate (VMA) % minimum	CP 48, AI-SP2	See Table 403-2

Property	Test Method	Value
Порегсу	1 est wicthou	
Voids Filled with Asphalt (VFA)	AI MS-2	65-80%
Dust to Asphalt Ratio:		
Fine Gradation	CP 50	0.6 - 1.2
Coarse Gradation		0.8 - 1.6

Note: AI MS-2 = Asphalt Institute Manual Series 2

Note: Mixes with gradations having less than 40% passing the 4.75 mm (No. 4) sieve shall be

approached with caution because of constructability problems.

Note: Gradations for mixes with a nominal maximum aggregate size of one-inch or larger are

considered a coarse gradation if they pass below the maximum density line at the #4

screen.

Gradations for mixes with a nominal maximum aggregate size of 3/4" to 3/8" are considered a coarse gradation if they pass below the maximum density line at the #8

Gradations for mixes with a nominal maximum aggregate size of #4 or smaller are considered a coarse gradation if they pass below the maximum density line at the #16 screen.

Table 403-2
Minimum Voids in Mineral Aggregate (VMA)

Nominal Maximum Size*,	***Design Air Voids **		
mm (inches)	3.5%	4.0%	4.5%
37.5 (1½)	11.6	11.7	11.8
25.0 (1)	12.6	12.7	12.8
19.0 (¾)	13.6	13.7	13.8
12.5 (½)	14.6	14.7	14.8
9.5 (3/8)	15.6	15.7	15.8
4.75 (No. 4)	16.6	16.7	16.8

<sup>\*</sup> The Nominal Maximum Size is defined as one sieve larger than the first sieve to retain more than 10%.

## **403.03 Construction Requirements**

Delete the first paragraph and replace with the following:

The construction requirements shall be as prescribed in subsections 401.3 through 401.14 of the Revised Section 401 above.

<sup>\*\*</sup> Interpolate specified VMA values for design air voids between those listed.

<sup>\*\*\*</sup> Extrapolate specified VMA values for production air voids beyond those listed.

#### 403.04 Method of Measurement

Delete and replace with the following:

Hot Mix Asphalt will be measured by the ton or the square yard. Batch weights will not be permitted as a method of measurement when measured by the ton. The tonnage shall be the weight used in the accepted pavement.

## 403.05 Basis of Payment

Delete and replace with the following:

The accepted quantities of hot mix asphalt will be paid for in accordance with subsection 401.22, at the contract unit price per ton or square yard for the asphalt mixture.

Payment will be made under:

Pay Item	Pay Unit
Hot Mix Asphalt (Grading)(PG)	Ton
Hot Mix Asphalt (Grading)(PG)	Square Yard
Hot Mix Asphalt (Patching)	Square Yard

Aggregate, asphalt cement, asphalt recycling agent, additives, hydrated lime, tack coat, and all other work necessary to complete each hot mix asphalt items will not be paid for separately but shall be included in the unit price bid.

Excavation, preparation, and tack coat of areas to be patched will not be measured and paid for separately, but shall be included in the work.

## SP-7 SECTION 407 - PRIME COAT, TACK COAT, AND REJUVINATING AGENT

## REVISIONS OF SECTION 407 PRIME COAT, TACK COAT, AND REJUVENATING AGENT

Section 407 of the Standard Specifications is hereby revised for this project as follows:

## 407.01 Description

Add the following:

Prior to placement of APM, a tack coat shall be applied to all existing concrete and asphalt surfaces.

## 407.02 Asphalt Material.

Add the following:

The tack coat shall meet the specification for emulsified asphalt, consisting of CSS-1h or SS-1h, and conform to AASHTO M208 or M140.

## 407.07 Application of Asphalt Material.

## Add the following:

The tack coat shall be applied at the rates specified in Table 407-1. The surface receiving the tack coat shall be dry and clean, and dust, debris, and foreign matter shall be removed. Tack coat shall be applied uniformly. The Contractor shall allow the tack coat to cure (dehydrate) prior to the placement of APM. If the tack becomes contaminated during construction, it shall be cleaned, and if necessary, additional tack coat shall be reapplied and allowed to cure before paving resumes.

TABLE 407-1
Tack Coat Application
Rates

Pavement Condition	Application Rate (gal/yd <sup>2</sup> )		
Pavement Condition	Residual	Undiluted	Diluted (1:1)
New asphalt	0.03 - 0.04	0.05 - 0.07	0.10 - 0.13
Oxidized asphalt	0.04 - 0.06	0.07 - 0.10	0.13 - 0.20
Milled Surface (asphalt)	0.06 - 0.08	0.10 - 0.13	0.20 - 0.30
Milled Surface (PCC)	0.06 - 0.08	0.10 - 0.13	0.20 - 0.30
Portland Cement Concrete	0.04 - 0.06	0.07 - 0.10	0.13 - 0.20

## 407.09 Method of Measurement and Basis of Payment.

Delete and replace the following:

Tack Coat will not be measured and paid separately but shall be considered included in the work for Section 401 – Asphalt Pavement Materials.

## <u>SP-7 SECTION 601 – STRUCTURAL CONCRETE</u>

Section 601 of the Standard Specifications is hereby revised for this project as follows:

Subsection 601.02, Classification:

## CONCRETE SHALL MEET THE FOLLOWING REQUIREMENTS:

- 4,500 PSI Compressive at 28 Days
- 6% air ±1.5%
- Slump 4", Loads exceeding 4 ½" shall be rejected
- Maximum Water Cement Ratio no greater than 0.45.

Subsection 601.06, Batching:

This CDOT Specification has been added to this Project:

The Contractor shall furnish a batch ticket (delivery ticket) with each load for all concrete.

Concrete delivered without a batch ticket containing complete information as specified shall be rejected. The Contractor shall collect and complete the batch ticket at the placement site and deliver all batch tickets to the Engineer or his representative at the end of each day. The Engineer or his representative shall have access to the batch tickets at any time during the placement. The following information shall be provided on each ticket:

- 1. Suppliers name and date
- 2. Truck number
- 3. Project name and location
- 4. Concrete class and designation number
- 5. Cubic yards batched
- 6. Type brand and amount of each admixture
- 7. Type, brand, and amount of cement and fly ash
- 8. Weights of fine and course aggregates
- 9. Moisture of fine and course aggregates
- 10. Gallons of batch water

The contractor shall add the following information to the batch ticket at time of placement:

- 1. Gallons of water added by the truck operator.
- 2. Number of revolutions of the drum for mixing
- 3. Discharge time

## SP-8 SECTION 608 – CURBS, GUTTERS, SIDEWALKS, AND TRAILS

Section 608 of the Standard Specifications is hereby revised for this project as follows:

Subsections 608.06, Basis of Payment shall include the following:

The Contract Unit Price for the various concrete items shall be full compensation for all equipment, labor, materials, and incidentals required for the complete installation. Incidental items include subgrade compaction, cutting and removal of asphalt in areas where concrete will be installed; removal of existing concrete, removal of existing base course, disposal of excavated and removed materials; furnishing, placement and compaction of Class 6 Aggregate Base Course; forming, furnishing and placement, finishing, curing and protection of the concrete; reinforcing steel and joint filler.

## **SP-9 SECTION 630 - CONSTRUCTION ZONE TRAFFIC CONTROL**

Section 630 of the Standard Specifications are hereby revised for this project as follows:

Subsection 630.09, Traffic Control Plan, shall include the following:

The following guidelines and limitations shall apply to the traffic control:

- 1. Two way traffic shall be maintained on all streets (unless otherwise approved).
- 2. Concrete activities shall be coordinated so that concrete trucks and other vehicles do not block the traffic lanes.

- 3. All incidental costs shall be included in the original contract price for the project.
- 4. Sidewalks that are obstructed or under construction shall be barricaded, as required for pedestrian safety.

Subsection 630.14, Method of Measurement, shall include the following:

Distribution of door-hanger notices to all businesses and / or residents located adjacent to the overlay work will not be paid for separately but shall be included in the pay item for Traffic Control (Complete in Place). The City will provide the door hangers for distribution.

## 3.5. Attachments: Click Links

Appendix A: Project Submittal Form Appendix B: Individual Street Quantities

Appendix C: Project Extents

Appendix D: Construction Drawings

- 3.6. Contractor Bid Documents: For Contractor's convenience, the following is a list of forms/items to be submitted with the Contractor's bid response. However, should a form/item not be listed in this section, but required in the solicitation documents, it is the Contractor's responsibility to ensure all forms/items are submitted.
  - Contractor's Bid Form
  - Bid Bond
  - Price Bid Schedule

## 3.7. IFB TENTATIVE TIME SCHEDULE:

Invitation For Bids available	April 10, 2021
Mandatory Pre-Bid Meeting	April 19, 2021
Inquiry deadline, no questions after this date	April 23, 2021
Addendum Posted	April 27, 2021
Submittal deadline for proposals	April 30, 2021
City Council Approval	May 19, 2021
Notice of Award & Contract execution	May 20, 2021
Bonding & Insurance Cert due	May 26, 2021
Preconstruction meeting	June 1, 2021
Work begins no later than	Upon Receipt

Upon Receipt of Notice to Work begins no later than

Proceed

**Final Completion** 90 Calendar Days from Notice

to Proceed

Holidays: July 5, 2021

## 4. Contractor's Bid Form

Bid Date:		
Project: IFB-4908-21-DH "2021 Contract \$	Street Maintenance – Asphalt	Overlays"
Bidding Company:		
Name of Authorized Agent:		
Email		
Telephone	Address	
City	State	Zip
Contract Conditions, Statement of Work, Sp of, and conditions affecting the proposed wo all work for the Project in accordance with	ecifications, and any and all Ad ork, hereby proposes to furnish Contract Documents, within the	g examined the Instruction to Bidders, General denda thereto, having investigated the location all labor, materials and supplies, and to perform time set forth and at the prices stated below. red under the Contract Documents, of which this
connection to any person(s) providing an of	fer for the same work, and tha	offer is made in good faith without collusion or it it is made in pursuance of, and subject to, all Il other Solicitation Documents, all of which have
	is offer will be taken by the Owr	ce certificates within ten (10) working days of the ner as a binding covenant that the Contractor will
or technicalities and to reject any or all offer	s. It is further agreed that this	leemed most favorable, to waive any formalities offer may not be withdrawn for a period of sixty ed offers automatically establish a new thirty day
Prices in the bid proposal have not knowingly	y been disclosed with another p	provider and will not be prior to award.
purpose of restricting competition.  No attempt has been made nor will be to inducompetition.  The individual signing this bid proposal certifis legally responsible for the offer with regard Direct purchases by the City of Grand Junction The undersigned certifies that no Federal, St. City of Grand Junction payment terms shall be Prompt payment discount of percentage.	ice any other person or firm to so fies they are a legal agent of the d to supporting documentation a on are tax exempt from Colorad tate, County or Municipal tax wi be Net 30 days. cent of the net dollar will be of	lo Sales or Use Tax. Tax exempt No. 98-03544.
RECEIPT OF ADDENDA: the undersigned and other Contract Documents.  State number of Addenda received:	•	pt of Addenda to the Solicitation, Specifications,
It is the responsibility of the Bidder to ensure	all Addenda have been receive	ed and acknowledged.
By signing below, the Undersigned agree to	comply with all terms and cond	itions contained herein.
Company:		
Authorized Signature:		
Title:		

## Bid Schedule: 2021 Contract Street Maintenance - Asphalt Overlays CONTRACTOR: \_\_\_\_

Item No.	CDOT,	Description	Quantity	Units		Unit Price	Total Price
	Oity 1 toi.	Doddipaon	Quantity	Office		01111 1 1100	1010111100
1	202	Asphalt Removal (Planing)(Thickness Varies)	55,127.	SY	ß	\$	
2	203	Excavation and Embankment (Bike Lanes - See SP-2)(Cut)	926.	CY	ß		
3	208	Erosion Control	Lump	Sum		<b>\$</b>	
4	209	Dust Abatement	Lump	Sum		B	
5	210	Restore Landscaping	Lump	Sum		B	
6	210	Regrade Behind New Concrete	545.	LF	Б	ь <u>——</u> Б	
		Driveway (Soil Lot)					
7	210	Adjust Mailbox	7.	EA	ß	\$	
8	210	Adjust Valve Box (Price to Include	139.	EA	ß		
		adjustment of Survey Monuments)					
9	210	Adjust Manhole Ring and Cover	74.	EA	\$	\$ <u></u>	
		(Sanitary and Storm Sewer)		_			
10	304	Aggregate Base Course (Class 6) -	456.	Tons	₿	\$ <u></u>	
11	304	Shoulder Edging Gravel Aggregate Base Course (Class 6) -	1,730.	Tons	ŀ	<b> B</b>	
	304	Bike Lanes (12" Thick)	1,730.	10115	P	P	
12	304	Subgrade Stabilization (Class 3	100.	Tons	Б	<b>b</b>	
		Aggregate Base Course - 24"			·	<u> </u>	
		Thick)(Complete in Place)					
13	401	Hot Mix Asphalt ( 1" thick Pre-Level)	584.	Tons	ß	\$ <u></u>	
		(Grading SX, Binder Grade 64-22)					
14	401	Hot Mix Asphalt (Bike Lanes - 3"	350.	Tons	ß		
		thick) (Grading SX, Binder Grade 64-					
15	401	22) Hot Mix Asphalt (2" thick) (Grading	10,664.	Tons			
13	701	SX, Binder Grade 64-22)	10,004.	10113	ν	v	
16	401	Hot Mix Asphalt (Patching - Up to 7"	205.	Tons	Б	\$	
		thick) (To Include 6" of Class 6					
		Aggregate Base Course)(Grading					
		SX, Binder Grade 64-22)					
17	608/304		230.	SY	ß	\$ <u></u>	
		(vertical or rolled type) to Include 6"					
		of Class 6 Aggregate Base Course					
18	608/304	Concrete Curb and Gutter (2' Wide)	1,062.	LF	8	Б	
.0	000/00-1	To Include 6" of Class 6 Aggregate	1,002.		<b>'</b>	v	
		Base Course					
19	608/304	Concrete Curb Ramp to include 6" of	441.	SY	ß		
		Class 6 Aggregate Base Course					
20	608	Detectable Warning (Wet Set)(Cast	88.	SF	\$	\$ <u></u>	
	00015	Iron)(2'x4')		• •			
21	608/304	Concrete Driveway Section (8"Thick)	1,469.	SY	ß	<b>6</b>	
		to Include 6" of Class 6 Aggregate					
		Base Course					

## Bid Schedule: 2021 Contract Street Maintenance - Asphalt Overlays contractor: \_\_\_\_\_

Item No.	CDOT, City Ref.	Description	Quantity	Units		Unit Price	€	Total Price
22	608	Sidewalk Drain Trough - See Sheet D13 and D14 of the Standard Contract Documents for details.	12.	LF	ß		\$	
23	620	Sanitary Facility	Lump	Sum			\$	
24	625	Construction Surveying	Lump	Sum			ß	
25	626	Mobilization	Lump	Sum			ß	
26	627- 30405	Preformed Thermoplastic Pavement Marking (Word/Symbol)	291.	SF	ß		· F	
27	627- 30410	Preformed Plastic Pavement Marking (X-Walk/Stopline)	653.	SF	ß		<b>.</b>	
28	630	Traffic Control (Complete In Place)	Lump	Sum			ß	
29	630	Flagging	3,720.	HR	\$		· •	
INC		Incentive HMA 64-22					\$	45,000.00
MCR		Minor Contract Revisions					\$	150,000.00
			Bio	l Amount	::	4	<u> </u>	

Bid Amount:	
	dollars

The undersigned Bidder proposes to subcontract the following portion of Work:

Name & address of	Description of work	% of
Sub-Contractor	to be performed	Contract
		<u> </u>
		<del></del>

The undersigned Bidder acknowledges the right of the City to reject any and all Bids submitted and to waive informalities and irregularities therein in the City's sole discretion.

By submission of the Bid, each Bidder certifies, and in the case of a joint Bid each party thereto certifies as to his own organization, that this Bid has been arrived at independently, without collusion, consultation, communication, or agreement as to any matter relating to this Bid with any other Bidder or with any competitor.



## **Purchasing Division**

## **ADDENDUM NO. 1**

**DATE:** April 21, 2021

FROM: City of Grand Junction Purchasing Division

TO: All Offerors

RE: 2021 Contract Street Maintenance – Asphalt Overlays IFB-4908-21-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

- 1. Q. Can driveway replacements be done half at a time?
  - A. It can be assumed that driveway replacements can be replaced ½ at a time where width accommodates traffic flow.
- 2. Q. Can we us non-calcium accelerator in concrete mix?
  - A. Non-calcium accelerator may be utilized, but for bidding purposes, is not required for driveway replacements.
- 3. Q. Can you provide a line item in the price bid schedule for a loader for asphalt millings?
  - A. A line item has been added for a loader to buck up the millings stockpile at the Legacy Way Storage Yard. Please see the updated bid schedule. Contractor shall utilize the attached Addendum 1 Price Bid Schedule when submitting their bid response.
- 4. Q. Please clarify pre-staging time for night work.
  - A. A typo was present in the pre-bid meeting agenda provided on April 19, 2021. As stated in the meeting, no traffic control shall be in in place, other than prestaging, prior to 8:00PM and all traffic control shall be removed prior to 6:00AM.
- 5. Q. When will striping be done by City? Does it have to be coordinated with project?
  - A. Long line, painted striping will be performed by the City as soon as possible after the overlay. However, the contractor is still required to provide temporary pavement marking tape per solicitation section 3.3.35. Thermoplastic striping and markings are also to be provided by the contractor.

- 6. Q. Plans for H Road have milling down through driveways. Please describe and clarify.
  - A. The driveways will be saw cut back to accommodate a the new, full pavement depth section for the widened shoulders per the plan set details.
- 7. Q. On 27 Road, will the contractor be running a miller through the chipseal?
  - A. On 27 Rd. north of G Rd. and south of the irrigation culvert, the eastern shoulder currently consists of a double pen chipseal on existing soil/basecourse materials. This shoulder is to be pulverized and left in place by a mill machine. This pulverized material is then to be moisture conditioned and compacted in place leaving an improved shoulder.
- 8. Q. Is the City going to provide message boards? If not, can a line item be added to the price bid schedule?
  - A. Message boards shall be provided by the contractor. They should be in place at least two (2) working days in advance of both milling and paving operations. These will be in conjunction with the required door hangers as indicated in the solicitation section 3.3.13. Please include this cost in line item #30 Traffic Control (Complete In Place).
- 9. Q. Is dust abatement required, and for what locations?
  - A. Dust Abatement will be required for the H Rd. Shoulder widening.
- 10. Q. Does shouldering need to be compacted after pulverize and spread?
  - A. After the chipseal shoulder is pulverized on 27 Rd., the material should be left in place, moisture conditioned, and compacted to leave an improved shoulder.
- 11. Q. Please verify what mixes the City wants and where?
  - A. In general, the City will be utilizing SX-75, PG 64-22 asphalt mix for overlays. An ST-75, PG 64-22 asphalt mix should be utilized for areas designated to receive a pre-level. Please refer to the updated bid schedule for quantities.

Please also see the attached maps showing approximate locations/quantities of concrete removals and replacements.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

Duane Hoff Jr., Senior Buyer City of Grand Junction, Colorado

# Bid Schedule: 2021 Contract Street Maintenance - Asphalt Overlays Addendum #1

CONTRACTOR:

Item	CDOT,	Description	O#4.	11-:4-	Unit Price Total Price
No.	City Rei.	Description	Quantity	Units	Unit Price Total Price
1	202	Asphalt Removal (Planing)(Thickness Varies)	55,127.	SY	ß
2	202	Asphalt Removal (Planing)(Thickness Varies)(Pulverized/Complete in Place Shoulder)	1,140.	SY	ß
3	203	Excavation and Embankment (Bike Lanes - See SP-2)(Cut)	926.	CY	ß
4	203	Front End Loader (End of Day Millings Buck Up)	40.	HR	<b>\$</b> \$
5	208	Erosion Control	Lump	Sum	B
6	209	Dust Abatement	Lump	Sum	ß
7	210	Restore Landscaping	Lump	Sum	ß
8	210	Regrade Behind New Concrete	545.	LF	<b>5 5</b>
		Driveway (Soil Lot)			·
9	210	Adjust Mailbox	7.	EA	ß
10	210	Adjust Valve Box (Price to Include	139.	EA	BB
		adjustment of Survey Monuments)			
11	210	Adjust Manhole Ring and Cover (Sanitary and Storm Sewer)	74.	EA	ß
12	304	Aggregate Base Course (Class 6) - Shoulder Edging Gravel	456.	Tons	\$\$_
13	304	Aggregate Base Course (Class 6) - Bike Lanes (12" Thick)	1,730.	Tons	<b>\$</b> \$
14	304	Subgrade Stabilization (Class 3 Aggregate Base Course - 24" Thick)(Complete in Place)	100.	Tons	ß
15	401	Hot Mix Asphalt (1" thick Pre-Level) (Grading ST, Binder Grade 64-22)	584.	Tons	ß
16	401	Hot Mix Asphalt (Bike Lanes - 3" thick) (Grading SX, Binder Grade 64-22)	350.	Tons	<b>\$</b>
17	401	Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22)	10,664.	Tons	\$\$_
18	401	Hot Mix Asphalt (Patching - Up to 7" thick) (To Include 6" of Class 6 Aggregate Base Course)(Grading	205.	Tons	<b>\$</b>
19	608/304	SX, Binder Grade 64-22) Monolithic Curb Gutter and Sidewalk (vertical or rolled type) to Include 6" of Class 6 Aggregate Base Course	230.	SY	ß
20	608/304	Concrete Curb and Gutter (2' Wide) To Include 6" of Class 6 Aggregate Base Course BF-2 (	1,062.	LF	ß

# Bid Schedule: 2021 Contract Street Maintenance - Asphalt Overlays Addendum #1

Item	CDOT,							
No.	City Ref.	Description	Quantity	Units		Unit Pric	се	Total Price
21	608/304	Concrete Curb Ramp to include 6" of	441.	SY	\$		_ \$	
22	608	Class 6 Aggregate Base Course Detectable Warning (Wet Set)(Cast Iron)(2'x4')	88.	SF	ß		_ \$	
23	608/304	Concrete Driveway Section (8"Thick) to Include 6" of Class 6 Aggregate Base Course	1,469.	SY	\$		_ \$	
24	608	Sidewalk Drain Trough - See Sheet D13 and D14 of the Standard Contract Documents for details.	12.	LF	ß		_ \$	
25	620	Sanitary Facility	Lump	Sum			\$	
26	625	Construction Surveying	Lump	Sum			\$	
27	626	Mobilization	Lump	Sum			ß	
28	627- 30405	Preformed Thermoplastic Pavement Marking (Word/Symbol)	291.	SF	ß		_ \$	
29	627- 30410	Preformed Plastic Pavement Marking (X-Walk/Stopline)	653.	SF	ß		_ \$	
30	630	Traffic Control (Complete In Place)	Lump	Sum			₿	
31	630	Flagging	3,720.	HR	ß		_ \$	
INC		Incentive HMA 64-22					\$	45,000.00
MCR		Minor Contract Revisions					\$	150,000.00
			Bio	l Amou	nt:		\$	
	Bid Am	ount:						

## **Bogart Lane**



Date: 4/20/2021

0.075

0.0375

1 inch = 94 feet




## Crossroads Area - 1 - 27 Rd to Compass Dr



0 0.075 0.15

Grand Junction







## **Purchasing Division**

## **ADDENDUM NO. 2**

**DATE:** April 27, 2021

FROM: City of Grand Junction Purchasing Division

TO: All Offerors

RE: 2021 Contract Street Maintenance – Asphalt Overlays IFB-4908-21-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

- 1. Q. On the streets slated for night work does this also include that the concrete needs to be done at night?
  - A. Concrete work will not be required to be completed at night.

Please also see the attached maps showing approximate locations/quantities of concrete removals and replacements.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

Duane Hoff Jr., Senior Buyer City of Grand Junction, Colorado



## **NOTICE OF AWARD**

Date:

May 4, 2021

Company:

Oldcastle SW Group, Inc. dba United Companies

Project:

2021 Contract street Maintenance - Asphalt Overlays IFB-4908-21-DH

You have been awarded the City of Grand Junction 2021 Contract street Maintenance – Asphalt Overlays IFB-4908-21-DH for a total price of **\$2,085,553.20**.

Please notify Eric, City of Grand Junction Eric Mocko 970-256-4017 for delivery schedule and return to the City Purchasing Division an acknowledged copy of this Notice of Award.

CITY OF GRAND JUNCTION, COLORADO

Duane Hoff Ir., Senior Buyer- City of Grand Junction

Duane Hoff Jr., Senior Buyer

## SUPPLIER ACKNOWLEDGEMENT

Kyle Alpha - General Manager, Oldcastle SW Gr

Receipt of this Notice to Award is hereby acknowledged:

Company: Oldcastle SW Group, Inc. dba United Companies

DocuSigned by:

By:

Title:

200 MARKON 2000000 00 300L20200

V.P./General Manager

5/20/2021 | 19:38 MDT

Date: \_\_\_\_\_\_



## **Purchasing Division**

## Invitation for Bid

IFB-4908-21-DH 2021 Contract Street Maintenance – Asphalt Overlays

## Responses Due:

April 30, 2021 prior to 3:00PM

<u>Accepting Electronic Responses Only</u>

<u>Responses Only Submitted Through the Rocky Mountain E-Purchasing</u>

System (RMEPS)

https://www.rockymountainbidsystem.com/default.asp

(Purchasing Representative does not have access or control of the vendor side of RMEPS. If website or other problems arise during response submission, vendor MUST contact RMEPS to resolve issue prior to the response deadline. 800-835-4603)

NOTE: All City solicitation openings will continue to be held virtually.

## Purchasing Representative:

Duane Hoff Jr., Senior Buyer duaneh@gjcity.org 970-244-1545

This document has been developed specifically to solicit competitive responses for this solicitation, and may not be the same as previous City of Grand Junction solicitations. All vendors are urged to thoroughly review this solicitation prior to responding. Submittal by FAX, EMAIL or HARD COPY IS NOT ACCEPTABLE for this solicitation.

4. Contractor's Bid Form
Bid Date: April 30, 2021
Project: IFB-4908-21-DH "2021 Contract Street Maintenance – Asphalt Overlays"
Bidding Company: Oldcastle SW Group, Inc. dba United Companies
Name of Authorized Agent: Kyle Alpha, Vice President
Email justin.vensel@unitedco.com
Telephone 970-243-4900 Address 2273 River Road
City Grand Junction State CO Zip 81505
The undersigned Bidder, in compliance with the Invitation for Bids, having examined the Instruction to Bidders, General Contract Conditions, Statement of Work, Specifications, and any and all Addenda thereto, having investigated the location of, and conditions affecting the proposed work, hereby proposes to furnish all labor, materials and supplies, and to perform all work for the Project in accordance with Contract Documents, within the time set forth and at the prices stated below. These prices are to cover all expenses incurred in performing the work required under the Contract Documents, of which this Contractor's Bid Form is a part.
The undersigned Contractor does hereby declare and stipulate that this offer is made in good faith without collusion or connection to any person(s) providing an offer for the same work, and that it is made in pursuance of, and subject to, all terms and conditions of the Instructions to Bidders, the Specifications, and all other Solicitation Documents, all of which have been examined by the undersigned.
The Contractor also agrees that if awarded the Contract, to provide insurance certificates within ten (10) working days of the date of Notification of Award. Submittal of this offer will be taken by the Owner as a binding covenant that the Contractor will be prepared to complete the project in its entirety.
The Owner reserves the right to make the award on the basis of the offer deemed most favorable, to waive any formalities or technicalities and to reject any or all offers. It is further agreed that this offer may not be withdrawn for a period of sixty (60) calendar days after closing time. Submission of clarifications and revised offers automatically establish a new thirty day (30) period.
Prices in the bid proposal have not knowingly been disclosed with another provider and will not be prior to award.
Prices in this bid proposal have been arrived at independently, without consultation, communication or agreement for the purpose of restricting competition.  No attempt has been made nor will be to induce any other person or firm to submit a bid proposal for the purpose of restricting competition.  The individual signing this bid proposal certifies they are a legal agent of the offeror, authorized to represent the offeror and is legally responsible for the offer with regard to supporting documentation and prices provided.  Direct purchases by the City of Grand Junction are tax exempt from Colorado Sales or Use Tax. Tax exempt No. 98-03544. The undersigned certifies that no Federal, State, County or Municipal tax will be added to the above quoted prices. City of Grand Junction payment terms shall be Net 30 days.
Prompt payment discount of percent of the net dollar will be offered to the Owner if the invoice is paid within days after the receipt of the invoice. The Owner reserves the right to take into account any such discounts when determining the bid award.
RECEIPT OF ADDENDA: the undersigned Contractor acknowledges receipt of Addenda to the Solicitation, Specifications, and other Contract Documents.  State number of Addenda received: 1, 2
It is the responsibility of the Bidder to ensure all Addenda have been received and acknowledged.
By signing below, the Undersigned agree to comply with all terms and conditions contained berein SW GRO
Company: Oldcastle SW Group, Inc. dba United Companies
Authorized Signature:

## **Bid Schedule: 2021 Contract Street Maintenance - Asphalt Overlays**

Addendum #1

CONTRACTOR: Oldcastle SW Group, Inc dba United Companies

Item	CDOT,						
No.		Description	Quantity	Units		Unit Price	Total Price
1	202	Asphalt Removal (Planing)(Thickness	55,127.	SY	ß	1.70 \$	93,715.90
2	202	Varies) Asphalt Removal (Planing)(Thickness	1,140.	SY	ß	3.00 \$	3,420.00
		Varies)(Pulverized/Complete in Place Shoulder)					
3	203	Excavation and Embankment (Bike Lanes - See SP-2)(Cut)	926.	CY	ß	19.80	18,334.80
4	203	Front End Loader (End of Day Millings Buck Up)	40.	HR	ß	112.00 \$	4,480.00
5	208	Erosion Control	Lump	Sum		ß_	3,120.00
6	209	Dust Abatement	Lump			B	1,800.00
7	210	Restore Landscaping	Lump	Sum		\$	3,600.00
8	210	Regrade Behind New Concrete	545.	LF	ß	4.10 \$	2,234.50
		Driveway (Soil Lot)	_			200.00	1 060 00
9	210	Adjust Mailbox	7.	EA	§	280.00	1,960.00
10	210	Adjust Valve Box (Price to Include adjustment of Survey Monuments)	139.	EA	F	79.00 \$	10,981.00
11	210	Adjust Manhole Ring and Cover (Sanitary and Storm Sewer)	74.	EA	₿	625.00 \$	46,250.00
12	304	Aggregate Base Course (Class 6) - Shoulder Edging Gravel	456.	Tons	ß	32.00 \$	14,592.00
13	304	Aggregate Base Course (Class 6) - Bike Lanes (12" Thick)	1,730.	Tons	₿	29.00 \$	50,170.00
14	304	Subgrade Stabilization (Class 3 Aggregate Base Course - 24" Thick)(Complete in Place)	100.	Tons	<b></b>	<u>61.00</u> §	6,100.00
15	401	Hot Mix Asphalt ( 1" thick Pre-Level) (Grading ST, Binder Grade 64-22)	584.	Tons	ß	100.00 \$	58,400.00
16	401	Hot Mix Asphalt (Bike Lanes - 3" thick) (Grading SX, Binder Grade 64-22)	350.	Tons	ß	100.00 \$	35,000.00
17	401	Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 64-22)	10,664.	Tons	ß	86.65 \$	924,035.60
18	401	Hot Mix Asphalt (Patching - Up to 7" thick) (To Include 6" of Class 6	205.	Tons	ß	144.00\$	29,520.00
		Aggregate Base Course)(Grading SX, Binder Grade 64-22)					
19	608/304	Monolithic Curb Gutter and Sidewalk (vertical or rolled type) to Include 6" of Class 6 Aggregate Base Course	230.	SY	\$	122.00\$	28,060.00
20	608/304	Concrete Curb and Gutter (2' Wide) To Include 6" of Class 6 Aggregate	1,062.	LF .	ß	35.50 \$	37,701.00
		Base Course BF-2 (2)	l of 2)				

## Bid Schedule: 2021 Contract Street Maintenance - Asphalt Overlays

## Addendum #1

CONTRACTOR: Oldcastle SW Group Inc, dba United Companies

Item No.	CDOT,	Description	Quantity	Units		Unit Price	<b>1</b>	Total Price
140.	Oity IXCI.	Description	Quartity	Office		OTHE T FIGURE		1000111100
21	608/304	Concrete Curb Ramp to include 6" of Class 6 Aggregate Base Course	441.	SY	ß	129.00	ß	56,889.00
22	608	Detectable Warning (Wet Set)(Cast Iron)(2'x4')	88.	SF	\$	47.00	₿	4,136.00
23	608/304	Concrete Driveway Section (8"Thick) to Include 6" of Class 6 Aggregate Base Course	1,469.	SY	\$	116.00	ß	170,404.00
24	608	Sidewalk Drain Trough - See Sheet D13 and D14 of the Standard Contract Documents for details.	12.	LF	\$	129.00	ß	1,548.00
25	620	Sanitary Facility	Lump	Sum			β	1,800.00
26	625	Construction Surveying	Lump	Sum			ß	6,026.00
27	626	Mobilization	Lump	Sum			5	92,000.00
28	627- 30405	Preformed Thermoplastic Pavement Marking (Word/Symbol)	291.	SF	\$	21.50	\$ <u></u>	6,256.50
29	627- 30410	Preformed Plastic Pavement Marking (X-Walk/Stopline)	653.	SF	\$	11.30	<b>5</b>	7,378.90
30	630	Traffic Control (Complete In Place)	Lump	Sum			β	79,500.00
31	630	Flagging	3,720.	HR	\$	24.50	5	91,140.00
INC		Incentive HMA 64-22					\$	45,000.00
MCR		Minor Contract Revisions					\$	150,000.00

Bid Amount:
Two million eight-four thousand eight hundred thirty-three dollars 20/100 dollars

**Bid Amount:** 

\$ 2,084,833.20

The undersigned Bidder proposes to subcontract the following portion of Work:

Name & address of Sub-Contractor	Description of work to be performed	% of Contract
Adcock Concrete, 2458 Industrial BLVD GJ	Concrete	14.0%
CC Ent, 830 21 1/2 Rd, GJ	Traffic Control/Flagging	8.0%
Mountian Valley Cont. F 1/2 Rd GJ	Milling	2.0%
TY Striping, Grand Junction	Pavement Markings	0.7%

The undersigned Bidder acknowledges the right of the City to reject any and all Bids submitted and to waive informalities and irregularities therein in the City's sole discretion.

By submission of the Bid, each Bidder certifies, and in the case of a joint Bid each party thereto certifies as to his own organization, that this Bid has been arrived at independently, without collusion, consultation, communication, or agreement as to any matter relating to this Bid with any other Bidder or with any competitor.



## Fidelity and Deposit Company of Maryland

## BID BOND

KNOW ALL MEN BY THESE PRESENTS:

That we, Oldcastle SW Group, Inc., dba United Companies of Mesa County, as Principal, (hereinafter called the "Principal"), and the FIDELITY AND DEPOSIT COMPANY OF MARYLAND, a corporation duly organized under the laws of the State of Illinois, as Surety, (hereinafter called the "Surety"), are held and firmly bound unto City of Grand Junction, Colorado as Obligee, (hereinafter called the "Obligee"), in the sum of FIVE PERCENT OF TOTAL AMOUNT BID Dollars (\$5%), for the payment of which sum well and truly to be made, the said Principal and the said Surety, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has submitted a bid for IFB-4908-21-DH 2021 Contract Street Maintenance - Asphalt Overlays.

NOW, THEREFORE, if the Obligee shall accept the bid of the Principal and the Principal shall enter into a contract with the Obligee in accordance with the terms of such bid and give such bond or bonds as may be specified in the bidding or contract documents with good and sufficient surety for the faithful performance of such contract and for the prompt payment of labor and material furnished in the prosecution thereof, or in the event of the failure of the principal to enter into such contract and give such bond or bonds, if the Principal shall pay to the Obligee the difference not to exceed the penalty hereof between the amount specified in said bid and such larger amount for which the Obligee may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect.

Oldcastle SW Group, Inc., dba United Companies
of Mesa County

By

Kyle Alpha, Vice President

FIDELITY AND DEPOSIT COMPANY OF MARYLAND

Sona Van Horn

Witness

By

Surety

By

Dorothy Feil, Attorney in Fact

C325-150M.

Approved by The American Institute of Architects, A.J.A. Document No. A-310 February 1970 Edition.

Signed and sealed this 30th day of April A.D. ,2021.

#### ZURICH AMERICAN INSURANCE COMPANY COLONIAL AMERICAN CASUALTY AND SURETY COMPANY FIDELITY AND DEPOSIT COMPANY OF MARYLAND POWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS: That the ZURICH AMERICAN INSURANCE COMPANY, a corporation of the State of New York, the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY, a corporation of the State of Illinois, and the FIDELITY AND DEPOSIT COMPANY OF MARYLAND a corporation of the State of Illinois (herein collectively called the "Companies"), by Robert D. Murray, Vice President, in pursuance of authority granted by Article V, Section 8, of the By-Laws of said Companies, which are set forth on the reverse side hereof and are hereby certified to be in full force and effect on the date hereof, do hereby nominate, constitute, and appoint, Kyle ALPHA, Dorothy FEIL, Debbie ELLIOTT and Janel TANNER all of Grand Junction, Colorado and EACH, its true and lawful agent and Attorney-in-Fact, to make, execute, seal and deliver, for, and on its behalf as surety, and as its act and deed: any and all bid bonds issued on behalf of Oldcastle SW Group, Inc. dba United Companies of Mesa and Oldcastle SW Group, Inc. dba Telluride Gravel, each with a penalty not to exceed the sum of \$1,000,000, and the execution of such bid bonds in pursuance of these presents, shall be as binding upon said Companies, as fully and amply, to all intents and purposes, as if they had been duly executed and acknowledged by the regularly elected officers of the ZURICH AMERICAN INSURANCE COMPANY at its office in New York, New York., the regularly elected officers of the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY at its office in Owings Mills, Maryland, and the regularly elected officers of the FIDELITY AND DEPOSIT COMPANY OF MARYLAND at its office in Owings Mills, Maryland, in their own proper persons.

The said Vice President does hereby certify that the extract set forth on the reverse side hereof is a true copy of Article V, Section 8, of the By-Laws of said Companies, and is now in force.

IN WITNESS WHEREOF, the said Vice-President has hereunto subscribed his/her names and affixed the Corporate Seals of the said ZURICH AMERICAN INSURANCE COMPANY, COLONIAL AMERICAN CASUALTY AND SURETY COMPANY, and FIDELITY AND DEPOSIT COMPANY OF MARYLAND, this 25th day of March, A.D. 2020.







ATTEST:

ZURICH AMERICAN INSURANCE COMPANY COLONIAL AMERICAN CASUALTY AND SURETY COMPANY FIDELITY AND DEPOSIT COMPANY OF MARYLAND

By: Robert D. Murray Vice President

Jaure & Brown

By: Dawn E. Brown Secretary

State of Maryland County of Baltimore

On this 25th day of March, A.D. 2020, before the subscriber, a Notary Public of the State of Maryland, duly commissioned and qualified, Robert D. Murray, Vice President and Dawn E. Brown, Secretary of the Companies, to me personally known to be the individuals and officers described in and who executed the preceding instrument, and acknowledged the execution of same, and being by me duly sworn, deposeth and saith, that he/she is the said officer of the Company aforesaid, and that the seals affixed to the preceding instrument are the Corporate Seals of said Companies, and that the said Corporate Seals and the signature as such officer were duly affixed and subscribed to the said instrument by the authority and direction of the said Corporations.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed my Official Seal the day and year first above written.

Constance A. Dunn, Notary Public My Commission Expires: July 9, 2023

Constance a. Dun

#### **EXTRACT FROM BY-LAWS OF THE COMPANIES**

"Article V, Section 8, <u>Attorneys-in-Fact</u>. The Chief Executive Officer, the President, or any Executive Vice President or Vice President may, by written instrument under the attested corporate seal, appoint attorneys-in-fact with authority to execute bonds, policies, recognizances, stipulations, undertakings, or other like instruments on behalf of the Company, and may authorize any officer or any such attorney-in-fact to affix the corporate seal thereto; and may with or without cause modify of revoke any such appointment or authority at any time."

#### CERTIFICATE

I, the undersigned, Vice President of the ZURICH AMERICAN INSURANCE COMPANY, the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY, and the FIDELITY AND DEPOSIT COMPANY OF MARYLAND, do hereby certify that the foregoing Power of Attorney is still in full force and effect on the date of this certificate; and I do further certify that Article V, Section 8, of the By-Laws of the Companies is still in force.

This Power of Attorney and Certificate may be signed by facsimile under and by authority of the following resolution of the Board of Directors of the ZURICH AMERICAN INSURANCE COMPANY at a meeting duly called and held on the 15th day of December 1998.

RESOLVED: "That the signature of the President or a Vice President and the attesting signature of a Secretary or an Assistant Secretary and the Seal of the Company may be affixed by facsimile on any Power of Attorney...Any such Power or any certificate thereof bearing such facsimile signature and seal shall be valid and binding on the Company."

This Power of Attorney and Certificate may be signed by facsimile under and by authority of the following resolution of the Board of Directors of the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY at a meeting duly called and held on the 5th day of May, 1994, and the following resolution of the Board of Directors of the FIDELITY AND DEPOSIT COMPANY OF MARYLAND at a meeting duly called and held on the 10th day of May, 1990.

RESOLVED: "That the facsimile or mechanically reproduced seal of the company and facsimile or mechanically reproduced signature of any Vice-President, Secretary, or Assistant Secretary of the Company, whether made heretofore or hereafter, wherever appearing upon a certified copy of any power of attorney issued by the Company, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

IN TESTIMONY WHEREOF, I have hereunto subscribed my name and affixed the corporate seals of the said Companies, this 30th day of April \_\_\_\_\_\_, 2021\_.







Brian M. Hodges, Vice President

Bush Hodger

TO REPORT A CLAIM WITH REGARD TO A SURETY BOND, PLEASE SUBMIT A COMPLETE DESCRIPTION OF THE CLAIM INCLUDING THE PRINCIPAL ON THE BOND, THE BOND NUMBER, AND YOUR CONTACT INFORMATION TO:

Zurich Surety Claims 1299 Zurich Way Schaumburg, IL 60196-1056 www.reportsfelaims@zurichna.com 800-626-4577 DocuSign Envelope ID: AF8369A1-2AE7-4592-A823-AB69858D2F2F

## ACTION BY WRITTEN CONSENT IN LIEU OF AN ANNUAL MEETING OF THE BOARD OF DIRECTORS

OF

## OLDCASTLE SW GROUP, INC.

The undersigned, being all of the members of the Board of Directors of Oldcastle SW Group, Inc., a Colorado corporation (the "*Corporation*"), do hereby, pursuant to §7-108-202 of the Colorado Business Corporation Act, give this written consent (a) to the dispensation of an annual meeting of the Board of Directors of the Corporation and (b) to the taking of the following actions, such actions to have the same force and effect had a meeting been duly called and held:

#### I. ELECTION OF OFFICERS

**RESOLVED**, that effective January 1, 2020 all previous elections of officers are terminated, and the following persons be, and hereby are, elected to serve as officers of the Corporation (each individually, an "Officer" and collectively, the "Officers") in the capacities set forth opposite their respective names until such time as their successors shall be elected and qualified:

Richard Umbel President

Kyle Alpha Vice President

Martin Merx Chief Financial Officer

Dorothy Feil Secretary, Treasurer, Controller

**FURTHER RESOLVED**, that the Officers be, and each of them hereby is, authorized to execute and deliver agreements, contracts, documents, certificates, and other instruments, under the seal of the Corporation if required, for the purpose of conducting the Corporation's business, including without limitation, selling products and securing construction work, and to take such other action, as they may deem necessary, advisable, convenient, or appropriate to carry out and fully perform duties incident to the office or offices so appointed, and such other duties as may be prescribed by the Board of Directors from time to time;

**FURTHER RESOLVED**, that the following persons are hereby designated officers solely for the purpose of attesting signatures of other officers on behalf of the Corporation, and for executing and attesting various corporate documents, tax returns, affidavits, and similar such instruments as may be necessary from time to time:

Gary P. Hickman	Assistant Secretary	Xavier Balderas	Assistant Secretary
William B. Miller	Assistant Secretary	David C. Lewis	Assistant Secretary
David M. Toolan	Assistant Secretary	Michael F. Deaton	Assistant Secretary

**FURTHER RESOLVED**, that the President of the Corporation may, from time to time, without further action by the Board of Directors, appoint other persons to serve as authorized employees, or remove any individuals from this capacity, and to direct those appointed to take such action, as he may deem necessary, advisable, convenient or appropriate to carry out and fully perform the duties incident to the office of President.

DocuSign Envelope ID: AF8369A1-2AE7-4592-A823-AB69858D2F2F

#### II. REMOVALS

**RESOLVED**, that any current officers of the Corporation not elected in the foregoing resolution are hereby removed.

## III. AUTHORIZATION OF TRADE AND DIVISIONAL NAMES

**RESOLVED**, that the activities and operations of the Corporation may be carried on in any of the following manners or styles as may from time-to-time be deemed necessary or appropriate:

B&B Excavating
Delta Sand & Gravel Co.
Four Corners Materials
Telluride Gravel
United Companies of Mesa County
United Paving, Incorporated
United Redi-Mix, Inc.
United Sand and Gravel Company, Inc.
United Companies

**FURTHER RESOLVED**, that the President of the Corporation may, from time to time, without further action by the Board of Directors, authorize the use of additional trade names, and to deem unauthorized any trade name previously authorized, as he may deem necessary, advisable, convenient or appropriate.

## IV. MISCELLANEOUS

**RESOLVED**, that all actions previously taken by any Officer of the Corporation appointed hereunder in his/her capacity as such Officer be, and each of them hereby is, adopted, ratified, confirmed and approved in all respects as the authorized acts and deeds of the Corporation;

FURTHER RESOLVED, that each undersigned agrees that electronic signatures, whether digital or encrypted, of the Board of Directors are intended to authenticate this consent and to have the same force and effect as manual signatures. As used in the previous sentence, the term "electronic signatures" means any electronic sound, symbol or process attached to or logically associated with this consent and executed and adopted by a member of the Board of Directors with the intent to sign such consent, including, but not limited to, e-mail electronic signatures executed through DocuSign; and

**FURTHER RESOLVED**, that this Consent, following execution by all of the members of the Board of Directors, be filed in appropriate order in the minute book of the Corporation.

PERFORMANCE BOND						
					BOND NO	9379630
KNOW ALL BY THESE PRESE	SENTS. That we. Oldcastle SW Group, Inc. d				United Companies	
	3 River Rd PO Box 360	9 Grand Junction,	CO 81502	9.47	(hereinafter	called the Principal),
as Principal, and				ryland		, a corporation
Duly organized under the la					ne Surety), as Sure	ety, are held and firmly
bound unto			f Grand Junction			·· · · ·
(hereinafter called the Oblig	gee), in the sum of	Two Milli	on Eighty-five Tho	usand Five Hu	ndred Fifty-three & 20	0/100
( \$2,085,553.20 )	Dollars, for the pay	ment of which	sum well and t	ruly to be m	ade, we, the said	Principal and the said
Surety, bind ourselves, our	heirs, executors, adm	ninistrators, suc	cessors and assi	igns, jointly a	nd severally, firmly	y by these presents.
Signed and sealed this	27th	day of	May	2021		
WHEREAS, said Principal ha	s entered into a writt	en Contract wi	th said Obligee,	dated	May 4, 2021	·
for _	IFB-4908-2	1-DH 2021 Contr	act Street Mainten	ance - Asphalt	Overlays	
in accordance with the term herein:		*	and a spanning of the second o		**************************************	φ.
NOW, THEREFORE, THE CO and perform each and ever kept, done and performed, the above named Obligee, Principal so to do, then this NO SUIT, ACTION OR PROC	ry, all and singular, the times and in the all loss and damage obligation shall be ne	ne matters and he manner in s which said Ob ull and void; ot ee to recover o	things in said c aid contract spe ligee may susta nerwise shall re n this bond shal	contract set for ecified, or sha nin by reason main in full fo	orth and specified Il pay over, make of of failure or defa orce and effect.	to be by said Principal good and reimburse to ult on the part of said
and perform each and ever kept, done and performed, the above named Obligee, Principal so to do, then this	ry, all and singular, the times and in the all loss and damage obligation shall be ne	ne matters and he manner in s which said Ob ull and void; ot ee to recover o	things in said c aid contract spe ligee may susta nerwise shall re n this bond shal	contract set for ecified, or sha nin by reason main in full fo	orth and specified Il pay over, make of of failure or defa orce and effect.	to be by said Principal good and reimburse to ult on the part of said
and perform each and ever kept, done and performed, the above named Obligee, Principal so to do, then this NO SUIT, ACTION OR PROC	ry, all and singular, the times and in the all loss and damage obligation shall be ne	ne matters and he manner in s which said Ob ull and void; ot ee to recover o	things in said of aid contract spelligee may sustainerwise shall refer this bond shall said Contract.	ontract set for contract set for contrac	orth and specified Il pay over, make of failure or defa orce and effect. d unless the same up, Inc. dba United C	to be by said Principal good and reimburse to ult on the part of said be commenced within

BOND NO. 9379630						
e SW Group, Inc. dba United Companies						
as Principal, hereinafter called Principal, and						
, a Illinois , Corporation, as Surety,						
City of Grand Junction						
d Owner, for the use and benefit of Claimants as herein defined, in						
ee & 20/100 Dollars (\$2,085,553.20), for the						
, administrators, successors and assigns, jointly and severally, firmly						
entered into a contract with Owner foraintenance - Asphalt Overlays						
NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION IS SUCH, That if the Principal shall promptly make payment to all Claimants as hereinafter defined, for all labor and material used or reasonably required for use in the performance of the Contract, then this obligation shall be void; otherwise it shall remain in full force and effect, subject, however, to the following conditions:  1. A Claimant is defined as one having a direct Contract with the Principal or with a Subcontractor of the Principal for labor, material, or both, used or reasonably required for use in the performance of the Contract.						
2. The above named Principal and Surety hereby jointly and severally agree with the Owner that every Claimant as herein defined, who has not been paid in full before the expiration of the period of ninety (90) days after the date on which the last of such Claimant's work or labor was done or performed, or materials where furnished by such Claimant, may sue on this bond for the use of such Claimant, prosecute the suit to final judgment for such sum or sums as my be justly due Claimant, and have execution thereon.						
3. No suit or action shall be commenced hereunder by any Claimant.						
a) Unless Claimant, other than one having a direct Contract with the Principal, shall have given notice to any two of the following: The Principal, the Owner, or the Surety above named, within ninety (90) days after such Claimant did or performed the last of the work or labor, or furnished the last of the materials for which said claim is made.						
b) After the expiration of one (1) year following the date on which Principal ceased work on said Contract. If the provisions of paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.						
c) Other than in a state court of competent jurisdiction in and for the county or other political subdivision of the state in which the Project, or any part thereof, is situated, or in the United States District Court for the district in which the Project, or any part thereof, is situated, and not elsewhere.						
ent or payments made in good faith hereunder.						
,						
Oldcastle SW Group, Inc. dba United Companies						
Principal						
Alpha, Vice Přesident						
Fidelity and Deposit Company of Maryland						
The soft soft soft soft soft soft soft soft						
The state of the s						
Linda Nipper, Attorney-in-Fact						
of train						

.

## ZURICH AMERICAN INSURANCE COMPANY COLONIAL AMERICAN CASUALTY AND SURETY COMPANY FIDELITY AND DEPOSIT COMPANY OF MARYLAND POWER OF ATTORNEY

The said Vice President does hereby certify that the extract set forth on the reverse side hereof is a true copy of Article V, Section 8, of the By-Laws of said Companies, and is now in force.

IN WITNESS WHEREOF, the said Vice-President has hereunto subscribed his/her names and affixed the Corporate Seals of the said ZURICH AMERICAN INSURANCE COMPANY, COLONIAL AMERICAN CASUALTY AND SURETY COMPANY, and FIDELITY AND DEPOSIT COMPANY OF MARYLAND, this 11th day of July, A.D. 2019.







ATTEST: ZURICH AMERICAN INSURANCE COMPANY COLONIAL AMERICAN CASUALTY AND SURETY COMPANY FIDELITY AND DEPOSIT COMPANY OF MARYLAND

By: Robert D. Murray Vice President

Dawn & Brown

By: Dawn E. Brown Secretary

State of Maryland County of Baltimore

On this 11th day of July, A.D. 2019, before the subscriber, a Notary Public of the State of Maryland, duly commissioned and qualified, Robert D. Murray, Vice President and Dawn E. Brown, Secretary of the Companies, to me personally known to be the individuals and officers described in and who executed the preceding instrument, and acknowledged the execution of same, and being by me duly sworn, deposeth and saith, that he/she is the said officer of the Company aforesaid, and that the seals affixed to the preceding instrument are the Corporate Seals of said Companies, and that the said Corporate Seals and the signature as such officer were duly affixed and subscribed to the said instrument by the authority and direction of the said Corporations.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed my Official Seal the day and year first above written.

Sandra Sandra

Constance A. Dunn, Notary Public My Commission Expires: July 9, 2023

Constance a. Dunn

## **EXTRACT FROM BY-LAWS OF THE COMPANIES**

"Article V, Section 8, <u>Attorneys-in-Fact</u>. The Chief Executive Officer, the President, or any Executive Vice President or Vice President may, by written instrument under the attested corporate seal, appoint attorneys-in-fact with authority to execute bonds, policies, recognizances, stipulations, undertakings, or other like instruments on behalf of the Company, and may authorize any officer or any such attorney-in-fact to affix the corporate seal thereto; and may with or without cause modify of revoke any such appointment or authority at any time."

#### CERTIFICATE

I, the undersigned, Vice President of the ZURICH AMERICAN INSURANCE COMPANY, the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY, and the FIDELITY AND DEPOSIT COMPANY OF MARYLAND, do hereby certify that the foregoing Power of Attorney is still in full force and effect on the date of this certificate; and I do further certify that Article V, Section 8, of the By-Laws of the Companies is still in force.

This Power of Attorney and Certificate may be signed by facsimile under and by authority of the following resolution of the Board of Directors of the ZURICH AMERICAN INSURANCE COMPANY at a meeting duly called and held on the 15th day of December 1998.

RESOLVED: "That the signature of the President or a Vice President and the attesting signature of a Secretary or an Assistant Secretary and the Seal of the Company may be affixed by facsimile on any Power of Attorney...Any such Power or any certificate thereof bearing such facsimile signature and seal shall be valid and binding on the Company."

This Power of Attorney and Certificate may be signed by facsimile under and by authority of the following resolution of the Board of Directors of the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY at a meeting duly called and held on the 5th day of May, 1994, and the following resolution of the Board of Directors of the FIDELITY AND DEPOSIT COMPANY OF MARYLAND at a meeting duly called and held on the 10th day of May, 1990.

RESOLVED: "That the facsimile or mechanically reproduced seal of the company and facsimile or mechanically reproduced signature of any Vice-President, Secretary, or Assistant Secretary of the Company, whether made heretofore or hereafter, wherever appearing upon a certified copy of any power of attorney issued by the Company, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

IN TESTIMONY WHEREOF, I have hereunto subscribed my name and affixed the corporate seals of the said Companies, this 27th day of May 2021.





Burn Hodyis

Brian M. Hodges, Vice President

TO REPORT A CLAIM WITH REGARD TO A SURETY BOND, PLEASE SUBMIT A COMPLETE DESCRIPTION OF THE CLAIM INCLUDING THE PRINCIPAL ON THE BOND, THE BOND NUMBER, AND YOUR CONTACT INFORMATION TO:

Zurich Surety Claims
1299 Zurich Way
Schaumburg, IL 60196-1056
www.reportsfclaims@zurichna.com
800-626-4577



## CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY) 5/28/2021

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

	9				
PRODUCER Liberty Mutual Insur-	ance Co. National Insurance East	CONTACT NAME:	Valerie Reece		
2000 Westwood Dr.		PHONE (A/C, No, Ext):	513-867-3822	FAX (A/C, No):	
Wausau, WI 54401		E-MAIL ADDRESS:	Oldcastle.certs@LibertyM	Didcastle.certs@LibertyMutual.com	
			INSURER(S) AFFORDING COVERA	GE	NAIC#
www.LibertyMutual.com		INSURER A: Liber	rty Mutual Fire Insurance Cor	npany	23035
INSURED	02-GRA)	INSURER B : Liber	rty Insurance Corporation		42404
Oldcastle SW Group, Inc. (1 2273 River Road		INSURER C:			
Grand Junction CO 81502		INSURER D :			
		INSURER E :			
		INSURER F:			
COVEDACES	CERTIFICATE NUMBER, ASSOCIATE		DEV/ICION I	MIMPED.	

CERTIFICATE NUMBER: 62062955 REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.								
NSR LTR	TYPE OF INSURANCE	ADDL : INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMIT	S
Α	CLAIMS-MADE OCCUR	1	1	TB2-C81-004095-110	9/1/2020	9/1/2021	EACH OCCURRENCE DAMAGE TO RENTED PREMISES (Ea occurrence)	\$2,000,000 \$300,000
	✓ Primary/Non-Contributory			XCU Coverage Included			MED EXP (Any one person)	\$50,000
	✓ Separation of Insured						PERSONAL & ADV INJURY	\$2,000,000
	GEN'L AGGREGATE LIMIT APPLIES PER:						GENERAL AGGREGATE	\$2,000,000
	POLICY PRO- LOC						PRODUCTS - COMP/OP AGG	\$2,000,000
	OTHER:							\$
4	AUTOMOBILE LIABILITY	1	1	AS2-C81-004095-120	9/1/2020	9/1/2021	COMBINED SINGLE LIMIT (Ea accident)	\$2,000,000
	✓ ANY AUTO			ACO COA OCACOO COO	0/4/0000	0/4/0004	BODILY INJURY (Per person)	\$
١.	OWNED SCHEDULED AUTOS ONLY AUTOS		AS2-C81-054502-520 Physical Damage only:	9/1/2020	9/1/2021	BODILY INJURY (Per accident)	\$	
	HIRED NON-OWNED AUTOS ONLY			Comprehensive Ded \$10,000			PROPERTY DAMAGE (Per accident)	\$
				Collision Ded \$10,000				\$
	UMBRELLA LIAB OCCUR						EACH OCCURRENCE	\$
	EXCESS LIAB CLAIMS-MADE						AGGREGATE	\$
	DED RETENTION \$							\$
3	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY		1	WA7-C8D-004095-020	9/1/2020	9/1/2021	✓ PER OTH- STATUTE ER	
	NYPROPRIETOR/PARTNER/EXECUTIVE	N/A		All except OH, ND, WA, WY			E.L. EACH ACCIDENT	\$1,000,000
3	OFFICER/MEMBEREXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below			WC7-C81-004095-010	9/1/2020	9/1/2021	E.L. DISEASE - EA EMPLOYEE	\$1,000,000
				WI, MN			E.L. DISEASE - POLICY LIMIT	\$1,000,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

RE: 2021 Contract Street Maintenance - Asphalt Overlays IFB-9808-21-DH.
City of Grand Junction is listed as additional insured with regards to the general liability and automobile liability policies, on a primary and non-contributory basis, where required by written contract. Waiver of subrogation is included in favor of the additional insured, where required by written contract, and where applicable by law.

CERTIFICATE HOLDER	CANCELLATION
City of Grand Junction Department of Public Works - Engineering Division Attn: Eric Mocko, Project Manager	SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.
333 West Avenue, Building C Grand Junction CO 81501	AUTHORIZED REPRESENTATIVE  Yaliric F. Keece
	Valerie Reece

CANCELL ATION

© 1988-2015 ACORD CORPORATION. All rights reserved.

CERTIFICATE UOI DED