

Bid Schedule: 2022 Waterline Replacement Phase 1

| Item No. | CDOT, City Ref. | Description | Quantity | Units | Unit Price | Total Price |
|----------|-----------------|---|----------|----------|------------|-------------|
| 1 | 108.2 | Water Main (6") (C-900 PVC, DR-18) (Includes cost of restrained connection to existing pipe) | 7,465. | LF | \$ _____ | \$ _____ |
| 2 | 108.3 | Cross (8" x 6") MJ | 1. | EA | \$ _____ | \$ _____ |
| 3 | 108.3 | End Cap/Plug (6") (Includes Concrete Thrustblock per City Std Detail W-07 & W-08) | 1. | EA | \$ _____ | \$ _____ |
| 4 | 108.3 | Tee (6" x 6") MJ Swivel Tee | 10. | EA | \$ _____ | \$ _____ |
| 5 | 108.3 | Fire Hydrant Assembly (6") | 12. | EA | \$ _____ | \$ _____ |
| 6 | 108.3 | Elbow (6" x less than 90 deg) | 16. | | \$ _____ | \$ _____ |
| 7 | 108.4 | Gate Valve (6") | 21. | EA | \$ _____ | \$ _____ |
| 7 | 108.4 | Service Tap - Includes Corporation Stop (3/4") | 62. | EA | \$ _____ | \$ _____ |
| 8 | 108.4 | Water Service Line (3/4") (Type K Copper) (If Lead or Poly service line is encountered, water service shall be replaced to meter) (Includes cost of connection to existing pipe) | 460. | LF | \$ _____ | \$ _____ |
| 9 | 202 | Remove Existing Fire Hydrant (Return Hydrant to City Shops) | 12. | EA | \$ _____ | \$ _____ |
| 10 | 202 | Abandon Existing Water Valve (Close valve, remove top half of existing valve box, fill cavity to finished subgrade with flow-fill material) | 15. | EA | \$ _____ | \$ _____ |
| 11 | 202 | Abandon Pipe (Abandon pipe by plugging ends with concrete) | 20. | EA | \$ _____ | \$ _____ |
| 12 | 202 | Removal of Concrete Curb and Gutter | 40. | LF | \$ _____ | \$ _____ |
| 13 | 202 | Removal of Concrete Sidewalk | 300. | SF | \$ _____ | \$ _____ |
| 14 | 202 | Removal of Asphalt +C20:C37Mat (Planning) (2" Thick for T-Top Section) | 47,000. | SF | \$ _____ | \$ _____ |
| 15 | 202 | Removal of Asphalt Mat (Full Depth) | 47,200. | SF | \$ _____ | \$ _____ |
| 16 | 208 | Erosion & Sediment Control | | Lump Sum | --- | \$ _____ |
| 17 | 210 | Reset Landscape Ground Cover (Match in Kind) (Contractor shall remove ground cover and underlying weed barrier as needed and stockpile materials. Contractor shall reset these materials and provide additional materials as needed) | 400. | SF | \$ _____ | \$ _____ |

Bid Schedule: 2022 Waterline Replacement Phase 1

| Item No. | CDOT, City Ref. | Description | Quantity | Units | Unit Price | Total Price |
|----------|-----------------|--|----------|----------|------------|----------------------|
| 18 | 212 | Seeding (20 lbs/AC) | 0.1 | AC | \$ _____ | \$ _____ |
| 19 | 304 | Aggregate Base Course (Class 6) (6" thick) | 5,250. | SY | \$ _____ | \$ _____ |
| 20 | 401 | Hot Bituminous Pavement (Patching) (3 " Thick Bottom Lift, 2" Thick Top Lift) (Grading SX, PG 64-22) (GYR.=75) (One 3" Lift Bottom Mat) Includes T-Top | 50,000. | SF | \$ _____ | \$ _____ |
| 21 | 608 | Concrete Drainage Pan (6' Wide x 8" Thick) (Match in Kind) (Includes #5 rebar tie-bars) (City Std. Detail C-12) | 5. | SY | \$ _____ | \$ _____ |
| 22 | 608 | Concrete Curb and Gutter (2' Wide) (Match in Kind) (City Std. Detail C-05) | 50. | LF | \$ _____ | \$ _____ |
| 23 | 608 | Concrete Sidewalk (6") (Match in Kind) (City Std. Detail C-10) | 300. | SF | \$ _____ | \$ _____ |
| 24 | 620 | Portable Sanitary Facility | | Lump Sum | --- | \$ _____ |
| 25 | 625 | Construction Surveying (Includes As-Built Drawings) | | Lump Sum | --- | \$ _____ |
| 26 | 626 | Mobilization | | Lump Sum | --- | \$ _____ |
| 27 | 630 | Traffic Control (Complete in Place) | | Lump Sum | --- | \$ _____ |
| FA | 202 | Disposal of Radioactive Material (Dispose at City Shops, 333 West Ave.) | 1,000. | CY | \$ _____ | \$ _____ |
| FA | 206 | Structure Backfill (Flow-Fill) (This flow-fill quantity takes into account the flow-fill quantity necessary for Abandon Existing Water Valve, and Abandon Manhole) | 50. | CY | \$ _____ | \$ _____ |
| FA | | Utility Allowance to Support & Relocate Existing Utilities | | Lump Sum | --- | \$ _____ |
| FA | | Utility Locates and Potholing | | Lump Sum | --- | \$ _____ |
| MCR | | Minor Contract Revisions | | --- | --- | \$ <u>150,000.00</u> |

Bid Amount: \$ _____

Bid Amount:

dollars