

N:\Landproj\24 Road and G Road Intersection\dwg\SUMMARY OF APPROXIMATE QUANTITIES.dwg, 11/22/2022 3:31:52 PM

Item No.	CDOT, City Ref.	Description	Quantity	Units
84	304	Aggregate Base Course (Class 1) (10" Thick) (G Road Pave)	19,435.	SY
85	304	Aggregate Base Course (Class 1) (10" Thick) (Spur Roads Pave)	600.	SY
86	304	Aggregate Base Course (Class 6) (8" Thick) (24 Road Pave)	21,010.	SY
87	304	Aggregate Base Course (Class 6) (8" Thick) (G Road Pave)	19,435.	SY
88	304	Aggregate Base Course (Class 6) (8" Thick) (Spur Roads Pave)	600.	SY
89	304	Aggregate Base Course (Class 6) (12" Thick) (Spur Roads Pave outside full rd section)	3,825.	SY
90	304	Aggregate Base Course (Class 6) (6" Thick) (639 24 Road parking Pave)	30.	SY
91	304	Aggregate Base Course (Class 6) (8" Thick) (Roundabout)	3,815.	SY
92	304	Aggregate Base Course (Class 6) (8" Thick) (Bus Pullout)	125.	SY
93	304	Washed Rock Surface Course (Driveway) (3" Thick)	75.	SY
94	306	Reconditioning (6" Deep) (24 Rd)	21,010.	SY
95	306	Reconditioning (6" Deep) (G Rd)	19,435.	SY
96	306	Reconditioning (6" Deep) (Spur Rds that achieve full rd section)	600.	SY
97	306	Reconditioning (6" Deep) (Spur Rds outside full rd section)	3,825.	SY
98	306	Reconditioning (6" Deep) (Roundabout)	3,815.	SY
99	306	Reconditioning (6" Deep) (Bus Pullout)	125.	SY
100	328	4 Inch PVC Irrigation Sleeve, 18" bury under walks	320.	LF
101	328	4 Inch PVC Irrigation Sleeve, 30" bury under roadways	340.	LF
102	328	6 Inch SDR 80 Irrigation Sleeve	2,340.	LF
103	328	3/4 Inch Quick Coupler Valve	13.	EA
104	328	1 Inch Automatic Control Valve	30.	EA
105	328	2-wire Control Wire	6,300.	LF
106	328	2-wire Control, including decoders, grounding	1.	LS
107	328	Jumbo Valve Box	15.	EA
108	328	Isolations Valves	19.	EA
109	328	1 Inch PVC Lateral Pipe	12,340.	LF
110	328	Riser Assembly to Compression Tee (not incl. tree rings)	158.	EA
111	328	1/2"/17mm Netafim Drip Tubing with emitters	6,450.	LF
112	328	Netafim CV Techline with emitters	8,000.	LF
113	328	Tree Ring Assembly	141.	EA
114	328	1/2 Inch Flush Box Assembly	103.	EA
115	328	Air Relief/Pressure Relief Assembly	3.	EA
116	328	Adjust Existing Gas Station Irrigation	1.	LS
117	329	Sod	2,285.	SF
118	329	Soil Amendment (To be tilled)	72,218.	SF
119	329	Type 1 Rock - 1/2" Tan Granite	91,851.	SF
120	329	Type 2 Rock - 3" La Sal Purple	5,208.	SF
121	329	Type 3 Rock - 1-1/2" Tan Granite	840.	SF
122	329	Concrete Edger	25.	LF
123	329	Landscape Boulder - Small (2'x2'x1.5')	22.	EACH

REVISION	DESCRIPTION	DATE	DRAWN BY	JCS	DATE	2022
REVISION	ADDENDUM 4	2022-11-17	DESIGNED BY	JCS	DATE	2022
REVISION			CHECKED BY	ALC/ER	DATE	2022
REVISION			APPROVED BY	KAH	DATE	2022

NO SCALE



PUBLIC WORKS  
ENGINEERING DIVISION  
PROJECT NO. 207-F210302L

24 ROAD AND G ROAD  
SUMMARY OF APPROXIMATE QUANTITIES  
- 3