

Bid Schedule: 2023 Overlays - Concrete

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	207	Restore Landscaping		Lump Sum	---	\$ _____
2	208	Erosion Control (Complete in Place)		Lump Sum	---	\$ _____
3	401	Hot Mix Asphalt (Patching)(4" thick)(Grading SX, Bider Grade 64-22) to include 6" of Aggregate Base Course (Class 6)	443.	SY	\$ _____	\$ _____
4	608	Detectable Warning (Wet Set)(Cast Iron)(2'x4')	46.	EA	\$ _____	\$ _____
5	620	Sanitary Facility		Lump Sum	---	\$ _____
6	626	Mobilization		Lump Sum	---	\$ _____
7	630	Traffic Control (Complete In Place) to include Traffic Control Plan(s)		Lump Sum	---	\$ _____
8	608/304	Concrete Tie-In to Existing Driveway (6" depth)(max 3' width) to Include 6" of Class 6 Aggregate Base Course	530.4	SY	\$ _____	\$ _____
9	608/304	Concrete Curb Ramp (Standard Concrete Detail C-21) to Include 6" of Class 6 Aggregate Base Course	74.8	SY	\$ _____	\$ _____
10	608/304	Concrete Ramp (Various)(Patterson) to Include 6" of Class 6 Aggregate Base Course	798.6	SY	\$ _____	\$ _____
11	609/304	Concrete Driveway Section (Standard Concrete Detail C-08) to Include 6" of Class 6 Aggregate Base Course	1,420.	SY	\$ _____	\$ _____
MCR		Minor Contract Revisions	---	---	---	\$ 30,000.00
Bid Amount:					\$	_____

Bid Amount:

dollars