To access the Agenda and Backup Materials electronically, go to <a href="https://www.gjcity.org">www.gjcity.org</a>



### PLANNING COMMISSION AGENDA IN-PERSON/VIRTUAL HYBRID MEETING CITY HALL AUDITORIUM, 250 N 5<sup>th</sup> STREET TUESDAY, OCTOBER 10, 2023 - 5:30 PM

Attend virtually: bit.ly/GJ-PC-10-10-23

#### Call to Order - 5:30 PM

#### **Consent Agenda**

**1.** Minutes of Previous Meeting(s)

#### Regular Agenda

- Consider a request by Senergy Builders, LLC to zone 0.23 acres from PD (Planned Development) to R-12 (Residential – 12 du/ac) located at the intersection of Brookwillow Loop and Orion Way, Parcel #2945-041-25-002 - WITHDRAWN
- 2. Consider a request from PERS Investments, LLC to zone 1.49 acres of property within the PERS Investments Annexation to C-2 (General Commercial) located at 3175 D Road.
- 3. Consider a Request by the City of Grand Junction (City) to Amend Title 29 of the Grand Junction Municipal Code to modify and clarify various provisions of the Transportation Engineering Design Standards (TEDS).

#### Other Business

#### **Adjournment**

#### GRAND JUNCTION PLANNING COMMISSION September 12, 2023, 5:30 PM MINUTES

The meeting of the Planning Commission was called to order at 5:33 p.m. by Commissioner Teske.

Those present were Planning Commissioners; Shanon Secrest, Sandra Weckerly, Kim Herek, JB Phillips, Melanie Duyvejonck and Keith Ehlers.

Also present were Jamie Beard (City Attorney), Niki Galehouse (Planning Supervisor), Dave Thornton (Principal Planner), Dani Stine (Senior Planner), Jessica Johnsen (Senior Planner), Madeline Robinson (Planning Technician), and Jacob Kaplan (Planning Technician).

There were 3 members of the public in attendance, and 1 virtually.

#### CONSENT AGENDA

#### 1. Approval of Minutes

Minutes of Previous Meeting(s) from August 22, 2023.

This item was moved to the regular agenda for further discussion.

#### 2. Village Center Way Easement Vacation

VAC-2023-529

Consider a request to partially vacate a 14-foot multipurpose easement and to partially vacate a 10-foot drainage easement on a 0.19-acre parcel located at 2698 Village Center Way.

This item was not heard or approved at this hearing

#### **REGULAR AGENDA**

#### 1. Approval of Minutes

Minutes of Previous Meeting(s) from August 22, 2023

#### **Questions for staff**

Commissioner Weckerly asked for clarification on why transcribed minutes were being provided for this hearing. She asked if continuing approval of these minutes to a future hearing would prevent the project from moving forward.

#### **Motion and Vote**

Commissioner Teske made the following motion "I would move that we continue determining our minutes from the August 22<sup>nd</sup> meeting until our next regularly scheduled meeting."

Commissioner Ehlers seconded; motion passed 7-0.

#### 2. NorthStar Towing CUP

CUP-2023-425

Consider a request by JHoward Enterprise, Inc. dba NorthStar Towing for a Conditional Use Permit to operate an Impound Lot on 1.24 acres located at 2105 H Road.

#### **Staff Presentation**

Jessica Johnsen, Senior Planner, introduced exhibits into the record and provided a presentation regarding the request.

Jenni Henson with NorthStar Towing was present and available for questions.

#### **Questions for staff**

#### **Public Hearing**

The public comment period was opened at 5:00 p.m. on Tuesday, September 5, 2023, via www.GJSpeaks.org.

There were no public comments.

The public comment period was closed at 5:53 p.m. on September 12, 2023.

#### **Discussion**

Commissioner Weckerly asked where impound lots are normally allowed without obtaining a conditional use permit.

#### **Motion and Vote**

Commissioner Secrest made the following motion "Mr. Chairman, on the Conditional Use Permit for the property located at 2105 H Road, City File number CUP-2023-425, I move that the Planning Commission approve the CUP with the findings of fact and conditions listed in the staff report."

Commissioner Ehlers seconded; motion passed 7-0.

#### 3. Adams Enclave Annexation

ANX-2023-262

Consider a zone of annexation of an area consisting of 0.23 acres of enclaved property, from County RSF-4 (Residential Single Family -4 dwelling units per acre) to City C-2 (General Commercial) located at 2738 B  $\frac{1}{4}$  Road.

#### **Staff Presentation**

Dave Thornton, Principal Planner, introduced exhibits into the record and provided a presentation regarding the request.

#### Questions for staff

Commissioner Ehlers asked what triggered the city to annex the property. He asked if the property had to be completely surrounded by City properties in order to be annexed. He asked if right-of-way was considered in determining adjacent properties. He asked if the property would be taxed as commercial or residential. He asked if the rezone to commercial would inhibit development of any future uses that are allowed in residential but not in commercial districts.

Commissioner Teske asked why staff felt Criteria 1 had not been met regarding the annexation itself being considered a subsequent event. He asked why the annexed property was being rezoned to City C-2 instead of a zone district that supported the current residential use. He asked for clarification that this annexation would be considered a "non-conforming use" per the code.

Niki Galehouse provided clarification on residential uses allowed in commercial zone districts per code.

Dave Thornton responded to commissioner questions.

#### **Public Hearing**

The public comment period was opened at 5:00 p.m. on Tuesday, September 5, 2023, via www.GJSpeaks.org.

Rick Crabtree asked if his taxes would increase as a consequence of being annexed.

Dave Thornton stated that he believed this property would continue to be taxed as residential.

Commissioner Ehlers recommended that Mr. Crabtree contact the County Assessor's Office with any tax questions he has.

The public comment period was closed at 6:18 p.m. on September 12, 2023.

#### Discussion

Commissioner Weckerly expressed concerns over creating a non-conforming use and potential tax increases by rezoning the property to commercial instead of residential.

Commissioner Secrest commented that because the current homeowner would not be impacted by the rezone to commercial, it made sense to rezone to commercial now versus requiring a prospective buyer to rezone in the future.

#### **Motion and Vote**

Commissioner Secrest made the following motion "Mr. Chairman, on the Zone of Annexation request for the property located at 2738 B ¼ Road, City file number ANX-2023-262, I move that the Planning Commission forward a recommendation of approval to City Council of the C-2 (General Commercial) with the findings of fact as listed in the staff report."

Commissioner Herek seconded; motion passed 7-0.

ANX-2023-263

Consider a zone of annexation of a 23.35-acre enclaved area consisting of 9.24 acres of enclaved properties from County C-2 (General Commercial District) to City C-2 (General Commercial) located at 232 27 ¼ Rd through 241 27 ¼ Rd and 2739 Hwy 50 and 2739 Hwy 50, and 2.04 acres of enclaved properties from County RSF-4 (Residential Single Family – 4 District) to City C-2 located at 2736 ½ B ¼ Rd and 2735 Hwy 50, and 0.51 acres of enclave property from County RSF-4 to City R-8 (Residential 8 du/ac) located at 2736 B ¼ Rd.

#### **Staff Presentation**

Dani Stine, Senior Planner, introduced exhibits into the record and provided a presentation regarding the request.

#### **Questions for staff**

Commissioner Ehlers asked if the affected businesses would be required to collect city sales tax as a consequence of this annexation. He asked if any of the affected businesses would be required to complete an Industrial Pre-Treatment Survey as a consequence of this annexation. He asked about the application fee for sales tax licenses. He asked how many legal non-conformities would be created as a result of the annexation.

Commissioner Teske asked why staff felt Criteria 1 had been met regarding the annexation itself being considered a subsequent event whereas it had not been met for the Adams Enclave Annexation. He asked about the legal non-conformities being created as a consequence of this annexation.

Dani Stine responded to commissioner questions and comments.

#### **Public Hearing**

The public comment period was opened at 5:00 p.m. on Tuesday, September 5, 2023, via www.GJSpeaks.org.

There were no public comments.

The public comment period was closed at 6:46 p.m. on September 12, 2023.

#### **Discussion**

Commissioner Secrest commented that while he was not in favor of potential tax increases, he noted that none of the affected owners attended the public hearing to oppose the annexation. He asked if the two proposed motions were either/or or if they should both be read.

Commissioner Ehlers echoed Commissioner Secrest's comments.

#### **Motion and Vote**

Commissioner Secrest made the following motion "Mr. Chairman, on the Zone of Annexation request for the properties located at 232 27 ¼ Rd through 241 27 ¼ Rd and 2739 Hwy 50, 2735 Hwy 50 and 2736 ½ B ¼ Rd, City file number ANX-2023-263, I move that the Planning Commission forward recommendation of approval to City Council of the C-2 (General Commercial) with the findings of fact as listed in the staff report.

Commissioner Ehlers seconded; motion passed 7-0.

Commissioner Secrest made the following motion "Mr. Chairman, on the Zone of Annexation request for the property located at 2736 B ¼ Rd, City file number ANX-2023-263, I move that the Planning Commission forward recommendation of approval to City Council of the R-8 (Residential 8 du/ac) with the findings of fact as listed in the staff report."

Commissioner Phillips seconded; motion passed 7-0.

#### 5. Brookwillow Village Filing 6 Rezone

RZN-2023-160

Consider a request by Senergy Builders, LLC to zone 0.23 acres from PD (Planned Development) to R-12 (Residential – 12 du/ac) located at the intersection of Brookwillow Loop and Orion Way, Parcel #2945-041-25-002.

The applicant requested that this item be moved to the October 10<sup>th</sup> Planning Commission hearing.

Commissioner Teske recused himself from deliberating on this item.

The motion to continue this item passed 6-0.

#### OTHER BUSINESS

#### **ADJOURNMENT**

Commissioner Ehlers moved to adjourn the meeting.

The vote to adjourn was 7-0.

The meeting adjourned at 6:51 p.m.

# GRAND JUNCTION PLANNING COMMISSION August 22, 2023, 5:30 PM MINUTES

The meeting of the Planning Commission was called to order at 5:30 p.m. by Commissioner Teske.

Those present were Planning Commissioners; Ken Scissors, Sandra Weckerly, Shanon Secrest, Melanie Duyvejonck, Kim Herek, and Keith Ehlers.

Also present were Jamie Beard (City Attorney), Niki Galehouse (Planning Supervisor), Kristen Ashbeck (Principal Planner), Trenton Prall (Public Works Director) and Madeline Robinson (Planning Technician).

There were 21 members of the public in attendance, and 1 virtually.

#### CONSENT AGENDA

#### 1. Approval of Minutes

Minutes of Previous Meeting(s) from August 8, 2023.

#### **REGULAR AGENDA**

1.

#### C ½ Road Gravel Pit CUP

CUP-2021-616

Consider a Request by M & D Enterprises for a Conditional Use Permit to Allow Sand and Gravel Extraction on a total of 27.8 acres in a CSR (Community Services and Recreation) Zone District located at 2855 C 1/2 Road.

#### **Staff Presentation**

Kristen Ashbeck, Principal Planner, introduced exhibits into the record and provided a presentation in conformity with her staff report regarding the request.

Trenton Prall, Kathleen Fisher with Colorado Parks and Wildlife, and Scott May the Mesa County Public Works Director were present for any questions.

Mark Austin with Austin Civil Group provided a presentation on behalf of the applicant M & D Enterprises, LLC. He began with a description of the background of the project as it progressed through the City's process: general meeting, two neighborhood meetings, Annexation and Zone of Annexation. He indicated it has taken them almost four years to get to this point and more steps to accomplish after the meeting.

He explained that the project will provide a minimum ten-foot-tall berm with 3 to 1 slopes and landscaping along the street frontage and the adjacent properties. The berm is taller than required by the Code to buffer the development from the neighbors. There are some limitations

on the south end due to the floodplain requirements. The buffer will be a visual amenity for the residential neighbors.

Additional buffers include a 125-foot excavation buffer and a 250-foot separation from the crusher equipment to the five existing homes adjacent to the development. Four of the homes are 200 feet from the excavation. The applicant will not generate more noise than 65 decibels at the property line. There will be a 100-foot buffer along the Colorado River with no disturbance from the development. Trees and vegetation shall be preserved in the buffer areas.

The project will include a trail along the Colorado River with an easement for use by the public.

As required by the Code, a traffic study was provided to the City from the applicant and the applicant has addressed all of the City's concerns. The operation will have only three employees working regularly at the site. On average five medium sized, smaller dump trucks will be coming and going from the site each day, but there are also five large gravel trucks. Basically, ten gravel trips per day. C½ Road currently has peak hours in the morning of 65 trips and 56 trips in the afternoon. The gravel pits operation will only be adding 7% capacity to C½ Road. This is a low amount of traffic on that road. C½ Road to 28 Road to the Riverside Parkway will be the primary route from the site. Only rights turns are allowed by the Public Works Director on 29 Road. The applicant has agreed to keep the haul routes cleaned and maintained. The applicant is paying \$155,000.00 towards the improvements to be made to C½ Road and will construct the public trail along the Colorado River.

Normal hours of operation will be 7:00 AM to 5:30 PM Monday through Friday. On occasion it may require some trips outside those hours on weekends and to support the City's requirements of doing construction work at night. Applicant knows that the Code restricts hours of operation to 6:00 AM to 6: PM but has agreed to even more limited hours.

Applicant is in support of the excavation, noise and vibration standards, emission standards of the Code. The applicant will make sure these are followed along with the staff's timetable for reclamation. The applicant has agreed to expedite the reclamation to a two-year period. (Kristen Ashbeck had informed the Commission that reclamation would also occur as portions of the permit area are mined with final reclamation occurring after all mining activities were completed.) Mr. Austin stated that the City has the right to revoke the permit if the standards are not met or the applicant does not meet schedules.

A brief explanation was provided as to what will be required by the State for its permits: mining, air, and water. There will be oversight and accountability from various state agencies and the City has the right to revoke its permit if the State requirements are not followed. An annual report will be made to the State with a map showing the extent of disturbance of affected land and reclamation accomplished to date. The applicant has financial warranty requirements to the State Mining Board to make sure that the reclamation permit is adequate to cover the work. The mining operations will be inspected each year to ensure compliance with laws and division rules.

Mr. Austin presented photographs of an eight-foot berm from another site, the Ute Water/Grand Valley Power site off 22 Road where it was clear one could not see what was on the other side of

the berm at 8 feet, but an air photo showed the storage behind the berm. He wrapped up his presentation with a summary of everything he explained that the applicant would be doing as a part of the project, everything required by the Code as well as some elements that are more restrictive, and how the applicant has had other projects over the years in the city and has done what was required and the City has been a major consumer of its gravel.

#### **Questions for staff/applicant**

Trent Prall clarified in response to a question from Commissioner Weckerly that the City is as close as it has ever been to actually bringing the riverfront trail to fruition along the Colorado River in this area. There are two properties left. One is this development and then one further to the west that Colorado Parks and Wildlife (CPW), Mesa County (County), and the City have been working very hard with the family who has the property. He explained that he expected an agreement where the City we'll be closing with them in January. Design of the trail from The Eddy to 29 Road is to begin with CPW. The design is anticipated to be completed about March-April 2024. Application for funding to Great Outdoors Colorado will occur timely and ideally construction will begin late 2024 with opening sometime in 2025 for the trail.

Kristen Ashbeck assured Commission Duyvejonck that the 100-foot setback is from the bank, not from the property line included within the river.

Kristen Ashbeck responded to Commission's Scissors inquiry that the criterion regarding adjoining properties has been met by virtue of what staff has seen from the reclamation plan and the operation plan and how they will proceed with the operations on the site. More detailed requirements will be addressed in greater detail with the state plan or the state permit.

Jamie Beard explained to Commissioner Ehlers that according to State statutes the Commission could not approve a development that would interfere with the present or future of extraction of the mineral deposits on the property. The request of the applicant is the opposite in that it is asking to extract the gravel with the approval of the CUP.

Mark Austin assured Commissioner Weckerly that a reclamation bond through the State of Colorado, through the Division of Mining Resource is the typical means to secure reclamation of the property. He explained that the sand and gravel mining operations will be for ten years, and then an additional two years for final site reclamation. He also answered for her that the pond that will be a part of the reclamation is sized larger than some because of the southern third of the property being in a floodway. Nothing could be built there anyway so the pond will be an amenity to the property.

Commissioner Secrest had questions about the pond and the water for the pond. Mark Austin explained that the groundwater is already there so the pond should not create additional water issues for the surrounding properties. The applicant will need to go through Court regarding the water rights but understands this may happen more easily on this section of the Colorado River.

Commissioner Scissors expressed concern that the river trail may not be built before the gravel pit opened for the bicyclists and pedestrians using C½ Road. Mr. Austin explained that C½ Road is not the responsibility of the applicant so it will be up to the City and the County when those

improvements occur. It will take the applicant at least a year to work through the state requirements so more time is available for the river trail to be completed.

#### **Public Hearing**

The public hearing was opened at 5:00 p.m. on Tuesday, August 15, 2023, via <a href="https://www.GJSpeaks.org">www.GJSpeaks.org</a>.

Sharon Bradshaw presented a video while expressing her concerns with the gravel pit. Showing a truck coming out of the pit with much dust created. She showed photos of various gravel pits in the area expressing concerns about the way the gravel pits looked, not maintained as they should be, and not being a land use that one would want to have as a neighbor. She was not pleased with the pond with reclamation as it will be a mosquito haven.

Jack Byrom asked for clarification on the number of trucks entering and exiting the gravel pit per day. He also requested clarification on the required street improvements for C ½ Rd.

Suzanne Daniels shares a fence line with the proposed gravel pit and expressed her concerns with the increased traffic and homeless camps along the river. She was not happy that the people who reside nearby are affected with the additional traffic including the children who wait in the dark for school buses, children riding their bikes along C ½ Road, or run into the street to retrieve an errant soccer ball. The road is in disrepair and already has issues, such as potholes, large cracks, and low and high spots, without more traffic added. She expressed disbelief that the traffic study was accurate and concern that the river trail will not solve all the problems.

Thaddeus Wilcox expressed disbelief that the Skinners were going to sell out or give an easement for the riverfront trail. He noted his concerns with the traffic and the size of the trucks on the road. There is not enough room for the trucks and a bicyclist on the road at the same time. He questioned whether the study was conducted when a concert was letting out at Las Colonias.

Ken Heinecke expressed his concerns about the wildlife and increased traffic creating danger for his grandchildren. He stressed that the road improvements be completed before any construction occur with the development.

Hanna Costanzo seconded all previously made comments, including that the traffic study was insulting and questioned that it considered the apartments, the campgrounds, and the park at full capacity, and expressed concerns about the hours of operation of the gravel pit. She wanted assurance that the gravel pit would be held to the requirements not just that the applicant was going to "try."

Michelle Wilcox seconded concerns about the increased traffic and dust from the gravel pit. She indicated she was making an emotional plea as the traffic is tremendous already. Cars speed through the area. An accident happened with a car landing on her neighbor's roof because of the speed it was traveling. Cars are parked on the edge of the streets, and it is worse by The Eddy apartments. The residences are putting up with much now and the development is adding to it.

Glen Bishard shared concerns about the additional impact to the road. He expressed that the truck numbers and the weight of the vehicle on the road will be significant. It is not clear enough regarding the number of trips and size of loads.

Charles Guenther made comments about the impact to the community. He is a flatland bicyclist and recognized that many of the ponds he passes when riding were originally gravel pits. He was pleased to hear the riverfront trail has moved along as well as it has with surprise at how far it is meant to reach. He was in favor of the development because its short term impacts with long terms benefits to the community.

Greg Mueller indicated he owns a neighboring property to the development but doesn't live there. It is agricultural land. He spoke in favor of the development as bringing employment opportunities for the community and the tax benefits for the city. He encouraged looking at the long term and the benefits to the city. The road will be improved. A property that was not allowing the river trail will be added with donation to the river trail construction. He would like to see a parking lot where the trail will lead from the riverfront portion to C ½ Road so people can park there to access the trail.

Sean Malone seconded comments about improving C 1/2 Road.

Keith Ensel commented on the need for another gravel pit and the benefit to the community. He has been in the construction industry for 30 years and resources are running out and more are needed. Local gravel is less expensive meaning less expense for completing local projects. He explained that he lives elsewhere in Orchard Mesa next to a gravel pit. He does put up with dust but it is an important asset to the community.

Terri Heinecke seconded previously made comments about the safety of C ½ Road. She questioned who is going to keep the residents safe.

Ken Ehlenberger participating online stated that the traffic survey needed to be redone. He was at home on C ½ Road and observed 25 to 30 bikes go by during the meeting.

Mark Austin responded to the public's comments. He expressed that the Code today has requirements which are more stringent than the Codes that were in place when the gravel pits in the video were approved. As explained earlier there will be landscaping and it will be irrigated. The gravel pit is a wet pit and the concerns for dust are less likely with a wet pit. The dust is much reduced because the pit is in water. He explained that the traffic study is based on peak hours. The recent numbers gathered indicated that the 2021 study was not off. The numbers increased but not more than 10%. The study considers conditions for 20 years. The five medium truck trips and five large truck trips have been the numbers planned from the beginning of the proposed project and are still the numbers. The gravel pit will be fenced to keep people out and at the time of reclamation the State will have input for fencing that is wildlife friendly.

Commissioner Ehlers asked if the individuals that conducted the studies pertaining to the gravel pit were licensed and Mark assured him that they were.

The public hearing was closed at 7:27 p.m. on August 22, 2023.

#### Discussion

Commissioner Weckerly expressed that her biggest concern is the road and the traffic. She inquired how road improvements are prioritized by the City and more specifically when the City requires developers to contribute payment does that payment definitely go to the road and does it raise the construction to a higher level of priority?

Trent Prall explained how the City prioritizes projects. There are many roads in similar conditions. In this instance the City and County will split the costs. It is recognized that the condition of the road needs to be upgraded. There will be a 2inch overlay which is the developer's contribution will be included in. The overlay is the additional structure that's needed to be able to handle that additional load and smoothing of the entire road. The widening of C ½ Road would be up to the city and the county to do at some point in the future. The City is expecting the river trail in early 2025 to be a key element in conveying the bicyclists. As there is more demand the multi-modal movements, concrete walks and so forth, would happen over time and will be done by the city, not by the developer. More development in the area will need to occur to justify the additional improvements. The density of vehicles on the road with this development even if the numbers were doubled in the traffic study is within the capacity of the road. He wants to see the improvements completed before many trucks hit the road as the additional surface is needed to handle the truck traffic.

Mr. Prall explained once the improvements are done maintenance will follow for C ½ Road in accordance with the improvements made and the City's regular maintenance schedule.

Kristen Ashbeck addressed Commissioner Secrest's concerns of the gravel pits shown in the video. He also inquired of methods to employ if the applicant does not do what is required. Ms. Ashbeck explained that the gravel pits shown may not be in the City. She was not certain where they all were located, but the City has only a few gravel pits. She assured the Commissioner that the City has the ability to shut the operations down if the requirements of the City are not being met or if the State permit requirements are not being met. There are various mechanisms the City may utilize to be certain the requirements are met.

Commissioner Ehlers stated that when he looked at the criteria with what's been proposed and was trying to understand how the impacts of a gravel mine are being mitigated, because it is not lost on him that a gravel mine is a very, very different use than what is in the area. And yet there's a lot of State, regional, local interests in making sure that extraction of those kinds of minerals are preserved and made possible. He stressed that the, the berm, the larger than necessary buffers, the more stringent requirements that the City applies to these kinds of uses met the criteria.

Commissioner Secrest stressed to the public that their voice has been heard. Properties are going to change. There will be impacts with the change. He thinks the benefit to the community with the development is great and he will vote in favor of the request.

Commissioner Scissors explained that most of the criteria are clearly met, but he was hung up with "minimal negative impacts on the use and enjoyment of the adjoining property" and that all "elements of the plan coexist in a harmonious manner with nearby existing and anticipated development". There is much uncertainty. When the road improvements will be completed, when the riverfront trail will be completed, and when the gravel operations will begin. He was questioning adding conditions to address the uncertainties.

Commissioner Weckerly agreed with Commissioner Scissors' concerns. I think three out of the four criteria are pretty easily met by this application. Her concern was the compatibility with the adjoining properties. It's very subjective. She expressed that the possible development of 200 dwelling units on the property would not be compatible either and yet that would be allowed. She would like a condition that the reclamation begin immediately upon the gravel operations ending not waiting the 10 years before reclamation.

Commissioner Teske questioned that everything included in the presentation be a condition of the approval as they were not specifically included within the conditions of the staff report.

Kristen Ashbeck explained that some of them are included and that she believed the applicant would have to start the reclamation immediately upon operations ending. She believed it was a requirement of the State permit.

Commissioner Teske wanted it clarified that the berm, the buffer, the landscaping requirements, hours of operation, traffic count limitations, the timeframes, that those are all addressed by the State permit or the City requirements and Ms. Ashbeck indicated that they were as a part of the permit or the operations plan provided to the City.

Kristen Ashbeck clarified for Commissioner Duyvejonck that the applicant is limited to hours of operation of 7AM to 5:30 PM, except for the infrequent nighttime and weekend, when necessary.

Commissioner Duyvejonck agreed she had concerns with the information provided by the public particularly the traffic. She also believed from what she heard during the hearing is that more development must happen before improvements would occur. Approving the development would provide more push to get the road widened and to make some of the other changes. Considering this plan, with the options that are provided in our Comprehensive Plan and this conditional use permit versus other options that may happen, may be a good option for our community going forward.

Commissioner Herek struggled with the compatibility but believed that the benefits outweigh the uncertainties expressed and the things that were addressed and mitigated did indicate that the compatibility is being met.

Commissioner Teske began with consideration of the state statutory requirement that there is to be no interference with present or future extraction. Keeping that in mind, he asked are steps being taken to make this impact minimal? He stated that the applicant has certainly demonstrated many, many efforts along those lines to go above and beyond what the minimum requirements

would be for this activity and to provide buffers and various protections for the neighbors to minimize that impact and to coexist in a harmonious manner with the nearby neighbors. He sympathized with the commissioner who mentioned sort of the overall community benefit here, and it's easy to get focused on truck traffic on C ½ Road, but if this gravel pit is not on C ½ Road. then there's going to be truck traffic somewhere else generating these same trips through our city to get to the same construction projects that need this aggregate. And if it comes from 30 or 60 or 90 miles away, that's heavier truck traffic somewhere, whether it's going to be along C ½ Road where the conditions are known and may be addressed versus not within the City's control. Conditions four and five, which at least to the extent that they are within the reasonable control of the applicant addressed the concerns of the traffic conditions. The applicant has to pay for the cost of the river trail construction through the applicant's property and provide a bond and development improvement agreement for that and pay its share of the C ½ Road improvements all prior to the commencement of mining operations on the site. So those are the things that the applicant specifically can control. Beyond that, there are things that the city rightfully can and should control. The rest of the acquisition of the right-of-way, construction of the rest of the pathway connections, and the improvements of C ½ Road themselves. So those things seem to be the result of either long deferred maintenance along C ½ Road or long-term planning from the city, which is sort of rightfully the city's burden. So at least from his point of view, those couple of additional conditions are addressed by this proposal as drafted.

Commissioner Scissors indicated he was persuaded by the Commissioner's comments to reconsider his position but was still concerned for safety on the road.

Commissioner Ehlers agreed with the safety concern but saw the issue as one for the City to resolve not the applicant. Commissioner Duyvejonck also considered it an undue burden for the applicant.

Questions and suggestions were made as to what could the City do. Mr. Prall explained that some bicyclists will continue to use the road, but signage may be used warning of the conditions and to provide awareness of alternative routes. He also pointed out that sidewalks were available on the Riverside Parkway and on 29 Road between D Road and C½ Road.

Before proposing a motion Commissioner Ehlers questioned if there were additional conditions to be addressed. He was not willing to consider a condition of holding operation for the gravel pit until after the C ½ Road improvements were complete as suggested by Commissioner Scissors who was uncertain if it should be a condition. Commissioner Ehlers felt this was holding the applicant hostage. There were no other indications from Commissioners for additional conditions.

#### **Motion and Vote**

Commissioner Ehlers made the following motion "Mr. Chairman, on the C ½ Road Gravel Pit to establish a Conditional Use Permit for a mining excavation operation, file number CUP-2021-616, I move that the Planning Commission approve the CUP with the findings of fact and conditions listed in the staff report."

Commissioner Duyvejonck seconded; motion passed 7-0.

### OTHER BUSINESS

#### **ADJOURNMENT**

Commissioner Secrest moved to adjourn the meeting. *The vote to adjourn was 7-0.* 

The meeting adjourned at 8:47 p.m.





#### **Grand Junction Planning Commission**

#### Regular Session

Item #2.

Meeting Date: October 10, 2023

**Presented By:** Timothy Lehrbach, Senior Planner

**Department:** Community Development

**Submitted By:** Tim Lehrbach, Senior Planner

#### Information

#### **SUBJECT:**

Consider a request from PERS Investments, LLC to zone 1.49 acres of property within the PERS Investments Annexation to C-2 (General Commercial) located at 3175 D Road.

#### **RECOMMENDATION:**

Staff recommends approval of the request.

#### **EXECUTIVE SUMMARY:**

The Applicant, PERS Investments, LLC, is requesting a zone of annexation to C-2 (General Commercial) for the PERS Investments Annexation. The approximately 1.49 acres of vacant land is located at 3175 D Road. The request for annexation will be considered separately by City Council but concurrently with the zoning request and is currently scheduled to be heard by the City Council on November 15, 2023.

The property is considered "annexable development" in accordance with the Persigo Agreement. The zone district of C-2 is consistent with the commercial land use category of the Comprehensive Plan.

#### **BACKGROUND OR DETAILED INFORMATION:**

#### BACKGROUND

The Applicant, PERS Investments, LLC, has requested annexation into the City of Grand Junction of its approximately 1.49 acres of land located at 3175 D Road and a zone of annexation to C-2 (General Commercial). The property is presently vacant. The applicant anticipates future development on the property, which constitutes "annexable development" under the Persigo Agreement.

The applicant is requesting a zone district of C-2 (General Commercial). The subject property is Lot 12 of the "D" Road Commercial Park subdivision and is currently zoned

PUD (Planned Unit Development) in Mesa County. The other properties within the "D" Road Commercial Park subdivision remain outside of the City limits and are zoned County PUD. Nearby properties within the City limits include the R-8 (Residential-8 du/ac) zoned Townhomes at the River Park subdivision located across D Road to the north and the C-2 zoned Pipe Trades subdivision located across an adjacent driveway to the west.

The annexation area has all urban services available to the property. The subject property abuts D Road, identified as a minor arterial on the Grand Junction Circulation Plan. The subject property is located within Tier 2 on the Intensification and Growth Tiers Map of the Comprehensive Plan. The goal to "encourage infill and redevelopment to leverage existing infrastructure" supports the Applicant's intent to develop the property and request of a zone of annexation of C-2.

The C-2 requested zoning implements the Comprehensive Plan's commercial land use category. The purpose of the C-2 (General Commercial) zone district is to provide for commercial activities such as repair shops, wholesale businesses, warehousing and retail sales with limited outdoor display of goods and even more limited outdoor operations.

In addition to the C-2 zoning requested by the petitioner, the following zone districts would also be consistent with the proposed Comprehensive Plan designation of Commercial:

- a. Mixed Use (M-U)
- b. Business Park (B-P)
- c. Industrial/Office Park (I-O)
- d. Light Commercial (C-1)
- e. Mixed Use Residential (MXR-8)
- f. Mixed Use General (MXG-3, 5, 8)
- g. Mixed Use Shopfront (MXS-3, 5, 8)

#### NOTIFICATION REQUIREMENTS

A Neighborhood Meeting regarding the proposed Annexation and Zoning was held on Zoom on May 30, 2023, in accordance with Section 21.02.080(e) of the Zoning and Development Code. Property owners within 500 feet of the subject property were notified of the meeting by mail sent May 17, 2023. There were two attendees including Tracy States of River City Consultants, representing the applicant, and Dave Thornton, Principal Planner, representing the City of Grand Junction. No members of the public attended the meeting.

Notice was completed consistent with the provisions in Section 21.02.080(g) of the City's Zoning and Development Code. The subject property was posted with application signs on August 9, 2023. Mailed notice of the public hearings before Planning Commission and City Council in the form of notification cards was sent to surrounding property owners within 500 feet of the subject property on September 28, 2023. The

notice of the Planning Commission public hearing was published October 1, 2023 in the Grand Junction Daily Sentinel. An online hearing with opportunity for public comment was held between October 3, 2023 and October 9, 2023 through the GJSpeaks platform.

#### **ANALYSIS**

Section 21.02.160(f) provides that land annexed to the City shall be zoned to a district that is consistent with the adopted Comprehensive Plan in accordance with the criteria for zoning map amendments set forth at Section 21.02.140(a). At least one such criterion must be met. These criteria and staff's findings are as follows:

- (1) Subsequent events have invalidated the original premises and findings; and/or The property owners have requested to annex and zone the property to C-2 which is compatible with the Comprehensive Plan Land Use Map designation of Commercial. When a property annexes into the City, the assumptions and facts used to assign County zoning are no longer valid. County zoning is not carried forward into the City and by Colorado Statute municipal zoning must be assigned to the property within 90 days of the effective date of annexation. The property currently has 'no zoning designation' within City limits, therefore there are no original premises and findings which must be invalidated. Staff finds that this criterion is not applicable.
- (2) The character and/or condition of the area has changed such that the amendment is consistent with the Plan; and/or

The "D" Road Commercial Park was platted in 1982 and has remained heavy commercial in nature since its initial development. Additional commercial and residential development has occurred to the west and north, respectively, of the subject property. Specifically, the Pipe Trades Subdivision to the west added commercially zoned lands to the City in 2001 and has developed with heavy commercial uses in the intervening years. The further development of the "D" Road Commercial Park over time has likewise been heavy commercial, consistent with the Plan. Therefore, staff finds that this criterion is met.

(3) Public and community facilities are adequate to serve the type and scope of land use proposed; and/or

Adequate public and community facilities and services are available to the property and are sufficient to serve land uses associated with the C-2 zone district. The site fronts D Road, identified in the Grand Junction Circulation Plan as a minor arterial. Clifton Water and City of Grand Junction sanitary sewer are presently available to the site in D Road and Roberts Court. Xcel Energy serves the area with electric and gas. The expected impact of the proposed development on emergency services, parks, and schools is minimal. In general, staff has found public and community facilities are adequate to serve the type and scope of the commercial land use proposed. Therefore, staff finds that this criterion is met.

- (4) An inadequate supply of suitably designated land is available in the community, as defined by the presiding body, to accommodate the proposed land use; and/or There is limited property in this area that has been incorporated into the City. Lands to the north of D Road are predominantly unincorporated residential development. South of D Road, the subject property is surrounded by other commercially and industrially developed properties. There is not a demonstrated lack of commercially zoned property in this area or in the city altogether which would necessitate the addition of this property to commercial zoning. Therefore, staff finds this criterion is not met.
- (5) The community or area, as defined by the presiding body, will derive benefits from the proposed amendment.

Annexation and zoning of the property will create additional land within the City limits for growth and help to fill in the patchwork of unincorporated and/or urban area that is adjacent to the City limits. The annexation and appropriate zoning of the property are also consistent with the City and County 1998 Persigo Agreement, which provides for the orderly urbanization of undeveloped land within the boundary subject to the Agreement. This area was reviewed as a part of the 2020 One Grand Junction Comprehensive Plan and it was determined that this subdivision area be changed to Commercial from Commercial/Industrial. Therefore, staff finds that this criterion is met.

#### **Consistency with Comprehensive Plan**

Section 21.02.160 (f) of the Grand Junction Zoning and Development Code provides that the zoning of an annexation area shall be consistent with the adopted Comprehensive Plan.

Land Use Plan: Relationship to Existing Zoning

Requests to rezone properties should be considered based on the Implementing Zone Districts assigned to each Land Use Designation. As a guide to future zoning changes, the Comprehensive Plan states that requests for zoning changes are required to implement the Comprehensive Plan.

The 2020 Comprehensive Plan provides the subject property with a land use designation of Commercial. The C-2 zone district implements the Commercial designation. While there are additional implementing districts for the Commercial land use designation, the C-2 zone district provides for a range of allowed uses most consistent with existing development and development standards most appropriate to the location of the subject property along D Road, opposite residential development.

Plan Principle 3: Responsible and Managed Growth

Where We are Today: Maintaining Quality – The Comprehensive Plan raises concerns about the unsightly development patterns resulting from the patchwork of City and unincorporated areas and expresses the community's desire to see continued improvements to the built environment. The annexation and appropriate zoning of property within this developed commercial and industrial area ensures the implementation and monitoring of City of Grand Junction standards for construction and property maintenance.

• Plan Principle 8: Resource & Stewardship

How We Will Get There – Part of properly managing the City's resources and being good stewards of the environment is to promote sustainable development. This can be done by maximizing existing infrastructure. The subject property is located adjacent to improved rights-of-way with existing water and sewer lines available to the site.

#### **RECOMMENDATION AND FINDINGS OF FACT**

After reviewing the PERS Investments Zone of Annexation, ANX-2023-439, request for the property located at 3175 D Road to zone to City C-2 (General Commercial), the following findings of fact have been made:

- 1. The request conforms with Section 21.02.140 of the Zoning and Development Code.
- 2. The request is consistent with the vision (intent), goals, and policies of the Comprehensive Plan.

Therefore, Staff recommends approval of the request.

#### SUGGESTED MOTION:

Mr. Chairman, on the Zone of Annexation request for the property located at 3175 D Road, City file number ANX-2023-439, I move that the Planning Commission forward a recommendation of approval to City Council with the findings of fact as listed in the staff report.

#### **Attachments**

- 1. Exhibit 1. Development Application
- 2. Exhibit 2. Schedule and Summary Table
- 3. Exhibit 3. Annexation Plat
- 4. Exhibit 4. Site Maps
- 5. Exhibit 5. Zone of Annexation Ordinance



### **Development Application**

We, the undersigned, being the owner's of the property adjacent to or situated in the City of Grand Junction, Mesa County, State of Colorado, as described herein do petition this:

Petition For: Annexation/Zone of Annex	ation			
Please fill in blanks below only fo	r Zone of Annexation, Rezor	nes, and Compr	ehensive Plan Amendments:	
Existing Land Use Designation Planned Unit Development		Existing Zoning	County PUD	
Proposed Land Use Designation Commercial		Proposed Zonii	ng C-2	
Property Information				
Site Location: 3175 D Road, Grand Junction, CO 81504		Site Acreage	Approx. 1.49 Acres	
Site Tax No(s): 2943-221-03-012		Site Zoning:	Proposed C-2	
Project Description: To Annex and Zone 1	1.49 acres located in the County a	and in the Persigo B	oundary, with a future land use of	
Property Owner Information  Name: PERS Investments, LLC	Applicant Information  Name: Same as Owner		resentative Information  Eliver City Consultants, Inc.	
Street Address: 362 Main Street #B	Street Address:		et Address: 215 Pitkin Ave. #201	
City/State/Zip: Grand Junction, CO	City/State/Zip:		State/Zip: Grand Junction, CO	
Business Phone #: 970-640-4678	Business Phone #:	Busir	ness Phone #: 970-241-4722	
E-Mail: eric@flukeyinvestmentgroup	E-Mail:	E-Ma	il: tstates@rccwest.com	
Fax #:	Fax #:	Fax #	t:	
Contact Person: Eric Flukey	Contact Person:	Conta	act Person: Tracy States	
Contact Phone #: 970-640-4678	Contact Phone #:	Conta	act Phone #: 970-241-4722	
We hereby acknowledge that we have familiarize foregoing information is true and complete to the and the review comments. We recognize that we represented, the item may be dropped from the a placed on the agenda.	ed ourselves with the rules and regulat best of our knowledge, and that we as or our representative(s) must be preser	sume the responsibility nt at all required hearin	y to monitor the status of the application gs. In the event that the petitioner is not	
Signature of Person Completing the Applicati		y signed by Tracy States 023.05.22 15:15:12 -06'00'	Date May 22, 2023	
Signature of Legal Property Owner & Pake				

### General Project Report

## Annexation/Zoning 3175 D Road, Grand Junction, CO Parcel No. 2943-221-03-012

June 8, 2023

Prepared for:

City of Grand Junction

250 N. 5th Street, Grand Junction, CO 81501

#### Prepared by:



215 Pitkin, Grand Junction, CO 81501

Grand Junction, CO 81506

Phone: (970) 241-4722

info@rccwest.com

#### A. Project Description

- 1) Location: The project is located at 3175 D Road (Parcel No. 2943-221-03-012).
- 2) Acreage: The subject parcel contains approximately 1.65 acres.
- 3) **Proposed Use:** This submittal is for the Annexation and zoning of this parcel. The proposed zoning is C-2 (Commercial). The future land use is Commercial. The proposed C-2 zoning meets the intent of the 2020 Comprehensive Plan with regards to density and use.

#### **B. Public Benefit**

The proposed Annexation and zoning would provide a commercial site in an area designated for commercial development. Subsequent development would provide jobs and tax revenue to the City of Grand Junction. It is proposed to construct storage units on the site.

#### C. Neighborhood Meeting

A neighborhood meeting was held virtually via a zoom on May 30, 2023. A summary of the meeting is included with this submittal.

#### D. Project Compliance, Compatibility, and Impact

#### 1) Adopted plans and/or policies:

The proposed Annexation and zoning are in conjunction with the 2020 Comprehensive Plan, and will comply with the adopted codes, plans and requirements for the property. The C-2 zoning is an appropriate district for the Commercial category of the Comprehensive Plan.

#### 2) Land use in the surrounding area:

The uses contained within the surrounding area include commercial, medium and low density residential.

#### 3) Site access and traffic patterns:

Access and traffic patterns will be determined upon subsequent development.

#### 4) Availability of utilities, including proximity of fire hydrants:

The subject parcel is served by the following:

Clifton Water
City of Grand Junction Sanitary and Storm Sewer
Grand Valley Drainage District
Grand Valley Irrigation District
Xcel Energy
City of Grand Junction Fire – Station 8
Spectrum/Charter
CenturyLink/Lumen

A Fire Flow Form has been obtained and is included with this submittal.

#### 5) Special or unusual demands on utilities:

There will be no unusual demand on utilities as a result of the Annexation and zoning.

#### 6) Effects on public facilities:

The Annexation and zoning will have no adverse effect on public facilities.

#### 7) Hours of operation:

To be determined upon development.

#### 8) Number of employees:

Not applicable.

#### 9) Signage:

Not applicable.

#### 10) Site Soils Geology:

Not applicable.

#### 11) Impact of project on site geology and geological hazards:

None are anticipated.

## E. Must address the review criteria contained in the Zoning and Development Code for the type of application being submitted

#### Section 21.02.070 (6) of the Zoning and Development Code:

General Approval Criteria. No permit may be approved unless all of the following criteria are satisfied:

#### (i) Compliance with the Comprehensive Plan and any applicable adopted plan.

The Annexation/Zoning request is in compliance with the newly adopted 2020 Comprehensive Plan.

#### (ii) Compliance with this zoning and development code.

The Annexation and zoning request is in compliance with the zoning and development code.

#### (iii) Conditions of any prior approvals.

There are no conditions of prior approvals.

#### (iv) Public facilities and utilities shall be available concurrent with the development.

All public facilities and utilities will be available concurrent with the Annexation and zoning.

#### (v) Received all applicable local, State and federal permits.

All applicable permits will be obtained for this project.

#### Section 21.02.140 Code Amendment and Rezoning:

- (a) **Approval Criteria.** In order to maintain internal consistency between this code and the zoning maps, map amendments must only occur if:
- (1) Subsequent events have invalidated the original premises and findings; and/or

The proposed Annexation and zoning request to the C-2 zone district will bring the parcel into compliance with the newly adopted 2020 Comprehensive Plan. The parcel is within the Persigo 201 boundary and must annex and zone within the City limits in order to develop.

(2) The character and/or condition of the area has changed such that the amendment is consistent with the Plan; and/or

The amendment is consistent with the Comprehensive Plan and the requirement to annex due to the parcel's location within the 201 boundary. Medium density development exists in the immediate area. The parcel is located in Tier 2 of the Tiered Growth Plan

(3) Public and community facilities are adequate to serve the type and scope of land use proposed; and/or

Public and community facilities are existing, adequate and will support commercial development.

(4) An inadequate supply of suitably designated land is available in the community, as defined by the presiding body, to accommodate the proposed land use; and/or

There is an inadequate supply of commercial development parcels in this area, that haven't already been developed.

(5) The community or area, as defined by the presiding body, will derive benefits from the proposed amendment.

The area will benefit with the eventual commercial development and the addition of storage units.

#### Section 21.02.160 Annexation:

**Approval Criteria.** The application shall meet all applicable statutory and City Administrative requirements:

a) A proper petition has been signed by more than 50% of the owners and more than 50% of the property described.

This will be complied with in conjunction with City staff.

b) Not less than one-sixth of the perimeter of the area to be annexed is contiguous with the existing City limits.

The one-sixth contiguous requirement is met.

- c) A community of interest exists between the area to be annexed and the City. The project is located within Tier 2 of the Tiered Growth Plan. The parcel must annex in order to develop. This creates a community of interest between the City and the property owner.
- d) The area is or will be urbanized in the near future. The area is urbanized. This is an infill parcel.
- e) <u>The area is capable of being integrated with the City.</u>
  All services and utilities are provided to integrate this parcel with the City.
- f) No land held in identical ownership is being divided by the proposed annexation. No land held in identical ownership is being divided by the proposed annexation.
- g) No land held in identical ownership comprising 20 contiguous acres or more with an assessed valuation of \$200,000 or more for tax purposes is included without the owner's consent.

Not applicable for this project.

#### F. Development Schedule

Not applicable for this submittal.

### PERS INVESTMENTS ANNEXATION PETITION FOR ANNEXATION

WE THE UNDERSIGNED do hereby petition the City Council of the City of Grand Junction, State of Colorado, to annex the following described parcels to the said City:

GENERAL LOCATION: 3175 D Road, Grand Junction, CO 81504 **Tax ID #: 2943-221-03-012** 

LOT 12 D ROAD COMMERCIAL PARK SEC 22 1S 1E COUNTY OF MESA, STATE OF COLORADO. 1.49 AC

This foregoing description describes the parcels; the perimeter boundary description, for purposes of the Annexation Act, is shown on the attached "Perimeter Boundary Legal Description, PERS Investments Annexation."

As grounds therefore, the petitioner respectfully state that annexation to the City of Grand Junction, Colorado is both necessary and desirable and that the said territory is eligible for annexation in that the provisions of the Municipal Annexation Act of 1965, Sections 31-12-104 and 31-12-105 CRS 1973 have been met.

This petition is accompanied by four copies of a map or plat of the said territory, showing its boundary and its relation to established city limit lines, and said map is prepared upon a material suitable for filing.

Your petitioners further state that they are the owners of more than fifty percent of the area of such territory to be annexed, exclusive of streets and alleys; that the mailing address of the signer and the date of signature are set forth hereafter opposite the name of the signer, and that the legal description of the property owned by the signer of said petition is attached hereto.

WHEREFORE, these petitioners pray that this petition be accepted and that the said annexation be approved and accepted by ordinance. These petitioners by his/her/their signature(s) acknowledge, understand and agree that if any development application concerning the property which is the subject hereof is denied, discontinued or disapproved, in whole or in part, that the annexation of the property to the City of Grand Junction shall proceed.

PERS Investments, LLC NAME	362 Main Street, Suite B, Grand Junction, CO ADDRESS
SIGNATURE	8/8/21
Eric Flukey, Member	DATE

(PERS Investments Annexation Petition)

SS

**AFFIDAVIT** 

**COUNTY OF MESA** 

Member, of lawful age, being first duly sworn, upon oath, deposes

That he is the circulator of the forgoing petition:

That each signature on the said petition is the signature of the person whose name it purports to be.

Witness my hand and official seal.

Notary Public

How Buffy Drive

Arand Junction, a 81504

TRACY A STATES NOTARY PUBLIC STATE OF COLORADO



## 3175 D Road, ANNEXATION/REZONE (Parcel No. 2943-221-03-012)

#### SUMMARY OF VIRTUAL NEIGHBORHOOD MEETING TUESDAY, MAY 30, 2023, @ 5:30 PM VIA ZOOM

A virtual neighborhood meeting for the above-referenced Annexation and Rezone, was held Tuesday, May 30, 2023, via Zoom, at 5:30 PM. The initial letter notifying the neighboring property owners within the surrounding 500 feet was sent on May 17, 2023, per the mailing list received from the City of Grand Junction. There were two attendees including Tracy States, Project Coordinator, with River City Consultants and David Thornton, Senior Planner with the City of Grand Junction. There was no one from the public in attendance.


The meeting began at approximately 5:30 PM. After it was determined that no one from the public was going to attend, Tracy shared with David the maps that would have been presented and that the plan was to construct storage units. No site plan was available for presentation at the time.

The meeting adjourned at approximately 5:45 PM.

## **Location Map**




Scale: 1:1,128



The Geographic Information System (GIS) and its components are designed as a source of reference for answering inquiries, for planning and for modeling. GIS is not inhended or does not replace legal description information in the chain of title and their information contained in official government secords such as the Courty Clerk and Recordes office or the counts. In addition, the representations of location in this GIS cannot be substitute for adual legal surveys.

The information contained hearin is believed accurate and suitable for the limited uses, and subject to the limitations, set forth above. Mesa County makes no warranty as to the accuracy or suitability of any information contained hearin. Uses assume attribution and additionance including consequential advances, which may flow from the user's use of this information.

County Zoning Map PrinpaetRetMagge 3923





## City Zoning Map



Scale: 1:1,128

# 2020 Comprehensive Plan YORK CIR S TORREYS PEAK S TORREYS PEAK ROBERTS RD Residential Parks and Open Space m D RD D RD D RD ROBERTS CT Commercial PIPE CT Commercial Printed: 5/30/2023 1 inch equals 94 feet 0.05 0.1 Scale: 1:1,128

#### OWNERSHIP STATEMENT - CORPORATION OR LIMITED LIABILITY COMPANY

(a) PERS Investments, LLC	_ ("Entity") is the owner of the following property:
(b) 3175 D Road, Grand Junction, CO 81504	
A copy of the deed(s) evidencing the owner's interest in tinterest in the property to someone else by the owner are	
I am the (c) Member for the Ent	ity. I have the legal authority to bind the Entity regarding
obligations and this property. I have attached the most re	ecent recorded Statement of Authority of the Entity.
My legal authority to bind the Entity both financially an	d concerning this property is unlimited.
O My legal authority to bind the Entity financially and/or of	concerning this property is limited as follows:
The Entity is the sole owner of the property.	
$\ensuremath{\bigcirc}$ The Entity owns the property with other(s). The other	owners of the property are:
On behalf of Entity, I have reviewed the application for th	e (d) Annexation/Zone of Annexation
I have the following knowledge or evidence of a possible	boundary conflict affecting the property:
(e) None	
	e City planner of any changes regarding my authority to bind f-way, encroachment, lienholder and any other interest in the
I swear under penalty of perjury that the information in th	is Ownership Statement is true, complete and correct.
Signature of Entity representative:	
Printed name of person signing: Eric Flukey, Member	
State of Colorado	)
County of Mesa	) ss.
Subscribed and sworn to before me on this	day of <u>July</u> , 20 <u>23</u>
by Eric Flukey, Member	
Witness my hand and seal.	
My Notary Commission expires on 1106 2026	
TRACY A STATES NOTARY PUBLIC STATE OF COLORADO NOTARY ID 20064045541 MY COMMISSION EXPIRES NOVEMBER 6, 2026	Hay A. States  Stary Public Signature

Packet Page 34

Document Fee: \$21.80

#### SPECIAL WARRANTY DEED

THIS SPECIAL WARRANTY DEED, dated 19th day of May, 2023, is made between SCF Partners, LLC, a Colorado Limited Liability Company ("Grantor"), duly organized and existing under the laws of the State of Colorado

AND

**PERS Investments, LLC, a Colorado Limited Liability Company** ("Grantee"), duly organized and existing under the laws of the State of Colorado, whose legal address is 633 Fletcher Ln, Grand Junction, CO 81505

WITNESS, that the Grantor(s), for and in consideration of TWO HUNDRED SEVENTEEN THOUSAND NINE HUNDRED FIFTY AND 00/100 DOLLARS (\$217,950.00) and other good and valuable consideration, the receipt and sufficiency of which is hereby acknowledged, has granted, bargained, sold and conveyed, and by these presents does grant, bargain, sell, and convey unto the Grantee, and the heirs, successors and assigns of the Grantee forever, all the real property, together with fixtures and improvements located thereon, if any, situate, lying and being in the County of **Mesa** and State of Colorado, described as follows:

Lot 12 of D ROAD COMMERCIAL PARK, County of Mesa, State of Colorado

ALSO KNOWN AS: 3175 D Road, Grand Junction, CO 81504

**TOGETHER WITH,** all and singular the hereditaments and appurtenances thereunto belonging, or in anywise appertaining, and the reversion and reversions, remainder and remainders, rents, issues and profits thereof, and all the estate, right, title, interest, claim and demand whatsoever of the Grantor(s), either in law or equity, of, in and to the above-bargained premises, with the hereditaments and appurtenances.

TO HAVE AND TO HOLD the said premises above bargained and described, with the appurtenances, unto the Grantee, and the heirs, successors and assigns of the Grantee forever. The Grantor, for the Grantor and the heirs, successors and assigns of the Grantor, <u>warrants title to the same against all persons claiming by, through or under the Grantor</u>, subject to <u>the Statutory Exceptions</u>

EXECUTED AND DELIVERED by Grantor on the date first set forth above.

SCF Partners, LLC a Colorado Limited Liability Company by

Smart Choice RES. LLC a Nevada Limited Liability Company, as Member

Raymord Beville, Member

State of: Colorado

County Of Mesa

The foregoing instrument was subscribed, sworn to, and acknowledged before me this May 19, 2023, by Raymond Beville as Member of Smart Choice RES. LLC, a Nevada Limited Liability Company as Member of SCF Partners, LLC, a Colorado Limited Liability Company

My Commission expires

Witness my hand and official seal.

WHITNEY RODRIGUEZ

NOTARY PUBLIC

STATE OF COLORADO

NOTARY ID #20164018077

ty Commission Expires May 11, 2024

\*\*If tenancy is unspecified, the legal presumption shall be tenants in common (C.R.S. 38-31-101)

RECEPTION#: 3068708
7/10/2023 3:13:20 PM, 1 of 1
Recording: \$13.00,
Bobbie Gross, Mesa County, CO.
CLERK AND RECORDER


#### STATEMENT OF AUTHORITY

PERS Investments, LLC	entity named:
and is executed on behalf of the entity pu C.R.S.	orsuant to the provisions of Section 38-30-172,
The type of entity is: Limited Liability (	Company .
The entity is formed under the laws of the	e State of <u>Colorado</u>
The maining address for the chilty is.	62 Main Street, Suite B Grand Junction, CO 81501
	thorized to execute instruments conveying, to real property on behalf of the entity is: nt, Member, OR Ronald Walz, Member,
The authority of the foregoing person(s) t follows):  not limited	to bind the entity is (not limited) (limited as
Other matters concerning the manner in v property:	which the entity deals with interests in real
Executed this 10th day of July	Signature (Type or Print Name Below)
STATE OF COLORADO )  COUNTY OF MESA )	Eric Flukey, Member
, 20, by Eric Flukey  Member (insert office)	cnowledged before me this day of (insert name of individual) as the held or role (President, Vice President or For LLCs) for PERS Investments LLC(insert
Witness my hand and official seal.  My commissioner expires: (1,06/2)  TRACY A STATES NOTARY PUBLIC STATE OF COLORADO NOTARY ID 20064045541 MY COMMISSION EXPIRES NOVEMBER 6, 2026	Notary Public

# IMPROVEMENT SURVEY PLAT

Mesa County Parcel Number 2943-221-03-012 Northeast Quarter of the Northeast Quarter of Section 22, Township 1 South, Range 1 East, Ute Meridian Mesa County, Colorado

Packet Page 37



NORTHWEST 1/4

NORTHEAST 1/4

VICINITY MAP 1:1000'

PROPERTY DESCRIPTION (as recorded at reception number

Lot 12 of D Road Commercial Park. 1.49 acres more or less.

# BASIS OF BEARINGS

The bearings hereon are grid bearings of the Mesa County Local Coordinate System, GVA, as defined at http://emap.mesacounty.us/gps\_survey/GVAZONE.htm, determined by GPS observation of the west line of Lot 12 of "D" Road Commercial Park, the southwest corner of said Lot 12 being a 1.5" aluminum cap marked PLS 38274 on a #5 rebar, whence the northwest corner of said Lot 12 being a 1.5" aluminum cap marked PLS 38274 on a #5 rebar, bears North 00°06'30" East, as shown hereon.

## Lineal Units of Measurement are U.S. Survey Foot.

TRANSVERSE MERCATOR PROJECTION POINT OF ORIGIN (SNOI)AND CENTRAL MERIDIAN: LATITUDE: 39°06'22.72746N LONGITUDE: 108°32'01.43552W NORTHING: 50,000FT EASTING: 100,000FT SCALE FACTOR: 1.000218181798 PROJECT/SCALE FACTOR HEIGHT: 4644FT(NAVD88)

This plat is a graphical representation of the professional opinion of the undersigned surveyor of the location of the property as described in the title documents referenced. The bearings of the boundary lines on the drawing represent the title description rotated to grid north of the Mesa County Local Coordinate System (MCLCS) noted above. The geometric integrity of the lines has been preserved except where they yield to record monuments and/or senior or controlling lines.

This survey plat does not constitute a title search by the undersigned surveyor or River City Consultants, Inc. and no certification as to title or ownership of any parcels shown hereon is made by either. All recorded and apparent rights-of-way and easements shown hereon were researched by the professional land surveyor, other documents may exist which would affect

#5 rebar found and accepted hereon shall be affixed with a 1.5" aluminum cap marked PLS


## SURVEYOR'S STATEMENT

I, Alec K Thomas, a registered Professional Land Surveyor in the State of Colorado, do hereby state: the Improvement Survey represented hereon was performed by me or under my responsible charge; it is based upon my knowledge, information and belief; it is in accordance with applicable standards of practice. This statement is not a guaranty, either expressed or implied.

Alec K Thomas, Colorado PLS 38274



NOTICE: According to Colorado law you must commence any legal action based upon any defect in this survey within three years after you first discover such defect. În no event may any action based upon any défect in this súrvey be commenced more than ten years from the date of the certification shown



LEGEND

SET 1.5" ALUMINUM CAP ON # 5 REBAR

FOUND ALIQUOT MONUMENT AS NOTED

20677, DH SURVEYS INC.

FOUND REBAR

SANITARY MANHOLE

IRRIGATION MANHOLE

TELEPHONE PEDESTAL

EDGE OF CONCRETE

OVERHEAD ELECTRIC LINE

CHAIN LINK/IRON FENCE

TREE MASS

WATER LINE

SANITARY LINE

POWER POLE

GUY ANCHOR

INTERSECTION SIGN

Drawn: BC

IMPROVEMENT SURVEY

Section 22,

Mesa County, Colorado

Drawina name: 5:/PROJECTS/1959 Flukey Investment Group/004 3175 D Road/Survey/DMG/1959-004 boundary.dmg

Job No. 1959-004

Checked: AKT

GAS LINE

CABLE TY PEDESTAL/PULL BOX


WATER VALVE

PLS 38274

FOUND 2" ALUMINUM CAP, MOUNTED ON #5 REBAR, LS

FOUND 1.25" PLASTIC CAP, MOUNTED ON #5 REBAR, LS 9960, PARAGON

ANNEXATION SCHEDULE & SUMMARY WORKSHEET								
10/4/2023		Referral of Petition, Intro	Proposed Ordinance, Exercise Land Use					
10/10/2023		Planning Commission Considers Zone of Annexation						
11/1/2023		City Council Intro Propos	sed Zoning Ord					
11/15/2023		City Council Accept Petit	tion/Annex and	Zoning Public Hea	aring			
12/17/2023		Effective date of Annexa	tion and Zoning					
		ANNEXATION SUMM	/IARY					
File Number			ANX-2023-4	39				
Location			3175 D Road					
Tax ID Number(s)			2943-221-03-012					
Number of Parcel(s)			1					
Existing Population			0					
No. of Parcels Owner Occupied			0					
Number of Dwelling Units			0					
Acres Land Annexed			1.486441					
Developable Acres Remaining			1.486441					
Right-of-way in Annexation			n/a					
Previous County Zoning			PUD					
Proposed City Zoning	1		C-2 General Commercial					
	North:		R-8					
Surrounding Zoning:	South:		PUD (Mesa County)					
3 3	East:		PUD (Mesa County)					
	West:		RSF-R (Mesa County)					
Current Land Use			Vacant					
Proposed Land Use			Mini-Warehouse					
	North:		Multifamily Residential					
Surrounding Land Use:	South	:	Light Commercial (HVAC)					
Surrounding Land Ose.			Heavy Commercial (Towing)					
			One-family Residential (Access Drive)					
Comprehensive Plan Designation:			Commercial		T			
Zoning within Comprehensive Plan Designation	1		Yes:	Yes	No:			
Values:	Asse		\$49,800					
	Actua	al 	\$178,490					
Address Ranges	Wate	er	3175 D Road Clifton					
	Sewe		Grand Junction					
	Fire		Clifton					
Special Districts:		tion/Drainage	Grand Valley Irrigation/Grand Valley Drainage					
	Scho		School District 51					
	Pest							



FOUND IN THIS SURVEY MUST COMMENCE WITHIN THREE (3) YEARS AFTER THE DISCOVERY OF SUCH DEFECT. IN NO EVENT MAY ANY ACTION BASED UPON ANY DEFECT FOUND IN THIS SURVEY BE COMMENCED MORE THAN TEN (10) YEARS FROM THE DATE OF THE CERTIFICATION SHOWN HEREON.

CHECKED BY: RBP/NCW DATE: 08/23/2023 APPROVED BY: RBP DATE: 08/25/2023


SCALE: 1" = 30' LINEAL UNITS = U.S. SURVEY FOOT




ENGINEERING DIVISION


244 N. 12th Street - Grand Junction, CO. 81501


Located in the NE1/4 NE1/4, SECTION 22, TOWNSHIP 1 SOUTH, RANGE 1 EAST, UTE MERIDIAN, COUNTY OF MESA, STATE OF COLORADO



# **PERS Investments Annexation** N TORREYS PEAK D RD D RD 0.05 0.1 Miles Grand Junction Annexation Site City Limits Date Created: 9/1/2023







#### CITY OF GRAND JUNCTION, COLORADO

DINANCE NO.
-------------

# AN ORDINANCE ZONING PERS INVESTMENTS ANNEXATION TO C-2 (GENERAL COMMERCIAL) ZONE DISTRICT

#### **LOCATED AT 3175 D ROAD**

#### Recitals:

The property owner has petitioned to annex their 1.49 acres into the City limits. The annexation is referred to as the "PERS Investments Annexation."

After public notice and public hearing as required by the Grand Junction Zoning & Development Code, the Grand Junction Planning Commission recommended zoning the PERS Investments Annexation consisting of 1.49 acres from County PUD (Planned Unit Development) to C-2 (General Commercial) finding that both the C-2 zone district conforms with the designation of Commercial as shown on the Land Use Map of the Comprehensive Plan and conforms with its designated zone with the Comprehensive Plan's goals and policies and is generally compatible with land uses located in the surrounding area.

After public notice and public hearing, the Grand Junction City Council finds that the C-2 (General Commercial) zone district is in conformance with at least one of the stated criteria of Section 21.02.140 of the Grand Junction Zoning & Development Code for the parcel as designated.

#### BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF GRAND JUNCTION THAT:

#### ZONING FOR THE PERS INVESTMENTS ANNEXATION

The following parcel in the City of Grand Junction, County of Mesa, State of Colorado is hereby zoned as follows:

A parcel of land being Lot 12, "D" ROAD COMMERCIAL PARK same as recorded at Reception No. 1284183, located in the Northeast Quarter of the Northeast Quarter (NE 1/4 NE 1/4) of Section 22, Township 1 South, Range 1 East, Ute Meridian, Mesa County, Colorado more particularly described as follows:

Commencing at the East Sixteenth Corner on the north line of said Section 22, whence the Northeast Corner of said Section 22 bears S89°53'30"E, a distance of 1,312.63 feet using the Mesa County Local Coordinate System with all other bearings contained herein being relative thereto; thence S00°06'30"W, a distance of 40.00 feet along the West line of said Northeast Quarter of the Northeast Quarter to a point on the Southerly line of Halliburton Annexation No.

2, Ordinance 3963; thence along said Southerly line of Halliburton Annexation for the following two (2) courses: 1) S89°53'30"E, a distance of 32.56 feet; 2) S00°06'30"W, a distance of 10.00 feet to the Northwest Corner of said Lot 12, "D" ROAD COMMERCIAL PARK being the Point of Beginning; thence the following courses along the perimeter of said Lot 12, "D" ROAD COMMERCIAL PARK, S89°53'30"E along the Southerly line of Halliburton Annexation, a distance of 201.22 feet; thence S44°53'30"E, a distance of 21.21 feet; thence S00°06'30"W, a distance of 285.00 feet; thence N89°53'30"W, a distance of 216.22 feet; thence N00°06'30"E 300.00 feet to the Point of Beginning.

Said parcel of land CONTAINING 64,753 Square Feet or 1.49 Acres, more or less.

Said parcel shall hereby be zoned C-2 (General Commercial).

**INTRODUCED** on first reading this 1st day of November 2023 and ordered published in pamphlet form.

**ADOPTED** on second reading this 15th day of November 2023 and ordered published in pamphlet form.

ATTEST:	Anna M. Stout President of the Council
Amy Phillips City Clerk	_



#### **Grand Junction Planning Commission**

#### Regular Session

Item #3.

Meeting Date: October 10, 2023

**Presented By:** Trenton Prall, Public Works Director, Rick Dorris, Henry Brown,

Mobility Planner, David Thornton, Principal Planner

**<u>Department:</u>** Community Development

**Submitted By:** David Thornton, Principal Planner

#### <u>Information</u>

#### **SUBJECT:**

Consider a Request by the City of Grand Junction (City) to Amend Title 29 of the Grand Junction Municipal Code to modify and clarify various provisions of the Transportation Engineering Design Standards (TEDS).

#### **RECOMMENDATION:**

Staff recommends approval of the request.

#### **EXECUTIVE SUMMARY:**

The City of Grand Junction is proposing to repeal and replace sections of the Grand Junction Municipal Code (GJMC) Title 29 to modify and clarify various provisions of the Transportation Engineering Design Standards (TEDS). The updated TEDS addresses items identified through the planning and development process and recommended by the City's Pedestrian and Bicycle Plan as a desired modernization of the required transportation standards in the Code. The TEDS applies to all transportation improvements within the public right-of-way and all private work dedicated to the public, either as right-of-way or as an easement. The proposed Updated TEDS Manual will repeal and replace the existing TEDS Manual last adopted in 2004.

#### **BACKGROUND OR DETAILED INFORMATION:**

#### **BACKGROUND**

The TEDS Manual was created and implemented in 1995. It was first adopted by reference in Chapter 6 of the Zoning and Development Code by the City on March 7, 2000. The manual was updated by resolution in November 2001, September 2003, and April 2004. It has not been amended for almost twenty years.

The TEDS Manual establishes requirements and provides guidance to the city and

developers on how streets and multimodal transportation infrastructure are to be designed within the City. It includes guidance and requirements for preparing a transportation impact study (TIS), street design standards, access control, traffic signal design, street lighting, pavement, and pedestrian, bicycle, and transit facility design standards.

The project kicked-off in late summer 2022 and finalized updates in late summer 2023. The project team consisted of the consultants, Fehr & Peers with their subconsultant Kimley Horn, the Technical Advisory Committee (TAC), city staff, and members of the development and engineering community. The TAC is made up of representatives of different city departments, CDOT, Mesa County, the RTPO, neighboring jurisdictions, private developers and engineers, and transportation engineering consultants in the Valley that regularly use the TEDS Manual. It met six times over the course of the project at key milestones.

The process for updating the TEDS Manual involved two major phases:

- 1. TEDS Manual Assessment: In fall 2022, the team conducted a thorough assessment of the existing TEDS Manual to identify needed updates to achieve the project goals. This included guidance from the TAC and a survey that was sent to stakeholder agencies, departments, and the broader development and transportation engineering community in Grand Junction.
- 2. TEDS Manual Draft Updates: Based on the outcomes of the assessment, the project team updated the TEDS Manual. The updates were made using an iterative process with city staff and the TAC and included two drafts prior to the final updates. The second draft was developed in May 2023 and stakeholder comment was solicited on this draft in early summer. Following feedback from meetings with stakeholders in June and July, it was updated to a final draft in August.

#### Project Schedule

- Sept 19, 2022 TAC meeting #1
- October November 2022 Fehr & Peers TEDS Assessment
- Dec 19th TAC meeting #2 shared TEDS Assessment
- January February 2023 TAC Review and Comment on TEDS Assessment
- March 6th TEDS Draft #1 to City and TAC from Fehr & Peers
- Mar 15th TAC meeting #3
- May 3rd TEDS Draft #2 from Fehr & Peers
- May 4th Planning Commission Workshop
- May 10th TEDS draft #2 Sent to TAC
- May 18th TAC meeting #4
- May 22nd through July 31st Public Review Listening Tour
- May 24th WCCA
- June 1st AMGD
- June 5th City Council Workshop
- June 7th Development Roundtable Group Discussion
- June 8th Planning Commission Workshop
- June 15th GJ Realtors Association

- June 29th TAC meeting #5
- July 12th Urban Trails Committee (UTC)
- July 20th Planning Commission Workshop
- July 31st Development Roundtable Group Workshop/Discussion
- Aug 3rd TAC Meeting #6
- August 17th Planning Commission Workshop
- Aug 18th Final Draft due to City from Fehr & Peers
- Aug 24th thru Sept 25th Public Review of Final TEDS document
- Aug 28th City Council Workshop
- Sept 7th Planning Commission Workshop
- Oct 5th Planning Commission Workshop

At the August 28, 2023 workshop, City Council discussed and directed staff to proceed with the proposed TEDS update adoption schedule. The Planning Commission did the same at their September 7th workshop.

#### **Adoption Schedule**

- Oct 10th Planning Commission Public Hearing
- Oct 18th 1st Reading City Council
- November 1st City Council Public Hearing

Over the past year, City staff worked with the project team to review and provide potential changes that consider best practices in the industry, promote and support the City's Pedestrian and Bicycle Plan, and implement the vision of the community though that planning effort. Some aspects of the Manual are out of date, don't meet regional and national standards, and are not reflective of current community values or current design practices being applied within the city. To keep the TEDS current and relevant, the following proposed modifications are outlined below.

#### Summary of Major Changes to TEDS Manual Chapters

- Reflect current design guidance from State and National sources such as the Colorado Department of Transportation (CDOT), American Association of State Highway and Transportation Officials (AASHTO), the Institute of Transportation Engineers (ITE), the National Association of City Transportation Officials (NACTO), which incorporate and promote industry best practices and standards for multi-modal public infrastructure.
- and other State and National sources.
- Update the standard street cross sections primarily to:
- o Incorporate low stress bicycle and pedestrian facilities in alignment with the Pedestrian and Bicycle Plan,
  - o To reflect current City design practices, and
  - o To be consistent with the current Fire Department Access standards.
- Include new requirements for Transportation Impact Studies (TIS) to:
- o Document bicycle and pedestrian impacts (does not need to be completed by a transportation engineer), and
  - o A Traffic Assessment for mid-size developments (generating 10 to 99 peak hour

trips) in alignment with current CDOT practice may be required to assess need for turn lanes, sight distance, and pedestrian and bicycle impacts.

- Add requirements for inter-parcel connectivity between developments to:
  - o Mitigate traffic impacts on streets,
- o Improve mobility and access for people walking and biking to and through developments, and
- o To provide access to transit by through more direct connections between developments and transit stops on the adjacent street network.
- Reduced driveway width requirement on commercial/industrial and major streets
- Made driveway spacing and offset requirements simpler and consistent with intersection spacing requirements.
- Updated block length requirement to reference Zoning and Development Code.
- Reduced the design speed of local streets from 25 mph to 20 mph to be consistent with current practice and updated design speed of other streets to be consistent with updated street section and current practice.
- Updated traffic calming requirements on local streets to support slower design speeds and provided new example graphics.
- Removed the Fire Department Access Document and only reference it in TEDS. TEDS Exceptions are only allowed for alternative streets.
- Modified "effective" turn radii requirements to account for streets with bike lanes and on-street parking to encourage slower design turning speeds to mitigate intersection conflicts with pedestrians and bicyclists.
- Added illuminance requirements for bicycle and pedestrian facilities.
- Updated signing and striping requirements and signal design to match current City practice.
- Updated pedestrian and bicycle design standards to match the vision and guidance in the Pedestrian & Bicycle Plan and to reflect current national best practices.
- Added design guidance on pedestrian and bicycle crossings.
- Chapters removed or with new external references:
- o 29.24 Fire Department Access: modified to refer to the Grand Junction Fire Department Access standards and the locally adopted fire code
- o 29.44 Traffic Signals and Construction Zones: Article II Traffic Signal Specifications were updated and removed from TEDS and now include a reference to the Traffic Signal Specifications as an external City document.
- o 29.52 Transit Design Standards and Guidelines: This chapter of TEDS was removed and Chapter 29.48 now includes a reference to the Mesa County Transit Design Standards and Guidelines and found online on the Mesa County's website.
- o 29.60 Private Streets, Shared Driveways, and Loop Lane: This chapter was removed from TEDS as it is addressed in the Zoning and Development Code.
- o The previously developed document titled Grand Junction Pedestrian Crossing Treatment Installation Guidelines is now referenced in TEDS as a tool when considering pedestrian crossing treatments in different contexts and will be made available online on the City's website.

Summary of Major Changes to the Standard Street Sections:

• Lane widths were updated to 11' on arterial and collector streets.

- Sidewalk widths were updated to 6' on local and collector streets with posted speeds less than 35 mph, and to 8' on arterial and collector streets with posted speed greater than or equal to 35 mph.
- o An Exception Request can be considered for sidewalks under 6' within a constrained environment or with very low volumes of vehicle traffic.
- Detached sidewalks are standard on all arterial and major collector streets and options for detached sidewalks are included on local and minor collector street standards.
- Low-stress bicycle facilities are included on all arterial and major collector street standards consistent with the Pedestrian and Bicycle Plan.
- Narrower street cross-section options (with and without parking on one or both sides as well as sections with attached or detached sidewalks) are included for local residential streets that meet requirements in the Fire Department Access standards.
- o Requirements for off-street parking and a fire site plan are included for narrow street standards in alignment with the Fire Department Access standards.
- The multipurpose easement was updated to 10' on street sections with a detached sidewalk, which is consistent with existing practice on major arterial streets (14' width was preserved on street sections with attached sidewalks).
- The Rural street section was removed.
- All streets are required to have a sidewalk on both sides of the street unless there is a public walkway on the other side of houses/businesses.
- A 5' sight zone has been added behind the walk to the local street sections.
- Right-of-Way width was increased on the following street sections to accommodate pedestrian and bicycle infrastructure:
  - o Major Arterial remains at 110'
  - Minor Arterial increases from 80' to 100'
  - o Major Collector increases from 60' to 78' or 70' depending on posted speed
  - o Minor Collector/Commercial increases from 52' to 64'
  - o Industrial increases from 48' to 55'
- o Local Residential Street standard with attached sidewalk increases from 44' to 46' (other options are provided that vary in ROW width from 38' to 63').
- G Road section was updated to include bicycle and pedestrian infrastructure with minimal changes to Right-of-Way
- Shared-Use Path name was changed to a Trail and a Pathway section was added that includes a 6' path for connections at the end of cul-de-sacs that are not a part of the Active Transportation Corridors.
- Notes were added to street sections where the sidewalk buffer (between the sidewalk and curb) may be less than 7' that the minimum sidewalk buffer width is 7' for planting trees.
- The following note was added to street sections with trails: "A trail is considered multi-use for wheeled traffic and pedestrians."

#### Changes to the TEDS Final Draft

The Final Draft TEDS was modified on October 5, 2023 with the following changes. Other than No. 3 regarding the storage length table, all the other changes are

minor with many correcting or making verbiage consistent throughout the document. The Storage Length Table changes were requested by the Engineering community.

#### Changes include:

- 1. Low Speed Major Collector section narrow sidewalk buffer from 5' to 4.5' to make the 70' right of way correct. At 5' it is 71' of right of way.
- 2. Principal arterial section, top right in section view, change to "principal arterial with trail," not "shared use path." Also change on line two in the table.
- 3. 29.16.110 storage length table. Change the second line (50-200) to be 40' for all columns. Change the third line (201-400) to be 40' in the first column.
- 4. Section 29.36.080(b), 29.48.040 (a)(6) change "paths" to "pathways."
- 5. Trail/path detail
- a. column A should be "width," not "path."
- b. Column B should be titled "subgrade/base width." Or something similar.
- c. For the trail, column a should say "varies" instead of 10.
- d. Change the first note to read "A Trail/Pathway shall be designed in accordance with the AASHTO "Guide for the Development of Bicycle Facilities" current edition." Delete "Off Street paths.
- 6. Residential and Industrial Local Street, change the first note to say "A sidewalk...only if a sidewalk, trail, or pathway...sidewalk." This adds the word trail and changes path to pathway.

#### **ANALYSIS**

In accordance with Section 21.02.140(c), a proposed Code amendment shall address in writing the reasons for the proposed amendment. There are no specific criteria for review because a code amendment is a legislative act and within the discretion of the City Council to amend the Code with a recommendation from the Planning Commission. The purpose for proposing these updates/amendments is to better align the standards with the City's vision established in the 2020 One Grand Junction Comprehensive Plan, the recently adopted Pedestrian and Bicycle Plan, to conform to national and regional best practices, and to modernize the Transportation Engineering Design Standards (TEDS).

#### Compliance with the Comprehensive Plan

The proposed TEDS update further supports and implements the 2020 One Grand Junction Comprehensive Plan. It supports Goal 4 of Plan Principle 5 "Strong Neighborhoods and Housing Choices" which reads, "Promote the integration of transportation mode choices into existing and new neighborhoods. A strategy under Plan Principle 5 addresses "Neighborhood Connections;" it reads "connect new and existing neighborhoods with features such as sidewalks, trails...to provide opportunities for interaction and strengthen a sense of community." The TEDS update increases sidewalk widths within new subdivisions to be 6 feet and pathways also 6 feet in width connecting neighborhoods with external connections for pedestrian and bicycle use. These will provide a safe and direct connection to neighborhood and employment centers as part of another strategy found in the Comprehensive Plan that addresses "Connectivity and Access."

#### NOTIFICATION REQUIREMENTS

Notice was completed as required by Section 21.02.080(g). Notice of the public hearing was published on October 1, 2023, in the Grand Junction Daily Sentinel. An online public hearing with opportunity for public comment was held between September 19, 2023 and September 25, 2023 through the GJ Speaks platform.

#### STAFF RECOMMENDATION AND FINDINGS OF FACT

After reviewing the proposed updated Transportation Engineering Design Standards (TEDS) Manual, Staff finds that the proposed TEDS Manual:

- 1. Reflects current community values for multimodal transportation (including for pedestrians, bicyclists, and transit users).
- 2. Incorporates current state and national design standards.
- 3. Improves the usability of the manual.
- 4. Supports implementation of the vision established in the recently adopted Pedestrian & Bicycle Plan.

#### SUGGESTED MOTION:

Chair Teske, on the adoption of the updated Transportation Engineering Design Standards (TEDS), TEDS-M-2023-461, I move that the Planning Commission forward a recommendation of approval with the findings as listed in the staff report.

Chair Teske, on the adoption of the updated Transportation Engineering Design Standards (TEDS), TEDS-M-2023-461, I move that the Planning Commission forward a recommendation of conditional approval with the changes listed in the document titled "Proposed Changes to TEDS" with the findings as listed in the staff report.

#### Attachments

- 1. TEDS Manual 100623
- 2. Proposed Changes to TEDS Related to Ped-Bke Plan Ref
- 3. Public Comments with City Response
- 4. Public Comments draft TEDS
- 5. Proposed ordinance 2023 TEDS Update



# TRANSPORTATION ENGINEERING DESIGN STANDARDS MANUAL

October 2023

Updated by:

FEHR PEERS

With support from:

Kimley»Horn

#### **CITY OF GRAND JUNCTION**

# TRANSPORTATION ENGINEERING DESIGN STANDARDS (TEDS)

### **TABLE OF CONTENTS**

29.01	Introduction
29.04	Street Classification Standards
29.08	Transportation Impact Studies
29.12	Access Management
29.16	Access Design and Site Circulation
29.20	Local & Minor Collector Streets, Landscaping & Traffic Calming
29.24	Fire Department Access
29.28	Arterial and Major Collector Design, Including Roundabouts
29.32	Pavement & Truck Routes
29.36	Street Lighting, Utilities, and Mailboxes
29.40	Striping and Signing
29.44	Traffic Signals and Construction Zones
29.48	Transit, Bicycle, and Pedestrian Facilities
29.56	Alley Standards
29.64	Design Exceptions
29.68	Alternate Street Standards

#### **APPENDIX**

Principal Arterial Street Section

Minor Arterial Street Section

Major	Collector 7	'8' ROW	greater	than o	r equ	al to 3	5 mpl	h Street	Section

Low Speed Major Collector 70' ROW less than 35 mph Street Section

Minor Collector Street Section

**Local Commercial Street Section** 

Residential and Industrial Local Street Section

G Road Street Section

Trail/Pathway Section

Cul-de-Sac Section

Alley Section

Pedestrian & Bicycle Analysis Worksheet

**TEDS Exception Request Application** 

**TEDS Exception Request Application Instructions** 

**Transportation Impact Study Base Assumptions** 

#### **29.01 INTRODUCTION**

#### 29.01.010 Forward

#### **Applicability**

The standards contained herein regulate all transportation improvements within the public rights-of-way, and all private work to be dedicated to the public, either as right-of-way or as an easement, and to site circulation. The standards are to be treated as law and applied to all development as defined by the Zoning and Development Code (Title 21 of the Grand Junction Municipal Code). To that extent they are imposed to provide for coordinated, modern development with safe and efficient transportation facilities for the benefit of and to serve and protect users. The standards apply within the City of Grand Junction Urban Development Boundary, which includes all areas within the city limits and portions of unincorporated Mesa County. The Urban Development Boundary can be seen on the Urban Development Boundary layer on the Grand Junction GIS Development Map.

All facilities and improvements within the public rights-of-way shall be designed by or under the direct supervision of a registered professional engineer licensed to practice in the State of Colorado. All drawings, designs, sections, detail and supporting data submitted to the City or County for approval must bear the engineer's seal and signature and a statement that:

This design complies with Grand Junction Municipal Code Title 29, the current Transportation Engineering Design Standards, dated mmmm dd, yvvv.

All designs submitted shall be in accordance with the latest edition of the TEDS manual.

Some projects financed wholly or in part with state or federal funds are subject to the standards prescribed by agencies other than the City and County. Such standards may be more or less restrictive than the City of Grand Junction and Mesa County standards. The City and County require that the more restrictive standards shall be met.

The TEDS addresses frequent construction and development problems and questions. The standards by adoption and application ensure consistent transportation engineering design practices for new development and redevelopment of land within the City of Grand Junction Urban Development Boundary. Some of the material contained in this document has been drawn from standards of other cities and states and nationally established texts and publications.

The TEDS applies to all new developments except in special cases as noted, limited and defined herein or defined in the Zoning and Development Code. Infill development within the City of Grand Junction Urban Development Boundary may be constrained by existing improvements. If such a condition exists, where existing infrastructure has been built but does not meet current TEDS, the Director may allow the existing infrastructure to remain if it is adequate to serve the existing and proposed traffic (vehicle, ped, bicycle) and in good working condition. If it is in poor condition or inadequate, all requirements shall be constructed unless an affirmative waiver of TEDS is obtained in accordance with Chapter 29.64.010.

On Colorado highways within the Urban Development Boundary, the Colorado Department of Transportation (CDOT) <u>Roadway Design Manual</u>, the <u>State Highway Access Code</u>, and any corridor-specific access control plan shall apply but only if more restrictive than TEDS.

If a proposed development within the City of Grand Junction Urban Development Boundary requires access to a County roadway or work will be performed in the County right-of-way, approval from the County must first be obtained.

# 29.01.020 Companion Documents and Software Recommended For Use with the Transportation Engineering Design Standards

#### **Publications**

#### City:

- City of Grand Junction Municipal Code, Title 21 Zoning & Development Code [GJMC Title 21]
- City of Grand Junction *Standard Contract Documents for Capital Improvements Construction* [Std Contract Docs]
- City of Grand Junction Circulation Plan [GJMC Title 31.08]
- City of Grand Junction *Pedestrian & Bicycle Plan* [Ped/Bike Plan]
- City of Grand Junction *Pedestrian Crossing Treatment Installation Guidelines* [Crosswalk Guide]
- City of Grand Junction Fire Department Access [GJ Fire Access]

#### County:

- Mesa County *Design Standards* [County Standards]
- Mesa County Transit Design Standards and Guidelines

#### State:

- Colorado Department of Transportation *Roadway Design Guide* [CDOT Road Design]
- Colorado Department of Transportation *State Highway Access Code* [CDOT Access Code]
- Colorado Department of Transportation Pedestrian Crossing Installation Guide
   [CDOT Ped Crossing Guide]

#### Federal:

- Transportation Research Board Highway Capacity Manual
- Transportation Research Board NCHRP *Guide for Roundabouts* [TRB Roundabouts]
- Federal Highway Administration *Manual on Uniform Traffic Control Devices* [MUTCD]
- Federal Highway Administration Separated Bicycle Lane Planning and Design Guide [FHWA Separated Bike Lane Guide]

#### **Professional Organizations:**

• Institute of Transportation Engineers *Trip Generation Guide* [ITE Trip Gen Guide]

- American Association of State Highway and Transportation Officials A Policy on Geometric Design of Highways and Streets
- American Association of State Highway and Transportation Officials Guide for Bicycle Facilities
- American Association of State Highway and Transportation Officials Roadside Design Guide
- American Association of State Highway and Transportation Officials A Guide for Erecting Mailboxes on Highways
- National Association of City Transportation Officials *Urban Bikeway Design Guide* [NACTO Bikeway Design Guide]
- National Association of City Transportation Officials *Designing for All Ages and Abilities* [NACTO All Ages Design Guide]
- National Association of City Transportation Officials *Don't Give Up at the Intersection* [NACTO Don't Give Up At Intersection]
- Colorado Asphalt Pavement Association Guideline for the Design and Use of Asphalt Pavements for Colorado [CO Pavement Guidelines]

#### Software

- Synchro or other software as approved by the city transportation engineer that aligns with methodologies from the latest Highway Capacity Manual (Signal Timing and Analysis)
- *SIDRA* or other software as approved by the city transportation engineer (Roundabout Analysis)
- AASHTO93 and M-E Design (Asphalt Pavement Design)
- WinPAS from American Concrete Pavement Association

#### 29.04 STREET CLASSIFICATION AND STANDARDS

#### 29.04.010 Street Classifications and Standards

All streets have different functions. The primary function of local streets is to serve land uses directly while the primary function of major streets is to move vehicles quickly and efficiently from one point to another. Ensuring that each street type can meet or maintain its primary function is crucial to the overall operation of the street system.

The streets in the Grand Junction urbanized area are classified according to their function in the transportation network. The major street types are Principal Arterial, Minor Arterial, Major Collector and Minor Collector. All others are local streets. The functionally classified streets have been identified on a functional classification map that has been adopted by the City of Grand Junction and accepted by Mesa County. Reference to the *Street Plan Functional Classification Map*, Figure 3 in the Grand Junction Circulation Plan and the Street Classifications layers on the Grand Junction GIS Transportation Map. Different access controls and design standards apply to different roadway classifications. The purpose is to preserve or enhance safety and traffic flow.

The <u>Pedestrian and Bicycle Plan</u> is referenced throughout this manual for compliance with the adopted plan. The existing and proposed routes in the Pedestrian and Bicycle Plan can be seen in the Pedestrian and Bicycle Plan layer on the <u>Grand Junction GIS Transportation Map</u>. Existing trails and bike routes can be seen in the Trails layer on the <u>Grand Junction GIS Transportation Map</u>.

Roadway segments with existing access management plans provide specific access control requirements on those roadways and should be referenced when applicable. The streets within the City of Grand Junction Urban Development Boundary with access control plans are shown on the Access Management Plans layer on the Grand Junction GIS Transportation Map. These include:

- The Patterson Road Access Management Plan
- The Pear Park Plan
- Access Control Plan's on CDOT Highways
  - o Clifton Access Control Plan
  - o CO 340 Access Control Plan
  - o US 50 Access Control Plan
  - o US 6 and I-70B Access Control Plan

The City Council and County Commission have adopted standard drawings and details for the construction of streets and location for utilities. These standards include minimum

right-of-way and street width requirements, and include construction details for major and local streets. These street section drawings will be referenced throughout the document and can be found in the Appendix.

The adopted Street Classification Map in the <u>Grand Junction Circulation Plan</u> as well as the Street and Utility Standard drawings are available online and in various formats including AutoCAD Files.

#### **29.08 TRANSPORTATION IMPACT STUDIES**

#### 29.08.010 Transportation Impact Study

The Transportation Impact Study (TIS) will assess the impacts of proposed development on the existing and planned street system. Comprehensive and coordinated transportation planning is critical to providing a balanced transportation system. The application of sound design principles for new streets, preserving street capacities in existing areas, ensuring smooth traffic flow, accommodating all transportation modes, and preserving or increasing safety are part of the TIS. To evaluate the impacts of development proposals on the transportation system, a professionally prepared TIS shall be required. This chapter provides standards for the preparation of a TIS. In addition, the following documents shall be referenced for more detailed information:

- (a) Street Classification Map, figure 3 in the <u>Grand Junction Circulation Plan</u>, or on the Grand Junction Circulation Plan and the Street Classifications layers on the Grand Junction GIS Transportation Map.
- (b) Mesa County Functional Classification Map
- (c) City of Grand Junction Standard Contract Documents for Capital Improvements
  Construction
- (d) Pedestrian & Bicycle Plan
- (e) Mesa County Transit Design Standards and Guidelines
- (f) Corridor Guidelines

For Projects with direct or indirect access onto a state highway.

- (a) CDOT State Highway Access Code
- (b) CDOT Roadway Design Manual

The primary responsibility for assessing the transportation impacts associated with a proposed development rests with the developer, and including but not limited to the City, County, Colorado Department of Transportation (CDOT) or Regional Transportation Planning Office (RTPO) which operates Grand Valley Transit (GVT) serving in a review capacity.

#### 29.08.020 Procedure

The following required steps describe the procedures required for the preparation and submittal of a TIS. This process can be altered slightly depending on the complexity of the project:

- (a) General Meeting or Pre-Application Meeting
- **(b)** Determination of Base Assumptions
- (c) Submittal
- (d) Review Agency Comments and Recommendations

#### 29.08.030 General Meeting or Pre-Application Meeting

As a general rule, a TIS shall be required for all land use applications for new development in the City and as required by Mesa County Land Development Code. The requirement to prepare a TIS - or portions of a TIS - may be waived by the Transportation Engineer if the peak hour vehicle trip generation of the proposed project is less than 100 trips.

If the peak hour vehicle trip generation is estimated to be between 10 trips and 99 trips and the TIS requirement is waived by the Transportation Engineer, the applicant may still be required to complete a Traffic Assessment to determine if turn lanes are needed and if the proposed circulation serves pedestrians, bicyclists, and access to transit. A Traffic Assessment may include the following portions of a TIS: 1) Project Description, 2) Trip Generation, 3) Site Design and Circulation Evaluation, 4) Turn Lane Warrant Analysis, 5) Sight Distance Evaluation, and 6) Pedestrian and Bicycle Analysis.

If the applicant can demonstrate to the satisfaction of the Transportation Engineer that no other concerns exist with the transportation aspects of the proposed project, then a memo shall be prepared by the engineering consultant documenting the trip generation and safety improvements of the project and conclusions of the TIS.

The peak hour trip threshold of 100 is consistent with the Colorado Department of Transportation (CDOT) thresholds for requiring impact studies on state highways. The peak hour trip threshold of 10 – 99 for completing a Traffic Assessment is also consistent with CDOT thresholds on state highways. The methodology documented in the current edition of the *Institute of Transportation Engineers'* (ITE) Trip Generation Manual should be used to identify the peak hour vehicle trip generation rates for a project. The current edition of ITE *Trip Generation Manual* is adopted and incorporated by this reference.

The applicant shall provide, to the Development Engineer and the Transportation Engineer, information regarding:

- (a) The project including type of land use (single family, townhomes, multi-family, office, retail, etc.) and size (number of dwelling units, square footage, etc.).
- **(b)** The project site plan showing all proposed access locations and proposed land uses in relation to the accesses.
- (c) Anticipated project completion date and project phasing.
- (d) Any other information necessary or required to evaluate the project.

The appropriate agencies shall review the project information and provide comments regarding transportation issues including, but not necessarily limited to, accesses (locations/type), impacts on adjacent neighborhoods, the size of the study area and the study methodology.

#### 29.08.040 Determination of Base Assumptions

The consultant preparing the TIS shall complete the Base Assumptions form (see Appendix). The Transportation Engineer will evaluate the TIS. The assumptions, once approved, shall confirm the base parameters and assumptions to be utilized by the traffic consultant in preparation of the TIS.

#### A <u>Base Assumptions</u> Form shall specify:

- (a) Study Area Boundaries
- (b) Study Years
- (c) Future Traffic Growth Rates
- (d) Study Intersections
- (e) Time Period for Study
- **(f)** Trip Generation Rates
- (g) Trip Adjustment Factors
- (h) Overall Trip Distribution
- (i) Mode Split Assumptions
- (j) Committed Roadway Improvements by other projects, CDOT, Grand Junction and Mesa County
- (k) Other Relevant Transportation Impact Studies

(I) Areas Requiring Special Study

#### 29.08.050 Pedestrian & Bicycle Analysis

As part of the Pedestrian and Bicycle Analysis the Applicant shall complete the Pedestrian & Bicycle Analysis Worksheet (see Appendix) and document the existing conditions of adjacent pedestrian and bicycle infrastructure. The Pedestrian and Bicycle Analysis Worksheet is intended to identify impacts (if any) and potential mitigations (if needed) to existing or planned pedestrian and bicycle infrastructure by the proposed development. A transportation engineer is not required to complete the Pedestrian and Bicycle Analysis Worksheet.

Documentation of the existing pedestrian and bicycle infrastructure should include the following areas near the development:

- (a) Pedestrian and bicycle infrastructure adjacent to the proposed development.
- (b) Pedestrian and bicycle infrastructure between the proposed development and the nearest adequate facilities if there are no or substandard pedestrian or bicycle facilities adjacent to the development.
- (c) Pedestrian and bicycle infrastructure to destinations within a quarter mile of the development that will likely generate pedestrian or bicycle trips (such as grocery stores, transit stops, housing, employment centers, recreational facilities, services, and schools).

As part of this analysis the Applicant shall identify missing or substandard pedestrian and bicycle infrastructure by specifically noting the following conditions for each.

For pedestrian infrastructure:

- (a) Pavement width
- **(b)** Pavement condition
- (c) Pavement material
- (d) Whether the walkway is attached (directly adjacent to the street), detached (separated by a landscaped or hardscaped buffer), part of a multiuse trail independent of a street, or missing.
- (e) Width of the buffer (between the sidewalk and the street) as applicable.
- **(f)** Presence of obstructions in the walkway (such as street poles, etc.).

- (g) Presence of pedestrian crossings and whether they are marked or unmarked, controlled (by a stop sign or signal) or uncontrolled.
- (h) ADA compliance of pedestrian ramps at crossings.
- (i) Number of conflicting driveways and lengths.

#### For bicycle infrastructure:

- (a) Presence of a bicycle facility and type of facility (Bicycle facilities are defined by the Pedestrian and Bicycle Plan and described in section 29.48 Transit, Bicycle, and Pedestrian Facilities of the TEDS Manual.)
- **(b)** Width of the bicycle facility and width of the buffer if applicable

The <u>Pedestrian & Bicycle Plan</u> shall be referenced and complied with for planned pedestrian and bicycle facilities within the study area boundaries. Pedestrian and bicycle standard widths and buffers by street type or context can be found in Chapter 29.20 for Local, Industrial, and Commercial Streets, and 29.28 for Collector and Arterial Streets, and Trails.

The analysis shall also discuss how pedestrians and bicyclists would access the proposed project to/from the adjacent neighborhood(s), and the need for special facilities to enhance pedestrian and bicycle connectivity.

The Pedestrian & Bicycle Analysis Worksheet (which can be found in the Appendix) will also identify existing pedestrian and bicycle facilities that may be impacted by the development and the extent of the impact, such as whether those facilities will result in an improvement, degradation, or no change to pedestrian and bicycle facilities. The form will also identify whether there is a proposed bicycle facility identified in the Pedestrian & Bicycle Plan on or adjacent to the proposed development and whether the development will impact the planned bicycle facility.

The form will also identify whether the proposed development is within an existing or planned shared micromobility zone as identified by the city. If so, the applicant should identify how the proposed development will include or accommodate storage space for shared micromobility devices. Similarly, the form will identify if the proposed development is within an overlay zone and whether the site plan is within compliance of the pedestrian and bicycle elements of the overlay zone.

#### 29.08.060 Submittal

Copies of the TIS shall be submitted to the City Community Development or County Planning Department, as part of the required planning information. Revisions to the TIS shall be made as required if:

- (a) Necessary to have a complete TIS; or
- **(b)** When changes to the development necessitate additional revisions to the study. Electronic files of capacity analyses must be submitted with the TIS.

#### 29.08.070 Review Agency Comments and Recommendations

The review agency or designee shall analyze, evaluate and/or review the TIS according to the adopted standards. Evaluative comments concerning the TIS shall be forwarded to the Project Planner. The Project Planner shall provide all review agency comments to the applicant. As a result of the engineering review the applicant may be required to:

- (a) Perform and submit supplemental analyses and/or address specific transportation issues or;
- (b) Prepare, perform, and submit a new study. Engineering review, shall to the extent practicable, cite references to this Manual, the Code, laws, rules, or regulation deficiencies in the TIS.

Review and evaluation of TISs are, and shall be, initially and principally based on local conditions and community expectations as articulated by local government and its officials. An example of such a local expectation is that eliminating existing left-turn phasing of a traffic signal at a nearby impacted intersection would not be a satisfactory solution to improving traffic level of service at that intersection.

If the TIS is based on assumptions that conflict with local conditions, and/or community expectations which may affect the usefulness or predictions proven by the TIS, the TIS will be rejected.

#### 29.08.080 Transportation Impact Study Report Contents

A Colorado licensed professional engineer shall prepare the TIS. The engineer shall have experience in traffic and transportation engineering. A statement of qualifications must be included in the submitted study. Certification as a Professional Traffic Operations Engineer by the *Institute of Transportation Engineers* is preferred. Each TIS shall address:

- (a) Project Description
- **(b)** Existing Conditions
- (c) Future Background Traffic Projections
- (d) Project Traffic
- (e) Total Traffic Projections
- (f) Future Total Traffic Projections
- (g) Site Circulation and Design Evaluation
- (h) Transportation Impact Analysis
- (i) Mitigation Measures
- (j) Neighborhood Transportation Impact Analysis
- (k) Conclusions
- (I) Recommendations
- (m) Any other information necessary or required to evaluate the project

#### 29.08.090 Project Description

A description of the proposed project shall be prepared and include the type of land use and size of the proposed project, generally known as density and intensity. Intensity may be described in terms of floor area ratio or square footage of proposed development. Phasing plans shall be proposed, including the anticipated completion date. The proposed site plan shall be included; the site plan shall include a description of all proposed vehicular access locations, dimensions, and movements. The project description shall include how pedestrian and bicycle travel shall be accommodated. This shall include a discussion of types of sidewalks (attached/detached), pathways, trails, and connections to local and perimeter destinations.

#### 29.08.100 Existing Conditions

The TIS shall identify the existing transportation system conditions. Existing conditions shall include a description of the surrounding roadway network, bicycle facilities, and pedestrian facilities; an evaluation of the peak hour capacity and level of service at the study intersections and traffic crash history.

#### 29.08.110 Description of Existing Transportation System

The study description of the existing roadway network shall include, but not necessarily be limited to, the number of travel lanes, presence or lack of pedestrian and bicycle facilities, posted speed limits, and adjacent land use(s). Traffic and intersection data compiled by the City and/or County Engineering Departments may be available. All recent (within two years) average daily traffic data that is available for the roadway network shall be shown on a figure in the study. Intersection peak hour traffic data shall be no older than one year; if new counts are necessary this is the sole responsibility of the applicant. The applicant may, at the direction of the Transportation Engineer, be required to collect data at a shorter interval. All traffic count data shall be included in an appendix to the TIS.

The TIS shall describe the existing bicycle and pedestrian facilities and shall include any facilities directly adjacent to the project site and within one-quarter mile or as described in section The Pedestrian and Bicycle Analysis section. The Pedestrian & Bicycle Plan shall be referenced and complied with for planned pedestrian and bicycle facilities within the study area boundaries.

Bicycle facilities are defined by *the* Pedestrian and Bicycle Plan and described in section 29.48 Transit, Bicycle, and Pedestrian Facilities of the TEDS Manual.

Special attention shall be given to the bicycle and pedestrian connections to specific uses including but not limited to: schools, parks, employment centers, commercial areas, shopping, and adjacent land uses.

#### 29.08.120 Capacity Analysis and Level of Service

The procedures set forth in the current edition of the <u>Highway Capacity Manual</u> (HCM) shall be used in analyzing the capacity and operational characteristics of vehicular, pedestrian and bicycle facilities.

HCM delay and queuing reports (such as Synchro or Sidra reports) shall be included in the appendices to the TIS report.

Roundabout analyses shall use SIDRA software or approved methodology. All worksheets shall be included in the appendices of the TIS report.

#### 29.08.130 Future Traffic Projections

The future traffic projections shall be determined for each of the study years identified earlier as part of the base assumptions. Future traffic projections for the TIS analysis shall include:

- (a) Planned System Improvements Capital Projects
- **(b)** Planned or in Process Development Projects
- (c) Background Traffic Growth

A description of project-specific planned transportation system improvements identified in City, County or CDOT capital improvement plans shall be provided. This shall include, but not be limited to: signalization, intersection improvements, roadway widening, bicycle/pedestrian projects, and transit capital and operating/service improvements.

The future traffic analysis shall include known development projects that are within the study area and would impact the study intersections. Projects outside the study area currently being developed shall also be considered. Every project(s) and the cumulative effect shall be listed in the TIS and include location, size, and proposed land use.

The background traffic growth within the study area shall also be accounted for when determining future traffic projections. Background traffic growth is defined as the expected growth in traffic from regional changes to land use and the transportation network exclusive of the project. Growth factors suggested by the consultant in the Base Assumptions form will be reviewed by the appropriate agency prior to use in the TIS.

The resulting future peak hour traffic projections at the study intersections shall be depicted on a figure in the TIS.

#### 29.08.140 Project Traffic

- (a) The transportation impacts of the project shall be generally determined based upon the following three-step process:
  - (1) Determination of Trip Generation
  - (2) Determination of Trip Distribution
  - (3) Assignment of Project Traffic

#### (b) Trip Generation.

The trips generated by the project shall be determined and provided in tabular form. The trip generation shall be determined for total build-out conditions and for any development phases. The trip generation table shall indicate the number of average daily trips and AM and PM peak hour trips and any other peak hour periods relevant to the development type.

The development of trip generation estimates for the project shall be based upon data from the current edition of the *Institute of Transportation Engineers'* - *Trip Generation Manual*. This includes using the selection process identified in the *Trip Generation Manual* to identify the appropriate land use code and trip generate rate. However, other data sources or trip generation rate studies may be utilized if the manual does not contain data for the type of project or other reliable data exists which better reflects the trip generation characteristics of the project. The use of other trip generation sources shall be discussed with the Transportation Engineer before being used, and if agreed, shall be memorialized in writing signed by the Transportation Engineer.

Adjustments to the standard trip generation of the proposed project may be made to account for internal site trips, pass-by trips, or other site specific/project specific characteristics of the proposed project. Adjustments for these characteristics shall be discussed with the City or County Transportation Engineer before use; in most cases the TIS shall follow guidelines set forth in documents such as the ITE *Trip Generation Manual*. The adjusted trip generation for the proposed project shall be provided in tabular form or illustrated on figures.

Pass-by trip percentages represent the percent of expected trips generated from the site that would have traveled along the adjacent roadway network even if the land use did not exist. The percent of pass-by trips may be deducted from the expected trip generation from a proposed development of the corresponding land use. The ITE *Trip Generation Manual* should be used to identify any applicable pass-by trip percentages.

#### (c) Trip Distribution.

The trip distribution for the proposed project shall be identified in the TIS. The distribution pattern shall be based upon: the project's location within the urban area, the traffic model maintained by the MPO, existing traffic volume data, project marketing data, and engineering judgment. A figure showing the percentage of site traffic on each street shall be provided as part of the traffic study graphic material.

#### (d) Trip Assignment.

The project traffic shall be assigned to the roadway system according to the established trip distribution. The resulting project site generated traffic shall be depicted on figures for build-out conditions and any project phases. Daily and peak hour traffic volume information shall specifically be included.

## 29.08.150 Total Traffic Projections

The total traffic projections shall be determined for each of the study years identified in the base assumptions. The project-related traffic shall be added to the existing peak hour traffic. The resulting total traffic projections shall be depicted on a figure in the TIS. For each of the study years, the total traffic projections shall include the future traffic plus the project-generated traffic. The future total traffic projections shall be depicted on figures for each study year.

## 29.08.160 Site Design and Circulation Evaluation

The project shall be analyzed to determine if the proposed circulation serves pedestrians, bicyclists and vehicles. The site design shall be evaluated to determine if facilities for vehicles, pedestrians and bicycles meet design standards and/or Codes. The project shall comply with the adopted <u>Pedestrian and Bicycle Plan</u>.

The project shall be evaluated to determine if traffic flows are properly designed. Proper design shall minimize areas where motorists would tend to speed, minimize potential conflict areas between vehicles and pedestrians/bicyclists, and to establish circulation patterns that avoid unnecessary traffic congestion, cut-through traffic and conflict points. Adequate throat lengths for on-site stacking at exit points is required (see 29.16.100). At signalized driveways, the HCM 90th percentile worst lane queue model shall determine the necessary storage. Businesses with drive-thrus must conduct a queuing analysis for the drive-thru to demonstrate that the queue will not extend back onto the public street.

# 29.08.170 Transportation Impact Analysis

The TIS shall determine if the project creates any significant impacts at the study intersections and/or corridors within the study area boundaries. The peak hour capacity and level of service at each of the study intersections and /or corridors shall be evaluated for:

- (a) Future Background Traffic Conditions for each Study Year;
- (b) Total Existing Traffic Conditions; and

(c) Future Total Traffic Conditions for each Study Year.

The capacity and level of service analysis for each traffic scenario and each study year needs to include mode split assumptions, if any. The findings shall be shown in the TIS in tabular form or illustrated on figures.

## 29.08.180 Calculations for Capacity and Level of Service

HCM delays and queues shall be calculated for signalized intersections using the current version of the Highway Capacity Manual. Synchro is the preferred software, however additional software that that utilize the current HCM methodologies may be utilized with prior approval from the Transportation Engineer. The HCM delay and queues shall be calculated for the identified peak hours for existing conditions, the projected traffic with build-out of the project, or at completion of phases of larger projects. An appropriate 15-minute peak hour factor shall be used. The performance evaluation of signalized intersections shall include the following:

- (a) Critical movements shall be identified and must meet or exceed the threshold requirement of 35 seconds of delay or less;
- **(b)** No movements shall have an adverse effect on the coordinated progression of the street system as determined by an approved coordination model consistent with the methods of HCM;
- (c) HCM 90<sup>th</sup> percentile worst lane queues shall be calculated and shall not obstruct upstream intersections or major driveways;
- (d) The analysis of a signalized corridor must show a reasonable progression band, identified as a usable (unblocked) band for major traffic movements.

Unsignalized intersections shall be analyzed using the current Highway Capacity Manual methods. In the performance evaluation of stop controlled intersections, measures of effectiveness to consider include the delay, volume/capacity ratios for individual movements, average queue lengths and 95<sup>th</sup>-percentile queue lengths to make appropriate traffic control recommendations. The Highway Capacity Manual recognizes that the delay equation used in the capacity analysis procedure will predict Level of Service F for many urban intersections that allow minor-street left-turn movements, regardless of the volume of minor-street left-turning traffic. In recognition of this, the TIS should evaluate the results of the intersection capacity analysis in terms of all of the measures of effectiveness.

Roundabouts shall be analyzed using the current version of SIDRA or approved methodology.

## 29.08.190 Mitigation Measures

The TIS shall include feasible measures that would mitigate the project's vehicular traffic impacts. The mitigation measures shall be in addition to the required improvements necessary to preserve corridor and intersection capacity. The acceptable mitigation measure(s) shall minimize the demand for trips by single occupant vehicles and increase the use of alternative modes. Mitigation listed in order of priority includes:

- (a) Transportation Demand Management Measures
- **(b)** Traffic Signal Operation Improvements
- (c) Street Widening and Other Physical Improvements

## 29.08.200 Transportation Demand Management (TDM) Measures

Transportation Demand Management measures are designed to facilitate the use of alternate transportation modes in order to decrease demand on the roadway system by single occupant vehicles. Example of TDM measures include:

- (a) Vehicle trip reduction incentives and services offered by employers to encourage employees to utilize alternative modes of travel such as carpooling, vanpooling, riding public transit, bicycling, walking and telecommuting.
- (b) Provision of a mix of land uses in close proximity, facilitating walking, bicycling or transit trips.

A detailed description of the proposed TDM measures and implementation plan shall be included in the TIS for any project seeking TDM-related trip reductions. If the proposed TDM program is acceptable to the Transportation Engineer, the applicant shall be allowed to reduce total project vehicle trips by an amount commensurate with applicable trip reduction policies.

The intersection capacity and level of service shall be calculated to reflect the application of the proposed mitigation measures; the calculation shall show that the project-related impacts have been reduced to an acceptable delay (see thresholds identified in 29.08.180) for all movements and transportation modes (vehicle, bicycles, pedestrians). The findings shall be shown in tabular form.

## 29.08.220 Traffic Signal Operational Improvements

Required traffic signal operational improvements may include upgrading signals with additional signal phases and/or signalization of an unsignalized intersection, addition of turn lanes and/or construction of a roundabout.

The need for new traffic signals shall be based on warrants established in the Manual on Uniform Traffic Control Devices, <u>MUTCD</u>. In determining the location of a new signal, traffic progression is of paramount importance. On arterial streets a spacing of one-half mile for all signalized intersections is necessary to achieve reasonable operating speed, capacity and optimum signal progression. Pedestrian movements shall be considered in the evaluation and adequate pedestrian clearance provided in the signal phasing assumptions.

The applicant shall submit an analysis addressing proposed access, proposed signals and capacity and level of service based on the City's operational practices. All assumptions shall be documented in the TIS. An approved traffic engineering analysis must be made to properly locate all proposed accesses that may require signalization. The roadway to be analyzed for signal progression shall be established by the City or County and shall include all existing and proposed signalized intersections.

- (a) The progression pattern calculations must match the existing cycle length on the corridor under analysis.
- (b) Signal phasing assumptions must relate to traffic volumes in the capacity analysis of individual intersections.
- (c) Approved computerized progression analysis techniques must be of the type which utilize turning movement volume data and pedestrian clearance times in the development of timing plans.
- (d) The green time allocated to the cross street shall be considered no less than the time which is required for a pedestrian to clear the main street using <u>MUTCD</u> standards.
- (e) Existing timing and phasing data for City and/or County signals on the corridor(s) being analyzed will be provided to the consultant on written request.
- (f) Elimination of or substantial changes to existing phases and/or timing will not be allowed without written approval of the Transportation Engineer.
- **(g)** Existing signal operations shall be presumed to reflect the local conditions and community expectations as determined and directed by the Transportation Engineer.

(h) If optimum usable bandwidth, as that term is defined by the Transportation Engineer, would be reduced if a traffic signal were installed then the intersection shall remain unsignalized and turning movements shall be limited.

## 29.08.230 Street Widening and Other Physical Improvements

Mitigation measures that include street widening and other physical improvements must be physically feasible and must meet minimum standards and Code(s) for both on-site and off-site improvements.

#### **29.08.250 Conclusions**

The findings of the TIS shall be provided in a summary report.

#### 29.08.260 Recommendations

The TIS should include an executive summary including recommendations. Recommended improvements/mitigation measures to achieve standards and safety improvements shall be stated. The recommendation section of the report shall describe the location, nature, and extent of proposed improvements. A sketch of each improvement shall be provided showing the length, width, and other pertinent geometric features of the proposed improvement.

## 29.12.010 Access Management

Access management is a means to protect the safety, traffic operations, and the assigned functional purpose of the street system while considering the access needs of the various elements of the system. Access management addresses the problems of congestion, capacity loss, and accidents. Providing access to land development while simultaneously preserving the flow of traffic, bicycles, and pedestrians on the surrounding road system in terms of safety, capacity needs, and speed is the goal of access management. Access is defined as any driveway or other point of ingress/egress such as a driveway, alley, street, road, or highway that connects to the public street system.

The street system provides mobility to the traveling public. This travel may serve one of two distinct purposes. The first is to provide throughput, allowing travelers to move efficiently. The second is to provide direct access to properties. Arterial streets are traditionally designed to prioritize throughput for motor vehicles by intentionally limiting access. In contrast, local streets provide direct access to properties, but do not provide high throughput for motor vehicles. To accommodate throughput for motor vehicles on city streets, access on collectors and arterials must be intentionally managed.

However, limiting access on collector and arterial streets can also limit mobility of non-motorized and mass transit modes along those corridors. Therefore, the design of streets should consider the impacts to active transportation and transit users and how they may use the system differently. The Active Transportation Corridors defined in the Pedestrian and Bicycle Plan are along a mix of arterial, collector, and local streets, but are effectively the arterial street network for people walking and biking. Thus, travel for these users should be prioritized on these corridors. In some cases limiting access for motor vehicles can improve throughput for both motor vehicles and active transportation users, such as limiting driveways and turning movement conflicts along an arterial street. However, in other cases they may conflict. For example, long gaps in an arterial road without a traffic signal can improve throughput for motor vehicles along that corridor, but can decrease mobility for active transportation users trying to cross the street. Therefore, access control measures must be sensitive to the mobility needs of all modes of transportation.

The existing and future function of each street is critical in determining the number, location, and design of access points and access control. Access management extends beyond simply specifying the number and separation of driveways and access points. Included are roadway design, such as auxiliary lanes, medians, stopping sight distance, channelization, and land development issues such as sign standards, internal site circulation, driveway layout, and alternative travel modes.

Appropriate access management strikes a balance in preserving the functional integrity of the street and providing access. Speed, capacity, and safety are the significant reasons for instituting access management. With proper access management, the speed differential between vehicles can be minimized or separated and proper access management will reduce the number of conflict points, resulting in fewer accidents. When the traffic on the street system can travel safely and efficiently, capacity is preserved. Access management recognizes the interests of both landowners and roadway users in providing a transportation system that better meets the needs of all interests.

# **29.12.020 State Highways**

Refer to the current edition of <u>The State Highway Access Code</u>. Under that code, all accesses constructed on a State Highway require an access permit approved by the State. The Access Code requires owners of land adjacent to a State Highway that is being developed or redeveloped to apply for an Access Permit for each access to the State Highway if the use of the property is being changed or the existing access modified. The definition of property change is included in Section 2.6 of the Code.

## 29.12.030 City or County Streets

Local jurisdictions approve the design, number, and location of access points. When changes in land use occur which result in changes in the type or nature of access operation, the access shall be approved with the development plans and constructed to meet current standards.

# 29.12.040 Backing Into the Right-of-Way

Parking pods that require backing maneuvers into a public street will be allowed only on streets posted at 25 mph or less and with an ADT of 3000 vehicles or less. Parking pods shall be privately owned, or a revocable permit obtained if in public right of way, and privately maintained. Landscape islands shall be required every 8 spaces.

Backing into alleys will be allowed from normal parking stalls, regardless of land use, under the following conditions:

(a) The parking is designed so the parking stall and aisle meet the requirements of section 21.06.090 of the Zoning and Development Code. The needed aisle width can include the existing alley.

(b) A maximum of four spaces in a row will be allowed. This standard is designed for perpendicular parking spaces and a 50' wide lot. Wider lots can create more spaces, up to a maximum of 8 spaces. Angle parking will be addressed on a case-by-case basis to achieve the intent of this standard.

#### 29.12.050 Provision of Access

If a property has frontage on more than one street, access will be permitted only on those street frontages where design and safety standards can be met. The primary access shall be on the lower-order street. Refer to the current edition of the <a href="State Highway Access">State Highway Access</a> <a href="Code">Code</a> for access requirements off a state highway.

## 29.12.060 Restriction of Turning Movements

Turning movements may be limited where necessary for the safe and efficient movement of traffic, both on and off-site.

#### 29.12.070 Number of Access Points and Joint Access

Each development applying for access to a collector or arterial street shall analyze its own internal circulation system and access points, as well as impacts to the surrounding properties and street system as part of the required TIS.

Cross-access connections and/or stub streets to abutting properties will be required between commercial and residential properties unless it can be shown that this won't facilitate better circulation or it creates safety hazards. The project site design shall include a circulation and access system that will safely and efficiently accommodate traffic from adjacent properties.

One access point per property ownership will be permitted, unless an approved site plan or TIS shows that additional access points are required to adequately handle driveway volumes and that the additional access points will not be detrimental to safety, traffic flow, and pedestrian and bicycle travel on adjacent public streets. Additional access points may also be allowed at the discretion of the director. Temporary access may be granted to accommodate phased development of a site. Temporary accesses are subject to removal, relocation, redesign or reconstruction after permanent approved access is constructed.

#### 29.12.080 Cross-Access Corridors

Cross-access corridors shall be designed to provide common access and circulation among parcels, to assist in local traffic, pedestrian, and bicycle movement. Cross access should be designed to include the following elements:

- (a) Sufficient separation between the public street and the cross-access corridor to allow storage and circulation to occur within the site.
- (b) Sufficient width to accommodate **two-way travel** aisles designed to accommodate automobiles, service and delivery vehicles.
- (c) Stub-outs to the abutting properties that will be tied in to provide cross-access.
- (d) Linkage to other cross-access corridors in the area, if applicable.
- (e) Sidewalks and/or trails to connect pedestrians and bicycles from existing facilities to, or through, the parcel to surrounding properties that will develop in the future and/or to existing facilities in a nearby location.

Wherever a cross-access corridor is designated on a subdivision plat, site plan or other development application, the property owner shall grant and record an easement allowing cross-access to and from the other properties in the area.

#### **29.12.090 Stub Streets**

A stub street is an existing or planned street that is or will be extended to the property line(s) of a development for the purpose of future extension onto adjacent property. A stub street may be for access and/or as a part of the comprehensive circulation system.

## 29.12.100 Abandoned Accesses

Existing driveways shall not be abandoned, relocated, altered, or reconstructed without a permit from the appropriate agency..

#### 29.12.110 Exclusive Turn Lanes

Exclusive turn lanes are described in detail in the <u>CDOT State Highway Access Code</u> and in Chapter 29.28.

## **29.12.120 Field Access**

Field access is defined as access used solely for agricultural purposes and traffic generation does not exceed one vehicle (two trip ends) per day when averaged over one calendar year. When an agricultural property changes to a new or more intensive land use, all field accesses to the property shall be considered abandoned and access points for the new or more intensive use will be determined by the standards contained within this document.

# 29.12.130 Access Exceptions

Exceptions to these standards shall be allowed only as set forth in Chapter 29.64.

## 29.16.010 Access and Site Design

Access is defined as any driveway or other point of ingress/egress such as a street, road, highway or driveway that connects to the public street system. This chapter defines the types of accesses, their locations, and geometric requirements.

Acceptable site design is achieved when three major elements – access location and design, site circulation and parking, building footprint and location – are integrated. Site circulation can directly affect the safety, traffic operations and the assigned functional purpose of the street system. Good site circulation is necessary to protect the integrity of the public streets as well as public safety within the site.

On collector and arterial streets, shared accesses will be required wherever possible to minimize the number of access points along a street. Shared access provides for safer and more efficient operation of the flow of traffic on the street and shall minimally meet the above requirements. Access easements are required.

#### 29.16.020 Access Locations

All entrances and exits to vehicular traffic areas shall be located and constructed to minimize traffic congestion on the public street system.

# 29.16.030 Spacing and Offsets

On local residential streets, single-family residential driveways on the same side of the street shall be located a minimum of 5 feet, from property line, to allow for maneuvering to occur without trespass. In locations where the 5 feet minimum spacing cannot be met due to limited lot frontage or other field constraint, the Development Engineer may permit a variance from the spacing standard.

On local commercial and industrial streets, driveways on the same (spacing) or opposite side (offset) of the street shall be spaced a minimum of 50 feet apart, measured from edge of access to edge of access. On collector streets, driveways on the same or opposite side of the street shall be spaced a minimum of 150 feet apart. (see <a href="Driveway Spacing, Width, and Offset Requirements by Street Classification">Driveway Spacing, Width, and Offset Requirements by Street Classification</a>). On minor arterial streets where no other access to lower order streets is available, driveways on the same or opposite side of the street may be allowed but must be spaced a minimum of 150 feet apart and may be restricted to right-in, right-out movements. On principal arterial streets where no other

access to lower order streets is available, driveways on the same or opposite side of the street may be allowed but must be spaced a minimum of 300 feet apart and may be restricted to right-in, right-out movements. Greater distances may be required for left turn storage lanes.

No new residential driveways shall be allowed on arterial streets serving less than three units and allowable driveways must be designed so vehicles are not backing into the street.

#### 29.16.050 Corner Clearance

Corner clearances are defined as the distance between the edge of a driveway (exclusive of the taper) and the edge of the nearest intersecting street. The clearance is necessary so that accesses do not interfere with street intersection operations and should provide drivers with adequate perception-reaction time to potential conflicts. On corner lots, the access location shall be on the street of lowest functional classification.

# Minimum Corner Clearance (ft) Measured from Flowline to Near Edge of Access

Street Classification Of Street Where Access Is Proposed	Clearance From Unsignalized Intersections	Clearance From Signalized Intersections	Single Family Residential Driveways
Local (≤ 300 ADT)	50'	150'	35'
Local (> 300 ADT)	50'	150'	50'
Collector	150'	150'	100'
Minor Arterial	150' *	300' *	N/A*
Major Arterial	300' *	300' *	N/A*

<sup>\*</sup>May be restricted to right-in, right-out only access. Single family access to arterial streets is not acceptable practice and will be permitted only in extreme hardship cases.

# 29.16.060 Access Design - Types of Access

Generally, all new private property access shall be designed as curb cuts. Radii type curb returns with handicap ramps will be required for accesses when the peak hour right turn entering volume exceeds 20 vehicles in the peak hour. Auxiliary lanes shall be constructed when turn volumes meet the minimum criteria in the right turn warrant chart in section 29.28.170.

## 29.16.070 Design Vehicles

All accesses shall be designed to accommodate the turning characteristics of the largest vehicle that will most commonly utilize the proposed access. Most residential and small commercial driveways only need to accommodate passenger cars; other commercial or industrial developments will usually require at least one access that can accommodate the efficient entry or exit of larger vehicles.

#### 29.16.080 Curb Cut Width

The width of the curb cut for a driveway will be wider than the driveway width to accommodate the turning radius of the entering and existing vehicles. The design turning radius shall be at least 15 feet. The effective turn radius (which accounts for on-street bike lanes or parking if applicable) shall be 20 feet for multi-family residential access and 25 feet for commercial access. The effective radii for industrial uses or truck delivery accesses shall be individually designed for the type of truck that will frequently use the access, with a maximum required radius of 50 feet.


## **29.16.090 Driveway Width**

Single-family residential driveway widths shall be between no more than 33 feet. All other access drive widths shall be between 25 feet and 36 feet. Multi-lane driveways shall be designed to accommodate a standard ingress lane of 14 feet and egress lanes of 11 feet.

## Driveway Spacing, Width, and Offset Requirements by Street Classification

Street Classification			
(Land Use)	<b>Driveway Spacing (S)</b>	Driveway Width (W)	Offset (OS)
Local (Residential)	10' Min.	33' Max.	No Requirement
Local (Commercial and	50' Min.	25' Min.	50' Min.*
Industrial)		36' Max.	
Collector	150' Min.	25' Min.	150' Min.*
		36' Max.	
Minor Arterial	150' Min	25' Min.	150' Min.*
		36' Max.	
Principal Arterial	300' Min.	25' Min.	300' Min.*
_		36' Max.	

<sup>\*</sup> Greater offsets may be required for left turn storage lanes.



## 29.16.100 Throat Lengths and Vehicle Storage


Adequate vehicle storage capacity shall be provided for both inbound and outbound vehicles. Adequate storage facilitates the safe and efficient movement of vehicles between the street and the development.


The access throat shall be of sufficient length to prevent vehicles from spilling onto the public street system. Inbound vehicle storage areas shall be of sufficient size to ensure that vehicles will not obstruct the adjacent street, sidewalk, or circulation within the facility. The throat shall be of sufficient length to provide adequate storage of outbound vehicles without them interfering with on-site circulation. Outbound vehicle storage areas shall be provided to eliminate backup and delay of vehicles within the development. At signalized intersections, adequate storage for the outbound movement must be provided to enable vehicles to exit efficiently on green.

The requirements for vehicle storage (see On-Site Driveway Vehicle Storage Lengths) in parking lots and at drive-up type facilities are generally based on a typical vehicle spacing of 20 feet, but may be increased where larger vehicles can be expected.

# 29.16.110 Accesses Serving Off-Street Parking Lots

On-site storage is measured from the flowline of the street to the first parking stall or aisle of a parking lot (see <a href="Throat Length Extents">Throat Length Extents</a>). Vehicle storage equivalent to or greater than the minimum distances shall be provided at accesses serving the site. The recommended distance for accesses with two approach lanes may be adjusted, subject to the TIS findings, roadway geometry, traffic volumes, and site layout.





On-Site Driveway Vehicle Storage Lengths (feet)

Parking	Storage Length Required <sup>1</sup>			
<b>Spaces Per</b>	<b>Multi-Family</b>	Retail	Office	Industrial
Exit Lane	Residential			
0-50	25	25	25	25
50-200	40	40	40	40
201-400	40	75	100	150
401-600	50	150	200	More Lanes
601-700	100	200	More Lanes	More Lanes
> 700	200	More Lanes	More Lanes	More Lanes

<sup>1</sup> High volume land uses or streets may necessitate greater storage lengths than shown.


# **Vehicle Storage Requirements for Drive-Up Facilities**

Type of Facility	Vehicle Storage		
Automated Tellers	4 spaces per machine		
Drive-In Bank	3 spaces per 1,000 sf		
Drive-In Restaurant	Identified through TIS		
Automatic Car Wash	7 spaces per wash line		
Self-Service Car Wash	2 spaces per wash line		
Drive-In Theater	15% of the total parking capacity		
Service Stations	1 space per nozzle + 1 space/island/direction		
Drive-In Liquor Store	3 spaces per window <sup>1</sup>		
Drive-In Dry Cleaners	2 spaces per window <sup>1</sup>		

Adapted from Table 9-4, NCHRP 348 Access Management Guidelines for Activity Centers

# 29.16.115 Dead-End Parking Aisles

Parking stalls located at the end of a dead-end parking aisle must be provided with adequate backing and turnaround space. The required depth of the turnaround space shall be determined as follows:



**Depth of Dead-End Parking Aisles** 

Width of Driving Aisle (A)	Depth of Turnaround Space (B)
24' or less	6'
25'	5'
26'	4'
27'	3'
28'	2'
29'	1'
30' or more	0'

<sup>&</sup>lt;sup>1</sup>Measured from the pick-up window and includes the vehicle at the window.

#### 29.16.120 Commercial Uses

The vehicle storage area that shall be provided for various drive-through commercial uses shall be:

- (a) Based on a 20' length vehicle and a 12'wide lane.
- (b) Separated from normal parking circulation aisles.
- (c) Designed using the appropriate design vehicle turning template.

#### 29.16.130 Grades

Access grades shall meet the same standard grades identified for intersections in Chapter 29.28.

## **29.16.140 Sight Distance**

Adequate sight distance (see GJMC 29.28.140) and sight zones (see GJMC 29.28.150) shall be provided at all access intersections and internal street or drive aisle intersections within a development.

#### 29.16.150 Channelization Islands

Channelizing islands are discouraged. Use of medians to control turning movements will be required where physical conditions allow.

Channelized islands will only be allowed in situations where medians to control access are not feasible. If allowed, the islands shall not be smaller than 100 square feet and shall provide vertical curb and exposed colored aggregate or patterned concrete treatment. Patterns and color shall match those of any nearby islands or medians. Additional right-of-way or easement may be required to accommodate these designs. The ends of the islands shall typically be constructed with 2-foot flowline radii.

Refer to the Intersection Chapter (Chapter 8 in the 2023 version) of the <u>CDOT Roadway</u> <u>Design Guide</u> for additional guidance.

## 29.16.160 Pedestrians and Bicycles

Pedestrians and bicyclists are especially vulnerable to turning vehicles at access drives. The consolidation of access points benefits pedestrians and bicyclists by reducing the number of conflict points along the roadway. Access designs for pedestrian and bicycle facilities shall conform to Chapter 29.20 and Chapter 29.28 requirements and with the Grand Junction Standard Contract Documents for Capital Improvements Construction.

#### 29.16.170 Transit

Where applicable, accesses shall be designed to accommodate busses or other transit vehicles in accordance with the Mesa County Transit Design Standards and Guidelines. These accommodations shall occur at shopping centers, malls, multifamily developments, or other mixed-use developments where transit vehicles may be frequent users of the onsite circulation system.

## 29.16.180 Emergency Vehicles

All accesses shall be designed to readily accommodate emergency vehicles that would ordinarily respond at the particular establishment (Refer to the current version of the Grand Junction Fire Department Access document and the locally adopted fire code).

## 29.16.190 Utilities and Lighting

Accesses shall be located to ensure that utility poles, electric boxes, and signs do not interfere with the visibility of the access or available sight distances. The design of site lighting shall maximize the visibility and location of the access.

# 29.16.210 Delivery and Service

Proposed development that includes truck loading/unloading shall provide adequate space for all truck operations. Adequate space minimally means that all truck operations be performed entirely on-site and off the public street system. Sufficient apron space shall be provided at all loading/unloading areas. Sufficient apron space is the area required for truck backing maneuvers. Delivery areas shall be separated from general traffic areas. Separation of delivery vehicle traffic from customer traffic shall occur entirely on-site. On-site roadways used by delivery vehicles shall be designed to accommodate the heavier payloads and turning characteristics of the largest vehicle expected to use the site.

#### 29.16.220 Transit and Pedestrians

In larger mixed-use developments, multi-family developments, shopping centers, and malls, on-site roadways shall be designed to accommodate transit. This includes the design of pick-up/drop-off areas as well as the circulating roadways. Transit stops shall be located within a reasonable walking distance of the main building entrance while minimizing potential conflicts with circulating vehicles. Continuous pedestrian walkways and crossings that meet ADA standards and follow a direct (non-circuitous alignment) must be designed on-site and connected with each other and to the adjacent pedestrian network to reduce conflicts between pedestrians and vehicles and provide convenient access between the land uses and transit.

## 29.16.230 Inter-parcel Circulation

Inter-parcel circulation with shared access is required between adjacent commercial properties for vehicles, bicycles, and pedestrians. Inter-parcel circulation with shared access may be required between residential and commercial. This will be evaluated on a case-by-case basis to consider the context of the situation. This will reduce the number of curb cuts on public streets and will increase the safety and comfort for all modes of transportation on the adjacent street and capacity of the street system. Within larger development sites public streets may be required as part of a connected network to facilitate inter-parcel circulation of vehicles, pedestrians, and bicyclists.

## **29.16.240 Landscaping**

Site landscaping requirements are detailed in the Zoning and Development Code. Landscaping at access points must meet the requirements for sight distance (see GJMC 29.28.140) and the sight zone (see GJMC 29.28.150). Landscaping islands shall also consider the same requirements.

# 29.20 LOCAL & MINOR COLLECTOR STREETS, LANDSCAPING & TRAFFIC CALMING

#### 29.20.010 Street Standards

Geometric street standards have been developed to provide livability for residents, safety for both vehicular and pedestrian traffic and efficient movement. This chapter sets the minimum standards for geometric design of local and minor collector streets that provide access to residential, commercial, and industrial land uses. These streets deserve special discussion because they are the most common streets built for development. Local streets are defined as streets whose primary function is to serve the abutting land use. Design criteria for both horizontal and vertical alignments are established in this chapter. Design criteria for major collector and higher classification streets are discussed in Chapter 29.28.

#### 29.20.020 Local and Minor Collector Streets

Streets shall conform with the adopted Street Plan Functional Classification Map, Figure 3 in the Grand Junction Circulation Plan. Minimally, the plan identifies locations where collector street connections are desired and identifies general alignments for local streets. Street layouts shall continue streets in adjoining subdivisions or their anticipated locations when adjoining property is not yet developed to provide interconnectivity.

## 29.20.030 Block and Lot Dimensions

Refer to the Zoning and Development Code for block and lot dimension requirements.

## 29.20.040 Right of Way, Street Lane Widths, and Street Lengths

The required right-of-way width for a street is stated in the Street Sections. Additional widths may be required for needed through lanes, turn lanes, speed change lanes, and where it is necessary to accommodate slopes, irrigation crossings, drainage structures, and timing of adjacent development.

#### 29.20.050 Cul-de-Sacs and Dead End Streets

No cul-de-sac shall be more than 750 feet long, measured from the center of the intersection to the center of the turnaround.

No more than 30 single family/duplex units shall be located on a cul-de-sac street. All cul-de-sacs shall have a turnaround at the terminus point. For single or two-family residential developments that exceed 30 units, a separate and approved fire apparatus access road will be required. If it is a multi-family residential development, the number of units can exceed 30 units and the fire code will govern.

Surface drainage of a cul-de-sac shall be conveyed toward the intersecting street, if possible, and if not possible a drainage easement shall be provided leading out of the cul-de-sac.

Fire Department Access standards contain additional details to assist developers and designers in meeting the requirements of the fire department (Fire department Access B.2-5) When two fire apparatus access roads are required, they shall be placed a distance apart equal to not less than one half of the length of the maximum overall diagonal dimension of the lot or area to be served, measured in a straight line between accesses.

Unless the street meets all of the requirements for a cul-de-sac, no dead end streets shall be allowed except in cases where such streets are designed to connect with future streets on adjacent land. In that case, if any lots in the subdivision are dependent upon the dead end street for access, the plat shall include a temporary turnaround easement at the terminus of the street.

A single access street system shall be allowed for a maximum 100 dwelling units. Before the 101<sup>st</sup> unit can be platted, a secondary access is required to be constructed or financially secured. This secondary access must be platted as public right-of-way and constructed to public street standards to the property line of the subdivision. A temporary turnaround shall be constructed if the stub street access is longer than 150 feet.

Pedestrian pathways or trails may be required off the end of cul-de-sacs to adjacent streets or cul-de-sacs to provide direct pedestrian and bicycle connectivity. See the Zoning and Development Code for pathway and trail connection requirements.

## **29.20.060 Alignments**

## (a) Horizontal Alignment

Designs must conform to the pattern of thoroughfares designated in the Street Plan Functional Classification Map in the Grand Junction Circulation Plan. Proposed streets align with existing or platted streets with which they are to connect.

Local streets (if not ending in a cul-de-sac) shall extend to the property lines of the project. A temporary turn around area capable of supporting a fire truck (HS-20 loading) shall be required at the end of the street improvement if a cul-de-sac is not provided and the street is longer than 150' from the flowline of the intersecting street. Proposed streets with widths different from existing streets to which they are being connected must be transitioned using the pavement transition taper standards.

## (b) Curve Radii

(1) All curve designs shall be based on the Horizontal Curve Design Criteria.

# **Horizontal Curve Design Criteria**

	Lo	Minor	
Design Criteria <sup>1</sup>	Hillside <sup>2</sup> / Residential	Industrial <sup>3</sup> / Commercial <sup>3</sup>	Collector <sup>3</sup>
Design Speed (mph)	20	25	25
Center <sup>4</sup> Line Radius (ft)	110	200	200
Horiz. Sight Dist. (ft)	150	200	200
Reverse Curve Tangent (ft)	0	0	0
Approach <sup>5</sup> Tangent at Intersections	50	75	75

<sup>1</sup> These criteria are to be used without super-elevation.

- 3 Design speeds and associated horizontal curve design criteria shown for Local Industrial/Commercial Streets and Minor Collector Streets are typical, but may vary depending on context. In situations where design speeds are different than what is shown in the table, consult the current edition of the "A Policy on Geometric Design of Highways and Streets," AASHTO for associated design criteria.
- 4 Radii shown are based on the street having a crown section with a pavement cross-slope of 2% on each side of the crown.
- 5 Where a curved road approaches an intersection, these tangent sections must be provided on the approach to the intersection to provide for adequate sight distance for traffic control devices at the intersection. The distance shall be measured from the flowline of the through street.

<sup>2</sup> Hillside is defined as having grades of 10% or greater, as defined in section 21.06.010(f) of the City Zoning and Development code.

(2) Intersections shall meet the minimum effective turn radii at public street intersections (which accounts for on-street bike lanes or parking if applicable) and must meet a minimum curb return flowline radius of 15 feet.

#### Minimum Effective Turn Radii at Public Street Intersections

	Intersecting Street				
Through Street <sup>2</sup>	Arterial	Collector	Local Residential	Local Commercial	Local Industrial <sup>1</sup>
Local Residential	30'	25'	20'		
Local Commercial	30'	30'	20'	30'	30'
Local Industrial		30'		30'	30'

- 1 Radii at intersections with industrial streets shall be designed on a case by case basis considering the turning requirements for the type of truck that will most commonly use the street.
- 2 At signalized intersections where right turn channelization islands are provided or high truck and bus volumes may use the access, a larger flowline radius may be required.
- 3 When bike lanes or parking are present consider a reduced flowline radii to match the effective flowline of the intersection, with a minimum flowline of 15'.

# (c) Bulb-Outs

If on-street parking is present on minor collectors and local commercial streets, steps should be taken to prevent vehicles from parking too close to the intersection. Bulb-outs should be used to reduce the intersection width and prevent parking in the sight zone. This will result in shorter crossing distances for pedestrians, increased sight distance, and increased visibility of pedestrians especially for turning vehicles, which will increase pedestrian safety and comfort at intersections. Bulb outs are not required on local residential or industrial streets but can be used as a traffic calming device.

# (d) Tangent Distance Between Curve

There is no minimum tangent distance between curves for residential or commercial street design.

# (e) Superelevation

Superelevation is not allowed on residential street curves.

## 29.20.070 Vertical Alignment - Grades

Design grades and vertical sight distance address drainage and/or safety concerns for vehicles and pedestrians. Grades of streets shall not be less than 0.5%, nor more than 8%. In hilly terrain (defined as having grades of 10% or greater, as defined in section 21.07.020 of the City Zoning and Development code), the maximum grade for local residential streets is 12% for a maximum distance of 500 feet. To help keep the grade of gutters at a minimum of 0.5% a maximum allowable grade break of 1% is allowable in sags and on crests. See section 29.20.150 for requirements for grades at intersections. See GJMC 29.28.050 for design control requirements for vertical curves.

#### **29.20.080 Cross Section**

## (a) Street Cross Slopes

The typical cross slope is 2% crown to provide for adequate drainage to the pavement edge. The minimum cross slope is 1% and the maximum is 4%. At the discretion of the City Engineer, the cross lope may deviate based on demonstrated physical constraints. Typical sections are shown in the Grand Junction Standard Contract Documents for Capital Improvements Construction.

# (b) Roadside Barrier and Bridge Rails

Roadside barriers shall be required in accordance with warrants, design criteria and standards for roadside barriers and bridge rails as defined in the most recent version of the AASHTO Roadside Design Guide.

# 29.20.090 Stopping Sight Distance

Stopping sight distance is defined as the length of roadway ahead visible to the driver. The minimum stopping sight distance available on a roadway must be sufficiently long to enable a vehicle traveling at or near the roadway design speed to stop before reaching a stationary object in its path or react to a traffic control device such as a stop sign.

The appropriate stopping sight distance (see GJMC 29.28.070) shall be provided. The distances shown assume vehicles traveling on wet pavement on flat grades. Factors that take in to account the effect of grade on stopping sight distance shall be used in determining appropriate stopping sight distance where the grades are 3% or higher.

## 29.20.100 Bicycle Treatments

Bicycle facilities shall be provided in accordance with the adopted Pedestrian and Bicycle Plan. Provisions for bicycle facilities shall be in accordance with the current version of the AASHTO Guide for Development of Bicycle Facilities.

The standard cross-section of off-street multi-use trails is included. Refer to Chapter 29.48 for design guidance on bicycle facility types, and minimum adherence standards. Refer to the NACTO Urban Bikeway Design Guide and the FHWA Separated Bike Lane Planning and Design Guide for additional guidance on designing bikeway facilities identified in the Pedestrian and Bicycle Plan.

#### 29.20.110 Intersections

There are two general types of intersections: unsignalized and signalized. Each of these shall have several different configurations and levels of traffic control. A roundabout is a form of an unsignalized intersection and is specifically discussed in GJMC 29.28.220 All intersection design shall conform to the guidelines set forth in AASHTO and the MUTCD.

# 29.20.120 Unsignalized Intersections

There are two appropriate levels of traffic control at unsignalized intersections: two-way stop controlled and all-way stop controlled. The appropriate use of each of these is discussed in the following sections.

# (a) Two-way Stop Controlled Intersections

- (1) Two-way stop controlled intersections shall be installed in new subdivisions.
- (2) STOP signs shall be installed in accordance with the MUTCD.
- (3) At intersections of two different types of roadways, a STOP sign shall be used on the minor street to stop the lesser flow of traffic. STOP signs will generally be used at all intersections that do not meet the all-way stop control or traffic signal warrants.

# (b) All-way Stop Controlled Intersections

An all-way or "multi-way" stop installation shall be used only as warranted in Part II of the MUTCD.

# **`29.20.130 Signalized Intersections**

Signals will not normally be considered for residential streets or commercial streets. Where signals may be warranted, the criteria in GJMC 29.28.130 shall be followed, and documented in a Transportation Impact Study (see Chapter 29.08).

## 29.20.140 Angles

Public streets shall intersect at 90° angles or as close to 90° as topography permits, in any event no less than 80°. Intersections on horizontal curves shall be avoided.

When an intersection is on a curve the center line of the intersection must be radial to the curve.

#### 29.20.150 Grades At Intersections

Intersections shall be on grades as flat as practical. At unsignalized intersections, the maximum allowable grade in the intersections is 4% and extends a minimum of 50 feet in each direction from the outside edge of the traveled way of the intersecting street. At signalized intersections, the maximum grade is 2% within the intersection and extends 200 feet in each direction from the centerline of intersecting roadway. Grades above 4% will only be allowed on local and collector streets in areas with steep topography or other unusual circumstances that prevent a flatter grade, and must be documented as a design exception (see Chapter 29.64).

When intersecting with State Highways, refer to Section 4 of the State Highway Access Code.

# 29.20.160 Spacing and Offsets

#### (a) Commercial Streets

Four legged intersections shall be spaced at least 300 feet apart from centerline to centerline. Where T-intersections are used, the centerlines of streets not in alignment shall be offset a minimum of 150 feet and be 150 feet from the nearest four-legged intersection. If the left turn storage requirements for adjacent intersections overlap, the minimum spacing must be increased to provide adequate left turn storage in both directions. If exclusive turn lanes are required, the design shall conform to the criteria in GJMC 28.28.170.

## (b) Local Residential Streets

Four legged intersections shall be spaced at least 300 feet apart from centerline to centerline. Where T-intersections are used, the centerlines of streets not in alignment shall be offset a minimum of 150 feet.

## **29.20.170 Intersection Sight Distance**

Street intersections and private access to public streets shall be planned and located to provide as much sight distance as possible. At a minimum, there must be sufficient sight distance for the driver on the minor street or driveway to cross or turn onto the intersecting street. Minimum sight distance values are provided (see GJMC 29.28.140) for passenger cars turning left or right from a minor street. When grades are steeper than 3.0%, adjustment factors must be applied.

The operating speed on each approach is assumed to be, in order of desirability, a) the 85<sup>th</sup> percentile speed, b) the posted speed if based on an engineering study, or c) in the case of a new facility, 80 percent of the design speed.

# 29.20.180 Sight Zones

The location of sight zones at intersections are identified in GJMC 29.28.140 and sight zones along streets are identified in the Street Sections (see appendix). Within the sight zone there shall be no sight obscuring sign, wall, fence, berming, or other object higher than 30 inches, or in the case of trees, no foliage lower than 8 feet (trees of any diameter may be planted as long as no foliage is lower then 8 feet). Vertical measurement shall be made from the flowline of the adjacent gutter or, if no gutter exists, from the edge of the nearest traveled way. Objects that may be located in the sight zones are items such as hydrants, utility poles, and traffic control devices. These shall be located to minimize visual obstruction.

#### 29.20.190 Pedestrian Treatments

In order to provide pedestrian safety, comfort, and access, accommodations for pedestrians shall be designed into all intersections and in accordance with the Pedestrian and Bicycle Plan. This includes sidewalks, crosswalks, pedestrian refuge islands and accessible ramps. The design shall conform to the standards set forth by the Americans with Disabilities Act and meet the details specified in the Grand Junction Standard Contract Documents for Capital Improvements Construction.

# 29.20.200 Landscaping – Site Distance at Intersections

Any landscaping in the sight distance triangles at intersections shall be low growing, and shall meet the sight distance requirements in Section 29.20.180.

## 29.20.210 Traffic Calming

According to the Institute of Traffic Engineers (ITE), "Traffic calming is the combination of mainly physical measures that reduce the negative effects of motor vehicle use, alter driver behavior and improve conditions for non-motorized street users." This differs from standard traffic control devices such as stop signs, which are regulatory. Traffic calming strategies are engineered to be self-enforcing physical measures.

This section provides guidance for appropriate applications of traffic calming on the existing street system, as well as the application of traffic calming measures during the planning and design stages of new sub-divisions. Refer to ITE's Traffic Calming Measures for additional guidance on design and considerations of each traffic calming tool.

#### 29.20.220 Methods to Divert Traffic from Residential Streets

Residents frequently complain that their residential street is being used by high speed and/or cut through traffic. One treatment of the traffic is the use of closures, diverters, and one-way treatments. Multiple treatments can be implemented on one street as part of a formal "Slow Streets Program" along with supporting signage such as "Local Traffic Only."

## (a) Street Closure

Streets may be fully or partially closed from one end to give drivers no choice but to travel another route, with vehicle access provided from the end that is not closed. A street closure is the most drastic form of traffic calming and shall be carefully considered before implementation. Street closures can lead to increased traffic on nearby streets as drivers are re-routed to other routes. Closures should be made passable by pedestrians and bicyclists.






Permanent Partial Closure

Retrofit Partial Closure

## (b) Diagonal Street Diverters

A diagonal street diverter can also be considered a partial street closure. With a diverter, traffic traveling in one direction is not given access to a street. As with street closures, implementation of diverters may shift traffic to another street where access is not regulated. Street diverters should provide cut throughs for pedestrians and bicyclists.



Source (drawing): Delaware Department of Transportation

# (c) One-Way Streets

One-way streets may be effective in decreasing the number of vehicles traveling on a given roadway. Traffic patterns shall be assessed to determine the effects of a one-way street on a given circulation pattern. Although traffic volumes are generally decreased by one-way treatments, speeds can often increase as drivers are channelized through the street.

#### 29.20.230 Methods to Slow Traffic on Residential Streets

Where speed is the recognized problem, the following methods can be effective in slowing existing traffic on residential and collector streets. These treatments are

appropriate on streets where the block length is at least 600 feet. For blocks less than 600 feet traffic circles at the intersections are the preferred traffic calming tool.

## (a) Chokers

Research has shown that traffic moves slower on narrow streets. Chokers reduce the width of a street by narrowing the road at a 'choke point'. Depending on the road segment length, one or several chokers can be used.



Permanent Choker (source: City of Ann Arbor, Michigan)



Retrofit Choker (source: City of Denver, Colorado)

# (b) Medians

A median can be installed on a street where width tends to encourage speed. Medians narrow the lanes, reducing the comfort of the driver while driving at higher speeds. Median treatments are particularly effective with landscaping.



Permanent Median (source: James Barrera, Harrocks New Mexico)



Retrofit Median (source: City of Denver, Colorado)

## (c) Chicanes

A chicane is essentially half of a choker. A chicane is placed on one side of the road to narrow a lane of traffic. A chicane can be used singly but is usually placed as a series on both sides of the road.






Permanent Chicane (source: City of Denver, Colorado)

Retrofit Chicane

## 29.20.240 Methods to Slow Traffic at Intersections

# (a) Raised Intersections


Raised intersections are flat raised areas covering entire intersections, with ramps on all approaches and often with brick or other textured materials on the flat section.



Source: (photo) Chuck Huffine, Phoenix AZ; (drawing) Delaware Department of Transportation

## (b) Realigned Intersections

Realigned intersections are changes in alignment that convert T-intersections with straight approaches into curving streets meeting at right angles – a straight shot along the top of the T becomes a turning movement.



Source: Delaware Department of Transportation

## (c) Traffic Circles

Traffic circles are set in the center of a three- way (driveways excluded) or four-way intersection to slow traffic coming from each direction. A traffic circle can be effective in creating a neighborhood gateway by providing a unique feature that can be creatively landscaped. This includes mini traffic circles which can be applied as a retrofit to existing STOP controlled intersections.



Example of a mini traffic circle

## (d) Bulb-Out/Corner Extension

A bulb-out or corner extension is the horizontal extension of the sidewalk and curb at an intersection, typically in place of on-street parking, resulting in a narrower roadway. Bulb-outs are most feasible on streets with on-street parking and are effective at narrowing the crossing distance for pedestrians, increasing visibility of pedestrians, slowing turning vehicles, and preventing drivers from parking too close to an intersection and blocking sight lines and/or the crosswalk.







Retrofit Bulb-Out (source: City of Denver, Colorado)

## (e) Other Methods

Other methods may be considered (such as hardened center lines) as approved by the jurisdiction.

## 29.20.250 Traffic Calming in New Developments

Long, wide streets with limited parking will generally increase speeds. As new developments occur, traffic calming can be planned as a feature of the neighborhood to keep vehicle travel speed low for maximum livability and safety of all street users. In large developments and developments that connect to existing residential streets, designs to control speeds and volumes are required. Design features such as curvilinear streets, Tintersections and entry treatments can reduce the need for traffic calming devices such as speed humps and chokers. Generally, horizontal calming measures will provide greater efficiency and livability in new developments.

The design speed of residential streets shall be 20 MPH. The design of local streets shall include positive traffic calming measures and devices. They are required when a straight street exceeds 600 feet in length. Horizontal curves used for traffic calming must achieve an offset of at least five feet (half the width of the lane - which equates to a length of curve of at least 35 feet assuming the minimum horizontal radius is used) and be consistent with the Horizontal Design Criteria Table in 29.20.060(b)(1). Such measures and devices shall be sufficient to minimize the ability of the average motorist to exceed 20 MPH. Narrow streets may not need specific measures.

## **29.24 FIRE DEPARTMENT ACCESS**

## 29.24.010 Fire Department Access

The Grand Junction Fire Department responds to a multitude of emergencies in various types of buildings and occupancies. To provide effective fire-fighting operations, the Fire Department must be able to reach all structures by way of approved access. Thus, street design and access must meet the requirements established in the current version of the Grand Junction Fire Department Access standards and the locally adopted fire code. The only potential exceptions to the requirements identified in Fire Department Access standards that would be considered are modifications of the Alternative Street Designs (see Chapter 29.68).

# 29.28 ARTERIAL AND MAJOR COLLECTOR DESIGN, INCLUDING ROUNDABOUTS

#### 29.28.010 Geometric Standards

Geometric standards have been developed to provide adequate safety for the traveling public. This chapter sets the minimum standards for geometric design of streets classified as major collector and above, as shown on the Street Plan Functional Classification Map, Figure 3 in the Grand Junction Circulation Plan. These streets are intended for higher traffic volumes and throughput than the local streets and minor collector streets discussed in Chapter 29.20. They function in transition from direct land use access to movement of traffic.

Roundabouts provide safety improvements, less delay than other forms of control, community enhancement and increased traffic circulation at some intersections. Roundabouts can efficiently handle many intersections with decreased delay and greater efficiency than traffic signals. This section defines the roundabout and provides a link to general design criteria.

#### 29.28.020 Arterial and Collector Streets

## (a) Arterial Streets

Principal arterials shall be designed to provide a high degree of mobility and serve longer trips, implying a higher operating speed and level of service. These streets are designated on the Street Plan Functional Classification Map in the Grand Junction Circulation Plan. Minor arterial streets interconnect with and augment the Principal arterial system. These streets accommodate trips of shorter lengths and may also serve more access functions than principal arterial streets.

## (b) Collector Streets

Collector streets provide both land access and movement within residential, commercial and industrial areas. Operating speeds are lower than arterial streets.

## (c) Pedestrians and Bicyclists

Pedestrians and bicyclists are users of the street system and street design needs to include consideration for them. The adopted Pedestrian & Bicycle Plan shows existing and future pedestrian and bicycle facilities.

# 29.28.030 Right of Way, Street Lane Widths, and Street Lengths

The required right-of-way width for a street is indicated in the Street Sections located in the Appendix. Additional widths may be required for needed through and turn lanes, and where it is necessary to accommodate slopes and drainage structures.

## 29.28.040 Alignments - Horizontal Alignment

Streets shall extend to the boundary lines of the land to be subdivided. Proposed streets with widths different from existing streets to which they are being connected must be transitioned using <u>pavement transition taper standards</u>.

All designs shall be based on the <u>Horizontal Curve Design Criteria</u>.

## Horizontal Curve Design Criteria

	Major Street <sup>1</sup>			
Design Criteria	Low Speed Collector	Collector/ Arterial	Arterial	
Min. Design Speed (mph)	30	35	40	
Min. Center Line Radius <sup>2</sup> (ft)	335	510	SEE <sup>4</sup>	
Min. Horizontal Sight Distance (ft)	200	250	325	
Min. Reverse Curve Tangent (ft)	0	200	200	
Min. Approach Tangent at Intersections <sup>3</sup>	100	200	300	

<sup>1</sup> These criteria are to be used without super-elevation.

# 29.28.050 Alignment - Vertical Alignment - Grades

<u>Grades, curve length and vertical sight distance</u> shall be designed to ensure proper drainage, sight distance and safety for vehicles and pedestrians. Grades of streets shall

<sup>2</sup> Radii shown are based on the street having a crown section with a pavement cross-slope of 2% on each side of the crown. For minimum radii required for other cross-slopes or where super-elevation is provided and approved, see Table 3-13 in "A Policy on Geometric Design of Highways and Streets," AASHTO, 2018 Edition or most current edition.

<sup>3</sup> Where a curved road approaches an intersection, these tangent sections must be provided on the approach to the intersection to provide for adequate sight distance for traffic control devices at the intersection.

<sup>4</sup> The maximum super-elevation rate allowed is e=6%. Where super-elevation is used, runoff lengths shall conform to Table 3-9 in "A Policy on Geometric Design of Highways and Streets," AASHTO, 2018 Edition or most current edition.

not be less than 0.5%. The grade of a street may be reduced only when matching existing streets or property. Maximum street grades shall be 8%. For algebraic differences of 0.5% or less, grade breaks shall be required for adequate drainage.

**Design Controls for Vertical Curves** 

Design Speed MPH	Stopping Sight Distance	Crest "K" Values	Sag "K" Values
20	(feet)	7	1.7
20	115	1	17
25	155	12	26
30	200	19	37
35	250	29	49
40	305	44	64
45	360	61	79
50	425	84	96
55	495	114	115
60	570	151	136

From Table 5-3, AASHTO A Policy on Geometric Design of Highways and Streets, 2018 1 All minimum stopping sight distances for vertical curves with crests must be shown on the construction plans. Sight distances are based on design speeds.

#### 29.28.060 Clearance of Structures

A minimum of 17.5 feet shall be provided for all overhead sign structures. The clearance shall be measured from the crown of the street to the lowest portion of the structure. A minimum vertical clearance of 16.5 feet for all other structures shall be provided on all arterial streets and designated truck routes. A minimum clearance of 14.5 feet may be allowed on collector streets per CDOT 2018 Roadway Design Guide.

# 29.28.070 Stopping Sight Distance

Stopping sight distance is defined as the length of roadway ahead visible to the driver. The minimum stopping sight distance available on a roadway must be sufficiently long to enable a vehicle traveling at or near the roadway design speed to stop before reaching a stationary object in its path or react to a traffic control device such as a stop sign.

The appropriate <u>stopping sight distance</u> shall be provided. The distances shown assume vehicles traveling on wet pavement on flat grades. Factors that take in to account the <u>effect of grade on stopping sight distance</u> shall be used in determining appropriate stopping sight distance where the grades are 3% or higher.

# **Minimum Stopping Sight Distance**

Design Speed (MPH)	Stopping Sight Distance (Ft.)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570

Based on Table 5-3, AASHTO A Policy on Geometric Design of Streets and Highways, 2018

# Effect of Grade on Stopping Sight Distance

Design	D	Downgrades			Upgrades	S
Speed (MPH)	3%	6%	9%	3%	6%	9%
20	116	120	126	109	107	104
25	158	165	173	147	143	140
30	205	215	227	200	184	179
35	257	271	287	237	229	222
40	315	333	354	289	278	269
45	378	400	427	344	331	320
50	446	474	507	405	388	375
55	520	553	593	469	450	433
60	598	638	686	538	515	495

From Exhibit 3-2, AASHTO A Policy on Geometric Design for Highways and Streets, 2018

#### 29.28.080 Cross Section

#### (a) Cross Slopes

The typical cross slope is 2% crown to provide for adequate drainage to the pavement edge. The maximum cross slope on the tangent sections shall not exceed 4%. The minimum cross slope shall be 1%.

# (b) Super-elevation

Super-elevation shall be designed in accordance with the <u>Horizontal Curve Design</u> <u>Criteria</u>.

# (c) Clear Zones

All roadways shall meet clear zone requirements as set forth in the current edition of the <u>AASHTO</u> Roadside Design Guide. Where under-improved streets are constructed (for example, a half-street construction), the minimum shoulder width shall be provided.

## (d) Roadside Barrier and Bridge Rails

Roadside barriers shall be required in accordance with warrants, design criteria and standards for roadside barriers and bridge rails as defined in the current edition of the <u>AASHTO</u> Roadside Design Guide.

#### 29.28.090 Tapers and Transitions- Road Width Transition Tapers

When constructing a roadway that will connect with an existing roadway of a different width, a transition taper is required. These ratios are not to be used in the design of exclusive turn lanes.

#### **Minimum Road Width Transition Tapers**

Design Speed (MPH)	Transition Run/Offset (Ft/Ft)
30 or less	15 / 1
35	20 / 1
40	25 / 1
45	45 / 1
50	50 / 1
55	55 / 1
60	60 / 1

Table based on Section 3B-8, MUTCD.

## 29.28.100 Bicycle Treatments

Bicycle facilities are required as shown on the Pedestrian and Bicycle Plan and the street sections included in the Appendix. Provisions for bicycle facilities and crossings shall be in accordance with the <u>AASHTO</u> Guide for Development of Bicycle Facilities. Refer to Chapter 28.48 for design guidance on bicycle facility types, and minimum adherence standards. Refer to the <u>Pedestrian and Bicycle Plan</u> for additional guidance on designing bikeway facilities and bikeway crossings.

#### **29.28.110 Intersections**

Generally, there are two types of intersections: unsignalized and signalized. Each of these may have several different configurations and levels of traffic control. A roundabout is a form of an unsignalized intersection and is specifically discussed in <a href="Section 29.28.220">Section 29.28.220</a>. All intersections shall conform to the guidelines set forth in <a href="AASHTO">AASHTO</a> and the <a href="MUTCD">MUTCD</a>. For streets with bicycle facilities, refer to Chapter 29.48 for additional guidance on bicycle intersection treatments as well as the street sections located within the Appendix.

# 29.28.120 Unsignalized Intersections

There are three acceptable levels of traffic control at unsignalized intersections: yield controlled, two-way stop controlled and all-way stop controlled. The appropriate use of each of these is discussed in the following sections.

#### (a) Yield Controlled Intersections

Yield controlled intersections will not generally be allowed, except at roundabouts.

# (b) Two-way Stop Controlled Intersections

Stop signs shall be used in accordance with the MUTCD.

## (c) All-way Stop Controlled Intersections

An all-way or "multi-way" stop installation shall be used only where the criteria of the MUTCD are met.

# 29.28.130 Signalized Intersections


A signalized intersection shall only be installed after a careful analysis and engineering study of the roadway and traffic conditions at the intersection and on the corridor. When a signal is proposed on a corridor where signals are coordinated, the TIS (see Chapter 29.08) shall analyze the impacts to the progression of traffic on the corridor and on surrounding land uses. This analysis shall include the progression bandwidth, efficiency and level of service determinations, signal timing and phasing including pedestrian movements, and an analysis of the storage queue lengths for exclusive turn lanes. Signal installations shall meet the spacing criteria in Section 29.28.200. Traffic signal warrants and design criteria are thoroughly discussed in the MUTCD, Part IV.

## **29.28.140** Sight Distance

Street intersections and private access to public streets shall be planned and located to provide as much sight distance as possible. At a minimum, there must be sufficient sight distance for the driver on the minor street or driveway to cross or turn onto the intersecting street. Minimum sight distance values are provided for passenger cars turning left or right from a minor street. When grades are steeper than 3.0%, <u>adjustment factors</u> must be applied.

The operating speed on each approach is assumed to be, in order of desirability, a) the 85th percentile speed, b) the speed limit if based on an engineering study, or c) in the case of a new facility, 80 percent of the design speed.

# Minimum Sight Distance for Left and Right Turns onto Major Street by Passenger **Cars at Stop-Controlled Intersections**



\*BASED ON AASHTO FIGURE 9-15

480 FT

FOR ALL APPROACHES.

A1 IS 18' MEASURED FROM THE MAJOR ROAD LIP OF GUTTER. IN CONSTRAINED SCENARIOS, A1 MAY BE REDUCED TO A MINIMUM OF 14.5' WITH CITY APPROVAL.

DISTANCE B MAY BE UTILIZED WITH CITY APPROVAL, WHEN THE INTERSECTION CONTROL ONLY ALLOWS RIGHT TURNS OUT FROM THE MINOR LEG.

#### **Factors for the Effect of Grade on Sight Distance**

Approach Grade (%)				Desig	gn Spo	eed (N	1РН)			
	15	20	25	30	35	40	45	50	55	60
-6	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.2	1.2	1.2
-5	1.0	1.0	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1
-4	1.0	1.0	1.0	1.1	1.1	1.1	1.1	1.1	1.1	1.1
-3 to +3	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
+4	1.0	1.0	1.0	1.0	1.0	0.9	0.9	0.9	0.9	0.9
+5	1.0	1.0	1.0	0.9	0.9	0.9	0.9	0.9	0.9	0.9
+6	1.0	1.0	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9


Based on Table 9-5, AASHTO A Policy on Geometric Design for Highways and Streets, 2018.

#### 29.28.150 Sight Zones

The location of sight zones at intersections are identified in GJMC 29.28.140 and sight zones along streets are identified in the Street Sections (see appendix). Design requirements within the sight zone for major collector and arterial streets are the same as for local and minor collector streets. Refer to GJMC 29.20.180.

#### 29.28.160 Intersection Radii

Minimum intersection effective radii must be maintained at public street intersections and a 15 foot minimum flowline radius is required to allow for proper drainage in situations where flowline radii is less than the effective radii. The "effective" radius is different than the flowline radius in that effective radius accounts for on-street parking or bike lanes which can cause the effective radius for a turning vehicle to be much larger than the flowline radius. An effective turn radius that is too large can encourage drivers to maintain a high speed while turning, which can compromise the comfort and safety of pedestrians crossing in the crosswalk. The NACTO Urban Street Design Guide recommends design corner radii to limit turning speeds to 15 mph to support a comfortable pedestrian environment. Thus, when a bike lane or parking lane is present on one or both of the intersecting streets, either a bulb-out (see 29.28.165) should be provided to maintain the desired effective radii or the flowline radius should be designed to be less than the minimum intersection effective radius in order to encourage slower turning vehicle speeds.



Example of "Effective" Turn Radius (source: NACTO Urban Street Design Guide)

#### **Minimum Intersection Effective Radii**

	Intersecting Street				
Through Street <sup>2</sup>	Arterial	Collector	Local Residential	Local Commercial	Local Industrial <sup>1</sup>
Arterial	35'	30'	30'	30'	30'
Collector	30'	30'	25'	30'	30'

- 1 Radii at intersections with industrial streets shall be individually designed based on the turning requirements for the type of truck that will most commonly use the street.
- 2 At signalized intersections where right turn channelization islands are provided or high truck and bus volumes may use the access, a larger flowline radius may be required.
- 3 When bike lanes are present consider a reduced flowline radii to match the effective flowline of the intersection, with a minimum required flowline radius of 15 feet.

#### 29.28.165 Bulb-Outs

If on-street parking is present, steps should be taken to prevent vehicles from parking too close to the intersection. Bulb-outs should be used to reduce the intersection width and prevent parking in the sight zone. This will result in shorter crossing distances for pedestrians, increased sight distance, and increased visibility of pedestrians especially for turning vehicles, which will increase pedestrian safety and comfort at intersections.

## 29.28.170 Lane Requirements

Lane design through an intersection shall be consistent with the lane design of the streets forming the intersection.

#### (a) Lane Widths

Lane widths shall be consistent with the cross-sections as shown in the City Standard Street Details.

## (b) Exclusive Turn Lanes.

- (1) The purpose of an exclusive turn lane is to expedite the movement of through traffic, increase intersection capacity, permit the controlled movement of turning traffic, and promote the safety of all traffic. The provision of left-turn lanes is essential from both capacity and safety standpoints where left turns would otherwise share the use of a through lane. Right-turn lanes remove the speed differences in the main travel lanes, reducing the frequency and severity of rear-end collisions.
- (2) Separate right turn lanes shall be required in accordance with the <u>right turn</u> warrant chart. Separate left turn lanes shall be required at all new signal locations and at unsignalized locations in accordance with the <u>left turn warrant chart</u>.

# Warrants for Right Turn Lanes Two Lane Roadways Number of Peak Hour Turning Vehicles

DDHV <sup>1</sup> (vph)	≤35 MPH	<b>40 MPH</b>	45 MPH	50 MPH	55 MPH
200				73	35
300			120	41	24
400	200	200	50	30	19
500	150	125	35	25	16
600	75	50	25	20	14
800	50	30	15	15	11
1000	25	25	15	11	9
1200	20	20	15	9	8

<sup>1</sup> DDHV – Directional Design Hourly Volume; volume of vehicles in the design hour using the through lane adjacent to which the right turn lane is to be constructed.

# Warrants for Right Turn Lanes Four Lane Roadways

**Number of Peak Hour Turning Vehicles** 

DDHV <sup>1</sup> (vph)	≤35 MPH	40 MPH	45 MPH	50 MPH	55 MPH
300					75
400			145	75	40
500			95	57	32
600	170	160	65	42	26
800	80	70	37	28	19
1200	50	25	20	18	14
1600	20	15	14	13	10
2000	15	10	9	9	8

<sup>1</sup> DDHV – Directional Design Hourly Volume; volume of vehicles in the design hour using the through lane adjacent to which the right turn lane is to be constructed.

Charts developed based on studies conducted by Kansas Department of Transportation and University of Nebraska

Warrants for Left Turn Lanes
Number of Peak Hour Turning Vehicles

TTUINDET OF	ramber of reak from running venteres					
DDHV	30-35 MPH	40 + MPH				
100	30	14				
200	15	12				
300 ±	12	12				

DDHV – Directional Design Hourly Volume; volume of vehicles in the design hour using the through lane adjacent to which the right turn lane is to be constructed.

- (3) Construction of turn lanes on state highways shall be determined in accordance with the <u>State Highway Access Code</u>.
- (4) Dual left turn lanes at signalized intersections shall be considered when the peak hour left turn volume exceeds 300 vehicles/hour. An analysis of the signal timing is required to measure the effects of the protected movement on the rest of the intersection movements. Intersection geometry shall allow for the operation of dual lefts. Permissive dual left turns are prohibited.

# (c) Left and Right Turn Lane Design


(1) The components of a left turn lane consist of a taper and the full width lane for storage as shown in the <u>turn lane elements</u> and design criteria. Right turn lanes shall be 11' in width (not including the gutter pan) and two-way left turn lanes shall be 12' in width.

# **Minimum Left-Turn Tapers for Redirecting Through Lanes**

Design Speed (MPH)	Tapers
25	10:1
30	15:1
35	20:1
40	30:1
45	45:1
50	50:1
55	55:1
60	60:1

Based on Table 4-9 CDOT Access Code

- (2) Use the same ratio for both approach and departure tapers.
- (3) Bay tapers shall be symmetrical reverse curves in accordance with the following:
  - i. Use 60' Reverse Curve for 25-35 MPH
  - ii. Use 90' Reverse Curve for 40-50 MPH
  - iii. Use 140' Reverse Curve for 55-65 MPH



(4) Storage lengths for turn lanes at signalized intersections shall be determined based on a signal timing analysis that predicts the 90% queue length required for the turn lane. At unsignalized intersections, the turn lane storage will be determined in accordance with the storage length table. Tapers for right turn lanes shall be designed in accordance with the right-turn lane taper table. Use of the reverse curve is encouraged as part of the taper length to allow vehicles to decelerate in the full lane width. If used, the difference in length between the required taper and the reverse curve shall be added to the required storage length of the turn lane.

#### **Minimum Storage Lengths for Unsignalized Turn Lanes**

Turning VPH	<u>≤</u> 60	100	200	300
Required Storage Length	50	100	175	250

Based on Table 9-7 CDOT Design Guide

## **Minimum Right-Turn Tapers**

Design Speed (MPH)	Tapers
25	7.5:1
30	8:1
35	10:1
40	12:1
45	13.5:1
50	15:1
55	18.5:1
60	25:1

Excerpted from Table 4-6, CDOT Access Code

(5) Standards for State Highway right turn and left turn speed change lanes are found in the <u>State Highway Access Code</u>.

## 29.28.180 Angles

Proposed public streets must intersect at 90° angles or as close to 90° as topography permits (no less than 80°). Intersections on sharp horizontal curves shall be prohibited based on sight distance and viewing angle for the driver.

#### 29.28.190 Grades at Intersections

See GJMC 29.20.150 for design requirements for grades at intersections.

## 29.28.200 Spacing and Offsets of Intersections

# (a) Principal Arterials

Signalized intersections shall be spaced at ½ mile intervals. Unsignalized intersections must be T-intersections spaced at least 600 feet apart, measured centerline to centerline. Unsignalized four legged intersections may be allowed on arterial streets provided that the design of the intersection precludes left turns onto and through movements across the arterial. If the overlap of left turn storage requirements for two T-intersections exceeds 600 feet, the minimum spacing must be increased to provide adequate left turn storage in both directions.

# (b) Minor Arterials and Major Collectors

Signalized intersections shall be spaced no closer than 1/4 mile intervals. Unsignalized four-legged intersections must be spaced at least 300 feet apart. When T-intersections are used, the centerlines of streets not in alignment shall be offset a minimum of 150 feet and be 150 feet from the nearest four-legged intersection. If the left turn storage requirements for adjacent intersections overlap, the minimum spacing must be increased to provide adequate left turn storage in both directions. For spacing and offset requirements of driveways see GJMC 29.16.030.

#### 29.28.210 Pedestrian Treatments

Accommodations for pedestrians must be designed into all intersections. Pedestrian accommodations include, but are not limited to sidewalks, crosswalks, pedestrian refuge islands, and accommodations for disabled pedestrians. Sidewalks are an integral part of urban streets and shall be included in the intersection design. Refer to the Bicycle and Pedestrian plan or city staff recommendations for detailed improvements at identified intersections. The Grand Junction Standard Contract Documents for Capital Improvements Construction shall be followed in designing and constructing pedestrian facilities. The intersection design shall conform to the standards set forth in the Americans with Disabilities Act. More information on the requirements can be found at <a href="http://www.access-board.gov/">http://www.access-board.gov/</a>. Design of pedestrian facilities should also adhere to the latest guidance according to the U.S. Access Board's Public Right-of-Way Accessibility Guidelines (<a href="PROWAG">PROWAG</a>). Where sidewalks are provided, accessible ramps must also be provided. Utility boxes, drainage inlets, signs, and other fixed objects shall not be located within the path defined by ramp. The ramp shall align with the sidewalk and must be located entirely within the marked crosswalk area.

#### (a) Crosswalks

Crosswalks shall be marked at signalized intersections and designed as part of the markings for the traffic signal. All crosswalk markings must conform to MUTCD standards. Crosswalks at un-signalized intersections or mid-block locations will only be considered when an engineering study is conducted in accordance with Institute of Traffic Engineers guidelines and indicates crosswalks would increase pedestrian safety. Refer to the current edition of the Grand Junction Pedestrian Crossing Treatment Installation Guidelines for guidance on applicability of pedestrian crossing treatments in different contexts, including at uncontrolled crossings. Refer to CDOT's Pedestrian Crossing Installation Guide for uncontrolled pedestrian crossings on state highways.

## (b) Pedestrian Refuge Islands

Pedestrian refuge islands may be constructed where mid-block crosswalks are proposed. Islands should be at least 6' wide and 6' length in advance and departing of crosswalk. All Islands must conform to the minimum standards established in the MUTCD, and must meet the design criteria for curbing and medians.

#### **29.28.220 Roundabouts**

## (a) Design Criteria

A roundabout brings together conflicting traffic streams, allows the streams to safely merge and traverse the roundabout, and exit in the desired directions. The geometric elements of the roundabout provide guidance to drivers approaching, entering, and traveling through a roundabout.

Good roundabout design places a high priority on speed reduction and speed consistency. Low vehicle speed provides safety benefits including reduced numbers and severity of crashes; more time for entering drivers to judge, adjust speed for and enter a gap in circulating traffic; and safer merging. Roundabout intersections typically operate with lower vehicle delays than other intersection control types.

A capacity analysis of any proposed roundabout shall be conducted in accordance with Highway Capacity methods. The analysis shall include consideration for the largest motorized vehicle likely to use the intersection.

Roundabouts shall be designed in conformance with the guidelines set forth in the NCHRP 1043 Guide for Roundabouts. All roundabout design is unique and the City will require review of the preliminary geometry prior to final design.

# (b) Signing, Striping, and Pavement Markings

All signing, striping, and pavement markings shall follow the MUTCD standards.

# (c) Lighting

Adequate lighting is essential for drivers to perceive the general layout and operation of the intersection in time to make the appropriate maneuvers. A lighting plan will be required as part of the construction drawings for roundabouts.

# (d) Landscaping

Landscaping in the central island, the splitter islands and along the approaches is a benefit to both public safety and community enhancement. Landscaping shall follow these general principles:

- (1) Make the central island more conspicuous;
- (2) Improve the aesthetics of the area while complementing surrounding streetscaping as much as possible;
- (3) Avoid obscuring the form of the roundabout or the signing to the driver;
- (4) Maintain adequate sight distances;
- (5) Clearly indicate to the driver that they cannot pass straight through the intersection;
- (6) Discourage pedestrian movements through the center of the roundabout.

## 29.28.230 Landscaping – General Requirements

All new developments must provide landscaping that meets the requirements of the City's Zoning and Development Code. Any landscaping in the sight distance triangles at intersections shall meet the sight distance requirements in the <u>Sight Distance</u> detail.

#### **29.32 PAVEMENTS & TRUCK ROUTES**

## 29.32.010 Design Methods and Procedures

The following pavement design methods and procedures shall be followed to create a consistent pavement thickness design throughout the urban area.

This chapter references the Truck Route map developed for the urban area of the City and County (see <u>Grand Junction GIS Transportation Map</u>). The truck route map must be consulted prior to beginning pavement design to assure that the design will accommodate anticipated truck loading.

## 29.32.010 Pavement Types

Pavement types which may be used for construction of City and County streets include asphalt concrete (AC) for flexible pavement design and plain jointed (JCP), jointed reinforced (JRCP), and continuously reinforced (CRCO) concrete pavements for rigid pavement design. The City and/or County shall approve in advance the type of pavement.

#### 29.32.020 Design Input Variables

Parameters that must be evaluated in order to design an adequate pavement structure include subgrade soil properties, surface and sub-surface drainage, materials properties, environmental factors and traffic loading over the analysis period.

The minimum traffic analysis period to be used for the design of pavements for City streets is 30 years. Traffic growth rates vary depending upon the street classification, zoning location and other variables. Growth rates for most major streets are available from the Mesa County Regional Transportation Planning Organization, phone (970) 244-1830.

Traffic distribution by vehicle type shall be determined from, actual traffic counts and projections based on land uses and future build-out of area serviced by the road. Classification of vehicles derived from traffic counts are available for most major streets from the City of Grand Junction, Transportation Engineering Division, phone (970) 256-4110.

All other pavement design parameters including 18 kip equivalency factors, lane distribution factors, Resilient Modulus (M<sub>R</sub>) conversion equations, drainage coefficients, reliability factors and serviceability indices shall be determined in accordance with the *Guideline for the Design and Use of Asphalt Pavements for Colorado Roadways* published by the Colorado Asphalt Pavement Association.

## 29.32.040 Pavement Design Procedures

## (a) Flexible Pavement Design Procedure

Flexible pavement design includes asphalt concrete (AC) surfaces and surface treatments (ST). Flexible pavements shall be designed in accordance with the principles and procedures illustrated in the <u>AASHTO</u> Guide for Design of Pavement Structures (current edition). The computer software for the AASHTO guide is AASHTO Ware are DARWin in 3.1 Pavement Design and Analysis System. All use of flexible pavement should have a design life of at least 30 years. Perpetual pavements may be used where appropriate. Perpetual pavement design should follow the recommendations of <u>CDOT M-E Pavement Design Manual 2021</u>, 6.3.2.

## (b) Rigid Pavement Design Procedure

Rigid pavement design includes plain jointed (JCP), jointed reinforced (JRCP), and continuously reinforced (CRCO) concrete pavements. Rigid pavements shall be designed in accordance with the principles and procedures illustrated in the <u>AASHTO</u> Guide for Design of Pavement Structures (latest edition). Approved software for design of rigid pavement includes AASHTOWare <u>DARWin 3.1</u> and <u>WinPAS</u> developed by the American Concrete Pavement Association. All use of rigid payment should have a design life of at least 30 years.

#### **29.32.050 Truck Routes**

Primary and secondary trucks routes are shown on the Truck Route layer of the <u>Grand Junction GIS Transportation Map</u>, additional information on truck routes can be found here.

# 29.36 STREET LIGHTING, UTILITIES, AND MAILBOXES

#### **29.36.010 Requirements**

This chapter outlines the requirements for street lighting, including whether lighting is required, installation, maintenance responsibilities, and acceptable poles and luminaries. Utilities are discussed for their placement in the rights-of-way.

#### 29.36.015 Telecommunication Facilities

Small cell telecommunication facilities shall be designed and implemented in accordance with the Grand Junction Small Cell Infrastructure Standards.

# 29.36.020 Street Lighting

Street lighting shall be installed on all new public streets at the expense of the developer. Streetlights shall be designed, furnished and installed by the utility company responsible for supplying electrical power to the development or area. The location of all streetlights shall be shown on the traffic plan or street plan, or other design drawings as required by the City or County. All street lighting must conform to city ordinances on Dark Sky requirements.

# 29.36.030 Luminance Requirements

Street lighting shall provide average illuminance in accordance with <u>Table 29.36-1</u>. A lighting plan is required for all street designs with the exception of local residential streets.

Table 29.36-1 Average Maintained Illuminance (Foot Candles) on Public Streets

Street	Area Classification			
Classification	Commercial	Intermediate	Residential	
Arterial	1.7	1.3	0.9	
Collector	1.2	0.9	0.6	
Local	0.9	0.7	*	

<sup>\*</sup> On local residential streets, a standard light shall be located at each street intersection, at or near the throat of each cul-de-sac, and at a maximum spacing of 250 feet measured along the centerline of the roadway. Additional lights may be required on horizontal curves and at other locations.

## 29.36.040 Acceptable Poles and Luminaires

The standard streetlights are shown in <u>Table 29.36-2</u>.

**Table 29.36-2 Standard Street Lights** 

Street Light Style	Used on Street	Wattage	Pole Color
	Classification		
GE Salem Luminaire	Local Residential,	N/A	Black
Full-Cutoff	Residential Collector		
Cobra Head Full-Cutoff	Collectors, Arterials,	250-400	Black
– Flat Lens	Commercial		
Cobra Head Full-Cutoff –	Arterials (for existing	100-400	Black, Silver,
Flat Lens	overhead power),		Galvanized or
	State Highways		existing wood pole

Height and wattage shall be determined by Utility Company in accordance with current IES standards. Where these standards conflict with existing lighting, design consideration will be given to consistency in the area. Supply chain or other circumstances may require substitutions which must be approved by the City.

## 29.36.050 Pedestrian and Bikeway Lighting

When required, lighting for detached public pedestrian and bicycle pathways and trails shall be designed, furnished and installed by the utility company responsible for supplying electrical power to the development or area. The lighting standard shall be the cutoff luminaire style that meets the illuminance requirements. Commercial grade solar lighting may be an option when A/C power is cost prohibitive.

Lighting for pedestrian walkways and bikeways should be considered in the following scenarios:

- Stairs and access ramps
- Pedestrian underpasses
- Conflict points along pathways
- Other locations depending on the context of the situation

Lighting levels can be set based on the level of pedestrian activity in the area as indicated in Table 29.36-3.

Table 29.36-3 Pedestrian and Bicycle Pathways and Trails Illuminance Standards

Conflict Type	Average Horizontal Illuminance (fc)	Average Vertical Illuminance	Horizontal Uniformity (avg:min)
Average illuminance with	0.5	0.2	4
anticipated pedestrian activity			
(typically > 10 pedestrians per hour)			
Average illuminance with minimal	0.2	0.1	10
pedestrian activity (typically < 10			
pedestrians per hour)			

Based on Section 2.2.8 of the CDOT Light Design Guidelines.

Refer to section 2.2.8 of the <u>CDOT Light Design Guidelines</u> for additional guidance and best practices on lighting applications for pedestrian walkways and bikeways.

Pedestrian lighting is not considered in street light illuminance calculations. Attached sidewalk lighting is often provided by adjacent street lighting. On streets where there is a sidewalk only on one side, lighting must be provided on that side of the street. The need for pedestrian lighting should be considered as part of the lighting process.

Pedestrian lighting is not normally required in residential subdivisions. The primary exception is along pedestrian pathways, typically located mid-block or at cul-de-sacs that provide pedestrian connectivity to adjacent streets. On these pathways pedestrian-scale bollard lighting may be required to enhance safety and visibility at night. Street lights are recommended at each end where a pathway meets the street.

Bollard lighting is only required in the following locations along these pathways:

- Locations where the pathway is greater than 100 feet in length from where the pathway meets a street. This assumes a street light is present at at least one end.
- Locations where there is a bend or horizontal curvature in the pathway.
- Locations where there is insufficient adjacent street lighting where the pathway meets the street.

When required along pedestrian pathways, bollard lighting should provide an average illuminance consistent with the standards set in <u>Table 29.36-3</u> for minimal pedestrian activity. Commercial grade solar powered bollard lights are considered acceptable so long as they are demonstrated to reliably meet the illuminance standards.

Pedestrian lighting that is installed for decorative purposes or is along pathways (connecting cul-de-sacs or adjacent streets) that are not along a designated Active

Transportation Corridor (see the Active Transportation Corridor layer on the <u>Grand Junction GIS Transportation Map</u>) shall be the responsibility of the homeowner's association or private developers for installation, cost of utilities, and maintenance.

## 29.36.060 Breakaway Structures and Lateral Clearances

All fixed objects such as utility, street light poles, fire hydrants, telephone junction boxes, installed in the right-of-way shall be of the breakaway type meeting AASHTO construction specifications regardless of roadway classification, with the exception of locations with high pedestrian activity. The breakaway type of design may not be appropriate in contexts with high pedestrian activity. In locations where required, if breakaway type construction cannot be provided, a minimum of 10 feet horizontal clearance shall be provided between the flowline of the street (or the edge of the paved traveled way) and any new or relocated non-breakaway structure in excess of 4 inches in height. For local streets, a 5-foot lateral clearance is recommended. If sufficient right-ofway or easement is not available for the 10-foot clear zone, all installations must be placed "as near as practical" to the edge of the public right-of-way. This policy is applicable to all local and collector roadways whose posted speed limit is in excess of 30 miles per hour and is intended to provide minimum standards for the purpose of protecting the public health, safety, and welfare. Dynamic performance for breakaway objects shall be evaluated in accordance with current AASHTO specifications. Arterial and major collector classifications should evaluate clear zone requirements per current AASHTO clear zone standards.

#### 29.36.070 Utilities

All utilities shall be placed in the roadway section as set forth in the City of Grand Junction Standard Contract Documents for Capital Improvements Construction.

#### 29.36.080 Mailboxes - Location

- (a) Mailboxes may be located within public rights-of-way so as not to obstruct pedestrian or vehicular traffic.
- (b) In no case shall a mailbox obstruct a sidewalk, the traveled way of a roadway, the road shoulder, or impede maintenance activities associated with the facility.

  Mailboxes shall not be permitted within sidewalks, pathways, or roadside ditches.
- (c) On roads without a curb, the mailbox face shall be located a minimum of eight feet from the traveled way and adequate shoulder areas shall be provided for mail pickup and delivery.

- (d) Streets with a curb and detached sidewalk: the mailbox face shall be located a minimum of 2 foot behind the curb face. Mailboxes must not pose an obstruction to the site zone. The mailbox should have a rear-facing door to facilitate mail removal without stepping into the street. Streets with attached sidewalk: the mailbox face shall be located a minimum of 2 foot behind back of walk.
- (e) Group, gang mailboxes, or neighborhood box units shall not be placed in the area designated for sight distance or sight zone. Neighborhood mailboxes shall be considered a commercial location and must maintain the required driveway setback from intersections. Neighborhood mailboxes shall be shown on the utility composite and road plans. Group mailboxes should be placed a minimum of 2ft behind the sidewalk. Group mailboxes shall be illuminated by a streetlight.

#### 29.36.090 Mailbox Construction Standards

Mailboxes erected on public right-of-way shall be of light sheet metal or plastic construction conforming to the requirements of the U.S. Postal Service. Construction of supports and details shall be in accordance with the current CDOT standards.

## 29.36.100 Mailbox Support Standards

- (a) A single 4-inch x 4-inch square wooden post embedded no more than 36 inches into the ground; a single 4½ inch diameter wooden post embedded no more than 36 inches into the ground; a single metal post with a strength no greater than a 2-inch standard strength steel pipe (2 3/8" O. D.) and embedded no more than 24 inches into the ground will be acceptable as a mailbox support.
- (b) A metal post shall not be fitted with an anchor plate, but it should have an antitwist device that extends no more than 10 inches below the ground surface.
- (c) Supports shall not be set in concrete unless the support design has been shown to be safe by crash tests when so installed.
- (d) The post-to-box attachment details should be of sufficient strength to prevent the box from separating from the post top if a vehicle strikes the installation.
- (e) No more than two mailboxes may be mounted on a support structure unless the support structure and mailbox arrangement have been shown to be safe by crash testing, or meet the requirements set forth in the above <u>AASHTO</u> guidelines.
- (f) Mailbox support designs that differ from the <u>AASHTO</u> guidelines are subject to the exception process outlined in Chapter 14.

(g) Lightweight newspaper boxes may be mounted below the mailbox on the side of the mailbox support. Newspaper delivery boxes shall be of light sheet metal or plastic construction of minimum dimensions suitable for holding a newspaper.

#### 29.40 STRIPING AND SIGNING

#### 29.40.010 Signs and Markings

Signs and markings must communicate to the users a clear and definitive message. Signs and markings must conform to industry standards given in the <u>MUTCD</u>. Modifications to signing and striping on the Colorado State Highway System shall be submitted to the Colorado Department of Transportation for approval.

## 29.40.020 Signing and Striping Plan

Preparation of a detailed traffic control plan, showing the locations of all traffic control devices, is required as part of the development plans. A signing and striping plan is required for all public street improvements. The signing and striping plan must be clear and it must contain all relevant information. Example striping plans may be found in the <a href="CDOT M & Standards">CDOT M & Standards</a>.

## 29.40.030 Signing Specifications.

All roadway signs shall conform to the latest edition of the <u>MUTCD</u> and any Colorado supplement. See <u>attached illustration</u> for street name sign specifications.

# 29.40.040 Materials Specifications:

# (a) All Signs

All signs shall be retroreflectorized sheeting on .125" thick tempered and anodized aluminum with radius corners. Letters and background shall faithfully reproduce their respective colors when illuminated at night.

# (b) All Other Signs:

- (1) Shall conform to MUTCD standard sign sizes
- (2) Shall be High Prismatic grade materials

# (c) Posts:

- (1) 12' length 3#/foot U channel posts shall be used for:
  - i. Single signs less than 7 sq. ft. wind loading area


- ii. Double post mounting for signs 8 sq. ft. wind loading area
- (2) 14' length 3#/foot U channel posts shall be used for:
  - i. Warning sign assembly (2 signs) up to 9 sq. ft. wind loading area
  - ii. Single square or diamond shaped signs 9 sq. ft. wind loading area
  - iii. Double post mounting for all signs 10 16 sq. ft. wind loading area
- (3) 8' length 3#/foot U channel posts shall be used for:
  - i. End of road markers
  - ii. Object markers
- (4) All other signs use MUTCD lateral clearance specifications. See 29.40.050 Installation Specifications: c) Lateral Clearance Restriction

#### (d) Fasteners:

- (1) Street Name Signs:
  - i. 180-degree or 90-degree U-Channel Post Cap: cast aluminum 12" length & 5/16" set screws, attached to channel post with 1"x 5/16" bolts
  - ii. 90-degree cross cast aluminum 12" L x .875" D x .200" W with 5/16" set screws
    - 1. Cantilever Wing Bracket: 16.5" L x 8.25" H x 2" W. For attaching to wood utility/light pole use 2" x 5/16" lag bolts and flat washer. *Each sign requires an individual bracket (i.e. Two signs requires two brackets)*.







- (2) All other Signs:
  - i. 3/8", grade 5 bolts with nylon lock nuts and flat washers. The bolt shall protrude beyond the lock nut by a full thread after assembly.
- (e) Street Name Sign Specifications: MUTCD Sign Code D3-1; D1-1; D1-2
  - (1) Logo: All street name signs (D3-1) shall have the City Logo or the Private Logo on the left side of the sign blank. D1-1 and D2-1 do not have logo. Logos are provided by the City of Grand Junction Traffic Department for City owned signs. Privately owned signs shall not display the City Logo.

## (2) Color & Font:

- i. Sign blank is White High Prismatic Sheeting
- ii. Background is 3M Blue 1175 C.
- iii. Border is White, ½" thickness.
- iv. Font is White FHWA Series C2000EX.
- v. Font size on post mounted D3-1 & D1-1: 9" sign blank is 6" tall upper & lower case letters with 4" abbreviation.
- vi. Font size on post mounted D3-1 & D1-1: 12" sign blank is 8" tall upper & lower case letters with 6" abbreviation.
- vii. Font size on post mounted D1-2 18" sign blank is 6" tall upper & lower case letters with 4" abbreviation.
- viii. Font size on overhead 24" sign blank is 12" tall upper & lower case letters with 10" abbreviation.

## (3) Sign Blank Size:

- i. Post mounted on local residential and collector streets: 9" X 24"-30"-36"-42"-48"-54"
- ii. Post mounted on Arterials and Multi Lane Roads with speed limits greater than 40 MPH: 12" X 30"-36"-42"-48"-54"-
- iii. Overhead signs 24" X 48" up to a maximum of 120" L
- iv. Exceptions may be made on longer street names with approval from the Traffic Supervisor.

## (4) Abbreviations:

Avenue; Av Boulevard; Blvd Circle; Cir Court; Ct Drive; Dr Road; Rd Street; St Way; Way Run; Run Trail; Trl

# 29.40.050 Installation Specifications

- (a) Minimum driven depth of post shall be 30 inches for all sign installation.
- **(b) Mounting Height Restrictions:** The mounting height is measured from the bottom of the sign to the top of the curb, or in the absence of curb, to the elevation of the near edge of the traveled way: See <a href="MUTCD Chapter 2A Figure 2A-2-C">MUTCD Chapter 2A Figure 2A-2-C</a>.
  - (1) Street Name Signs (D3-1); Dead End Placard (W14-1a) & No Outlet Placard (W14-2a): 9ft min., 9.5ft max.
  - (2) End of Road Markers: 4ft min., 5ft max.

- (3) All other signs: 7ft min., 7.5ft max.
- (c) Lateral Clearance Restriction: The near edge of sign shall not be less than 2 feet behind the face of curb or edge of sidewalk. Exceptions may be made on roads with a landscape strip with the approval of the Traffic Supervisor. On roads without curb, the near edge of sign shall not be less than 6 feet from the shoulder or 12 feet from the travel way. See MUTCD Chapter 2A Figure 2A-2 & 2A-3
- (d) To maintain sign uniformity, no substitute or decorative materials will be allowed. The use of concrete for mount stabilization will not be allowed. If a stable mount cannot be achieved at the minimum driven depths, greater depths must be used in conjunction with longer posts. Minimum sign heights shall be maintained.
- (e) All signs (other than street name signs) shall be mounted on the wide, or open, side of the channel post. Care should be taken when tightening the bolts so as not to create a "dimple" in the aluminum sign.
- (f) At least two 'end of road' markers "OM4-2" signs shall be used where there is no alternate vehicular path. More than two markers may be required. Where a hazard exists such as an open ditch, the engineer may require permanent Type III Barricades to mark the roadway terminus. The design criteria for the permanent Type III barricade shall be the most recent Colorado Department of Transportation Standard Plan No. S-630-2
- (g) The developer shall bear all expenses for the fabrication and installation of permanent barricades and/or signs for implementing the approved project design (i.e. one way, no parking, dead end and private drive).

# D3-1-D1-2 Examples






Figure 2A-2. Examples of Heights and Lateral Locations of Sign Installations



Note:

See Section 2A.19 for reduced lateral offset distances that may be used in areas where lateral offsets are limited, and in business, commercial, or residential areas where sidewalk width is limited or where existing poles are close to the curb.

Figure 2A-3. Examples of Locations for Some Typical Signs at Intersections



Note: Lateral offset is a minimum of 6 feet measured from the edge of the shoulder, or 12 feet measured from the edge of the traveled way. See Section 2A.19 for lower minimums that may be used in urban areas, or where lateral offset space is limited.

# 29.40.060 Striping Specifications

All striping shall conform to the latest edition of the <u>MUTCD</u> and any Colorado supplement.

All words, letter, symbol and arrow markings shall be installed in accordance with the design details in the Pavement Markings chapter of the latest edition of the "Standards Highway Signs and Markings" book adopted by the Federal Highway Administration.

## (a) Striping and Marking Materials

- (1) All painted lines shall be applied at a minimum thickness of 15 mils, with 6-8 pounds of reflective glass beads applied per gallon of paint.
- (2) All permanent markings such as elongated arrows, stop lines, yield lines, crosswalks, preferential and bike lane markings must be an approved type thermoplastic material, applied a minimum of 125 mils thickness.

#### (b) Colors

Markings shall be yellow, white, red, blue, black or purple. The colors for markings shall conform to the standard highway colors.

<u>WHITE</u>: Longitudinal lane lines, edge lines along the right side of the roadway or any ramp, transverse lines (except for cross-hatching markings in medians or safety zones separating opposing traffic flows or in left shoulders). Arrows, words and symbol markings (except the special interstate route shield symbol marking). Speed hump markings and parking space markings.

<u>YELLOW</u>: Centerlines separating lanes traveling in opposing directions. Edge lines along the left edge of a one-way roadway or one-way ramp. Cross-hatching markings in medians or safety zones separating opposing traffic flows or in left shoulders.

<u>BLACK</u>: Black in conjunction with one of the standard colors shall be a usable color where a light-colored pavement or concrete does not provide sufficient contrast with the markings. When used in combination with other colors, black is not considered a marking color, but only a contrast-enhancing system for the markings.

<u>BLUE</u>: Used for special markings that supplement white markings in a parking space specifically designated as reserved for the disabled. Blue raised pavement markers used to indicate the location of a fire hydrant adjacent to the road. Exception is for interstate route shield pavement markings, which is red, white, and blue.

<u>RED</u>: The only markings that are red are special raised pavement markers that are placed to be visible to "wrong-way" drivers. These special markers warn drives not to enter one-way roadways or one-way ramps in the wrong direction.

<u>PURPLE</u>: Shall supplement lane line or edge line markings for toll plaza approach lanes that are restricted to use only by vehicles with registered electronic toll collection accounts.

**GREEN**: Interim approval for bike lanes.

# (c) Re-Striping

When the removal of pavement striping or markings is necessary, the old striping/markings must be ground off, sand-blasted or covered with a chip-seal. Covering the markings with black paint is prohibited.

#### 29.44 TRAFFIC SIGNALS AND CONSTRUCTION ZONES

#### 29.44.010 Installation/Relocation of Traffic Signals

New traffic signal installations and relocations of existing signal equipment may be required in the developer's public improvement agreement. New signals will be installed only when warranted as specified in the <u>MUTCD</u> and when the new signal will not have a detrimental effect on the traffic flow. The need for a traffic signal will be addressed in the Transportation Impact Studies (see Chapter 29.08) and be designed in accordance with the criteria in GJMC 29.28.130.

The installation, modification or relocation of a traffic signal must follow the specifications defined in the City of Grand Junction Traffic Signal Specifications document.

## 29.44.020 Signal Design Plans

Signal design plans shall be submitted as part of the development plans. The design of the traffic signal shall follow the <u>ITE</u> *Manual of Traffic Signal Design* and the <u>MUTCD</u> standards. The signal design shall follow the Traffic Signal Specifications of the City.

Signal design plans shall contain all necessary information. Typical traffic signal installation and design details are included in the City of Grand Junction Traffic Signal Specification.

New signals or improvements to existing signals shall be required to install conduit for fiber optic cable and all necessary fiber optic equipment to connect to adjacent signals on streets as shown on the Signal Communications Plan.

#### 29.44.030 Traffic Control Plans for Construction Zones

All maintenance of traffic plans for construction areas shall be submitted to and approved as part of the permitting process for work in the public right of way. All plans shall conform to the <u>MUTCD</u> and be prepared by a certified traffic worksite supervisor. On State Highways, the <u>Colorado Department of Transportation</u> shall approve work area traffic control signing and detour plans.

## 29.48 TRANSIT, BICYCLE, AND PEDESTRIAN FACILITIES

## 29.48.010 Planning and Implementation

Transit, bicycle, and pedestrian facilities are an integral part of the transportation system.

This chapter establishes how to plan and implement these facilities. Transit, bicycle and pedestrian accommodations shall be addressed in transportation impact studies as discussed in Chapter 29.08. Additionally, the provision of transit, bicycle, or pedestrian facilities or easements for such facilities may be required as part of the development review process in order to facilitate multimodal circulation and access through or adjacent to the development consistent with the Mesa County Transit Design Standards and Guidelines, existing or planned transit routes, and the <u>Pedestrian and Bicycle Plan</u>. Section 29.16.230 provides requirements for inter-parcel circulation of walkways and bikeways to facilitate multimodal circulation.

#### 29.48.020 Transit Facilities

All transit facilities shall conform to the latest version of the Mesa County RTPO Transit Design Standards and Guidelines. As part of the development review process, the city may require the developer to accommodate transit. Transit facilities could include provision of infrastructure for bus stop amenities including concrete pads, sign posts, and easements in order to allow for the installation of benches, shelters, bike and micromobility parking, and other similar amenities. If a bus pullout is needed to accommodate transit, the city may require the developer to provide the pullout and/or related easements, or additional right-of-way.


## 29.48.030 Planning and Design Standards for Bicycles

Refer to the current version of the <u>AASHTO</u> Guide for the Development of Bicycle Facilities, as well as the <u>NACTO Urban Bikeway Design Guide</u>, and <u>FHWA Separated Bike Lane Planning and Design Guide</u> to address planning and design of bike facilities. NACTO also publishes two additional guides on designing low stress bike facilities: <u>Designing for All Ages and Abilities</u>, and <u>Don't Give Up At The Intersection</u>, which provides guidance on low-stress intersection design, and may be applicable when implementing bike facilities in Grand Junction..

The Grand Junction area has adopted a <u>Pedestrian and Bicycle Plan</u>. The plan shows the future bicycle network in Grand Junction by facility type, including off-street trails and on-street bikeways. The Plan gives guidance on design for bike facility types given the street context in order to eventually achieve a well-connected low-stress bicycle network throughout Grand Junction. All development shall comply with the current version of the Plan.

## **29.48.040** Facility Type


- (a) The Pedestrian and Bicycle Plan identifies six bicycle facility types. They are:
  - (1) **Bicycle Boulevard.** A street which is officially designated and marked [by signage and/or sharrow markings in the pavement] as a bicycle route, but which is open to motor vehicle travel and upon which no bicycle lane is designated. A bicycle boulevard may include other traffic calming features to mitigate the speed and volume of motor vehicle traffic on the street to create a more comfortable environment for bicyclists, such as curb extensions, mini roundabouts, speed humps, and traffic diverters. Generally, streets designated as bike boulevards should be designed for 15 to 20 mph, and the average daily traffic volume should not exceed 1,000 vehicles per day.




Mini roundabout on a Bicycle Boulevard

(2) **Bike Lane.** A portion of street, which has been designated (by pavement markings and signage) for use by bicyclists. The bike lane is typically 5 feet wide, measured from the lip of gutter pan when adjacent to the curb and is 6.5 feet wide when measured from the face of the curb. When adjacent to a parking lane (and on the outside of the parking lane) the outside stripe of the


bike lane is typically 14 feet from the face of the curb (and a minimum of 12.5 feet from the lip of the gutter pan). A buffer between the parking lane and the bike lane may also be implemented when there is a heightened "door zone" concern either through the use of a separate solid lane at least 18 inches from the bike lane or parking "Ts" to delineate parking spaces.



Bike lane adjacent to a curb



Bike lane adjacent to a parking lane



Example of a Parking "T" adjacent to a bike lane (source: NACTO)

(3) **Buffered Bike Lane.** A portion of street, which has been designated (pavement markings and signage) for use by bicyclists with a painted buffer

between a general purpose travel lane and the bike lane. The buffer width is typically 3 feet.




(4) **Protected Bike Lane.** A portion of street, which has been designated (by paint stripe, pavement markings, and signage) for use by bicyclists with a physical buffer between the general purpose travel lanes and the bike lane. The physical buffer may be delineator posts, planters, rigid bollards, a parking strip (parked cars), or a concrete barrier. The lane is typically 6.5 feet wide from the curb and the buffer is typically 3 feet.



(5) **Multi-use Trail.** A separate two-way trail from which motor vehicles are prohibited and which is for the shared use of bicycles and pedestrians. The trail is typically 10 feet wide but may be 12' wide to meet anticipated demand and to mitigate conflicts between bicyclists and pedestrians. The width can be greater than 12 feet where bicycle and pedestrian demand warrants or conflicts between pedestrians and bicyclists are more frequent, for example, the Riverfront Trail.



(6) **Raised Cycle Track.** A separate trail or pathway from which motor vehicles are prohibited, and raised from the general purpose travel lanes, and which is for the exclusive use of bicycles and other allowable micro-mobility devices (such as electric scooters). The trail is typically 6.5 feet wide or wider.



- (b) The design standards for bike lanes and multiuse trails are contained in the <u>AASHTO</u> manual and additional design guidance for these facilities are contained in the NACTO Urban Bikeway Design Guide and FHWA Separated Bike Lane Planning and Design Guide provide hot link. Typical widths and locations of bicycle facilities on the street are also provided in the street sections in Chapters 29.20 and 29.28. The list below are the minimum bicycle facility design standards to be provided:
  - (1) Uniformity in on-street facility design, signage, and pavement markings for bicyclist and motorist safety.
  - (2) Absolute minimum widths are 4 feet on an open shoulder and 5 feet against a curb or guardrail or next to a parking lane. Bike lanes must provide at a minimum 4 feet of width from lip of gutter when adjacent to the curb. When adjacent to a parking lane the outside painted line of the bike lane must be at

- least 12 feet from the edge of the curb. Minimum widths should not be the default, but should only be applied in environments with constrained right-of-way. On most street segments, typical widths will be provided.
- (3) Cross railroad tracks perpendicular to direction of bike travel with appropriate treatment to ensure smooth and safe crossings.
- (4) On-street bicycle facilities shall provide bicycle-safe curb inlet grates.
- (5) Avoid diagonal on-street parking on streets with a striped bike lane (unless the bike lane is between the parking lane and the curb).
- (6) Implement bicycle detection at all traffic signal approaches with an existing or planned on-street bicycle facility at an actuated signal.
- (7) Carry the bike lane through all intersections to the extent that is feasible.

### **29.48.045** Bicycle Intersection Treatments

Refer to the <u>AASHTO</u> Guide for the Development of Bicycle Facilities, as well as the <u>NACTO Urban Bikeway Design Guide</u>, and <u>Don't Give Up At The Intersection</u> for guidance on designing bicycle facilities through intersections. Effective treatments may include <u>bike boxes</u>, <u>intersection crossing markings</u>, <u>two-stage turn queue boxes</u>, <u>median refuge islands</u>, or other paint, signage, or vertical elements. Active transportation corridors and bike routes will likely require context sensitive treatments.

(a) Trail Crossings. Where multiuse trails intersect driveways or side-street STOP controlled minor streets, trails should bend away so that they are set back from the major street. The total setback from the edge of the travel lane (or bike lane if present) to the edge of the trail should be 15 to 25 feet (one vehicle length).

#### 29.48.050 Pedestrian Facilities

Pedestrian facilities are required as a part of the street cross-section, as detailed in the Grand Junction <u>Standard Contract Documents for Capital Improvements Construction</u> and street cross section in Chapters 29.20 and 29.28. Additional guidance on pedestrian design is included in the <u>Pedestrian and Bicycle Plan</u> and reflected in the typical street cross sections. Detached walkways that are constructed must conform to these details as well.

Environmental factors that contribute to the walking experience and therefore to the perceived level of service include:

- (a) Comfort factors that include weather protection, climate control, transit shelters, and other pedestrian amenities.
- (b) Convenience factors such as walking distances, walkway directness, grades, sidewalk ramps, directional signing, directory maps and other features that make pedestrian travel easy and uncomplicated.
- (c) Safety that is provided by separation of pedestrians from vehicular traffic, or traffic control devices that can provide for time separation of pedestrian and vehicular traffic.
- (d) Security features include lighting, open lines of sight, and the degree and type of street activity.
- (e) Economy aspects related to user-costs associated with travel delays and inconvenience, and to the rental value and retail development as influenced by the pedestrian environment.

The quality of the pedestrian environment should be evaluated in three broad areas:

- (a) Walking along the street includes continuity, capacity, and comfort.
- **(b)** Crossing the street includes safety, sufficient space, delay, and route deviation.
- (c) Some place to walk to in terms of travel time on foot, destinations, and how much of an area can be reached within a reasonable time or distance.

The Pedestrian and Bicycle Plan includes pedestrian design recommendations for sidewalk and buffer widths in different street contexts to provide sufficient space and separation from traffic in order to achieve a high level of pedestrian comfort given the speed and volume of traffic. These recommendations are reflected in the typical street sections included in Chapters 29.20 and 29.28.

#### 29.48.060 Pedestrian Intersection Treatments

All pedestrian crossings shall comply with the Grand Junction Standard Contract Documents for Capital Improvements Construction and be designed in accordance with the Americans with Disabilities Act, including accessible ramps, accessible push buttons when applicable, detectable surfaces, and other universal design features. Refer to the current edition of the Grand Junction Pedestrian Crossing Treatment Installation Guidelines for guidance on applicability of pedestrian crossing treatments in different contexts, including at uncontrolled crossings. Refer to CDOT's Pedestrian Crossing Installation Guide for uncontrolled pedestrian crossings on state highways.

Potential pedestrian treatments at uncontrolled crossings may include:

### (a) Advance Warning Signing and Striping

See Chapter 2C of the MUTCD for guidance on advance warning pedestrian crossing signs and Chapter 3B for yield line pavement markings.

HERE

# (b) High Visibility Marked Crosswalks

According to FHWA <u>high-visibility crosswalks</u> use patterns such as bar pairs, continental, or ladder that are visible from farther distances to drivers and pedestrians. Additionally, consider using inlay or thermoplastic tape instead of paint for highly reflective markings.

### (c) Raised Crossings

A raised mid-block crossing or raised intersection treatment may be installed as a treatment to slow vehicle traffic and function as an extension of the sidewalk to allow a pedestrian to cross the street at a constant grade. According to <a href="FHWA">FHWA</a> raised crossings are typically a candidate on 2-lane or 3-lane roads with speed limits of 30 mph or less and AADTs below 9,000.

## (d) Pedestrian Refuge Medians

A pedestrian refuge median is a location in the middle of a pedestrian crossing where a pedestrian can take refuge, thereby separating their crossing into two steps and must include some type of raised median. Additional design guidance can be found in the Grand Junction Pedestrian Crossing Treatment Installation Guidelines.



#### (e) Bulb-Outs

A bulb-out (or corner extension) is a roadway edge treatment where a curb line is bulged out toward the middle of the roadway to narrow the width of the street. Bulb-outs are often used at the location of a pedestrian crosswalk to minimize the distance and time that a crossing pedestrian must be in the roadway and are typically implemented on streets with on-street parking. Bulb-outs also increase visibility of pedestrians waiting to cross and are an effective means to slow vehicles, including slowing turning vehicles when implemented at intersections.



## (f) Rapid Rectangular Flashing Beacons (RRFB)

RRFBs are small rectangular yellow flashing lights that are deployed with pedestrian crossing warning signs. They are typically actuated by a pedestrian push button and flash for a predetermined amount of time, to allow a pedestrian to

cross the roadway, before going dark. RRFBs are warning devices and do not themselves create a legal requirement for a vehicle to stop when they are flashing. Guidance on the appropriate context for RRFBs are provided in the Grand Junction Pedestrian Crossing Treatment Installation Guidelines.



#### (g) Pedestrian Hybrid Beacons (also known as HAWK beacons)

A pedestrian hybrid beacon is used to both warn and control traffic at a pedestrian crossing. It is actuated by a pedestrian push button and uses a combination of circular yellow and red traffic signal displays to first warn motorists of a pedestrian that is about to cross the street, then require the motorist to stop for the pedestrian crossing, and then release the motorist to proceed once the pedestrian has cleared the crossing. The Beacon is a hybrid between a pedestrian traffic signal and a stop sign.



## (h) Traffic Signals

Depending on factors defined in the Grand Junction Pedestrian Crossing Treatment Installation Guidelines, such as vehicle traffic volume, vehicle speed, and the number of lanes, or other contextual factors (such as pedestrian volume, crash history, or adjacent land use), it may be appropriate to signalize a pedestrian crossing.

## **29.56 ALLEY STANDARDS**

## 29.56.010 Alley Construction

Alleys are a useful alternative for accessing properties, especially in the Central Business District (CBD). The construction of new alleys shall follow the design standards defined in the standard detail for alleys located in the Appendix. Any variation from the specifications defined in this drawing must go through the design exception process.

### 29.64 DESIGN EXCEPTIONS

#### 29.64.010 Design Exceptions

This manual establishes standards for the construction of transportation and infrastructure improvements in the City and within the Urban Development Boundary. There may be certain circumstances where those standards do not adequately meet the public's needs. The public needs, as defined by these standards, may conflict with constraints on the property or a new or innovative development proposal.

This chapter describes an exception process. It may be that an exception is a one-time event or it may be that the Manual will be revised to incorporate the exception.

The <u>flowchart</u> depicts the design exception process.

The burden in the development process shall be on the applicant to demonstrate that the proposed exception, if granted, will not result in a dangerous condition as determined by the City or County. No exception shall be allowed if the resulting design is dangerous or otherwise fails to meet the fundamental needs of the community. The fundamental needs of the community shall be determined by the City or County, but primarily are the provision of safe, efficient and effective transportation.


Any exceptions to the TEDS manual should be clearly proposed as early as possible in the project development and review process. Exceptions to TEDS should be identified no later than preliminary plan submittal.

If a design exception is to be a permanent modification to the TEDS Manual, it will be the responsibility of the City and County staff to update TEDS and disseminate the change to CDOT, other municipal or county departments and the development community.

When geometric standards or other design criteria are not specifically addressed in the City or County standards, then the latest editions of the following standards and criteria shall govern the design.

- Colorado State Highway Access Code
- CDOT Roadway Design Manual
- Institute of Transportation Engineers (ITE) Traffic Engineering Handbook
- American Association of State Highway and Transportation Officials (AASHTO) A Policy on Geometric Design of Highways and Streets

## **Design Exception Process**



#### 29.68 ALTERNATE STREET STANDARDS

#### 29.68.010 Intent of Provisions

The intent of this chapter is to provide flexibility in the creation, approval and use of public street infrastructure that varies from the cross-sectional standards provided in Chapter 29.20, and to accommodate such proposals under administrative approval procedures. This resulting alternate street standard may be used to create neighborhood character, enhance visual appeal, and to accommodate unique topographical or site features. Further, implementation of these standards should result in "a better solution," allowing alterations to the standard street section that produce benefit to the community.

#### 29.68.020 Performance Criteria

All public streets considered for alternate cross-sections shall meet certain minimum performance-based standards and meet all intent for function of a public right-of-way. Each proposal must be framed within the specific context of the use.

### (a) Horizontal Geometry

- (1) The horizontal geometry of street, pathway, and trail layouts must meet TEDS requirements elsewhere herein. The design must accommodate large vehicles such as fire trucks, trash trucks and semi-trucks at an appropriate level of service.
- (2) A minimum pavement width of 20 feet, from flow line of gutter to flow line of gutter, is required for all streets. Pathway and trail widths or pedestrian walkways shall meet minimum widths as required in the Standard Contract Documents for Capital Improvements Construction by pathway and trail classification.
- (3) Horizontal curb radii must be 15 feet minimum for chicanes, parking bulb-outs and other similar features to maintain proper drainage (see GJMC 29.28.160).
- (4) Intersection geometry is as required elsewhere herein.

## (b) Vertical Geometry

The vertical geometry of street, pathway, and trail layouts must meet TEDS requirements elsewhere herein and ADA requirements.

### (c) Sight Distance

The design must achieve all sight distance requirements listed elsewhere in TEDS.

#### (d) Connectivity

- (1) Minimum connectivity requirements remain unchanged, including pedestrian and bicycle connectivity. Provision of access to adjacent parcels is required. Additional inter- or intra-parcel connectivity may be necessary where reduced street width is considered.
- (2) Example: One case where narrow streets and the concept of "queuing" are frequently and successfully used is in older downtown neighborhoods across the country. The streets typically have a grid layout, short block length, and possibly an alley, all providing a high-degree of connectivity, thus allowing a narrow street with fairly high density and high use of on-street parking to function satisfactorily.

#### (e) Parking

- (1) Adequate parking must be provided both on- and off-street. Zoning and development code minimums are required on-site. The on-street parking range is required at 0.5 to 1.5 on-street parking spaces per dwelling unit (see the Local Street Section Notes in Chapter 29.20). Higher density development will demand on-street parking in the upper end of that range.
- (2) Clustering of on-street parking in pods is encouraged where full on-street parking is not provided. The provision of on-street parking shall consider availability of parking for long vehicles or vehicles with trailers.
- (3) Adequate parking outside of the travel lane must be provided. On the other hand, excessive availability of parking contributes to higher speeds due to width of travel lane available as well as to increased construction and maintenance costs.

#### (f) Pedestrian Facilities

- (1) The design must provide adequate pedestrian facilities equal to or better than existing adopted street sections. Detached walk and additional walk width are encouraged.
- (2) Sidewalk is required to create continuous pedestrian walkways parallel with the public roadway. Generally, if lots front both sides of the street, sidewalk will be required on both sides of the street.

### (g) Drainage

- (1) Curb and gutter is generally considered necessary. However, in limited instances, other options may be considered. Examples include an inverted crown as typically used in concrete alley applications and areas where attached curb and gutter may not be practical due to certain soil conditions. In these cases, adequate drainage facilities must be provided per the Stormwater Management Manual (GJMC Title 28). Alternate drainage facilities must not require additional maintenance effort above conventional facilities.
- (2) Surface drainage at bulb-outs and chicanes is preferred along a continuous gutter without drain troughs or otherwise inaccessible sections of gutter.
- (3) Narrower street sections will not carry the same amount of water as the standard street sections. Analysis of the street stormwater carrying capacity by use of the SWMM nomographs will not be permitted.

### (h) Surfacing and Construction Requirements

Hard surfacing (Portland cement concrete or asphalt pavement) is required and shall meet the structural design requirements contained in Chapter 29.32 GJMC. Gravel surfacing is not allowed. Construction requirements are contained in the Grand Junction Standard Contract Documents for Capital Improvements Construction.

### (i) Right-of-Way and Multi-Purpose Easements

- (1) Right-of-way and infrastructure dimension and configuration must provide adequate room for all necessary public facilities including, but not limited to, storm drainage; water lines and meters; sanitary sewer lines; electrical, natural gas, cable, telephone supply lines, service lines, pedestals and appurtenances; traffic control signage; irrigation supply and drainage; cut or fill slopes; and other public utility lines and appurtenances.
- (2) The standard 14-foot multi-purpose easement may be reduced in width if adequate space is shown to exist within the right-of-way. The standard multi-purpose easement width on streets with a buffer between the sidewalk and the curb is 10-feet.
- (3) Right-of-way configuration must provide adequate access to public utilities. Fencing of easement areas is discouraged as it reduces access to utilities and improvements.
- (j) Private Streets, Shared Drives and Alleys.

- (1) Nothing in this section shall expressly prohibit the use of private streets and shared drives, as allowed elsewhere herein, to be used in conjunction with alternate standard streets.
- (2) The use of alleys is likewise permitted and may be used in conjunction with alternate standard streets to achieve utility service delivery, alternate access to off-street parking or enhance connectivity.

#### (k) Traffic Calming

Traffic calming requirements are the same as required elsewhere herein. Elements of narrowed streets may be considered part of the traffic calming system.

### (I) Other Right-of-Way Elements

All elements of the function of the right-of-way must be considered in the design process.

- (1) **Mail Receptacles.** Streets shall include design elements necessary to meet USPS requirements for access to mail receptacles. Mail receptacles will not be permitted within sight distance triangles at intersections or located such that they interfere with the safe and normal function of the street. Parking shall be provided adjacent to the mail receptacle.
- (2) **Urban Trails.** Where urban trails, primary school walk routes, bike lanes, or other non-motorized transportation routes are indicated on adopted City, school district, or other plans, these elements must be incorporated into the design. The design must meet all requirements of City, State and federal standards, including ADA.

### **29.68.030** Application

The process for an alternative street request is similar to the Design Exception Process depicted on the flowchart in Chapter 29.64. The applicant shall submit a written report requesting alteration of the standard as a part of a pre-application conference, preliminary plan or other application process. The applicant is encouraged to make this application as early in the process as feasible. The report and plan shall contain the following:

- (a) A specific request for alteration of the standard, detailing elements of the standard that are altered and the proposed alternative.
- **(b)** A narrative explaining the reasons for requesting the alteration and proposed benefits.
- (c) A narrative, individually addressing each criterion in the performance criteria above.

- (d) A site plan showing limits and extents of proposed alterations.
- (e) A site plan indicating proposed density, approximate lot size and frontage, access locations, street network, and other pertinent elements. Approximate horizontal and vertical geometry may be required, dependent on topography or other site constraints.
- (f) A parking plan demonstrating on-street and off-street parking to demonstrate conformance with parking standards listed above.
- (g) A fire site plan demonstrating that a fire truck can negotiate the development with the proposed on-street parking from both directions.


### 29.68.040 Approval

The Director or his/her assigned representative(s) shall make a final determination of adequate conformance to these criteria and have the authority to approve or reject each proposed alternative. Staff or agency members may provide comment or modification to the proposal. The Director may consult with or delegate review and approval authority to City Staff, outside review agencies, or outside consultants.

Where the proposed alternate may affect utility placement, approval of the Utility Coordinating Committee is required prior to the consideration by the Director or his designee.

Deviation from the standard street cross-sections may continue to be accomplished through a variance or a planned development procedure as permitted in the zoning and development code.

# **Principal Arterial**




				Principa	al Arterial R	OW 110'				
	Α	В	(	С		E	F	G	Н	J
Туре	Travel Lanes	Median/ Turn Lane	Bike Lane (On Street)	Bike Lane (Off Street)	Bike Buffer	Curb and Gutter	Sidewalk Buffer*	Sidewalk/ Trail	Multi- Purpose Easement	Frontage
1. Principal Arterial with PBL	11	17	5		3	2	6	8	10	.5
2. Principal Arterial with Trail	11	17			0	2	12	10	10	.5
3. Principal Arterial with Cycle Track	11	17		6.5	.5	2	7	8	10	.5

 $<sup>{}^{\</sup>star}\text{The Sidewalk Buffer allows space for landscaping, street furniture (benches, bike, racks), and utility polls}$ 

# **Principal Arterial**

- See Grand Junction Urbanized Area Functional Classification Map for principal arterial street designation.
- Vertical curbs, gutters and sidewalks are required on both sides of all arterial streets.
- Attached sidewalks may be approved where existing development precludes construction of detached sidewalks.
- All arterial streets shall be surfaced with Hot Bituminous Pavement (HBP) or Portland Cement Concrete (PCC).
- Additional right-of-way width will be required for construction of dedicated right-turn lanes. See chapters of the City's Transportation Engineering Design Standards for Speed Change Lane Dimensions.
- See details of Multi-purpose Easement Adjacent to Right-of-Way in the standard contract documents.
- For Sight Zone requirements refer to 29.28.150 of the TEDS Manual.
- Vertical elements required in the buffer zone between the travel lane and bike lane to satisfy the condition of a protected bike lane (PBL) when speed is => 40 mph. Buffered bike lane (without vertical elements) may be acceptable when <40 mph.
- Vertical separators would only be used between intersections.
- The standard design for a street with a trail includes a 10' trail on both sides of the street. In situations where there are ROW constraints, higher bicycle demand on one side, or differing land uses on one side, an 8' sidewalk can be provided on one side with a 12' or 14' trail on the other side.
- The standard design for a street with buffered bike lanes or a cycle track includes a one-way bikeway on both sides of the street. In some contexts where land use or other constraints dictate a two-way bikeway on one side of the street can be implemented. Refer to the NACTO Urban Bikeway Design Guide and the FHWA Separated Bike Lane Planning and Design Guide for special design considerations, particularly at driveways and intersections, when designing twoway protected bikeways.
- A trail is considered multi-use for wheeled traffic and pedestrians.
- The minimum sidewalk buffer width is 7 feet for planting trees.

# **Minor Arterial**




	Minor Arterial ROW 100'													
		Α	В	C	;	D	E	F	G	Н	J			
Туре	# of Travel Lanes	Travel Lanes	Median/ Turn Lane	Bike Lane (On Street)	Bike Lane (Off Street)	Bike Buffer	Curb and Gutter	Sidewalk Buffer	Sidewalk/ Trail	Multi- Purpose Easement	Frontage			
1. Minor Arterial with Buffered Bike Lane/ PBL	4	11	12	5		3	2	3.5	8	10	.5			
2. Minor Arterial with Trail	4	11	12			0	2	9.5	10	10	.5			
3. Minor Arterial with Cycle Track	4	11	12		6.5	.5	2	4.5	8	10	.5			

## **Minor Arterial**

- See Grand Junction Urbanized Area Functional Classification Map for minor arterial street designation.
- Vertical curbs, gutters and sidewalks are required on both sides of all arterial streets.
- All arterial streets shall be surfaced with Hot Bituminous Pavement (HBP) or Portland Cement Concrete (PCC).
- Additional right-of-way width will be required for construction of dedicated right-turn lanes. See chapters of the City's Transportation Engineering Design Standards for Speed Change Lane Dimensions.
- See details of Multi-purpose Easement Adjacent to Right-of-Way in the standard contract documents.
- For Sight Zone requirements refer to 29.28.150 of the TEDS Manual.
- Vertical separators can be added to a buffered bike lane where additional cyclist protection is deemed necessary to achieve Level of Traffic Stress standards.
- Vertical elements required in the buffer zone between the travel lane and bike lane to satisfy the
  condition of a protected bike lane (PBL) when speed is => 40 mph. Buffered bike lane (without
  vertical elements) may be acceptable when <40 mph.</li>
- Vertical separators would only be used between intersections.
- The standard design for a street with a trail includes a 10' trail on both sides of the street. In situations where there are ROW constraints, higher bicycle demand on one side, or differing land uses on one side, an 8' sidewalk can be provided on one side with a 12' or 14' trail on the other side.
- The standard design for a street with buffered bike lanes or a cycle track includes a one-way bikeway on both sides of the street. In some contexts where land use or other constraints dictate a two-way bikeway on one side of the street can be implemented. Refer to the NACTO Urban Bikeway Design Guide and the FHWA Separated Bike Lane Planning and Design Guide for special design considerations, particularly at driveways and intersections, when designing twoway protected bikeways.
- When necessary, the two way left tun lane can be a raised median.
- The minimum sidewalk buffer width is 7 feet for planting trees.
- A trail is considered multi-use for wheeled traffic and pedestrians.

# Major Collector 78' ROW ≥35 MPH




			Ма	jor Collec	ctor ROW	78' ≥35MI	РН			
	Α	В	С		D	E	F	G	Н	J
Туре	Travel Lanes	Median/ Turn Lane	Bike Lane (On Street)	Bike Lane (Off Street)	Bike Buffer	Curb and Gutter	Sidewalk Buffer	Sidewalk/ Trail	Multi- Purpose Easement	Frontage
1. Major Collector with Buffered Bike Lane/ PBL	11	12	5		3	2	3.5	8	10	.5
2. Major Collector with Trail	11	12	0		0	2	9.5	10	10	.5
3. Major Collector with Cycle Track	11	12		6.5	.5	2	4.5	8	10	.5

# Major Collector 78' ROW ≥35 MPH

- See Grand Junction Urbanized Area Functional Classification Map for collector street designation.
- Vertical curbs, gutters and sidewalks are required on both sides of all collector streets.
- Attached sidewalks may be approved where existing development precludes construction of detached sidewalks.
- All collector streets shall be surfaced with Hot Bituminous Pavement (HBP) or Portland Cement Concrete (PCC).
- Additional right-of-way width will be required for construction of dedicated right-turn lanes. See chapters of the City's Transportation Engineering Design Standards for Speed Change Lane Dimensions.
- See details of Multi-purpose Easement Adjacent to Right-of-Way in the standard contract documents.
- For Sight Zone requirements refer to 29.28.150 of the TEDS Manual.
- Vertical separators can be added to a buffered bike lane where additional cyclist protection is deemed necessary to achieve Level of Traffic Stress standards.
- Vertical elements required in the buffer zone between the travel lane and bike lane to satisfy the condition of a protected bike lane (PBL) when speed is => 40 mph. Buffered bike lane (without vertical elements) may be acceptable when <40 mph.
- Vertical separators would only be used between intersections.
- The standard design for a street with a trail includes a 10' trail on both sides of the street. In situations where there are ROW constraints, higher bicycle demand on one side, or differing land uses on one side, an 8' sidewalk can be provided on one side with a 12' or 14' trail on the other side.
- The standard design for a street with buffered bike lanes or a cycle track includes a one-way bikeway on both sides of the street. In some contexts where land use or other constraints dictate a two-way bikeway on one side of the street can be implemented. Refer to the NACTO Urban Bikeway Design Guide and the FHWA Separated Bike Lane Planning and Design Guide for special design considerations, particularly at driveways and intersections, when designing twoway protected bikeways.
- In segments of the street where there is lower left turn demand (at low volume intersections, low volume driveways, or where there are no driveways) the center turn lane can be removed and replaced with a painted buffer between the bike lane and the travel lane to provide additional comfort to bicyclists and/or the pavement width can be narrowed and the buffer between the sidewalk and curb widened.
- The minimum sidewalk buffer width is 7 feet for planting trees.
- A trail is considered multi-use for wheeled traffic and pedestrians.

# Low Speed Major Collector 70' ROW < 35MPH



Major Collector ROW 70' < 35 MPH												
	A B C D E F G H J											
Туре	Criteria	Travel Lanes	Median/ Turn Lane	Bike Lane (On Street)	Bike Lane (Off Street)	Bike Buffer	Curb and Gutter	Sidewalk Buffer	Sidewalk	Multi- Purpose Easement	Frontage	
1. Major Collector with Bike Lane Both Sides	<35 MPH	11	12	5		0	2	4.5	6	10	.5	

Pavement Width 44'

1. Major Collector with Bike Lane Both Sides


# Low Speed Major Collector 70' ROW < 35MPH

- See Grand Junction Urbanized Area Functional Classification Map for collector street designation.
- Vertical curbs, gutters and sidewalks are required on both sides of all collector streets.
- Attached sidewalks may be approved where existing development precludes construction of detached sidewalks.
- All collector streets shall be surfaced with Hot Bituminous Pavement (HBP) or Portland Cement Concrete (PCC).
- Additional right-of-way width will be required for construction of dedicated right-turn lanes. See chapters of the City's Transportation Engineering Design Standards for Speed Change Lane Dimensions.
- See details of Multi-purpose Easement Adjacent to Right-of-Way in the standard contract documents.
- For Sight Zone requirements refer to 29.28.150 of the TEDS Manual.
- In segments of the street where there is lower left turn demand (at low volume intersections, low volume driveways, or where there are no driveways) the center turn lane can be removed and replaced with a painted buffer between the bike lane and the travel lane to provide additional comfort to bicyclists and/or the pavement width can be narrowed and the buffer between the sidewalk and curb widened.
- If the Major Collector street corridor has a posted speed of 35 mph or higher within a mile of a particular location design may need to meet the standards of the Major Collector 78' ROW.
- The minimum sidewalk buffer width is 7 feet for planting trees.

# **Minor Collector**

1. Minor Collector with Bike Lane and Parking and Attached Sidewalk

2. Minor Collector with Bike Lane and No Parking and Detached Sidewalk



	Minor Collector ROW 64'												
		Α	В	(		D	E	F	G	н	I	J	
Туре	Criteria	Travel Lanes	Median/ Turn Lane	Bike Lane (On Street)	Bike Lane (Off Street)	Bike Buffer	Curb and Gutter	Sidewalk Buffer	Sidewalk	Multi- Purpose Easement	Parking	Frontage	
1. Minor Collector with Bike Lane with Parking and Attached Sidewalk	≤30 MPH	11	0	5		0	2	0	6	14	7.5	.5	
2. Minor Collector with Bike Lane No Parking and Detached Sidewalk	≤30 MPH	11	0	5		0	2	7.5	6	10	0	.5	

Pavement Width 47'

1. Minor Collector with Bike Lane and Parking on Both Sides

Pavement Width 32'

2. Minor Collector with Bike Lane Both Sides (No Parking)


## **Minor Collector**

- If the street classification changes, efforts should be made maintain the facility type for the entire length of the corridor.
- See Grand Junction Urbanized Area Functional Classification Map for collector street designation.
- All collector streets shall be surfaced with Hot Bituminous Pavement (HBP) or Portland Cement Concrete (PCC).
- Additional right-of-way width will be required for construction of dedicated right-turn lanes. See chapters of the City's Transportation Engineering Design Standards for Speed Change Lane Dimensions.
- When a bike lane is adjacent to a parking lane, separation may be provided between the bike lane striping and parking boundary by marking the parking spaces to mitigate conflicts by bikers with the "door zone" of parked cars.
- See details of Multi-purpose Easement Adjacent to Right-of-Way in the standard contract documents.
- On Street parking may be prohibited as required to provide left turn lanes at intersections.
- For Sight Zone requirements refer to 29.28.150 of the TEDS Manual.

# **Local Commercial**

1. Local Commercial with Bike Lane and Parking and Detached Sidewalk

2. Local Commercial with Bike Lane and No Parking and Attached Sidewalk



	Local Commercial ROW 64'												
	Α	В			D	E	F	G	Н	I	J		
Туре	Travel Lanes	Median/ Turn Lane	Bike Lane (On Street)	Bike Lane (Off Street)	Bike Buffer	Curb and Gutter	Sidewalk Buffer	Sidewalk	Multi- Purpose Easement	Parking	Frontage		
1. Local Commercial with Bike Lane with Parking and Attached Sidewalk	11	See note	5		0	2	0	6	14	7.5	.5		
2. Local Commercial with Bike Lane No Parking and Detached Sidewalk	11	See note	5		0	2	7.5	6	10	0	.5		

Pavement Width 47'

1. Local Commercial with Bike Lane and Parking on Both Sides


Pavement Width 32'

2. Local Commercial with Bike Lane Both Sides (No Parking)

## **Local Commercial**

- See Grand Junction Urbanized Area Functional Classification Map for collector street designation
- All collector streets shall be surfaced with Hot Bituminous Pavement (HBP) or Portland Cement Concrete (PCC. All pavement shall be designed in accordance with the AASHTO Guide for Design of Pavement Structures.
- Additional right-of-way width will be required for construction of dedicated right-turn lanes. See chapters of the City's Transportation Engineering Design Standards for Speed Change Lane Dimensions.
- See details of Multi-purpose Easement Adjacent to Right-of-Way in the standard contract documents.
- (On Street) parking may be prohibited as required to provide left turn lanes at intersections.
- For Sight Zone requirements refer to 29.28.150 of the TEDS Manual.
- Parking may be prohibited on streets with high traffic volumes, or based on other contextual factors.
- If turn lanes are warranted, they will be 11 feet in width for right turn lanes (exclusive of the gutter pan) and 12 feet for left turn lanes.

# **Residential and Industrial Local Street**




	Residential Street ROW 38'- 63'													
			Α	E	F	G	Н	I	J					
Туре	Criteria	# of Travel Lanes	Travel Lanes	Drive Over Curb and Gutter	Sidewalk Buffer	Sidewalk	Multi- Purpose Easement	Parking	Frontage	ROW				
1. Residential No Parking Attached Sidewalk	<1000 ADT, ≤ 20 MPH	2	10	2.5	0	6	14	0	.5	38				
2. Residential with Parking One Side Attached Sidewalk	<1000 ADT, ≤ 20 MPH	2	8.5	2.5	0	6	14	7	.5	42				
3. Residential Attached Sidewalk	<1000 ADT, ≤ 20 MPH	2	7	2.5	0	6	14	7	.5	46				
4. Residential Attached Sidewalk 1 Side Detached Sidewalk 1 Side	<1000 ADT, ≤ 20 MPH	2	8	3	4-8 One Side	6	10 and 14	7 One Side	.5	45.5-49.5				
5. Residential Detached Sidewalk	<1000 ADT, ≤ 20 MPH	2	7	3	4-8	6	10	7	.5	55-63				
	Local Industrial ROW 53'													
6. Local Industrial Attached Sidewalk		2	12	Vertical Curb 2	0	6	10	7	.5	55				



## Residential and Industrial Local Street

- A sidewalk can be provided on only one side of the street only if a sidewalk, trail, or pathway is located behind the houses/businesses on the side of the street without a sidewalk.
- If an attached sidewalk is included on a side of the street with no on-street parking the street must be designed for speeds of 20 mph or less and have less than 1,000 average vehicles per day.
- When parking is restricted, an off-lot parking plan (showing on-street and parking pods) is required. When density is R-4, 0.5 off lot parking spaces are required per unit, R-5 requires 1.0 space per unit, and R-8 requires 1.5 spaces per unit.
- When asphalt width is narrower than 28', a fire site plan is required demonstrating designated GJFD design apparatus can maneuver the site with on-street parking.
- Drive over curb, gutter and sidewalk shall be installed only on urban residential streets with less than 1.000 A.D.T.
- Vertical curb and gutter can be used instead of drive over, but driveway cuts must be built with the subdivision and efforts should be made to maintain grade at sidewalks.
- Street sections can be changed to include detached sidewalks using the buffer in street section 5. Right of way width will change accordingly.
- The minimum sidewalk buffer width is 7 feet for planting trees.
- An Exception Request can be considered for sidewalks under 6 ft. width within a constrained environment and/or where low volume of 10 peak hour (vehicular) trips or less can be shown and no through access is provided or planned.
- Where driveways cross detached sidewalks, sidewalks shall be 6" thick concrete for residential and 8" thick concrete for industrial.

# **G** Road




	G Road ROW 70' - 85'											
	Α	В	С	D	E	F	G	Н	J	K		
Туре	Travel Lanes	Median/ Turn Lane	Bike Lane	Bike Buffer	Curb and Gutter	Sidewalk Buffer	Trail/ Sidewalk	Muli-Purpose Easement	Frontage	Stream Channel/ Drainage		
1. 23 1/2 Road to Highway 6 & 50	11	11         12         5         3         2         7 minimum both sides         8 both sides         10         0.5         0										
2. 24 Road to 23 1/2 Road	24 road to 23 1/2 road is newly constructed. Only requirement is to install meandering sidewalk, along the North side of 24 road to 23 3/4 road mimicking the sidewalk to the west.											
3. 24 1/2 Road to 24 Road	Newly Constructed of Leach Creek ro											

## **G** Road

				G R	oad RO	N 70' - 85'				
	Α	В	С	D	E	F	G	Н	J	K
Туре	Travel Lanes	Median/ Turn Lane	Bike Lane	Bike Buffer	Curb and Gutter	Sidewalk Buffer	Trail/ Sidewalk	Muli-Purpose Easement	Frontage	Stream Channel/ Drainage
4. 25 Road to 24 1/2 Road	11	12	5	3	2	7 minimum North side	8 on North side, 12 on the South side,of Leach Creek.	14 South 10 North	0.5	20' stream channel with 4:1 slope on non- roadway side and 3:1 on roadway side
5. 25 1/2 Road to 25 Road	11	12	5	3	2	7 minimum North side	8 on North side, 12 along Leach Creek	14 South 10 North	0.5	Developable land
6. Horizon Drive to 25 1/2 Road	11	12	5	3	2	7 minimum both sides	8 both sides	10	0.5	0


- G Road is classified as a minor arterial but will be built to a modified major collector section as depicted herein.
- Vertical curbs, gutters and sidewalks are required on both sides of all collector streets
- All collector streets shall be surfaced with Hot Bituminous Pavement (HBP) or Portland Cement Concrete (PCC).
- Additional right-of-way width will be required for construction of dedicated right-turn lanes. See chapters of the City's Transportation Engineering Design Standards for Speed Change Lane Dimensions.
- See details of Multi-purpose Easement Adjacent to Right-of-Way in the standard contract documents.
- For Sight Zone requirements refer to 29.28.150 of the TEDS Manual.
- From 23 1/2 road to Highway 6 & 50, the ditch along the North side will need to be piped.
- 24 road to 23 1/2 road is existing. Only requirement is to install meandering sidewalks, along the North side of 24 road to 23 3/4 road mimicking the sidewalk to the west.
- 25 1/2 to 25 has developable ground in place of the channel.
- As ROW varies in G road segments so does the width of the vegetated buffer.
- The trail on the South side of Leach Creek is part of the active transportation corridor.
- Vertical elements required in the buffer zone between the travel lane and bike lane to satisfy the
  condition of a protected bike lane (PBL) when speed is => 40 mph. Buffered bike lane (without
  vertical elements) may be acceptable when <40 mph or a parallel trail with a width of 10 feet or
  more is provided.</li>
- \* At approximately 24 1/4 road Leach Creek moves South, the detached sidewalk is required on the South side of G road.
- \*\* Where Leach Creek is adjacent to G Road, the south right of right-of-way line shall be established 6" north of the top of the bank.

# **Trail/Pathway**




Trail/Pathway												
A B C D												
Туре	Ownership	Width	Subgrade/Base Width	Shoulder	Railing							
Trail	Right of Way, Tract, or Public Easement	Varies	Width of Trail + 12"	2.5 Base Course or Landscaping	42" High							
Pathway	HOA Tract with Public Easement	6	7	2.5 Base Course or Landscaping	42" High							

- A Trail/Pathway shall be designed in accordance with the AASHTO "Guide for the Development of Bicycle Facilities" current edition.
- A minimum width of 8' may be allowed were physical constraints preclude the standard width.
- Trail/pathway has a maximum slope of 2%.
- Shoulder has a max slope of 6:1.
- Where slopes exceed 3:1 and E>2' a railing is required.
- Drainage should be designed for 2 year storm.
- If the trail/pathway is along an Active Transportation Corridor or is near a high volume destination like a school or hospital, a 12 foot width may be required to meet demand and mitigate conflicts between bicyclists and pedestrians..
- Refer to Zoning and Development Code for fencing requirements.
- Trails/pathway shall be a minimum of 4" of concrete on 6" of class 6 base course on 6" of reconditioned subgrade.



NOTES: CENTER OF CUL-DE-SAC NEED NOT BE ON CENTER LINE OF STREET. EDGE OF CONCRETE GUTTER \_ RIGHT-OF-WAY LINE \_ 6" WIDTH VARIES DEPENDING ON -ON OPTION CHOSEN -R=30' TO CURB FACE WIDTH VARIES DEPENDING ON ON OPTION CHOSEN CUL-DE-SAC TURN AROUND - MIN. DIMENSIONS - COMMERCIAL/INDUSTRIAL COURT



THE NOTES BELOW PERTAIN TO THE STANDARD CONTRACT DOCUMENTS FOR CAPITAL IMPROVEMENTS CONSTRUCTION:

- SAW CUT LONGITUDINAL CONTRACTION JOINTS SPACED AT 1/3 PAVEMENT WIDTH. (SEE DETAIL ON PAGE C-29)
- 2 SAW CUT TRANSVERSE CONTRACTION JOINTS AT 10' SPACING (SEE DETAIL ON PAGE C-29)
- (3) SEE PAGE C-06 FOR EXPANSION JOINT SPACING.
- 4 ALL EXPANSION AND CONTRACTION JOINTS SHALL BE SEALED IN ACCORDANCE WITH DETAILS ON PAGE C-28.
- (5) PCC PAVEMENT SHALL BE DESIGNED IN ACCORDANCE WITH THE AASHTO GUIDE FOR DESIGN OF PAVEMENT STRUCTURES.



# PEDESTRIAN & BICYCLE ANALYSIS WORKSHEET

# IMPACTED PEDESTRIAN & BICYCLE FACILITIES

Question	Yes/No	If answered YES, please describe.	Identify mitigations (where applicable)
Does the proposed land use			
change existing pedestrian or			
bicycle facilities?			
Is the land use on or adjacent			
to a proposed bicycle facility			
identified in the Pedestrian &			
Bicycle Plan?			
Does the project conflict with			
a proposed bicycle facility			
identified in the Pedestrian &			
Bicycle Plan?			
Is the site within an existing or			
proposed shared			
micromobility zone? If so,			
does the site plan include			
dedicated space for storage of			
shared bicycles and scooters?			
Is the project within an overlay			
zone? If so does it comply			
with pedestrian and bicycle			
elements of the overlay zone?			

DATE:

TRANSPORTATION PLANNER/ENGINEER:



# **APPLICATION**

# **Transportation Engineering Design Standards (TEDS) Exception** Request

City File No.	.: <u>TED-</u>	(To be filled in by City Staff)
Project	t:	
Site Address	s:	
1		
Date	<b>:</b> :	
Parent Project	t:	
Projec	t Name:	
City F	File No.:	
1. <u>Ref</u> e	erenced cha	apter in TEDS and a brief description of the request(s)
Request #1 -		
Request #2 -		
Request #3 -		
2. Site Description	<u>on</u>	
REQUEST #1 -		
A. Description	ı:	
B. Exception	Consideration	ons
1. How wi	ill the excen	otion affect safety?



2. Have other alternatives been considered that would meet the standard?
3. Has the proposed design been used in other areas?
4. Will the exception require CDOT or FHWA coordination?
5. Is this a one-time exception or a request to change the TEDS manual?
REQUEST #2 -
A. Description:
B. Exception Considerations
1. How will the exception affect safety?
2. Have other alternatives been considered that would meet the standard?
3. Has the proposed design been used in other areas?
4. Will the exception require CDOT or FHWA coordination?
5. Is this a one-time exception or a request to change the TEDS manual?
REQUEST #3 -
A. Description:
•
B. Exception Considerations
1. How will the exception affect safety?



- 2. Have other alternatives been considered that would meet the standard?
- 3. Has the proposed design been used in other areas?
- 4. Will the exception require CDOT or FHWA coordination?
- 5. Is this a one-time exception or a request to change the TEDS manual?



#### **APPLICATION INSTRUCTIONS**

# Transportation Engineering Design Standards (TEDS) Exception Request

Submit the application and associated drawings, in electronic format, using the following instructions.

City File No.:	(To be filled in by City Staff)
Project:	Fill in all lines in this section unless otherwise noted
Site Address:	
Applicant:	
Representative:	
Date:	
Parent Project:	
Project N	ame:
City File	No.:

# 1. Referenced chapter in TEDS and a brief description of the request(s)

Cite the section of TEDS for which the exception is being sought and briefly state what the request is. Examples are shown below:

Request #1 - Chapter 29.12.040 - Allow backing into the right of way

Request #2 - Chapter 29.20.060(b)- Reduce the centerline radius of a street

Request #3 - Chapter -.

# 2. Site Description

Describe the site in detail as necessary to explain the project and the TEDS exception request(s). Include a description of surrounding properties and access points when necessary. There should be plenty of detail in this section. Better to include too much than not enough.

Include pictures and drawings as necessary. NOTE: aerial pictures from the City's GIS system, including contours, can be copied and pasted into the document. <a href="www.gicity.org">www.gicity.org</a>

For each TEDS exception request, please complete A and B below



# **REQUEST #1**

# A. Description

Describe the request in detail using the applicable section(s) of the TEDS. Why should this request be granted? What does it do for the project? Describe problems created by not granting the TEDS exception; Why can't the TEDS requirement be met? Describe benefits created by granting the TEDS exception.

# B. Exception Considerations

- 1. How will the exception affect safety?

  Do you believe the exception will compromise safety? If not, explain why and be specific.
- 2. Have other alternatives been considered that would meet the standard? Show as many alternatives as possible including those that meet TEDS. This is critical. Think out of the box. The committee will ask questions like "Can they buy an adjoining parcel and design it to meet TEDS requirements?"

# Include pictures and drawings.

Any applications submitted without examples will be returned. Only in rare instances are there requests that don't have alternatives.

- 3. Has the proposed design been used in other areas?

  Describe how this request has been used in other areas; here or in other locales.

  Be sure to describe the advantages or disadvantages seen in these areas.

  Pictures and drawings would be helpful.
- 4. Will the exception require CDOT or FHWA coordination? "No" or "Yes" and a description of what the agency will be looking for.
- 5. Is this a one-time exception or a request to change the TEDS manual? Explain if this is a one-time exception or if you think the TEDS manual should be modified to allow this request permanently.

REQUEST #2 —Provide complete information for each request as shown for REQUEST #1 above.



# TRANSPORTATION IMPACT STUDY BASE ASSUMPTIONS

Project Information				
Project Name				
Project Location				
TIS Assumptions				
Study Area Boundaries	North:		South:	
	East:		West:	
Study Years				
Future Traffic Growth Rate				
Study Intersections	1.All Access 1	Drives	2.	1
	3.		4.	
	5.		6.	
	7.		8.	
Time Period For Study	AM	PM Sat N	oon	
Trip Generation Rates				
Trip Adjustment Factors	Pass by:		Captive Market:	
Overall Trip Distribution	North	South	East	West
Mode Split Assumptions		1	1	
Committed Roadway Improvements				
Other Traffic Studies				
Areas Requiring Special Study				

DATE:

TRANSPORTATION ENGINEER:

#### Proposed Changes to TEDS Related to Pedestrian/Bicycle Plan References

From commissioner Ehler's September 22, 2022 Email.

"My question stems from page 85 of the Bike/Ped plan (see screen capture below) which appears to be a relevant to our Land Development Code Update as a result of the pending TEDS update because of how the Land Development Code states the design criteria of the TEDS must be implemented and, in turn, the TEDS states the elements of the Bike/Ped Plan must be implemented. For example, below is a list of some of the Sections in the new TEDS update that seem to effectively codify and mandate all the elements of the Bike/Ped immediately upon the approval of the TEDS:

- a. Section 29.08.160 Site Design and Circulation Evaluation.
- b. Paragraph 3 of 29.04.010 Street Classifications and Standards
- c. 29.08.050 Pedestrian & Bicycle Analysis
- d. Paragraph 3 of 29.08.110 Description of Existing Transportation System
- e. The last sentence of the first paragraph of section 29.08.160 Site Design and Circulation Evaluation
- f. 29.20.030 Block and Lot Dimensions. Refer to the Zoning and Development Code for block and lot dimension requirements.
- g. 29.20.100 Bicycle Treatments
- h. 29.20.190 Pedestrian Treatments
- i. 29.48.010 Planning and Implementation"

Staff has reviewed the sections outlined above and proposes the following revisions (additions are <u>underlined</u>, deletions are shown as <u>strike-through</u>). Ther is a clean version of the proposed changes on the last two pages of this document.

a. Section 29.08.160 Site Design and Circulation Evaluation.

The project shall be analyzed to determine if the proposed circulation serves pedestrians, bicyclists and vehicles. The site design shall be evaluated to determine if facilities for vehicles, pedestrians and bicycles are consistent with the location and facility type as shown in the Pedestrian and Bicycle Plan. meet design standards and/or Codes. The project shall comply withthe adopted Pedestrian and Bicycle Plan.

- b. Paragraph 3 of 29.04.010 Street Classifications and Standards

  The Pedestrian and Bicycle Plan is referenced throughout this manual for compliance with the adopted plan. The existing and proposed routes in the Pedestrian and Bicycle Plan can be seen in the Pedestrian and Bicycle Plan layer on the Grand Junction GIS Transportation Map. Existing trails and bike routes can be seen in the Trails layer on the Grand Junction GIS Transportation Map.
  - c. 29.08.050 Pedestrian & Bicycle Analysis (paragraph after list "For bicycle infrastructure")

For bicycle infrastructure:

- (a) Presence of a bicycle facility and type of facility as shown and defined in the Pedestrian and Bicycle Plan) (Bicycle facilities are defined by the Pedestrian and Bicycle Plan and described in section 29.48 Transit, Bicycle, and Pedestrian Facilities of the TEDS Manual.)
- (b) Width of the bicycle facility and width of the buffer if applicable

The Pedestrian & Bicycle Plan shall be referenced and complied with for planned pedestrian and bicycle facilities within the study area boundaries. Pedestrian and bicycle standard widths and buffers by street type or context can be found in Chapter 29.20 for Local, Industrial, and Commercial Streets, and 29.28 for Collector and Arterial Streets, and Trails.

d. Paragraph 3 of 29.08.110 Description of Existing Transportation System
The TIS shall describe the existing bicycle and pedestrian facilities <u>as defined in Section 29.48</u>
(Transit, Bicycle and Pedestrian Facilities) and shall include any facilities <u>directly adjacent to the project site and within one-quarter mile or as described in Section 29.08.050 The Pedestrian and Bicycle Analysis \*section. The Pedestrian & Bicycle Plan shall be referenced and complied with for planned pedestrian and bicycle facilities within the study area boundaries.</u>

Bicycle facilities are defined by the Pedestrian and Bicycle Plan and described in section 29.48 Transit, Bicycle, and Pedestrian Facilities of the TEDS Manual.

e. The last sentence of the first paragraph of section 29.08.160 Site Design and Circulation Evaluation

The project shall be analyzed to determine if the proposed circulation serves pedestrians, bicyclists and vehicles . The site design shall be evaluated to determine if facilities for vehicles, pedestrians, and bicycles meet design standards and/or Codes. The project shall comply with the adopted Pedestrian and Bicycle Plan. The project shall be evaluated to determine and if traffic flows are properly designed. Proper design shall minimize areas where motorists would tend to speed, minimize potential conflict areas between vehicles and pedestrians/bicyclists, and to establish circulation patterns that avoid unnecessary traffic congestion, cut-through traffic, and conflict points. Adequate throat lengths for on-site stacking at exit points is required (see 29.16.100). At signalized driveways, the HCM 90th percentile worst lane queue model shall determine the necessary storage. Businesses with drive-thrus must conduct a queuing analysis for the drive-thru to demonstrate that the queue will not extend back onto the public street.

f. 29.20.030 Block and Lot Dimensions. Refer to the Zoning and Development Code for block and lot dimension requirements.

Refer to the Zoning and Development Code for block and lot dimension requirements.

Guide for Development of Bicycle Facilities.

No change recommended by staff. This refers to ZDC regulations, which is where block and lot dimensions should live since they are subdivision standards.

g. 29.20.100 Bicycle Treatments

The location and type of bicycle facilities shall be consistent with provided, in accordance with refer to the adopted Pedestrian and Bicycle Plan. The design of the bicycle facilities shall comply Section 29.48. Provisions for bicycle facilities shall be in accordance with the current version of the AASHTO

The standard cross-section of off-street multi-use trails is included. Refer to Chapter 29.48 for design guidance on bicycle facility types, and minimum adherence standards. Refer to the NACTO Urban Bikeway Design Guide and the FHWA Separated Bike Lane Planning and Design Guide for additional guidance on designing bikeway facilities identified in the Pedestrian and Bicycle Plan.

#### h. 29.20.190 Pedestrian Treatments

In order to provide pedestrian safety, comfort, and access, accommodations for pedestrians shall be designed into all intersections per Section 29.28.110; and in accordance with the Pedestrian and Bicycle Plan. This including sidewalks, crosswalks, pedestrian refuge islands and accessible ramps. The design shall conform to the standards set forth by the Americans with Disabilities Act and meet the details specified in the Grand Junction Standard Contract Documents for Capital Improvements Construction.

#### i. 29.48.010 Planning and Implementation

Transit, bicycle, and pedestrian facilities are an integral part of the transportation system. This chapter establishes how to plan and implement these facilities. \*\*ITransit\*, bicycle and pedestrian accommodations shall be addressed in transportation impact studies as \*\*set forth\* discussed in Chapter 29.08. Additionally, the provision of transit, bicycle, or pedestrian facilities or easements for such facilities may be required as part of the development review process in order to facilitate multimodal circulation and access through or adjacent to the development. Refer to consistent with the Mesa County Transit Design Standards and Guidelines, existing or planned transit routes, and the Pedestrian and Bicycle Plan \*\*for guidance\*. Section 29.16.230 provides requirements for interparcel circulation of walkways and bikeways to facilitate multimodal circulation.

a. Section 29.08.160 Site Design and Circulation Evaluation.

The project shall be analyzed to determine if the proposed circulation serves pedestrians, bicyclists and vehicles. The site design shall be evaluated to determine if facilities for vehicles, pedestrians and bicycles are consistent with the location and facility type as shown in the Pedestrian and Bicycle Plan.

b. Paragraph 3 of 29.04.010 Street Classifications and Standards

Staff recommend deleting this section.

c. 29.08.050 Pedestrian & Bicycle Analysis (paragraph after list "For bicycle infrastructure")

For bicycle infrastructure:

- (a) Presence of a bicycle facility and type of facility as shown and defined in the Pedestrian and Bicycle Plan) (Bicycle facilities are defined by the Pedestrian and Bicycle Plan and described in section 29.48 Transit, Bicycle, and Pedestrian Facilities of the TEDS Manual.)
- (b) Width of the bicycle facility and width of the buffer if applicable

Pedestrian and bicycle standard widths and buffers by street type or context can be found in Chapter 29.20 for Local, Industrial, and Commercial Streets, and 29.28 for Collector and Arterial Streets, and Trails.

- d. Paragraph 3 of 29.08.110 Description of Existing Transportation System The TIS shall describe the existing bicycle and pedestrian facilities as defined in Section 29.48 (Transit, Bicycle and Pedestrian Facilities) and shall include any facilities described in Section 29.08.050.
  - e. The last sentence of the first paragraph of section 29.08.160 Site Design and Circulation Evaluation

The project shall be analyzed to determine if the proposed circulation serves pedestrians, bicyclists and vehicles and if traffic flows are properly designed. Proper design shall minimize areas where motorists would tend to speed, minimize potential conflict areas between vehicles and pedestrians/bicyclists, and to establish circulation patterns that avoid unnecessary traffic congestion, cut-through traffic, and conflict points. Adequate throat lengths for on-site stacking at exit points is required (see 29.16.100). At signalized driveways, the HCM 90th percentile worst lane queue model shall determine the necessary storage. Businesses with drive-thrus must conduct a queuing analysis for the drive-thru to demonstrate that the queue will not extend back onto the public street.

f. 29.20.030 Block and Lot Dimensions.

Refer to the Zoning and Development Code for block and lot dimension requirements.

No change recommended by staff. This refers to ZDC regulations, which is where block and lot dimensions should live since they are subdivision standards.

#### g. 29.20.100 Bicycle Treatments

The location and type of bicycle facilities shall be consistent with the Pedestrian and Bicycle Plan. The design of the bicycle facilities shall comply Section 29.48.

#### h. 29.20.190 Pedestrian Treatments

In order to provide pedestrian safety, comfort, and access, accommodations for pedestrians shall be designed into all intersections\_per Section 29.28.110; including sidewalks, crosswalks, pedestrian refuge islands and accessible ramps. The design shall conform to the standards set forth by the Americans with Disabilities Act and meet the details specified in the Grand Junction Standard Contract Documents for Capital Improvements Construction.

### i. 29.48.010 Planning and Implementation

Transit, bicycle, and pedestrian facilities are an integral part of the transportation system. This chapter establishes how to plan and implement these facilities.

# Response to Public Comments received on the Draft Transportation Engineering Design Standards (TEDS) Update Manual

Comment No.	Listening Tour/Developers Roundtable/Public Comments ITEM/ISSUE/CONCERN	TEDS UPDATE PROPOSAL	CITY PROPOSED RESOLUTION/RESPONSE
1	<ul> <li>Sidewalk specification requirement – proposed 6' versus current 4' on local streets.</li> <li>Pedestrian volume is low and the public doesn't complain to builders about 4' wide sidewalks.</li> <li>Require only at higher volume locations. This lowers cost in housing and city long term maintenance costs.</li> <li>Perhaps only require the wider width on one side of the street.</li> <li>Proposal exceeds CDOT minimum 5' sidewalk standard.</li> <li>What is the additional benefit of the 6' sidewalk and is it worth the added home cost?</li> <li>Continued interest in narrower sidewalk widths, even with 200' passing area.</li> <li>Want more options based on volumes. Create a hierarchy of standards.</li> </ul>	The Pedestrian and Bicycle Plan establishes that local streets should provide a 6' wide sidewalk to provide for an acceptable (LOS) level of traffic stress of 2 or less on all local streets and low speed collector streets.	<ul> <li>Level of acceptable traffic stress was key in the Pedestrian and Bicycle Plan (PBP) study. This was determined through public engagement and industry standards.</li> <li>It is difficult for two people side by side, a pedestrian to pass a wheelchair or baby stroller, etc. on a 4' sidewalk.</li> <li>Sidewalk encroachments such as landscaping and side mirrors on vehicles often reduce the effective area of the sidewalk width.</li> <li>In addition, the PBP proposes 6' based on NACTO to meet the LOS 2 criterium.</li> <li>The TEDS update proposes multiple street options that provide the ability for narrower streets.</li> <li>Constructing different Sidewalk widths will be troublesome during construction.</li> <li>Pedestrian volume will remain low as long as the facilities are substandard (a width where citizens choose to not use them due to the level of stress).</li> <li>The expected minimum standard is 6', however a developer can request an exception and narrow to 5' sidewalks in a constrained environment if justified.</li> <li>A note has been added to the residential street section saying an exception request can be considered for sidewalks under 6' width within a constrained environment and/or where low volume of 10 peak hour vehicular trips or less can be shown and no through access is provided or planned.</li> </ul>
2	<ul> <li>Issue: Right-of-Way size regulations and parameters.</li> <li>Want further review and benchmark comparable cities.</li> <li>Concern this reduces available land contributing to sprawl and decreases density.</li> </ul>	Most street sections will see a wider roadway. However, for local streets, many options are available.  • Local Street (currently 44') – options vary between 38' to 63' in total ROW width.	City researched peer cities. Proposed Sections are now benchmarked to peer Cities, see graph below:

Comment No.	Listening Tour/Developers Roundtable/Public Comments ITEM/ISSUE/CONCERN	TEDS UPDATE PROPOSAL	CITY PROPOSED RESOLUTION/RESPONSE
	<ul> <li>How do we know which ROW to give on Maj. Collector? Speed criteria +/- 35MPH</li> <li>Current Impact Fee structure does not reflect these sections.</li> </ul>	<ul> <li>Minor Collector (currently 52')/ Local Commercial (currently 52')         <ul> <li>change to 64' ROW width.</li> </ul> </li> <li>Industrial Street (currently 48') – change to 55'.</li> <li>Collector (currently 60') – change to 70'-78' ROW width.</li> <li>Minor Arterial (currently 80') – change to 100' ROW width.</li> <li>Principal Arterial (currently 110')         <ul> <li>no change, continues to be</li> <li>110' ROW width.</li> </ul> </li> </ul>	At General Meeting staff will determine Major vs Minor Street section for proposed development.      The current impact fee structure does not reflect these sections, however the City will study impact fees in 2024.      Flexibility of zoning code requirements will minimize the reduction of any density limitations for new development.
3	Concern with what is required for Minimum Access to new development and what those standards will be.  Can paths be used for fire access.  Concern about ownership of these paths.  Will fencing be restricted along path corridors?	Requirement for a 6' path between subdivisions when existing or proposed street connections are greater than 750' apart. Path connections may occur off the end of cul-de-sacs.	<ul> <li>The path will be called "pathway" and has been reduced in width from 10' to 6', and the easement width has been reduced from 15' to 11'.</li> <li>Fencing along pathways will be regulated by the Zoning and Development Code.</li> <li>Pathways will be constructed in tracts owned by the HOA. This is already established practice.</li> <li>The new 11' easement width will accommodate the ability to replace concrete in the future, a concern raised by the Technical Advisory Committee.</li> <li>The Block length and pedestrian block length are being removed from TEDS and will become part of the ZDC.</li> </ul>

Comment No.	Listening Tour/Developers Roundtable/Public Comments ITEM/ISSUE/CONCERN  Traffic Study Requirements  • Knowing the information upfront is most helpful – add as an agenda item on General Mtg.  • Clearly identify what level of effort is required on each question so the checklist does not become subject to interpretation.  • Incorporate ped/bike analysis only and clarify that the pedestrian/bike evaluation does not need to be completed by a traffic	TEDS UPDATE PROPOSAL  New traffic assessment for between 10 and 100 peak hour trips.	CITY PROPOSED RESOLUTION/RESPONSE  The assessment is for peak hour trips which is a minimum of 10 houses.  The language has been changed from "shall" to "may require" the assessment. Approach is not to require a study if it won't tell anything new.  The proposed checklists have been revised for clarification.  Staff will identify what is required and the level of effort with the applicant at the general meeting.  The pedestrian/bike evaluation does not need to be performed by a traffic engineer.
5	engineer.  Pathway illumination Standards  Handle like normal streetlights.  What are the spacing requirements between lights? Need a standard.  In practice, this likely creates an inconsistent variety of lighting types.  HOA's are often unreliable for maintenance, and this exceeds the role of private development.  Make solar lighting an option.  Request dedicating tract to City for city to maintain pedestrian lighting.	HOA to install and maintain bollard type lights for pathways.	<ul> <li>City pays for regional trail facilities.</li> <li>It is not uncommon for an HOA to be responsible for lighting within their subdivisions. Note, Mesa County requires the HOA to pay for street lighting.</li> <li>The installation of commercial grade Solar lights is permissible and may be a good option.</li> <li>Strategically orienting streetlights to illuminate pathways or portions of pathways can help reduce costs.</li> <li>Establishing a citywide standard for light spacing may actually cost more for a proposed development than creating a site-specific lighting plan for a that development.</li> </ul>
6	Increase the current Cul-de-sac length from 750 feet to 1000 feet.	The TEDS update proposes keeping the maximum Cul-de-sac length at 750'.	This standard has been left at 750'. The developer can always request a TEDS exception. This allows context evaluation. After discussing with the development community, they are okay with keeping this as it has been.

Comment No.	Listening Tour/Developers Roundtable/Public Comments ITEM/ISSUE/CONCERN	TEDS UPDATE PROPOSAL	CITY PROPOSED RESOLUTION/RESPONSE
7	Can the number of dwelling units on a Shared Drive be expanded from 5 to 7?	Not in TEDS, include in Zoning and Development Code Update.	The number of dwelling units accessing a shared driveway is set forth in the Zoning and Development Code (ZDC). Staff is now proposing as part of the ZDC update to eliminate the number of units but keep the length of the shared drive at 150'. Parking pods may be required as part of the development of homes on a shared drive.
8	What is the expected width of Paths and Trails, 10' or 12', 8' if constrained?	Pathways and trails are pedestrian and bicycle facilities for connections between subdivisions, the end of cul-desacs and neighboring streets, etc. and for Active Transportation Corridors (ATC).	The pathway has been separated out from trails and therefore the TEDS Update is now establishing trails at 10', except 12' in high volume areas. The minimum width is 8' in constrained areas. The 10' width standard is needed to accommodate the multi-use of bikes, rollers and pedestrians sharing the trail. These standards apply to all ATC's. Pathways connect subdivisions to surrounding streets and in some cases from the end of a cul-de-sac, they are now proposed to be 6' in width.
9	What is the policy for upgrading existing infrastructure? TEDS does not address this.  • Will new developments have to remove attached sidewalk and install detached sidewalk when developing a new a site along an existing street when the street section requires it?  • Or have to expand sidewalk width of an existing sidewalk when the street section calls for it?	This is specifically addressed in the introduction of TEDS, Section 29.01.010 Forward under Applicability.	Generally recent street construction within new development would be expected to remain as it was constructed prior to the adoption of this revised TEDS. To formalize these conditions the TEDS manual has established language permitting the City to issue a deviation. TEDS Section 29.01.010 Forward under Applicability states "Infill development within the City of Grand Junction Urban Development Boundary may be constrained by existing improvements. If such a condition exists an affirmative waiver of TEDS shall be required in accordance with Chapter 29.64.010. The City and County may approve a deviation from these standards only when and if the deviation is shown to be warranted and safe."
10	Allow for the construction of streets in new development without sidewalks on local streets.	The TEDS update requires sidewalk along all local streets within new development.	<ul> <li>The Pedestrian and Bicycle Plan recommends a minimum of 6 feet for sidewalk infrastructure for all new local streets constructed.</li> <li>Sidewalks provide accessibility and greater safety for all users.</li> <li>The level of traffic stress is reduced when sidewalks are constructed at 6' widths permitting all users including pedestrians, rollers and bicycles to use them.</li> </ul>

Comment No.	Listening Tour/Developers Roundtable/Public Comments ITEM/ISSUE/CONCERN	TEDS UPDATE PROPOSAL	CITY PROPOSED RESOLUTION/RESPONSE
11	Lighting plans for public streets, need to provide spacing criteria on all streets.	TEDS provides spacing of streetlights on local residential streets and provides standards for illuminance on other street classifications.	Variation in street widths and fixtures (over time) requires an illuminance plan. The City is currently performing a study to determine if it makes sense for the City to take over street lights from Xcel and GVP.
12	Pedestrian Bicycle Plan (PBP) didn't survey non-biking public	Not in TEDS.	<ul> <li>Nationally, FHWA estimates 65% of the population is underserved by existing conditions.</li> <li>WHICH FACILITIES WILL MAKE RIDERS FEEL SAFER?</li> <li>The pedestrian and Bicycle Plan (PBP) surveyed both biking public and non-biking public.</li> <li>Of 669 Surveys, 23% of the survey respondents listed Bikes as the mode they typically take, 72% use a personal vehicle.</li> <li>95% said they would like to walk or roll or bike more often or for more types of trips than they currently do.</li> <li>Biggest walking challenges identified – 1) nonexistent or insufficient sidewalks and 2) streets are uncomfortable or unsafe to walk along.</li> <li>Biggest biking challenges identified include streets are uncomfortable or unsafe to walk along.</li> <li>For walking/rolling/biking to school 34% said they did, 51% take a personal vehicle. School bus only 9%.</li> <li>Study findings: Total 347 ped (125) /bike (222) crashes between 2016 and 2020. 42 crashes led to severe injury or death. That's one crash every 5 to 6 days.</li> </ul>

Comment No.	Listening Tour/Developers Roundtable/Public Comments ITEM/ISSUE/CONCERN	TEDS UPDATE PROPOSAL	CITY PROPOSED RESOLUTION/RESPONSE
13	Increased cost and impact on affordable/attainable housing, shouldn't a cost/benefit analysis be conducted?	TEDS doesn't address the cost/benefit of development infrastructure with the cost of housing.	<ul> <li>The Pedestrian and Bicycle Plan (PBP) provided the analysis of community need for safe/low stress pedestrian and bicycle facility needs in the community. Participants in the planning process provided input on what they saw as the important needed infrastructure that would permit them to utilize nonmotorized transportation, thus reducing their personal transportation costs.</li> <li>Reduce the number of cars a household has to maintain can reduce transportation costs if other nonmotorized modes of travel are available, safe and doable.</li> <li>Typically, a person spends approx. ¼ of personal income on Transportation.</li> <li>Providing citizens with transportation options helps lower personal transportation costs which helps them in meeting their housing costs.</li> <li>See discussion from local survey, (next row).</li> </ul>
14	Traffic Calming, previous implementation of this in new development was not effective.	Required if a straight street is longer than 600'.	<ul> <li>Narrower street options will help limit speed without specific measures.</li> <li>Bulb outs, chokers, and mini roundabouts are effective if done well. Local examples (Spanish Trail subdivision) bear this out.</li> <li>Curvilinear streets can be used to help slow traffic.</li> <li>Recommend densely parking on only one side of street for narrower street section to lower speeds and costs. This can be accomplished using some of the local street sections permitted.</li> </ul>
15	Why require landscaping islands in parking pods located off alleys?	A parking lot endcap landscape island has been required.	The TEDS update proposes to remove the requirement of an endcap for parking along alleys.
16	All paths have to be concrete	All Active Transportation Corridors (ATCs), sidewalks, and pathways shall be constructed with concrete.	A development can propose paths within their own HOA open space system that are not concrete. It is only ATCs, sidewalks within the public ROW, and pathways connecting between streets and from cul-de-sacs, for public use, that are required to be concrete. Other treatment types on surfaces areas such as asphalt have not fared as well with buckling and general maintenance is a larger issue.

Comment No.	Listening Tour/Developers Roundtable/Public Comments ITEM/ISSUE/CONCERN	TEDS UPDATE PROPOSAL	CITY PROPOSED RESOLUTION/RESPONSE
17	Landscaping in cul-de-sacs/parking pods	Not in TEDS, include in Zoning and Development Code Update.	Example 1 (The Legends)  Example 2 (Summerhill)
			Two general sizes have occurred in the city with Example 1 (The Legends subdivision example) fitting within a standard cul-de-sac and Example 2 (Summerhill Subdivision example) needing a larger area for the parking area. Proposed to not require landscaping for Example 1 and to require landscaping for Example 2. These options will be proposed with the Zoning and Development Code Update.





City of Grand Junction Community Development Department,

Thank you for the opportunity to comment on the proposed TEDS revision. We greatly appreciate the extension of the original public comment period, which provided valuable time to formulate constructive feedback in support of the highest quality outcome for the public.

We commend the department's efforts to create increased flexibility in the plan, modernize standards, and implement the bike and pedestrian plan.

As representatives of the Grand Junction Area Realtors Association and Housing and Building Association of Western Colorado, we represent a coalition of over 300 design, engineering, and development professionals and over 900 real estate professionals collectively employing thousands of local citizens.

We're confident that the inclusion of technical expertise informed by this depth of experience will help guide adoption of a plan that functions as intended in fully implementing the core values identified through the planning process. It is our shared vision to facilitate the enactment of standards consistent with the spirit of those guiding principles.

After our initial review, we've prepared comments on a number of items in the current TEDS draft as practical considerations that would fortify the plan, protect against the potential for unforeseen consequences, and ultimately ensure successful implementation for the benefit of our present and future community.

We place particular emphasis on three elements of the draft TEDS plan:

- Right of Way Size Regulations, Parameters, and Variances
- Minimum Access Standards
- Traffic Study Requirements

Two additional elements also warrant consideration:

- Pathway Illumination Standards
- Sidewalk Specification Requirements

The proposed form of each of these elements reflects efforts to achieve commendable goals, but also presents concerns of technical feasibility, outcomes counter to the identified values, and negative impacts on housing affordability.

In each instance, our comments identify alternatives or the need for further clarity to address these concerns while preserving the original ambition of the goals.

Grand Junction Area REALTOR® Association 2473 Crossroads Blvd. Grand Junction CO 81506 970.243.3322

Housing and Building Association of Western Colorado 569 S. Westgate Dr, Unit 3 Grand Junction Colorado81505 970.852.5707





#### **Public Comments**

# Right of Way Size Regulations, Parameters, and Variances

#### Concerns

- Reduces quantity of land available for the creation of housing inventory, which will increase costs, decrease density, and contribute to sprawl with traffic and commuter impacts.
- Although we appreciate the flexibility provided by the several potential variances, their use would essentially shift interior boundaries.
- Implementing this standard is impractical in scope and lacks technical feasibility. Implementation in existing, developed corridors would require substantial and costly land acquisitions, particularly for infill, and will reduce existing housing inventory.

#### Comment

• We would like to see further review of the right of way requirements in consideration of emerging trends, as this proposal would benefit from clarity and data benchmarked to standards, impacts, and outcomes adopted by comparable communities.

### **Minimum Access Standards**

#### Concerns

• These standards need general clarification regarding the definition of minimum access and what specifications are required to meet the stated goal of connectivity.

#### Comment

- Additional technical clarity is required, and references to similar levels of required access in comparable jurisdictions would serve as a useful point of reference.
- For most infrastructure development, there is a tier based system to determine the size of streets, waterlines, etc. A tier based system should also be established for pathways based on the size of the development, particularly in areas where connectivity is already achieved and secondary access has been established for fire vehicles.





# Public Comments (continued)

# **Traffic Study Requirements**

#### Concerns

The proposed requirement for traffic impact studies (TIS) of developments that generate between 10 and 99 ADUs is needlessly low, and the lower threshold of 10 peak hour trips could easily be achieved by a single home with one house multiple drivers or bicyclists, which will increase development costs and decrease affordability.

#### Comment

• The current traffic study requirements in the existing TEDS should be maintained, but with an addendum for estimating impacts to bicycle and pedestrian traffic. This would incorporate bike and pedestrian considerations while mitigating higher costs.

# **Pathway Illumination Standards**

#### Concerns

- The draft proposes an uncommon management structure in which responsibilities are assigned to HOAs, private development, or not defined clearly.
- HOAs are unlikely to reliably manage illumination, while assigning responsibility to development in perpetuity is unusual and exceeds the role of private development.
- This structure is likely to create an inconsistent variety of lighting types and specifications.

### Comment

 Apply the current system for local street lighting to pathway illumination to ensure reliability, simplicity, and consistency in type of lighting.





### Public Comments (continued)

# **Sidewalk Specifications**

#### Concerns

• The proposed standard requiring sidewalks 6 feet in width and on both sides of the street will remove excessive amounts of already limited land available for the creation of housing inventory, with minimal additional utility for multimodal usage.

#### Comment

• The six foot sidewalk requirement should be modified to be required only at higher vehicular volumes and on only one side of the street, with an emphasis on connectivity. This will lower costs in the creation of housing and also the City's long-term maintenance costs, leading to the creation of more affordable housing stock while still accommodating multimodal usage.

### **Additional Feedback**

The incorporation of this professional feedback will meaningfully improve the quality of the plan thanks to your gracious extension. That said, TEDS is a complex document that has not undergone a revision for many years, and the outcome would benefit from further review and refinement. We understand it may be challenging but with a plan of this magnitude, it's worth taking the extra time to get it right. We appreciate your collaboration to date, but respectfully request that you consider additional time for review.

If this additional time is granted, it will allow our professional community to provide several and more thorough contributions.. For example, we would:

- Explore how the new proposed standards complement or conflict with the latest trends in context-based development.
- Investigate experimentations and comparative models underway in front range communities that have already or previously incorporated multimodal uses and other additional values into their roadways and systems, so as for our Grand Junction to benefit from the best available data and practices as we tailor the right variables for our own community.

Additionally, we suggest that it would be mutually beneficial to convene a workshop between city staff and industry practitioners to further discuss our comments and opportunities to refine these standards.

Thank you again for offering these feedback opportunities to date. Please don't hesitate to contact our team with any questions, and we would be happy to serve as a resource throughout the remainder of the process.

We look forward to your response, and thank you for your consideration.

Submitted on behalf of the Grand Junction Area Realtors Association and Housing and Building Association of Western Colorado

Grand Junction Area REALTOR® Association 2473 Crossroads Blvd. Grand Junction CO 81506 970.243.3322

Housing and Building Association of Western Colorado 569 S. Westgate Dr, Unit 3 Grand Junction Colorado81505 970.852.5707

# The following are comments compiled and received by the City via email from the development community and interested parties.

### From Keith Ehlers on 6-29-23 via email

I've shared this with a few of you in conversation recently, but I hadn't done so in writing yet so here it is. The top two items at this stage that I'd like to see further vetting for in regards to the draft TEDs manual are:

- 1. Current development impact fees were influenced by the calculated cost of the existing cross sections and improvement requirements for roads, BUT if the new TEDS manual gets adopted before any responsible vetting of the additional cost implications of the expanded improvements being required is completed the TIF fees will automatically be out of alignment with every calculation that went into the 2019 nexus study and ultimately guided the impact fee implementation schedule that was approved by council and is utilized by the city manager and public works for budgetary planning. There are repeated comments about concern that the impact fees are currently only 75% of what is needed (based on the cost assessment of existing road cross sections), but the adoption of this TEDS policy would amplify the related budget shortfall. Can someone discuss this issue with me in detail please to help me understand what the thinking is and educate me on anything I may be missing?
- 2. If the new cross sections are consuming more right of way and requiring a detachment of sidewalks away from the vehicular activity then do we still need the same level of expensive landscape strips, buffers, and screening requirements that we currently require in our code? Perhaps there is a trade-off to be found here in which the private property owner may have to give up more land for ROW, but gets that's developable ground back through the relief of required landscape strips wherever detached walks are required since they inherently create a landscape strip between the roadway and the sidewalk. Does this question get addressed in the code update project or the TEDS project?

Thanks for your time on this.

-Keith

From Kevin Bray on 6-14-23

Rick, Trent, and Dave,

I like the idea of a drive lane that accommodates 2 way traffic. Its traffic calming and also keeps the space available for the fire trucks. I'm not sure I totally understand Fire's need for a second access. I thought we designed streets to have two firetrucks drive by each other at the same time. In that case one can be dropping a hose while the other is passing to drop the next. The 2<sup>nd</sup> access, if it was a path, would not need to be 20' width because there is not a hydrant or a home to service from that so whatever emergency vehicle would use it would then dump onto the residential road that had the proper width for the above scenario to unfold. Maybe you have a better explanation but I thought it would be a good trade-off if we are going to do a path(700' block rule) connection this should allow us to have some flexibility on longer cul-de-sacs and meeting second access requirements. In the example below, you can see that the drive lane is intended for two way traffic but I think it would/may require queuing. The presentation also brings up some good points about reducing the amount of asphalt/concrete that must be maintained.

For a good example of context-based multimodal street design I think the section of Mariposa that goes through residential neighborhood is a good example. A joint drive lane that does not have a middle stripe, allows for parking on the sides, and when pedestrians are in the street there is no psychological resistance to crossing the centerline and giving peds and bikers a wide space. I don't think that design is necessarily the best for mariposa as it serves very few residential homes and has a high design speed and more of a collector context, however, this was a practical and costeffective approach to providing some traffic calming and mitigating uncomfortable ped/bike/car relationship. Notice the local residential Pleateau drive is 35' wide and has many private signs up and down the street "Kids at play" "please slow down". I think we have an opportunity to explore whether sidewalks in residential neighborhoods create safety or if they create a contextual assumption that people are on the side, and the drivelane is a speedway for cars. We all grew up on streets with no sidewalks or narrow sidewalks. We played football and basketball in them, we rode our bikes in them, we walk in them comfortably. Is it possible that the separation is the problem? The street I live on is full 44' with sidewalk on both sides, its over 1,000' long with more lots than are currently allowed in a dead-end cul-de-sac. There is very little traffic but the cars that come through there are usually doing mach 10. It's a design issue. We should build neighborhoods that people drive through like campgrounds.

Also, see his email with embedded photos and a powerpoint presentation.

# From Kevin Bray on 7-17-23

Thanks Rick, I did hear Steve address the fire truck need in a roundtable I attended. Steve did a pretty thorough job and articulated well the need for the two lanes which I understand. I think the path would qualify as its not intended or needed to

provide the ability for two trucks to pass. I think you can come to the same conclusion or get with Steve if you need to. My comment is only to provide flexibility where it makes sense and can save the City and the consumer unnecessary costs.

## From Mark Austin on 7-13-23

TEDS Plan Comments from ACG:

- 1. This is just a general comment, but the Ped and Bike Plan is now significantly impacting the cost for projects. The concern I have is the vast majority of "input" and involvement on this plan was provided from the bicycle community and was it really a representation of the entire community? The bicycle community just scored a huge win because they really aren't having to pay for any of these improvements. It would seem to me that before fully embracing this Bike and Ped Plan, there needs to be a cost analysis study to determine the cost to implement this plan and method that funds the construction and maintenance of the plan. The reality is the City is the agency that is ultimately going to have to pay for these improvements because the vast majority are on collector-type streets. If the community really wants to fully embrace this plan, they must also provide the funding to do it. This is really no different than what the City just did for the Rec Center. All of the planning documents and "surveys" from the community said they wanted a Rec Center. However, the City didn't move forward with this until there was a way to pay for it. Why isn't this same approach being taken for the Bike and Ped plan?
- 2. Section 29.08.030 1<sup>st</sup> Paragraph, last sentence and Paragraph 2. This should state 100 PEAK HOUR trips, not 100 trips (this would be 10 houses).
- 3. Section 29.12.040, part B. A maximum of 4 parking spaces without an island is unrealistic, or even 8 spaces. Why is a landscape island needed in an alley? This is not the place for a landscape island. Please look at the Catholic Outreach projects along alleys in the 200 and 300 blocks south of Ute. Also look at 951 Main Street.
- 4. I'm concerned all of the new street sections and various ROW widths will be difficult to determine when and how much additional ROW a site plan approval project must dedicate. For the most part, most of the existing commercial lots already have curb and gutter along them and are generally located along a street that is a collector street and above. When the site wants to develop, is the City now going to require additional ROW dedication along these streets and then require the sidewalks for instance to be detached? Maybe this isn't an

issue for the sidewalk because it's a collector street, but which ROW section for a collector street will the developer have to follow? If it's up to them, it will be the one that has to give up the least amount of ROW.

- 5. The TIS requirement to do for Bike and Ped analysis is silly. Most of the streets and sidewalks don't have much ped or bike traffic, so why are we trying to measure this? It isn't going to tell anyone anything and what is going to be the basis to project future bike and ped usage? All this does is cost projects another \$2,000 for traffic study consultants that provides no real useful information. Every question on this checklist can be answered by the City's development engineer.
- 6. I can assure you the general public will use the Ped and Bike Analysis Worksheet to oppose every project that has a ped or bike facility along a collector roadway. A good example is the C-1/2 Road Gravel Pit. This project is currently pushed out by the Planning Commission because of the neighbors' complaints about inadequate bike and ped routes on C-1/2 Road. I can assure you the public will use the "stress" table maps to push their point once they understand how much this bike and ped plan drives the level of improvements required for a project approval.
- 7. Every project that has opposition will always raise the concerns that their roadways are too congested and can't handle the additional traffic, and the kids playing in the streets will be killed from the additional traffic generated by the proposed development. At least with a Traffic Study you can use ADT numbers to show the street has additional capacity to handle the development, but even with a Stamped Traffic Report, Planning Commission members will cave on this with enough public opposition at a hearing. Now you are going to have to say that it's ok that the kids playing in the street can't walk safely without a sidewalk and a bicycle can't travel down the road safely without having more pavement. We are setting ourselves up to get killed in public hearings, and the City will be the one getting yelled at because the streets are collectors.
- 8. Requiring individual lighting plans for all streets is another \$1,500 burden on EVERY SINGLE PROJECT. All that needs to be done is do the lighting analysis for the various street sections and you should be able to determine a "typical" light pole spacing to provide the lighting levels needed. This is even more ridiculous because Xcel Energy is the one providing and installing the light types and I seriously doubt they check to make sure the lighting analysis light fixture details and deflectors match the equipment they install and maintain. This is just not a realistic expectation.
- 9. Section 29.20.030 Providing pedestrian lighting on all ped paths and trails is extremely expensive for all projects.

- 10. Expecting HOA's to maintain pedestrian level lighting in subdivision projects is unrealistic. They can barely handle getting irrigation water to their homeowners, now you want to have them maintain and operate pedestrian level lights for the entire public to use on their property and they are the ones that have to pay for them? This makes no sense. If the lights are provided, they need to be turned over to the City to maintain and operate, just like the lights along the street. Pedestrian and Bike trails are now considered "multi-model" and therefore they should be treated just like a public street lighting system for vehicles.
- 11. It would seem to me the street options need to include the low stress vs high stress design requirements from the ped and bike plan. I still don't know what that means, but from what I understand, we have to now assess the Bike and Ped plan to determine the stress level, which then drives the required sections required.
- 12. I was not part of the ped and bike plan, but how did the low stress vs high street analysis in the bike and ped plan get developed? This level of stress analysis is now significantly impacting the cost to develop street sections, and most of these street sections are paid for by the City through taxes. Has anyone thought about how this is really going to be paid for?
- 13. Section 29.20.060 (c)—Bulb outs. Just about every local street section has street parking. Does this now mean that bulb outs are now required at every intersection on local streets?
- 14. Section 29.20.070 (B)— Why can't this be a 2% to 2%? Requiring vertical curves at Stop Control intersections is ridiculous. Anyone driving across a typical crowned street drives up and down a 2% crown all the time without a safety issue. All the vertical curve does is create complexities in construction that aren't needed.
- 15. Private driveway access locations should not be restricted to a maximum 4% grade.
- 16. Section 29.20.210/ 29.28.250 Traffic Calming. The City enforced this in the mid 2000 with chokers and tabletops in subdivisions. The reality is these really didn't do anything and so over time, this "requirement" went away. Is it now back? Did we not learn anything from the last time this was required?
- 17. G Road Section 70-ft ROW. Why is it acceptable for G Road to have a narrower Bike Lane but it's not acceptable for a Low-Speed Collector road, or

even a local commercial street or lower volume local streets?

- 18. Two Way Shared Use off Street Path I'm not seeing where dimension E, slope information, is defined?
- 19. Two Way Shared Use Paths Canyonview park has multiple 8-ft paths and is highly used in the community. These paths typically don't have 2-ft gravel shoulders, but some paths have a 3-ft soft surface path for people who don't' want to walk on hard surfaces. Several of the paths have no shoulder and transition into the adjacent grass. Why isn't this an acceptable section for everyone else?
- 20. What is driving the requirement that all paths have to be concrete? Again, Canyonview has several soft surface paths and in many locations, such as Redlands 360, concrete paths are not practical in open space areas.

# From Ron Abeloe on 7-14-23

To: Trent Prall

Rick Doris

Thank you for the presentations of the proposed update of the TEDS along with the opportunity to provide comments from a Land Development and Housing Provider perspective.

My comments are mostly focused around the multimodal, Bike and Ped portions of the update. These portions of the update will add thousands of dollars of additional cost to each new housing unit that is produced under these proposed standards. That alone is not a reason to not propose them if the proposal eliminates a serious safety issue that is resulting in high numbers of injury or death.

It is however a reason to gather the information and statistics to support not only the new standards but also where they are warranted based on the significantly negative impact they will have on all new housing types.

Increasing new housing costs drives additional inflationary pressure on new home prices to the consumer. More troubling than this is the fact that new home price inflation is tied directly to increased prices on lower cost housing units as well. New home prices move in tandem with all other housing groups as a rule. These lower priced housing units are what the lower income level buyers and renters are using for shelter. These units are our work force housing stock.

Based on these facts it seems very important to take the time to identify where these new standards will have a safety impact large enough to warrant the significant negative impacts on housing prices, and where they will only serve to increase costs without much benefit.

In addition, adding concrete and asphalt in places where it is not necessary seems environmentally irresponsible and inefficient for future City Maintenance as well as the development itself. Considering the amount of carbon needed to produce concrete and asphalt along with the significant heat generated year after year for every additional square foot of these surfaces that are required to be installed, it seems prudent to make sure that it is truly needed.

I have heard the term quality of life or a more comfortable experience when referring to these improvements, I would ask you to keep in mind that there are few quality-of-life issues that are more important than being able to provide housing for yourself and your loved ones, and it is quite an uncomfortable experience when you can't afford to do that.

#### From Ron Abeloe on 7-17-23

Rick I wanted to backup our conversation on the costs associated with the TEDS update, specifically the requirement for 6 foot wide sidewalks in new residential subdivisions. I am estimating that on a 60 foot wide lot this will add approximately \$2,000.00 of cost to each lot. This cost is being proposed without any compelling reason to do so. The pedestrian traffic inside of most subdivisions is so extremely low and a significant part of that traffic is single user which will receive almost no benefit from a wider walk. This cost may be warranted on high volume higher speed streets but inside of new residential subdivisions what we are currently required to provide seems more than adequate. I say this because in the 30 years I have been developing residential subdivisions of various densities along with the hundreds of homes I have built and sold I have yet to have heard a single complaint or even a comment regarding the width of the City Sidewalks inside the subdivision. As a matter of fact, the standard entry walk to the front door of our homes is 4 feet wide, and again, I have never received a comment or complaint about this standard either. Now I know that this is not a scientific study but it does lead me to believe that if a 4 foot wide sidewalk width was an issue of concern, I certainly would have heard about it by now. I would simply request that if the City truly believes that this is worth the additional burden on the home buying public that you should work with our industry to determine where this burden is truly warranted based on real data and where it is unnecessary. I would remind you that the cost of new homes is directly related to the market price of new homes and more importantly that as new home prices rise, that all other housing prices follow including rents. This is a well-documented market reaction, therefore additional cost should be very carefully and thoroughly investigated prior to any requirement that ends in that additional cost. I realize the City has no control over market forced but that in no way relieves the City from the those additional cost items that it does have direct control over unless there is a truly compelling reason that has been proven out through thoughtful and thorough research.

Thank You for your consideration, Ron Abeloe Chaparral West Inc.

# From Andy Gingerich on 7-14-23

I agree with the basic concept, Rick, that gov't agencies would build them on the main roadways, and developers would build them on the others. In reality that's what would happen. I just don't know if roadway classification is the best guideline. From the examples I gave, North Ave is a minor arterial, Rimrock is a major collector, 24 3/4 Rd and Market St are local roads. I suspect that North Ave is covered by the North Ave Overlay. But in the other examples it looks like it's based more on a traffic flow issue, trying to prevent traffic back up at intersections, etc. These were decisions made before my time, so I am making some assumptions.

How is it determined which roadways TCP funds will be used for vs which roadways developers will build? Maybe that's a decent guideline to determine areas where developers would and wouldn't be required to build a pullout. I'm just thinking that if a developer is building a roadway and sidewalks, and it's determined that a pullout is needed, they should build it along with everything else. In reality, bus pullouts are unlikely to be needed in local and lower classified roads in most situations.

There is a decision tree in the current Transit Design Standards and Guidelines that determines stop locations and whether or not a bus pullout is needed. I don't think this decision tree has been closely followed over the years, and should be updated to reflect more recent practices. But I think it's the right place for these standards to be located.

# CITY OF GRAND JUNCTION, COLORADO

O	RD	INA	NCE	NO.	
---	----	-----	-----	-----	--

# AN ORDINANCE ADOPTING THE TRANSPORTATION ENGINEERING DESIGN STANDARDS (TEDS) MANUAL

TRANSPORTATION ENGINEERING DESIGN STANDARDS (TEDS) IS FOR THE CITY'S URBAN DEVELOPMEBNT BOUNDARY (UDB) LOCATED GENERALLY BETWEEN 21 ROAD ON THE WEST, J ROAD ON THE NORTH, 32 ROAD ON THE EAST AND A SOUTH BOUNDARY APPROXIMATELY ONE-QUARTER OF A MILE NORTH OF THE MESA COUNTY LANDFILL

# THE TRANSPORTATION ENGINEERING DESIGN STANDARDS (TEDS) AND ORDINANCE TO BE PUBLISHED IN PAMPHLET FORM

# Recitals

The City of Grand Junction Public Works Department, Traffic Engineering Division and Community Development Department have completed a comprehensive update to the Transportation Engineering Design Standards (TEDS) manual.

TEDS was first adopted by reference in Chapter 6 of the Zoning and Development Code by the City on March 7, 2000. The manual was updated by resolution in November 2001, September 2003 and April 2004.

Over the past year, City staff have worked with Fehr & Peers, a consultant firm and a selected Technical Advisory Committee (TAC) to review and provide changes to TEDS that consider best practices in the industry, promote and support the City's Pedestrian and Bicycle Plan and implement the vision of the community though that planning effort. Some aspects of the Manual were out of date and not reflective of current community values or current design practices being applied within the city.

The 2023 updated TEDS manual has been referred to various public and private agencies and design consultation and engineering firms for their review and comments; those comments have been incorporated and resulted in revisions to the document as appropriate.

The updated TEDS Manual incorporates the following general improvements:

- Reflect current community values for multimodal transportation (including for pedestrians, bicyclists, and transit users).
- Incorporate current state and national design standards.
- Improve the usability of the manual.

 Support implementation of the vision established in the recently adopted Pedestrian & Bicycle Plan.

This 2023 updated Transportation Engineering Design Standards (TEDS) will repeal and replace the 2004 Transportation Engineering Design Standards (TEDS).

Changes to the TEDS manual support and implement the Pedestrian and Bicycle Plan including changes to City transportation infrastructure by increasing sidewalk and roadway width to improve and increase bicycle and pedestrian safety.

Changes to the TEDS manual implement the 2020 One Grand Junction Comprehensive Plan by promoting the integration of transportation mode choices into existing and new neighborhoods, providing opportunities for interaction and strengthening a sense of community.

The Planning Commission is charged with the legal duty to prepare and recommend for adoption to City Council master plans for the City.

The updated Transportation Engineering Design Standards (TEDS) manual was heard in a public hearing on September 26, 2023 by the Grand Junction Planning Commission.

The Planning Commission recommended that the City Council adopt the Transportation Engineering Design Standards (TEDS) manual.

# NOW, THEREFORE, BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF GRAND JUNCTION THAT:

That the Transportation Engineering Manual Standards (TEDS) manual for the City of Grand Junction, Colorado, in the form of the document attached hereto, and as recommended for adoption by the Grand Junction Planning Commission is hereby adopted.

Furthermore, be it ordained that the previously adopted Transportation Engineering Manual Standards (TEDS) manual last adopted in 2004 is hereby repealed.

The full text of this Ordinance, including the text of the Transportation Engineering Design Standards (TEDS), in accordance with paragraph 51 of the Charter of the City of Grand Junction, shall be published in pamphlet form with notice published in accordance with the Charter.

INTRODUCED on first reading the	day of	, 2023 and ordered
published in pamphlet form.		

<b>ADOPTED</b> on second reading the _ published in pamphlet form.	day of, 2023 and ordered
ATTEST:	Anna M. Stout President of the Council
Amy Phillips City Clerk	