




SAFE HAVEN DEFENSE

TECHNICAL DATA

PROTECTION LEVEL	EXIGENT PROTECTION
THICKNESS PER LAYER	VARIES
NUMBER PLYS	VARIES
BREAK STRENGTH	STARTING AT 1320PSI
TENSILE STRENGTH	34,000 PSI
PEEL STRENGTH	6 PSI
TOTAL SOLAR REJECTION	20%
IR REJECTION	CAPABLE OF 59%
UV REJECTION	99%
WEIGHT/SQ FT	1.6 OUNCES/FT2



LAB TESTINGS

- ANSI Z97.1 - BLDG GLAZE MATERIALS
- CPSG 16 CFR 1201 - IMPACT TEST
- ASTM E-1886 - HURRICANE WIND
- GSA EXPLOSIVE TEST - GSA TS01-2003
- BMAG LEVEL 1 - BLAST MITIGATION
- UL972 / ULC - 332 - BURGLARY PROTECTION
- NIJ 0108.01 - BULLET RESISTANCE (3RD PARTY LAB)
- UL752 - BULLET RESISTANCE (3RD PARTY LAB)

USES/APPLICATION

- Retail
- Distribution Centers
- K-12/Colleges
- Hospitals
- Financial Institutions
- Corporate HQ's
- Gov't Buildings

- Bullet resistance can be achieved on glass as thin as 1/4"
- One-Way Bullet Resistance for armed guards to stop threats before they enter the building.
- Various products and resistances to ensure proper resistance is achieved depending on your threat.
- All installations are conducted by corporate installers; eliminating poor subcontracted installs.

NOTE:EXISTING WINDOW MUST BE INSPECTED TO BE STRUCTURALLY SOUND.
 WINDOW MUST BE FREE FROM DEBRIS AND THOROUGHLY CLEANED PRIOR TO APPLICATION.

VISIT WWW.SAFEHAVENDEFENSE.COM TO WATCH OUR COMPELLING DEMOS