

## **Purchasing Division**

## **ADDENDUM NO. 1**

**DATE:** October 25, 2024

FROM: City of Grand Junction Purchasing Division

TO: All Offerors

RE: B ½ Road Repair IFB-5528-24-DD

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded, and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

- 1. Revised Bid Schedule Sheet: Added line item for lane striping and white lane lines to match existing layout. Use this Bid Schedule when submitting your bid (Attached)
- **2. Schedule Clarification:** If inclement weather temporarily impacts the schedule, contract time may be added with concurrence of the Project Engineer, provided a drivable surface is provided; or as provided for by standard City Specifications. No payment for repair to work conducted would be made.
- 3. Schedule Clarification: If inclement weather impacts the project for the duration of the season, a temporary durable surface (hot or cold mix asphalt with testing requirements waved) shall be provided until final paving completed in 2025. Partial acceptance and a stop work order could be issued if the durable, temporary surface is provided. Temporary, durable surface is payable under bid line item 12. Start work would be issued in conjunction with local asphalt plant start up in the spring at the Project Engineer's discretion.

The original solicitation for the project noted above is amended as noted. All other conditions of the subject remain the same.

Respectfully.

Sales Sanie to

Dolly Daniels, Senior Buyer

City of Grand Junction, Colorado

## Bid Schedule: B 1/2 Road Patch Addendum No. 1

Item	CDOT,							
No.	City Ref.	Description	Quantity	Units		Unit Price	Total Price	
1	304	Class 3 Material (24" thick)	500.	Ton	\$	\$		
2	420	Geotextile (Mirafi RS580i or engineer approved equal)	450.	SY	\$	\$		
3	304	Class 6 Aggregate Base Course (8" thick)	575.	Ton	\$	\$		
4	401	Hot Mix Asphalt (4" thick, 2 lifts) (Grading SX 75, Binder Grade 64-22)	100.	Ton	\$	\$		
5	210	Adjust Manhole Ring and Cover	2.	EA	\$	\$		
6	627	Thermoplastic Bike Symbol	1.	EA	\$	\$		
7	203	Excavation (3 ft depth)	450.	CY	\$	\$		
8	203	Unsuitable Material Haul	450.	CY	\$	\$		
9	626	Mobilization	Lump	Sum		\$		
10	630	Traffic Control (Complete In Place)	12.	Days	\$	\$		
11	627	Lane Striping (match existing, white and yellow)	325.	LF	\$	\$		
12	401	Temporary Asphalt Surface, as-directed by Project Engineer	100.	Ton	\$	\$		
MCR		Minor Contract Revisions				\$	5,000.00	
		Bid Amount:				\$	\$	
Bid Amount:							lars	