

**Geotechnical Investigation Report  
F 1/2 Road Parkway and 24 1/2 Road Widening  
City of Grand Junction, Colorado  
RockSol Project No. 599.37  
August 2, 2023**



Prepared for:

**City of Grand Junction**  
Public Works Department  
333 West Avenue, Building D  
Grand Junction, Colorado 81501

Attention: Brendan Hines, P.E., Project Engineer

*Prepared by:*



**RockSol Consulting Group, Inc.**  
566 W Crete Circle, Unit 2  
Grand Junction, Colorado 81505  
(970) 822-4350

**Geotechnical Investigation Report  
F 1/2 Road Parkway and 24 1/2 Road Widening  
City of Grand Junction, Colorado  
RockSol Project No. 599.37  
August 2, 2023**

Prepared for:

**City of Grand Junction**  
Public Works Department  
333 West Avenue, Building D  
Grand Junction, Colorado 81501

Attention: Brendan Hines, P.E., Project Engineer

*Prepared by:*



**RockSol Consulting Group, Inc.**  
566 W Crete Circle, Unit 2  
Grand Junction, Colorado 81505  
(970) 822-4350

*Madison Philips*  
Madison Philips, E.I.T.  
Civil Engineering Associate



Jay Goldbaum, P.E.  
Senior Pavement Engineer



Donald G. Hunt, P.E.  
Senior Geotechnical Engineer

**Table of Contents**

1.0	PROJECT OBJECTIVE AND DESCRIPTION .....	1
2.0	PROJECT SITE CONDITIONS.....	2
3.0	GEOLOGICAL CONDITIONS.....	3
4.0	SUBSURFACE EXPLORATION.....	3
5.0	SURFACE AND SUBSURFACE CONDITIONS .....	5
5.1	Existing Asphalt Pavement Sections.....	5
5.2	Fill Material .....	5
5.3	Native Subgrade Soils .....	6
5.4	Sedimentary Bedrock.....	6
5.5	Groundwater.....	6
6.0	LABORATORY TESTING.....	7
7.0	SUBGRADE CHARACTERIZATION .....	7
7.1	Roadway Subgrade Soil Classification.....	7
7.2	Swell/Consolidation Potential of Subgrade Soils .....	8
7.3	Water-Soluble Sulfate Content.....	8
8.0	PAVEMENT DESIGN RECOMMENDATIONS .....	10
8.1	Traffic Loading .....	11
8.2	Pavement Subgrade Characterization.....	12
8.3	Pavement Section Recommendations, .....	12
8.3.1	Flexible ME-Pavement Design Recommendations .....	13
8.3.2	Rigid ME-Pavement Design Recommendations .....	14
8.3.3	AASHTO 1993 Flexible Pavement Design .....	15
8.3.4	AASHTO 1998 Rigid Pavement Design.....	16
8.4	Subgrade Preparation (Prior to Pavement Construction) .....	17
9.0	CONCRETE BOX CULVERT EXTENSION DISCUSSION .....	18
10.0	EARTHWORK.....	20
11.0	SEISMICITY DISCUSSION .....	21
11.1	General .....	21
11.2	Seismic Design Parameters .....	21
12.0	OTHER DESIGN AND CONSTRUCTION CONSIDERATIONS.....	22
13.0	LIMITATIONS.....	23

**ATTACHMENTS**

- Figure 1: F 1/2 Road Parkway Conceptual Layout (24 Road to 24 1/2 Road)
- Figure 2: F 1/2 Road Parkway Conceptual Layout (24 1/2 Road to 25 Road)
- Figure 3: F 1/2 Road Parkway Conceptual Layout (25 Road, F 1/2 Road to F/Patterson Road)
- Figure 4: F 1/2 Road Parkway Conceptual Layout (25 Road, Buchanan Drive to F 1/2 Road)
- Figure 5: F 1/2 Road Parkway Conceptual Layout (24 1/2 Road from Brookwillow Loop to Tennis Courts)

## APPENDICIES

- Appendix A: Legend and Individual Borehole Logs
- Appendix B: Summary of Laboratory Test Results
- Appendix C: 20 and 30-Year Flexible ME-Pavement Design Output Sheets (F 1/2 Road)
- Appendix C1: Rigid ME-Pavement Design Output Sheets (F 1/2 Road)
- Appendix D: 20 and 30-Year Flexible ME-Pavement Design Output Sheets (24 1/2 Road)
- Appendix D1: Rigid ME-Pavement Design Output Sheets (24 1/2 Road)
- Appendix E: 20 and 30-Year Flexible ME-Pavement Design Output Sheets (24 1/2 Road & F 1/2 Road Roundabout)
- Appendix E1: Rigid ME-Pavement Design Output Sheets (24 1/2 Road & F 1/2 Road Roundabout)
- Appendix F: 20 and 30-Year Flexible ME-Pavement Design Output Sheets (25 Road)
- Appendix F1: Rigid ME-Pavement Design Output Sheets (25 Road)
- Appendix G: 20 and 30-Year Flexible ME-Pavement Design Output Sheets (25 Road & F 1/2 Road Intersection)
- Appendix G1: Rigid ME-Pavement Design Output Sheets (25 Road & F 1/2 Road Intersection)
- Appendix H: 20 and 30-Year Flexible ME-Pavement Design Output Sheets (Foresight Circle and F 1/4 Roads)
- Appendix H1: Rigid ME-Pavement Design Output Sheets (Foresight Circle and F 1/4 Roads)
- Appendix I: 20 and 30-Year Flexible 1993 AASHTO Pavement Design Output Sheets (F 1/2 Road)
- Appendix I1: Rigid 1998 AASHTO Pavement Design Output Sheets (F 1/2 Road)
- Appendix J: 20 and 30-Year Flexible 1993 AASHTO Pavement Design Output Sheets (24 1/2 Road)
- Appendix J1: Rigid 1998 AASHTO Pavement Design Output Sheets (24 1/2 Road)
- Appendix K: 20 and 30-Year Flexible 1993 AASHTO Pavement Design Output Sheets (24 1/2 Road & F 1/2 Road Roundabout)
- Appendix K1: Rigid 1998 AASHTO Pavement Design Output Sheets (24 1/2 Road & F 1/2 Road Roundabout)
- Appendix L: 20 and 30-Year Flexible 1993 AASHTO Pavement Design Output Sheets (25 Road)
- Appendix L1: Rigid 1998 AASHTO Pavement Design Output Sheets (25 Road)
- Appendix M: 20 and 30-Year Flexible 1993 AASHTO Pavement Design Output Sheets (25 Road & F 1/2 Road Intersection)
- Appendix M1: Rigid 1998 AASHTO Pavement Design Output Sheets (25 Road & F 1/2 Road Intersection)
- Appendix N: 20 and 30-Year Flexible 1993 AASHTO Pavement Design Output Sheets (Foresight Circle and F 1/4 Roads)
- Appendix N1: Rigid 1998 AASHTO Pavement Design Output Sheets (Foresight Circle and F 1/4 Roads)
- Appendix O: Record Drawing CBC Structure (From Value Place Hotel Plan Set)
- Appendix P: Slope Stability Models at NW Wall



## 1.0 PROJECT OBJECTIVE AND DESCRIPTION

This report documents the geotechnical engineering investigation performed by RockSol Consulting Group, Inc. (RockSol) for the F 1/2 Road Parkway and 24 1/2 Road Widening Project in the City of Grand Junction, Colorado (see Image 1, *Site Vicinity Map*).

**Image 1 – Site Vicinity Map (Google Earth)**



This project focuses on the design and construction of two sites for the City of Grand Junction. Site 1 includes new construction for F 1/2 Road Parkway connecting 24 Road and 25 Road, as well as major improvements of existing adjacent roads/driveways, a new roundabout at the 24 1/2 Intersection, and a new realignment of the F 1/2 Road and 25 Road intersection. F 1/2 Road Parkway and 25 Road will be 4-lane roads with turn lanes and a center median.

In addition to the new parkway, major improvements will be made to 25 Road beginning at the intersection with F Road/Patterson Road, up to the intersection with Blichmann Avenue. North of Blichmann Avenue, 25 Road will be accessed by a new intersection off the diagonal portion of the parkway adjacent to the Heritage Heights development. In addition to the parkway and 25 Road work, improvements will be made to 25 Road north of F 1/2 Road, as well as to F 1/2 Road east of 25 Road.

Improvements are planned for F ¼ Road, Zenith Lane, and Flat Top Lane, which will continue east and connect with 25 Road. Lastly, the western leg of Foresight Circle will be modified at the connection to 25 Road.

Included in the new parkway construction will be an extension of the existing box culvert to the north that carries Leach Creek water under F ½ Road to accommodate the Parkway Widening.

Site 2 consists of widening and reconstruction of 24 ½ Road, from F 3/8 Road north to Jack Creek Road (Canyon View Park), approximately 1.5 miles. Construction will include minor widening of the existing two lanes to incorporate a center turn lane, shoulder widening, and sidewalks to accommodate pedestrian and bike traffic. This construction will be completed in a separate project, but the City of Grand Junction would like to complete the Geotechnical Work at the same time as F ½ Parkway.

The geotechnical investigation was conducted by RockSol for the City of Grand Junction. The scope of work for this geotechnical investigation included:

- Preparing a drilling/sampling program to perform a subsurface investigation and implementing the program to collect soil samples for laboratory testing.
- Performing laboratory tests and analyzing the data.
- Preparing a report that presents the field and laboratory data obtained, geological setting and conditions, geotechnical design parameters for the proposed structures, project site improvements, and roadway pavement thickness recommendations.

Surface and groundwater hydrology, hydraulic engineering, and environmental evaluation of site soils and groundwater for possible contaminant characterization were not included in RockSol's geotechnical scope of work.

Unless otherwise specified, all recommendations presented in this report are based on the Colorado Department of Transportation (CDOT) 2021 Standard Specifications for Road and Bridge Construction; the City of Grand Junction Standard Specifications for Road and Bridge Construction; and the City of Grand Junction Transportation Engineering Design Standards.

## **2.0 PROJECT SITE CONDITIONS**

A combination of farm, commercial, residential, and undeveloped land immediately surrounds the project limits. The Colorado River is located approximately 0.5 miles southwest of the project site.

Currently, 24 ½ Road consists of one travel lane in each direction within Site 2 project limits. 25 Road currently consists of two lanes, one in each direction and a center turn lane within the project vicinity. F ½ Road consists of one travel lane in each direction with a center turn lane. The existing lanes are approximately 12 feet wide and surfaced with asphalt pavement throughout the project vicinity.


Topography throughout the project limits consist of nearly flat slopes in all directions. Within the project vicinity, Main Line Grand Valley Canal crosses 25 ½ Road between G road and F ½ Road, and North Leach Creek runs along the south side of G Road and then along the east side of 24 Road.



### 3.0 GEOLOGICAL CONDITIONS

Based on information presented in the United States Geological Survey (USGS) Geologic Map (See Image 2, *Site Geology Map*) of the Grand Junction Quadrangle, Mesa County, Colorado, by Roger B. Scott, Paul E. Carrara, William C. Hood, and Kyle E. Murray, dated 2002, alluvium and colluvium, undivided, (Holocene and late Pleistocene) (Qac) is mapped at the project site, as well as at the immediate surrounding areas. Alluvium generally consists of silt, sand and gravel and the colluvium generally consists of sandy silt, silty to clayey sand, and sandy clay. The materials identified by the USGS mapping were consistent with native soils encountered during our geotechnical investigation. Mancos Shale bedrock (Km) is mapped at or near the surface in two locations northeast of the project site. This correlates with the Claystone/shale bedrock identified at the bottom of Boreholes LC-2 and LC-3.

**Image 2 – Site Geology Map (Grand Junction, Mesa County, Colorado 2002)**



### 4.0 SUBSURFACE EXPLORATION

For this investigation, RockSol completed a total of 25 boreholes identified as B-1 through B-6, F-1 through F-16, and LC-1 through LC-3. (See Figures 1 through 5).

Boreholes F-1 through F-16 were drilled for the purpose of improvements, modifications, and new alignments within Site 1, including the design of the new F 1/2 Road connecting 24 Road and 25 Road. Boreholes B-1 through B-6 were drilled along 24 1/2 Road for the purpose of rehabilitation and road widening within Site 2 (See Figures 1 through 4). Boreholes LC-1 through LC-3 were drilled at the intersection of 24 Road and F 1/2 Road (See Figure 1). To assist with development of pavement thickness and structure foundation recommendations, “B” and “F” boreholes extended to approximate depths of 5 feet to 10 feet and “LC” boreholes extended to approximate

depths of 20 feet to 40 feet for characterization of subsurface conditions, including depths to bedrock and groundwater.

The locations of the geotechnical investigation boreholes are summarized below in Table 1. The boreholes were drilled between October 4, 2021, and October 20, 2021.

**Table 1 – Borehole and Pavement Core Location Summary**

Borehole ID	Borehole Location
B-1	24 ½ Road, at Tennis Court, southbound lane
B-2	24 ½ Road, just west of 6 Road, southbound lane
B-3	24 ½ Road, just south of roundabout, northbound lane
B-4	675 24 ½ Road, southbound shoulder
B-5	24 ½ Road, just north of Ajay Avenue, northbound lane
B-6	24 ½ Road at F 3/8 Road intersection, northbound lane
F-1	New F ½ Rd, ~240 feet east of existing F ½ Road and Market Street
F-2	Field along new proposed F ½ Road
F-3	Field near 24 ½ Road and new F ½ Road
F-4	Northeast side of 24 ½ Road and F ½ Road
F-5	24 ½ Road, ~135 feet north of F 3/8 Road
F-6	Southeast side of 24 ½ Road and F ½ Road
F-7	24 ¾ Road and west side of new F ½ Road
F-8	New F ½ Road alignment, vacant land
F-9	East end of proposed F ½ Road, west of 25 Road
F-10	653 25 Road (private property)
F-11	25 Road, front 645 25 Road, northbound lane
F-12	Corner of F 1/2 Road and 25 Road, ~18 feet off 25 Road
F-13	F ¼ Road, westbound lane
F-14	25 Road, ~320 feet south of F ¼ Road
F-15	Foresight Circle, ~250 feet east of 25 Road, eastbound lane
F-16	Field north of 6.5 Climb Gym (new road alignment)
LC-1	Northeast corner of 24 Road and F ½ Road (wingwall)
LC-2	Northeast corner of F ½ Road and 24 Road intersection
LC-3	Southeast corner of F ½ Road and 24 Road intersection

Boreholes were advanced with a truck mounted Simco 2800 drill rig using 4.25-inch outside diameter solid stem auger. The boreholes were logged in the field by a representative of RockSol with the depth to groundwater, if encountered, noted at the time of drilling. The boreholes were backfilled at the completion of drilling and groundwater level checks and patched with surface asphalt patch mix when drilled within existing pavement.

Subsurface materials were sampled and resistance of the soil to penetration of the sampler was performed using modified California barrel and standard split spoon samplers. Penetration Tests were performed using an automatic lift system and a hammer weighing 140 pounds falling 30 inches. The modified California barrel sampler has an outside diameter of approximately 2.5 inches and an inside diameter of 2 inches. The standard split spoon sampler used had an outside diameter of 2 inches and an inside diameter of 1¾-inches. Brass tube liners were used with the

modified California barrel sampler. Brass tube liners are not used with the standard split spoon sampler.

The standard split spoon sampling method is the Standard Penetration Test (SPT) described by ASTM Method D-1586.

The modified California Barrel sampling method is similar to the SPT test with the difference being the sampler dimensions and the number of 6-inch intervals driven with the hammer per ASTM D-3550. It is RockSol’s experience that blow counts obtained with the modified California sampler tend to be slightly greater than a standard split spoon sampler.

The boreholes were logged in general accordance with ASTM D-2488. Penetration resistance values (blow counts) were recorded for each sampling event. Blow counts, when properly evaluated, indicate the relative density or consistency of the soils. Depths at which the samples were taken, the type of sampler used, and the blow counts that were obtained are shown on the Borehole Logs (See Appendix A).

**5.0 SURFACE AND SUBSURFACE CONDITIONS**

The surface and subsurface materials encountered by RockSol at our borehole locations included asphaltic pavement, road base (aggregate base course/pit run material), topsoil, fill material, native soils, and sedimentary bedrock. A brief description of the materials encountered is presented below.

**5.1 Existing Asphalt Pavement Sections**

Asphalt pavement was encountered in Boreholes B-1, B-3, B-5, B-6, F-5, F-11, and F-13 through F-15. Asphalt pavement ranged in thickness from 2 to 7 inches and was underlain by 4 to 12 inches of aggregate base course (ABC). A summary of existing pavement section thickness encountered at each borehole location is presented in Table 2. Existing pavement section thicknesses are also shown on the individual borehole logs found in Appendix A.

**Table 2 – Existing Pavement Sections**

Borehole ID	HMA Pavement Thickness (in)	ABC Thickness (in)
B-1	6.0	11.0
B-3	5.0	12.0
B-5	7.0	11.0
B-6	5.0	11.0
F-5	6.0	6.0
F-11	6.0	6.0
F-13	2.0	10.0
F-14	6.0	4.0
F-15	3.0	9.0

HMA = Hot Mix Asphalt; ABC = Aggregate Base Course

**5.2 Fill Material**

Fill material was encountered in Boreholes B-6, F-5, F-11, F-14, and F-15 and extended to depths ranging from 2 feet to 4 feet below existing grades. Fill material generally consisted of a rocky and gravelly sand mixture and is locally described as pit-run material.



### 5.3 Native Subgrade Soils

Native soils were encountered at the ground surface of Boreholes B-2, B-4, F-1 through F-4, F-6 through F-10, F-12, F-16, and LC-1 through LC-3, and below existing pavement and fill materials at all other borehole locations. Native soils extended to maximum depths drilled at the borehole locations, except for Borehole LC-3. Native soils encountered generally consisted of very soft to very stiff, moist to wet, brown, sandy to silty clay to clay with sand or gravel. At Borehole LC-2, a medium stiff to very hard, brown to gray, very moist, sand with silt and gravel was encountered below the sandy clay layer, and at Borehole LC-3, a native sandy gravel was located at the ground surface. The native soils encountered by RockSol are generally consistent with the alluvium and colluvium materials identified on the USGS Geological Map (See Image 2) found in Section 3.0 of this report.

### 5.4 Sedimentary Bedrock

Claystone/shale bedrock was encountered in Boreholes LC-2 and LC-3 at depths of approximately 37 feet and 40 feet, respectively, below existing grades. Claystone/Shale was identified in the field as slightly moist, gray, and medium stiff to very hard, and is consistent with the Mancos Shale Formation mapped near the project site on the USGS Geological Map (Image 2). Bedrock was not encountered to the depth drilled at any other borehole locations for this project.

### 5.5 Groundwater

Groundwater was encountered during drilling/sampling activities at borehole locations B-2 and LC-1 through LC-3 at approximate depths ranging from 7 feet to 10 feet below existing grades at the time of drilling operations. Additionally, piezometers were installed in Boreholes LC-2 and LC-3 for continued groundwater monitoring. Depth to groundwater where encountered is recorded in Table 3, *Approximate Depths to Groundwater* and presented on individual borehole logs in Appendix A. Depth to sedimentary bedrock, if encountered is included in Table 3.

**Table 3 – Approximate Depths to Groundwater**

Borehole I.D.	Depth to Bedrock (feet)	Depth to Groundwater at time of drilling, (feet)	Depth to Groundwater 11/1/2021, (feet)	Depth to Groundwater 11/30/2021, (feet)	Depth to Groundwater 12/30/2021, (feet)
B-2	-	7.0	-	-	-
LC-1	-	7.0	-	-	-
LC-2	37.0	7.0	5.1	4.8	7.0
LC-3	40.0	10.0	10.3	10.6	10.0

Depth to groundwater is subject to change depending on climatic conditions, water flows in North Leach Creek and Main Line Grand Valley Canal, local irrigation practices, changes in local topography, and changes in surface storm water management. Long-term monitoring of groundwater elevations is required to establish groundwater fluctuations.

## **6.0 LABORATORY TESTING**

Soil samples retrieved from the borehole locations were examined by the project geotechnical engineer in the RockSol laboratory. Selected samples were tested and classified per the Unified Soil Classification System (USCS). The following laboratory tests were performed in accordance with the American Society for Testing and Materials (ASTM), American Association of State Highway and Transportation Officials (AASHTO), and current local practices:

- Natural Moisture Content (ASTM D-2216)
- Percent Passing No. 200 Sieve (ASTM D-1140)
- Liquid and Plastic Limits (ASTM D-4318)
- Dry Density (ASTM D-2937)
- Gradation (ASTM D 6913)
- Water-Soluble Sulfates (CDOT CP-L 2103)
- Water-Soluble Chloride Content (CDOT CP-L 2104)
- Standard Test Method for pH of Soils (ASTM D4972-01)
- Soil Resistivity (ASTM G187 - Soil Box)
- Soil Classification (ASTM D-2487 and AASHTO M145)
- Swell Test (Denver Swell Test, modified from ASTM D-4546)
- Resistance Value (AASHTO T-190)

R-Values (Resistance Values) were tested by Cesare, Inc. and water-soluble chlorides were tested by Colorado Analytical Laboratories. All other laboratory tests were performed by RockSol. Laboratory test results are presented in Appendix B and are also summarized on the Borehole Logs presented in Appendix A.

## **7.0 SUBGRADE CHARACTERIZATION**

Laboratory test results were used to characterize the engineering properties of the subsurface material encountered. For soil classification, RockSol conducted sieve analyses and Atterberg Limits tests. Swell tests were used to determine the swell or consolidation characteristics of the subsurface materials. Lab testing was also performed on selected samples to determine the water-soluble sulfate content of subsurface materials to assist with cement type recommendations. A summary of physical and chemical test results is included in Appendix B.

### **7.1 Roadway Subgrade Soil Classification**

Subgrade bulk samples of existing roadway grades were obtained at various depths from each pavement borehole location and were tested for AASHTO soil classification. The subgrade soils tested generally varied between A-4 and A-6 AASHTO soil types. A summary of the roadway subgrade soil classifications is presented in Table 4 and summarized by group index in Table 5.

**Table 4 – Roadway Subgrade Soil Classifications**

Borehole Location	Depth (feet)	AASHTO Classification
B-1	2-10	A-6 (9)
B-2	0-7	A-6 (7)
B-3	2-9	A-6 (8)
B-5	3-10	A-6 (16)
B-6	4-10	A-4 (0)
F-1	0-5	A-6 (17)
F-2	0-6	A-6 (17)
F-3	0-4	A-6 (13)
F-4	0-5	A-6 (10)
F-5	2-10	A-6 (8)
F-6	0-7	A-6 (10)
F-7	0-5	A-6 (8)
F-8	0-5	A-4 (3)
F-9	0-3	A-6 (13)
F-10	0-5	A-4 (7)
F-16	0-10	A-6 (8)
LC-1	0-5	A-6 (7)
LC-2	0-5	A-4 (4)
LC-3	2-4	A-6 (7)

**Table 5 – Soil Classifications by Group Index Range**

AASHTO Soil Type	Group Index Range	Number of Tests
A-4	0 – 7	4
A-6	7 – 10	10
A-6	11 – 17	6

## 7.2 Swell/Consolidation Potential of Subgrade Soils

Based on swell test results and plasticity index (PI) testing, the subgrade soils encountered within the upper 3 to 10 feet of the pavement surface exhibit low consolidation potential and no swell potential (-1.7 percent consolidation to 0.0 percent swell under 500 pounds per square foot (psf) surcharge pressure).

Based on the swell test results and subgrade soil classifications obtained, special mitigation methods for expansive soil are not deemed necessary for new pavement construction or for the proposed improvements planned for this project.

However, based on consolidation and penetration data obtained from the boreholes drilled, special mitigation is recommended for design and construction of shallow foundation systems being considered (See Section 9) due to settlement potential and constructability. Mitigation may consist of over excavation and replacement with coarse, granular material with geosynthetic fabrics and geogrids to help stabilize shallow foundation soils.

## 7.3 Water-Soluble Sulfate Content

Cementitious material requirements for concrete in contact with soils or groundwater are based on the percentage of water-soluble sulfate. Mix design requirements for concrete exposed to water-soluble sulfates in soils or water is considered by the Colorado Department of Transportation (CDOT) as shown in Table 6 and in the CDOT Standard Specifications for Road and Bridge Construction, dated 2022. Water-soluble Sulfate Testing Results are summarized in Table 7.

**Table 6: Concrete Sulfate Exposure Class**

Water-Soluble Sulfate (SO <sub>4</sub> ) in Dry Soil, (%)	Sulfate (SO <sub>4</sub> ) In Water, ppm	Cementitious Material Requirements
0.00 to 0.10	0 to 150	Class 0
0.11 to 0.20	151 to 1,500	Class 1
0.21 to 2.0	1,500 to 10,000	Class 2
2.01 or greater	10,001 or greater	Class 3

**Table 7 – Water-Soluble Sulfate Testing Summary**

Borehole I.D.	Sample Depth (Feet)	Water-Soluble Sulfate (SO <sub>4</sub> ) in dry soil, percent	Cementitious Material Requirements
F-1	0-5	0.38	Class 2
F-4	0-5	0.16	Class 1
F-5	2-10	0.26	Class 2
F-8	0-5	0.28	Class 2
F-10	0-5	1.04	Class 2
F-16	0-10	0.14	Class 1
LC-1	0-5	0.51	Class 2
LC-2	20	0.47	Class 2
LC-3	20	0.19	Class 1
LC-3	30	0.15	Class 1


The concentration of water-soluble sulfates measured in soil samples obtained from RockSol's exploratory boreholes ranged from 0.14 percent to 1.04 percent by weight. Based on the results of the water-soluble sulfate testing, **Class 2** cementitious material mix design requirements for concrete exposed to water soluble sulfates in soils is recommended. Refer to CDOT's current *Standard Specifications for Road and Bridge Construction Section 601* for concrete mixtures that satisfy appropriate sulfate exposure *Class* requirements.



**8.0 PAVEMENT DESIGN RECOMMENDATIONS**

24 Road and F 1/2 Road are classified as principal arterials, 24 1/2 Road and F Road/Patterson Road are classified as minor arterials. All other roadways applicable to Sites 1 and 2 are classified as minor collector or unclassified roadways by the City of Grand Junction. The roadway classification for this project were found on the website for the City of Grand Junction's Transportation Map as shown in Image 4.

**Image 4 – Roadway Classifications**



- |                               |                            |
|-------------------------------|----------------------------|
| Interstate 70                 | Major Collector            |
| Interstate 70 - Proposed      | Major Collector - Proposed |
| Principal Arterial            | Minor Collector            |
| Principal Arterial - Proposed | Minor Collector - Proposed |
| Minor Arterial                | Unclassified               |
| Minor Arterial - Proposed     |                            |



New pavement is planned for the New F ½ Road connecting 24 Road and 25 Road, as well as the reconstruction of 24 ½ Road from F 3/8 Road to Jack Creek, and a new F ½ Road and 24 ½ Road roundabout. New pavement is also planned for 25 Road and the new 25 Road and F ½ Road intersection, as well as for the reconstruction of Foresight Circle and F ¼ Road. In this report Hot Mix Asphalt (HMA) pavement is identified as flexible pavement. Portland Cement Concrete (PCC) pavement is identified as rigid pavement.

Pavement thickness evaluation for the development of flexible and rigid pavement design recommendations within the City of Grand Junction right of way were performed in accordance with CDOT's 2021 M-E Pavement Design Manual as modified in 2022 which uses Version 2.3.1 of AASHTO's Pavement Mechanistic-Empirical Design (PMED) software, *Subsection 29.32 – Pavements and Truck Routes* in the City of Grand Junction Municipal Code as passed in Ordinance 5136 on March 15, 2023, and a spreadsheet developed by RockSol to replicate the 1993 AASHTO flexible pavement design as recommended in 29.32.040(a).

The correlation of subgrade soil R-Value to Resilient Modulus for this report was performed using equation 4-1 from CDOT's 2021 Mechanistic-Empirical Pavement Design Manual.

## 8.1 Traffic Loading

Traffic loading was estimated for a 30-year flexible pavement design life and 30-year rigid pavement design life in accordance with the City of Grand Junction Municipal Code (Subsection 29.32.030). RockSol included the estimated traffic loading for a 20-year flexible pavement design life since it is recommended in CDOT's Pavement Design Manual for reconstruction using flexible pavement. The current average daily traffic (ADT) for 24 ½ Road was supplied to RockSol by the Transportation Engineer from the City of Grand Junction. The ADT for 24 Road and 25 Road were obtained from the traffic counts found on the website for the City of Grand Junction's Transportation Map. The ADT for F ½ Road was estimated to be 16,000 by the City of Grand Junction. Since this project will close the gap between 24 and 25 Roads, it was estimated by the Transportation Engineer for the City of Grand Junction that 24 ½ Road, Foresight Circle and F ¼ Roads, as well as the 24 ½ Road and F ½ Road roundabout within this area will have an increase of approximately 10 percent above the current ADT. The Average Annual Daily Truck Traffic (AADTT) has a significant effect on the predicted pavement performance as compared to cars and pick-up trucks. For this project, predominately Class 5 vehicles when using the Federal Highway vehicle type classification system were noted on 24 ½ Road. Based on the ADT from 24 ½ Road, an average of 12.9 percent trucks will be used for this project. The AADTT used for the pavement designs of roadway segments is shown in Table 9. A compound growth rate of 2.2 percent over a 20-year and 30-year design life was used to develop the 18,000-pound equivalent single axle loads (ESAL's) from the PMED calculated value. Based on CDOT's Pavement Design Manual, Cluster 1 truck percentages will be used to model the truck traffic in the PMED software. Traffic data and projections are summarized in Table 9.

**Table 9 – Summary of Traffic Loading**

<b>Pavement Section</b>	<b>Estimated Truck Traffic</b>	<b>20-Year Flexible Design Life 18k ESALS</b>	<b>30-Year Flexible Design Life 18k ESALS</b>	<b>30-Year Rigid Design Life 18k ESALS</b>
F 1/2 Road (Site 1)	2,100	5,510,000	9,300,000	12,020,000
24 1/2 Road (Site 2)	1,078	3,770,000	6,360,000	8,230,000
24 1/2 Road & F 1/2 Road Roundabout (Site 1)	3,178	8,330,000	14,070,000	18,190,000
25 Road (Site 1)	850	2,970,000	5,020,000	6,490,000
25 Road & F 1/2 Road Intersection (Site 1)	2,950	7,730,000	13,060,000	16,890,000
Foresight Circle & F 1/4 Road (Site 1)	231	810,000	1,360,000	1,760,000

## 8.2 Pavement Subgrade Characterization

Subgrade bulk samples within the upper 5 to 10 feet of existing roadway grades were obtained at each borehole location and were tested for AASHTO soil classification. The subgrade soils tested were AASHTO classified as A-1-a, A-4, and A-6 soil types (See Sections 5.2 and 5.3).

Based on R-Value testing, a conservative R-Value of 5 with a corresponding subgrade resilient modulus value of 5,356 psi was used by RockSol as the design R-value for evaluation of new pavement constructed on the existing soils at 24 1/2 Road, F 1/2 Road, 24 1/2 Road, and F 1/2 Road roundabout, F 1/4 Road, and Foresight Circle.

An R-Value of 10 with a corresponding subgrade resilient modulus value of 6,482 psi was used by RockSol as the design R-value for evaluation of new pavement constructed on the existing soils at 25 Road, and the F 1/2 Road and 25 Road intersection.

To provide an appropriate structural layer for Hot Mix Asphalt (HMA), RockSol recommends 12 inches of a subbase layer of non-stabilized A-1-b Pit Run (Class 3) material be included as part of the pavement design section in addition to 8 inches of Aggregate Base Course (ABC) directly underlying the pavement. A structural coefficient of 0.12 was used for Class 6 Aggregate Base Course (ABC), 0.11 for Class 3 ABC, and 0.44 for HMA. The Class 3 material must have an R-Value of at least 40 and the Class 6 material must have an R-Value of at least 78 when tested in accordance with AASHTO T 190.

## 8.3 Pavement Section Recommendations,

Three pavement thickness design procedures were developed for new flexible and rigid pavement. The first procedure used for flexible and rigid pavement design was performed in accordance with the 2021 Colorado Department of Transportation M-E Pavement Design Manual as modified in 2022 and the PMED software, Version 2.3.1. The second procedure used a spreadsheet developed by RockSol to replicate the 1993 AASHTO flexible pavement design since the AASHTOWare DARWin version 3.1 Pavement Design and Analysis System recommended in subsection 29.32.040(a) of the City of Grand Junction Transportation Engineering Design Standards is no longer available. The third procedure used the 1998 version of the AASHTO Guide for the Design of Pavement Structures for rigid pavement in accordance with subsection 29.32.040 (b) of the City of Grand Junction Transportation Engineering Design Standards. The thicknesses of ABC Class 3 and Class 6 were taken from the typical sections supplied to RockSol by the City of Grand Junction. Class 2 ABC may be used in lieu of Class 3 ABC.

### 8.3.1 Flexible ME-Pavement Design Recommendations

A summary of the PMED recommended pavement section thicknesses for the 20 and 30-year design life of flexible pavement Site 1 and Site 2 are presented in Table 10 and the pavement design output sheets are included in Appendices C through H.

**Table 10 – PMED Flexible Pavement Section Thickness Recommendations**

Pavement Section	Material Type	20-year Pavement Design Thickness (inches)	30-year Pavement Design Thickness (inches)	Appendix
F ½ Road (Site 1)	HMA SX(100) PG 64-28	2.0	2.0	C
	HMA SX(100) PG 64-22	5.5	6.5	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	14.0	14.0	
24 ½ Road (Site 2)	HMA SX(100) PG 64-28	2.0	2.0	D
	HMA SX(100) PG 64-22	5.0	6.0	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	10.0	10.0	
24 ½ Road & F ½ Road Roundabout (Site 1)	HMA SX(100) PG 64-28	2.0	2.0	E
	HMA SX(100) PG 64-22	8.0	9.0	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	16.0	16.0	
25 Road (Site 1)	SX(100) PG 64-28	2.0	2.0	F
	SX(100) PG 64-22	5.0	6.0	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	10.0	10.0	
25 Road & F ½ Road Intersection (Site 1)	HMA SX(100) PG 64-28	2.0	2.0	G
	HMA SX(100) PG 64-22	7.0	9.0	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	12.0	12.0	
Foresight Circle and F ¼ Road (Site 1)	HMA SX(75) PG 64-28	2.0	2.0	H
	HMA SX(75) PG 64-22	4.0	5.0	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	12.0	12.0	

HMA = Hot Mix Asphalt; ABC = Aggregate Base Course

### 8.3.2 Rigid ME-Pavement Design Recommendations

A summary of the PMED recommended pavement section thicknesses for the 30-year design life of rigid pavement Site 1 and Site 2 are presented in Table 11 and the pavement design output sheets are included in Appendices C1 through H1.

**Table 11 – PMED Rigid Pavement Section Thickness Recommendations**

Pavement Section	Material Type	Thickness (inches)	Appendix
F 1/2 Road (Site 1)	PCC	9.0	C1
	ABC Class 6	8.0	
	ABC Class 2 or 3	12.0	
24 1/2 Road (Site 2)	PCC	9.0	D1
	ABC Class 6	8.0	
	ABC Class 2 or 3	12.0	
24 1/2 Road & F 1/2 Road Roundabout (Site 1)	PCC	9.0	E1
	ABC Class 6	8.0	
	ABC Class 2 or 3	16.0	
25 Road (Site 1)	PCC	9.0	F1
	ABC Class 6	8.0	
	ABC Class 2 or 3	12.0	
25 Road & F 1/2 Road Intersection (Site 1)	PCC	9.0	G1
	ABC Class 6	8.0	
	ABC Class 2 or 3	12.0	
Foresight Circle and F 1/4 Road (Site 1)	PCC	8.0	H1
	ABC Class 6	8.0	
	ABC Class 2 or 3	12.0	

PCC = Portland Cement Concrete; ABC = Aggregate Base Course

### 8.3.3 AASHTO 1993 Flexible Pavement Design

A summary of the AASHTO 1993 Pavement Design recommended pavement section thicknesses for the 20 and 30-year design life of flexible pavement Site 1 and Site 2 are presented in Table 12 and the pavement design output sheets are included in Appendices I through N.

**Table 12 – AASHTO 1993 Flexible Pavement Section Thickness Recommendations**

Pavement Section	Material Type	20-year Pavement Design Thickness (inches)	30-year Pavement Design Thickness (inches)	Appendix
F 1/2 Road (Site 1)	HMA SX(100) PG 64-28	2.0	2.0	I
	HMA SX(100) PG 64-22	3.0	4.0	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	14.0	14.0	
24 1/2 Road (Site 2)	HMA SX(100) PG 64-28	2.0	2.0	J
	HMA SX(100) PG 64-22	3.5	4.0	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	10.0	10.0	
24 1/2 Road & F 1/2 Road Roundabout (Site 1)	HMA SX(100) PG 64-28	2.0	2.0	K
	HMA SX(100) PG 64-22	3.0	5.0	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	16.0	16.0	
25 Road (Site 1)	HMA SX(100) PG 64-28	2.0	2.0	L
	HMA SX(100) PG 64-22	2.5	3.0	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	10.0	10.0	
25 Road & F 1/2 Road Intersection (Site 1)	HMA SX(100) PG 64-28	2.0	2.0	M
	HMA SX(100) PG 64-22	3.5	4.0	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	12.0	12.0	
Foresight Circle and F 1/4 Road (Site 1)	HMA SX(75) PG 64-28	2.0	2.0	N
	HMA SX(75) PG 64-22	1.0	1.5	
	ABC Class 6	8.0	8.0	
	ABC Class 2 or 3	12.0	12.0	

HMA = Hot Mix Asphalt; ABC = Aggregate Base Course



### 8.3.4 AASHTO 1998 Rigid Pavement Design

A summary of the AASHTO 1998 Pavement Design recommended pavement section thicknesses for the 30-year design life of rigid pavement Site 1 and Site 2 are presented in Table 13 and the pavement design output sheets are included in Appendices I1 through N1.

**Table 13 – AASHTO 1998 Rigid Pavement Section Thickness Recommendations**

Pavement Section	Material Type	Thickness (inches)	Appendix
F 1/2 Road (Site 1)	PCC	9.5	I1
	ABC Class 6	8.0	
	ABC Class 2 or 3	12.0	
24 1/2 Road (Site 2)	PCC	8.5	J1
	ABC Class 6	8.0	
	ABC Class 2 or 3	12.0	
24 1/2 Road & F 1/2 Road Roundabout (Site 1)	PCC	10.0	K1
	ABC Class 6	8.0	
	ABC Class 2 or 3	12.0	
25 Road (Site 1)	PCC	8.5	L1
	ABC Class 6	8.0	
	ABC Class 2 or 3	10.0	
25 Road & F 1/2 Road Intersection (Site 1)	PCC	10.0	M1
	ABC Class 6	8.0	
	ABC Class 2 or 3	12.0	
Foresight Circle and F 1/4 Road (Site 1)	PCC	7.0 (Note 1)	N1
	ABC Class 6	8.0	
	ABC Class 2 or 3	12.0	

Note 1: Minimum recommended thickness by AASHTO and CDOT is 7.0 inches for rigid pavement design.

RockSol recommends the pavement thicknesses shown in Table 10 for the 20-year design life or Table 11 be used since the PMED software accounts for site specific variables that AASHTO 1993 and 1998 do not. The 20-year design life is recommended since the top layer of most HMA pavements will require rehabilitation within 20 years after construction that should remove the top-down fatigue cracking along with other surface defects and there is no significant difference between the 20 and 30-year design lives for the predicted rutting and bottom-up fatigue cracking. HMA or Rigid pavement shall consist of CDOT-approved mix designs. The bottom layers of HMA should consist of Grading S or SX(100) PG 64-22 for all roads except Foresight Circle and F 1/4 Road. Grading SX(75) PG 64-22 is recommended on Foresight Circle and F 1/4 Road since the 20-year design traffic is less than 3,000,000 18k ESAL's. To resist rutting and thermal cracking damage, the top two inches of HMA should consist of Grading SX(100) PG 64-28 material. Grading SX(75) PG 64-28 is recommended for the top two inches of Foresight Circle and F 1/4 Road. Grading SX(75) may be feasible and the top layer for all roads but will decrease the resistance to rutting. ABC should consist of material meeting CDOT Class 6 Aggregate Base Course and pit run should consist of material meeting CDOT Class 2 or 3 Aggregate Base Course per CDOT 703.03.

#### **8.4 Subgrade Preparation (Prior to Pavement Construction)**

Prior to construction of new pavements on subgrade soils, the underlying subgrade should be properly prepared by removal of all organic matter (topsoil), debris, loose material, and any deleterious material identified by the Project Engineer followed by scarification, moisture conditioning and re-compaction. The minimum depth of scarification, moisture conditioning and re-compaction in all cases shall be 6 inches. Based on the results of our field and laboratory tests, A-1-a, A-4, and A-6 soils are anticipated to be encountered at existing pavement subgrade elevations within the project limits.

Materials classified as AASHTO A-1, A-2-4, A-2-5, and A-3 soils shall be compacted at plus or minus 2 percent of Optimum Moisture Content (OMC) and to at least 95 percent of maximum dry density determined in accordance with AASHTO T 180 as modified by CDOT CP 23. All other soil types shall be compacted to 95 percent of the maximum dry density determined in accordance with AASHTO T 99 as modified by CDOT CP 23. Soils with 35 percent fines or less shall be compacted at plus or minus 2 percent of OMC. Soils with greater than 35 percent fines shall be compacted at a moisture content equal to or above OMC to achieve stability of the compacted lift. Stability is defined as the absence of rutting or pumping as observed and documented by the Contractor's Process Control Representative and as approved by the Project Engineer. If the soils cannot be compacted and prove to be unstable at a moisture content equal to or above OMC, then the required moisture content for compaction may be reduced below OMC if approved by the Engineer.

Where areas of unstable, wet subgrade soils are encountered, overexcavation and replacement with Class 3 Aggregate Base Course meeting the following requirements:

- Maximum Particle Dimension: 8-inches
- Percent passing No. 4 sieve: 20% min.
- Minus 200 Screen Size: 20% max.
- Plasticity Index (PI): 7 maximum

Prior to pavement section construction, subgrade proof rolling with pneumatic tire equipment shall be performed using a minimum axle load of 18 kips per axle after specified subgrade compaction has been obtained. Areas found to be weak and those areas which exhibit soft spots, non-uniform deflection or excessive deflection as determined by the project engineer shall be ripped, scarified, wetted, or dried if necessary, and re-compacted to the requirements for density and moisture. Complete coverage of the proof roller will be required.

## 9.0 CONCRETE BOX CULVERT EXTENSION DISCUSSION

As part of this project, the existing three-cell concrete box culvert (CBC) structure that carries Leach Creek water under F 1/2 Road will be extended to the North to accommodate the parkway widening (See Image 3). RockSol anticipates the CBC extensions will be performed in a phased approach. RockSol understands the extensions will be with precast CBC components.

**Image 3 – North Side of F 1/2 Road CBC (Looking Southeast)**



The CBC extensions will require removal of accumulated soil and vegetation and control of the water flow in Leach Creek during construction. Currently, block retaining walls are in place on the north side of the CBC structure, as well as on the south side. The walls on the west side of Leach Creek are roughly parallel with 24 Road for significant distances while the walls on the east side are relatively short in length and constructed as typical wingwalls. The wall blocks appear to be consistent with the “Redi-Rock” type of blocks. Design information and as-built plans of the retaining walls were not available from the City, so the wall backfill type and bottom of wall elevations are not confirmed. Several construction-phase images of the wall construction appear to show some type of granular material was placed behind the retaining wall on the south side of F 1/2 Road. A plan sheet identified as a “Record Drawing” showing an end view of the existing CBC structure and a typical detail of a RediRock Wall are shown in Appendix O.

The short, existing block retaining wall on the northeast side of the CBC structure will need to be reconstructed as part of the CBC extension. The existing block retaining wall on the northwest



side of the CBC will require consideration as to whether it is left in place or modified to allow the CBC extension. An image of the west wall on the north side of the CBC is shown in Image 4.

**Image 4 – North Side of F 1/2 Road CBC (Looking southwest)**



Whether the west side retaining wall can be left in place or will require removal will depend on how the CBC will be extended. If a portion of the existing retaining wall is to be removed, RockSol anticipates temporary shoring will be required.

RockSol anticipates soft, yielding subgrade conditions will be encountered within the Leach Creek channel that will require stabilization to allow placement of the CBC extensions and wingwalls. The amount, or degree, of stabilization will depend on whether heavy equipment will need to access the bottom of the Leach Creek channel during construction or if all heavy equipment can stay out of the channel and work from the sides. It will be important that the stabilization of the CBC subgrade soils does not adversely impact, or otherwise destabilize, the existing retaining wall. Modifications to the existing retaining walls will also require continuation of the proper “behind the wall” drainage systems.

At a minimum, RockSol recommends the following subgrade stabilization and subgrade improvements for proper support of the CBC extensions. RockSol recommends ground improvement consisting of overexcavation of subgrade soils to a minimum depth of 5 feet below the bottom of the CBC bottom slab and replacement with at least 2-feet of a Class 3 Aggregate Base Course to provide a stable working platform. Over the Class 3 material, a minimum of 3 feet of crushed aggregate material meeting CDOT No. 57 Concrete Aggregate which is fully

wrapped every 12-inches with a CDOT approved Class 1 stabilization/separator geotextile. The crushed aggregate and geotextile shall extend horizontally beyond the limits of the CBC a minimum of 1 foot in each direction (north/south and east/west). Placement of the aggregate material should be in horizontal lifts with a maximum lift thickness of 6 inches. Compaction of each lift with vibratory methods using lightweight equipment is recommended.

RockSol evaluated three scenarios to illustrate the issues associated with subgrade stabilization for the CBC extension in front of the existing west side retaining wall and removal of a portion of the existing wall to allow CBC extension. Each scenario was modeled with RocScience Slide program. The scenarios are identified as Case 1, Case 2, and Case 3. A summary output of each model is included in Appendix P of this report.

Case 1 was our model which simulates the existing condition of the channel and existing wall. Our model is not intended to be a precise representation of the existing conditions but a reasonable approximation. We created this model to be the basis of Cases 2 and 3. The Factor of Safety (FOS) of Case 1 was 1.48 which indicates a satisfactory FOS. The observed conditions at the existing wall would indicate satisfactory wall performance, suggesting our model is appropriate.

Case 2 was prepared to model a scenario where the existing retaining wall is left in place and a limited subexcavation is performed adjacent to the wall to remove unstable channel soils prior to replacement with suitable materials and construction of the CBC extension. For our model we assumed the subexcavation extended 3.5 feet below the bottom of the blocks placed for the wall. We also assumed the water in the channel was controlled and kept at the bottom of the excavation. In this model a FOS of 0.961 was obtained indicating movement of the wall is likely unless the bottom of the wall is stabilized with some form of temporary, or permanent, shoring. Another consideration if the existing retaining wall is left in place is the compatibility of the edge of the CBC extension with the outside edge of the wall blocks.

Case 3 was prepared to model a scenario where a portion of the existing retaining wall is removed to allow extension of the CBC structure. Our model assumed a cut slope that extended to the same subexcavation elevation noted in Case 2. The cut slope extended to the back of the existing curb and gutter of 24 Road and did not remove any of the existing roadway structure. The cut slope obtained was approximately 1H:1.25V. With traffic loading considered in the roadway the resulting FOS was 0.996, indicating slope movement is likely without temporary, or permanent, shoring or flattening the cut slope. To flatten the cut slope a portion of the existing roadway of 24 Road would need to be removed and a temporary traffic detour condition created.

## 10.0 EARTHWORK

### New Embankment

To accommodate the new F 1/2 Road and widening of 24 Road, new embankment may be required along the roadway alignments. At some locations minor cuts may be required. Materials used to construct embankments, roadway side slopes, structure backfill, and aggregate base course materials should meet the material and moisture density control requirements specified Section 8.4 of this report.

At a minimum, the ground surface underlying all embankment fills should be carefully prepared by removing all organic matter (topsoil), scarification to a minimum depth of 6 inches and recompacting to the requirements for maximum dry density/compaction and moisture content presented in Section 8.4 of this report prior to fill placement.

Where fill material is to be placed on existing slopes steeper than 4 (H):1 (V), benching must be performed to tie the new fill into the existing slope. Benching into the existing slopes shall allow



sufficient bench width to accommodate placing and compaction equipment to operate in a horizontal orientation.

Broken concrete, broken asphalt, or other solid materials more than 6 inches in greatest dimension shall not be placed within embankment areas supporting the roadway shoulders and pavement structure. Claystone/shale materials shall not be used for construction of new embankment. Imported fill material used for embankment construction shall be compatible with designed side slopes. Material excavated from utility trenches may be used for backfilling provided it does not contain unsuitable material. Unsuitable material includes, but is limited to, topsoil, vegetation, brush, sod, trash, and other deleterious substances.

## 11.0 SEISMICITY DISCUSSION

### 11.1 General

The City of Grand Junction uses the 2018 International Building Code (IBC-2018) for development of seismic design parameters. The IBC-2018 references the American Society of Civil Engineers 7-16 (ASCE 7-16) seismic design code. Based on the subsurface conditions encountered, it is our opinion that the subject site meets criteria for Seismic Site Class D. Shear wave velocity testing was not performed by RockSol. Seismic design parameters for Seismic Site Class D are discussed below.

For final design, RockSol recommends performing shear wave velocity testing or performing penetration tests to a depth of 100 feet if determination of Seismic Site Class C conditions is necessary, otherwise Seismic Site Class D may be used for final design. Seismic design parameters for Seismic Site Class D are discussed below.

### 11.2 Seismic Design Parameters

Seismic design parameters were obtained from the United States Geological Survey (USGS) Earthquake Design Maps using the 2018 International Building Code specifications which reference ASCE 7-16. Values were obtained using the USGS site: <https://seismicmaps.org>. Since the proposed grandstands are structures, whose primary occupancy is public assembly with an occupant load greater than 300, the grandstands qualify as risk category III per Table 1604.5 of the *IBC-2018*. Interpolated values for Peak Ground Acceleration Coefficient (PGA), Spectral Acceleration Coefficient at Period 0.2 sec ( $S_s$ ), and Spectral Acceleration Coefficient at Period 1.0 sec ( $S_1$ ) were obtained using the latitude and longitude for the site. The seismic acceleration coefficients obtained (data based on 0.05-degree grid spacing) are presented in Table 14.

**Table 14 – Seismic Acceleration Coefficients**

F 1/2 Road and 24 Road (Latitude°/Longitude°)	Peak Ground Acceleration (PGA)	Spectral Acceleration Coefficient - $S_s$ (Period 0.2 sec)	Spectral Acceleration Coefficient - $S_1$ (Period 1.0 sec)
(39° 05' 56.69"/ -108° 36' 29.08")	0.13	0.236	0.065

The acceleration coefficients are then used to obtain Site Factors  $F_a$ , and  $F_v$  based on the defined Site Class as shown in Tables 1613.2.3(1) and 1613.2.3(2) of the *IBC-2018*. A summary of the Site Factor values obtained are shown in Table 15.

**Table 15 – Seismic Site Factor Values**

F 1/2 Road and 24 Road (Latitude°/Longitude°)	F <sub>pga</sub> (at zero-period on acceleration spectrum)	F <sub>a</sub> (for short period range of acceleration spectrum)	F <sub>v</sub> (for long period range of acceleration spectrum)
(39° 05' 56.69"/ -108° 36' 29.08")	1.54	1.6	2.4

Table 16 summarizes the Seismic Zone determination and horizontal response spectral Acceleration Coefficients ( $S_{D1}$ ) and ( $S_{DS}$ ) obtained for the proposed structures. Seismic Performance Zone determination is based on the value of the horizontal response spectral Acceleration Coefficient at 1.0 Seconds,  $S_{D1}$ , as determined by Eq. 16-39 of the IBC-2018 and the horizontal response spectral Acceleration Coefficient at 0.2 Seconds,  $S_{DS}$ , as determined by Eq. 16-38. Values for  $S_1$  and  $F_v$  are presented in Tables 14 and 15, shown above. The seismic performance zone was determined IBC-2018 Tables 1613.2.5(1) and (2).

**Table 16 – Seismic Performance Zone**

F 1/2 Road and 24 Road (Latitude°/Longitude°)	Acceleration Coefficient ( $S_{D1}$ )	Acceleration Coefficient, $S_{DS}$	Seismic Design Category
(39° 05' 56.69"/ -108° 36' 29.08")	0.105	0.252	B

Note: Seismic Design Category B (For Risk Category II) is assigned when  $0.167g \leq S_{DS} < 0.33g$

## 12.0 OTHER DESIGN AND CONSTRUCTION CONSIDERATIONS

Proper construction practices, in accordance with the Colorado Department of Transportation (CDOT) 2021 Standard Specifications for Road and Bridge Construction; the City of Grand Junction Standard Specifications for Road and Bridge Construction; and the City of Grand Junction Transportation Engineering Design Standards, should be followed during site preparation, earthwork, excavations, roadway and bridge construction, and embankment and retaining wall construction for the suitable long-term performance of the proposed improvements. Excavation support should be provided to maintain onsite safety and the stability of excavations and slopes. Excavations shall be constructed in accordance with local, state, and federal regulations including OSHA guidelines. The contractor must provide a competent person to determine compliance with OSHA excavation requirements. For preliminary planning, existing fill material and native soils may be considered as OSHA Type C soils.

Surface drainage patterns may be altered during construction and local landscape irrigation (if any) must be controlled to prevent excessive moisture infiltration into the subgrade soils during and after construction.

Environmentally contaminated material, if encountered, should be characterized, and removed under the direction of the project environmental consultant. Design and construction plans should be reviewed, and onsite construction should be observed by the professional engineers.

### **13.0 LIMITATIONS**


This geotechnical investigation was conducted in general accordance with the scope of work. RockSol's geotechnical practices are similar to those used in Colorado with similar soil conditions and based on our understanding of the proposed work. This report has been prepared for use by the City of Grand Junction for the project described in this report. The report is based on our exploratory boreholes and does not consider variations in the subsurface conditions that may exist between boreholes. Additional investigation is required to address such variation. If during construction activities, materials or water conditions appear to be different from those described herein, RockSol should be advised at once so that a re-evaluation of the recommendations presented in this report can be made. RockSol is not responsible for liability associated with interpretation of subsurface data by others.





**Figure 1: F.5 Road Parkway Conceptual Layout**  
24 Road to 24.5 Road

PUBLIC WORKS  
ENGINEERING DIVISION




REVISION	DESCRIPTION	DATE	DATE	DATE	DATE
REVISION 1		DESIGNED BY JCS	DATE 2019	DESIGNED BY JCS	DATE 2019
REVISION 2		CHECKED BY TGP	DATE 2019	CHECKED BY TGP	DATE 2019
REVISION 3		APPROVED BY TGP	DATE 2019	APPROVED BY TGP	DATE 2019





**Figure 2: F.5 Road Parkway Conceptual Layout**  
24.5 Road to 25 Road

PUBLIC WORKS  
ENGINEERING DIVISION



DATE	DATE	DATE	DATE
DESIGNED BY	DESIGNED BY	CHECKED BY	APPROVED BY
DATE	DATE	DATE	DATE

REVISION	DATE	DESCRIPTION





**Figure 3: F:5 Road Parkway Conceptual Layout**  
 25 Road from F:5 Road to F:5 Road / Patterson Road

PUBLIC WORKS  
 ENGINEERING DIVISION



DATE	DATE
DESIGNED BY	DATE
CHECKED BY	DATE
APPROVED BY	DATE

DESCRIPTION	DATE
REVISION	
REVISION	
REVISION	
REVISION	





**Figure 4: F.5 Road Parkway Conceptual Layout**  
 25 Road from Buchanan Drive to F.5 Road

PUBLIC WORKS  
 ENGINEERING DIVISION

CITY OF  
**Grand Junction**  
 COLORADO

REVISION	DATE	DESCRIPTION

DATE	DATE	DATE	DATE

DRAWN BY: JGS    DATE: 2019  
 DESIGNED BY: JGS    DATE: 2019  
 CHECKED BY: JCP    DATE: 2019  
 APPROVED BY: JCP    DATE: 2019

SCALES: 1" = 50'


WESTERN COLORADO UNIVERSITY  
 MESA COUNTY SHERIFF'S POSSE  
 CHRONOS PROPERTIES  
 LEO GRAP  
 BEROAH D HOEDEL-DAMS  
 BARN LLC  
 APPERWOOD LANE LLC  
 APPERWOOD LANE LLC  
 JIMMY JONES  
 CHARLES FACKOCK  
 APX AVE  
 DEMENSE AVE  
 COPPER CANYON DRIVE  
 WAITE AVE  
 GARRETT WAY  
 F 1/2 ROAD  
 BLICHMANN AVE  
 25 ROAD  
 BUCHANAN DRIVE  
 HAYES DR





**Figure 5: F.5 Road Parkway**  
 Conceptual Layout 24.5 Road from  
 Brookwillow Loop to Tennis Courts

PUBLIC WORKS  
 ENGINEERING DIVISION



REVISION	DATE	DESCRIPTION	DATE	DATE	DATE
REVISION A					
REVISION A					
REVISION A					

DRAWN BY	JCS	DATE	2019
DESIGNED BY	JCS	DATE	2019
CHECKED BY	TCP	DATE	2019
APPROVED BY	TCP	DATE	2019

## **APPENDIX A**

### **LEGEND AND INDIVIDUAL BOREHOLE LOGS**














**CLIENT** City of Grand Junction

**PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening

**PROJECT NUMBER** 599.37


**PROJECT LOCATION** Grand Junction, Colorado

## LITHOLOGY

- |   |                              |   |                                     |
|---|------------------------------|---|-------------------------------------|
|  | <b>Asphalt Pavement</b>      |  | <b>Fill - Aggregate Base Course</b> |
|  | <b>Fill - SAND, gravelly</b> |  | <b>Fill - SAND, clayey to silty</b> |
|  | <b>Fill - CLAY</b>           |  | <b>Native - SAND</b>                |
|  | <b>Native - CLAY</b>         |  | <b>Native - CLAY, silty</b>         |
|  | <b>Native - CLAY, sandy</b>  |  | <b>Native - GRAVEL, silty</b>       |
|  | <b>Bedrock - SHALE</b>       |   |                                     |

## SAMPLE TYPE

 Bulk Sample (Auger Cuttings)

 MODIFIED CALIFORNIA SAMPLER  
2.5" O.D. AND 2" I.D.  
WITH BRASS LINERS INCLUDED




 SPLIT SPOON SAMPLER  
2" O.D. AND 1 3/8" I.D.  
NO LINERS

Fines Content indicates amount of material, by weight, passing the US No 200 Sieve (%)

15/12 Indicates 15 blows of a 140 pound hammer falling 30 inches was required to drive the sampler 12 inches.









50/11 Indicates 50 blows of a 140 pound hammer falling 30 inches was required to drive the sampler 11 inches.

5,5,5 Indicates 5 blows, 5 blows, 5 blows of a 140 pound hammer falling 30 inches was required to drive the sampler 18 inches.


-  GROUND WATER LEVEL AT TIME OF DRILLING
-  GROUND WATER LEVEL AT 2ND MEASUREMENT
-  GROUND WATER LEVEL AT 3RD MEASUREMENT

















**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** 24.5 Rd., SB lane, at Tennis Court  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			Asphalt pavement, approximately 6 inches thick										
			Aggregate Base Course, approximately 11 inches thick	B BULK									
2.5			(Native) CLAY, with sand, moist to very moist, brown, medium stiff										
				MC	6/12			103.7	18.9				
5.0													
			<b>Approximate Bulk Depth 2-10</b> Liquid Limit= 27 Plastic Limit= 13 Plasticity Index= 14 Fines Content= 83.3	B BULK						27	13	14	83.3
7.5													
10.0													
			Bottom of hole at 10.0 feet.										







**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_ **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** 24.5 Rd. SB Shoulder, just west of 6 Rd.  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** 7.0 ft on 10/20/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, sandy, very moist, brown, very stiff										
	2.5		<p><b>Approximate Bulk Depth 0-7</b>            Liquid Limit= 28            Plastic Limit= 13            Plasticity Index= 15            Fines Content= 68.9</p>	BULK						28	13	15	68.9
	5.0												
			Bottom of hole at 7.0 feet.										

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_ **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** McCracken Drilling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** 24.5 Rd. NB lane, just south of roundabout  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			Asphalt pavement, approximately 5 inches thick										
			Aggregate Base Course, approximately 12 inches thick	B BULK									
			(Native) CLAY, sandy, very moist, brown, medium stiff										
2.5													
													
													
													
5.0			<b>Approximate Bulk Depth 2-9</b> Liquid Limit= 28 Plastic Limit= 12 Plasticity Index= 16 Fines Content= 66.6	MC	5/12			105.8	19.6				
				B BULK						28	12	16	66.6
													
													
													
													
			Bottom of hole at 9.0 feet.										





**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_ **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** 675 24.5 Rd., SB shoulder  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, silty, very wet, brown, very stiff										
2.5			Large rock @ 2'-3'										
5.0													
7.5													
10.0			Bottom of hole at 10.0 feet.										





**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_ **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** 24.5 Rd. NB lane, @ F 3/8 Rd  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			Asphalt pavement, approximately 5 inches thick										
			Aggregate Base Course										
			(Fill) SAND, gravelly										
2.5													
			(Native) CLAY, silty, with sand, very moist, brown, very stiff										
5.0													
			<b>Approximate Bulk Depth 4-10</b> Liquid Limit= 19 Plastic Limit= 15 Plasticity Index= 4 Fines Content= 73.1	B BULK						19	15	4	73.1
7.5													
10.0			Bottom of hole at 10.0 feet.										

LOG - STANDARD 599.37\_CITY OF GJ PARKWAY PROJECT.GPJ 12/9/21

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/4/21      **COMPLETED** 10/4/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** \_\_\_\_\_  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/4/21


ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, moist to very moist, brown, soft										
	2.5		<u>Approximate Bulk Depth 0-5</u> Liquid Limit= 38 Plastic Limit= 19 Plasticity Index= 19 Fines Content= 88.8 Sulfate= 0.38	BULK			0.38			38	19	19	88.8
				MC	3/12	0.0		97.9	19.5				
	5.0												
	7.5												
	10.0		Bottom of hole at 10.0 feet.										

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/5/21      **COMPLETED** 10/5/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** Field along new proposed F.5 Rd  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/5/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, moist, brown, stiff										
2.5			<b>Approximate Bulk Depth 0-6</b> Liquid Limit= 37 Plastic Limit= 19 Plasticity Index= 18 Fines Content= 92.3	BULK						37	19	18	92.3
				MC	9/12			105.9	16.9				
5.0													
7.5													
10.0			Bottom of hole at 10.0 feet.										



**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/5/21      **COMPLETED** 10/5/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** Field near 24.5 Rd and new F.5 Rd  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/5/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, moist, brown, soft										
	2.5		<u>Approximate Bulk Depth 0-4</u> Liquid Limit= 33 Plastic Limit= 18 Plasticity Index= 15 Fines Content= 92.2	B BULK						33	18	15	92.2
	5.0			MC	3/12			103.3	13.1				
	7.5												
	10.0		Bottom of hole at 10.0 feet.										


**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/5/21      **COMPLETED** 10/5/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** NE side of 24.5 Rd. and F.5 Rd.  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/5/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, with sand, moist, brown, soft										
	2.5		<b>Approximate Bulk Depth 0-5</b> Liquid Limit= 37 Plastic Limit= 21 Plasticity Index= 16 Fines Content= 72.2 Sulfate= 0.16	BULK			0.16			37	21	16	72.2
	5.0												
	7.5		(Native) CLAY, silty, very moist, brown, soft										
	10.0		Bottom of hole at 10.0 feet.										

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION**      **STATION NO.**        
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:**        
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**        
**NOTES**      **WATER DEPTH** None Encountered on 10/20/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			Asphalt pavement, approximately 6 inches thick										
			Aggregate Base Course, approximately 6 inches thick										
			(Fill) SAND, gravelly										
2.5			(Native) CLAY, with sand, very moist, brown, very stiff										
			<b>Approximate Bulk Depth 2-10</b> Liquid Limit= 27 Plastic Limit= 14 Plasticity Index= 13 Fines Content= 81.3 Sulfate= 0.26	B BULK			0.26		27	14	13	81.3	
5.0													
7.5													
10.0			Bottom of hole at 10.0 feet.										

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/5/21      **COMPLETED** 10/5/21      **GROUND ELEVATION** \_\_\_\_\_ **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** SE side of 24.5 Rd and F.5 Rd  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/5/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, with gravel, moist to very moist, brown, stiff										
2.5			<b>Approximate Bulk Depth 0-7</b> Liquid Limit= 32 Plastic Limit= 18 Plasticity Index= 14 Fines Content= 79.9	MC	11/12			103.0	21.1				
				B BULK							32	18	14
5.0													
7.5													
10.0			Bottom of hole at 10.0 feet.										



**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/5/21      **COMPLETED** 10/5/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** 24 3/4 RD and new F.5 Rd (west side)  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/5/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, with sand, slightly moist, brown, very stiff										
2.5			<b>Approximate Bulk Depth 0-5</b> Liquid Limit= 30 Plastic Limit= 18 Plasticity Index= 12 Fines Content= 79.6	BULK						30	18	12	79.6
				MC	22/12			109.5	4.8				73.7
5.0			(Native) CLAY, silt, moist, brown, stiff										
7.5													
10.0			Bottom of hole at 10.0 feet.										



**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/5/21      **COMPLETED** 10/5/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** New F.5 alignment, Vacant land  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/5/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, silty with sand, slightly moist to moist, brown, medium stiff										
	2.5		<b>Approximate Bulk Depth 0-5</b> Liquid Limit= 26 Plastic Limit= 19 Plasticity Index= 7 Fines Content= 75.4 Sulfate= 0.28	BULK			0.28			26	19	7	75.4
	5.0			MC	6/12			107.2	9.2				62.4
	7.5												
	10.0		Bottom of hole at 10.0 feet.										





**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/5/21      **COMPLETED** 10/5/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** East end new proposed F.5, west of 25 Rd.  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/5/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, moist, brown, soft										
			<b>Approximate Bulk Depth 0-3</b> Liquid Limit= 33 Plastic Limit= 18 Plasticity Index= 15 Fines Content= 89.5	BULK						33	18	15	89.5
2.5													
5.0													
7.5			(Native) CLAY, silty, very moist, brown, soft										
10.0			Bottom of hole at 10.0 feet.										

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_ **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** Private property, 653 25 Rd. (new road)  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21


ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0			(Native) CLAY, with sand, moist, brown, medium stiff										
	0-5		<b>Approximate Bulk Depth 0-5</b> Liquid Limit= 30 Plastic Limit= 20 Plasticity Index= 10 Fines Content= 79.1 Sulfate= 1.04	BULK			1.04			30	20	10	79.1
	2-3			MC	5/12			101.4	18.3				76.5
	5		Bottom of hole at 5.0 feet.										

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_ **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** 25 Rd. NB lane, Front 645 25 Rd  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21







ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			Asphalt pavement, approximately 6 inches thick										
			Aggregate Base Course, approximately 6 inches thick										
			(Fill) SAND, gravelly										
2.5													
			(Native) CLAY, silty, very moist, brown, stiff	BULK									
5.0													
7.5													
10.0			Bottom of hole at 10.0 feet.										









**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_ **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** Corner of F.5 and 25 Rd, ~18' off 25 Rd  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, sandy, very moist, brown, very soft	BULK									
2.5													
5.0													
7.5													
10.0			Bottom of hole at 10.0 feet.										





**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** F 1/4 Rd. WB lane  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			Asphalt pavement, approximately 2 inches thick Aggregate Base Course, approximately 10 inches thick										
			(Native) CLAY, silty, very moist, brown, very stiff										
2.5				BULK									
5.0													
7.5													
10.0			Bottom of hole at 10.0 feet.										

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_ **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** \_\_\_\_\_  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:** \_\_\_\_\_  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			Asphalt pavement, approximately 6 inches thick										
			Aggregate Base Course, approximately 4 inches thick										
			(Fill) CLAY, silty, slightly moist to moist, brown, hard	MC	24/12			114.2	10.8				
			(Fill) SAND, gavelly										
2.5			(Native) CLAY, silty, very moist, brown, stiff										
5.0				BULK									
7.5													
10.0			Bottom of hole at 10.0 feet.										

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_ **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** Foresight Circle, EB, ~250' E of 25 Rd  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21




ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			Asphalt pavement, approximately 3 inches thick										
			Aggregate Base Course, approximately 9 inches thick										
			(Fill) SAND, gravelly										
2.5			(Native) CLAY, silty, very moist, brown, stiff	B BULK									
5.0													
7.5													
10.0			Bottom of hole at 10.0 feet.										



**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/20/21      **COMPLETED** 10/20/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** Field N of 6.5 Climb Gym - new road  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      **WATER DEPTH** None Encountered on 10/20/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0.0			(Native) CLAY, with sand, slightly moist, brown, stiff										
2.5				MC	14/12			95.8	7.1				96.5
5.0			<u>Approximate Bulk Depth 0-10</u> Liquid Limit= 28 Plastic Limit= 16 Plasticity Index= 12 Fines Content= 84.7 Sulfate= 0.14	BULK			0.14			28	16	12	84.7
10.0			Bottom of hole at 10.0 feet.										









**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/4/21      **COMPLETED** 10/4/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** NE corner of 24 Rd and F.5 Rd - wingwall  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:**  
**NOTES** \_\_\_\_\_      ▼ **WATER DEPTH** 7.0 ft on 10/4/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	BLOW COUNTS	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0			(Native) CLAY, with sand, moist to wet, brown, soft										
	0-5		<u>Approximate Bulk Depth 0-5</u> Liquid Limit= 27 Plastic Limit= 15 Plasticity Index= 12 Fines Content= 76.6 Sulfate= 0.51	BULK			0.51			27	15	12	76.6
	5-13												
	13-14												
	14-15												
	15-16			SS	1/2/2				28.5				84.1
	16-20												
	20-21.5			SS	1/2/2				29.5				49.5
	21.5		Bottom of hole at 21.5 feet.										

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/4/21      **COMPLETED** 10/4/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** NE Corner of F.5 Rd and 24 Rd underpass  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:** ▼ **1ST DEPTH** 7.0 ft on 10/4/21  
**NOTES** \_\_\_\_\_      ▼ **2ND DEPTH** 5.1 ft on 11/1/21      ▼ **3RD DEPTH** 4.8 ft on 11/30/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0			(Native) CLAY, sandy, moist to wet, soft										
	5		<b>Approximate Bulk Depth 0-5</b> Liquid Limit= 25 Plastic Limit= 15 Plasticity Index= 10 Fines Content= 68.2	BULK						25	15	10	68.2
	10			MC		-0.2		87.9	25.0				55.1
	20			SS	1/1/2		0.47		29.0				58.4
	25		(Native) SAND, with silt and gravel, slightly moist, brown to gray, medium stiff to very hard										
	30			SS	81/12				6.4	NP	NP	NP	7.7
	35												
	40		(Bedrock) Shale, very moist to slightly moist, gray, medium stiff to very hard										
			Bottom of hole at 40.3 feet.	SS	50/3				15.1				42.1

**CLIENT** City of Grand Junction      **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37      **PROJECT LOCATION** Grand Junction, Colorado  
**DATE STARTED** 10/4/21      **COMPLETED** 10/4/21      **GROUND ELEVATION** \_\_\_\_\_      **STATION NO.** \_\_\_\_\_  
**DRILLING CONTRACTOR** Colorado Drilling and Sampling      **LATITUDE** 39.1      **LONGITUDE** 108.6  
**DRILLING METHOD** Solid Stem Auger      **HOLE SIZE** 4.25"      **BORING LOCATION:** SE corner of F.5 Rd and 24 Rd underpass  
**LOGGED BY** D. Compton      **HAMMER TYPE** Automatic      **GROUND WATER LEVELS:** ▼ **1ST DEPTH** 10.0 ft on 10/4/21  
**NOTES** \_\_\_\_\_      ▼ **2ND DEPTH** 10.3 ft on 11/1/21      ▼ **3RD DEPTH** 10.6 ft on 11/30/21

ELEVATION (ft)	DEPTH (ft)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	SWELL POTENTIAL (%)	SULFATE (%)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	ATTERBERG LIMITS			FINES CONTENT (%)
										LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	
0			(Native) GRAVEL, sandy, moist, brown, stiff	B BULK									58.1
			(Native) CLAY, with sand, very moist to wet, brown, soft	B BULK						28	15	13	74.9
	5		<b>Approximate Bulk Depth 0-2</b> Fines Content= 58.1	MC	4/12	-1.7		102.2	19.6				
	10		<b>Approximate Bulk Depth 2-4</b> Liquid Limit= 28 Plastic Limit= 15 Plasticity Index= 13 Fines Content= 74.9										
	10			SS	1/1/1				26.6	29	16	13	94.4
	20			SS	1/1/1		0.19		34.4				83.7
	25		(Native) CLAY, with sand, slightly moist to moist, brown, hard										
	30			SS	71/10		0.15		6.2				
	40		(Bedrock) SHALE, slightly moist, gray, very hard Bottom of hole at 40.1 feet.	SS	50/1				14.8				53.2



## **APPENDIX B**

### **SUMMARY OF LABORATORY TEST RESULTS**



CLIENT City of Grand Junction

PROJECT NUMBER 599.37

PROJECT NAME F-5 Road Parkway and 24.5 Road Widening

PROJECT LOCATION Grand Junction, Colorado

**SUMMARY OF PHYSICAL & CHEMICAL TEST RESULTS**  
PAGE 1 OF 2

Borehole	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	Swell Potential (%)	% #200 Sieve	Classification		Water Content (%)	Dry Density (pcf)	Unconfined Compressive Strength (psi)	Sulfate (%)	Resistivity (ohm-cm)	pH	Chlorides (%)	Proctor	
							USCS	AASHTO								MDD	OMC
B-1	2-10	27	13	14		83	CL	A-6 (9)									
B-1	3								18.9	103.7							
B-2	0-7	28	13	15		69	CL	A-6 (7)									
B-3	2-9	28	12	16		67	CL	A-6 (8)									
B-3	4								19.6	105.8							
B-5	5								24.9	98.3							
B-6	4-10	19	15	4		73	CL-ML	A-4 (0)									
F-1	0-5	38	19	19		89	CL	A-6 (17)			0.38	420 @ 28.2%	8.0	0.0787			
F-1	3				0.0				19.5	97.9							
F-2	0-6	37	19	18		92	CL	A-6 (17)									
F-2	3								16.9	105.9							
F-3	0-4	33	18	15		92	CL	A-6 (13)									
F-3	4								13.1	103.3							
F-4	0-5	37	21	16		72	CL	A-6 (10)			0.16	580 @ 26.4%	8.0	0.0332			
F-5	2-10	27	14	13		81	CL	A-6 (8)			0.26	690 @ 19.0%	8.2	0.0159			
F-6	0-7	32	18	14		80	CL	A-6 (10)									
F-6	2								21.1	103.0							
F-7	0-5	30	18	12		80	CL	A-6 (8)									
F-7	3					74			4.8	109.5							
F-8	0-5	26	19	7		75	CL-ML	A-4 (3)			0.28	970 @ 19.8%	7.9	0.0157			
F-8	5					62			9.2	107.2							
F-9	0-3	33	18	15		90	CL	A-6 (13)									
F-10	0-5	30	20	10		79	CL	A-4 (7)			1.04	320 @ 25.3%	8.0	0.1012			
F-10	2					76			18.3	101.4							
F-14	1								10.8	114.2							
F-16	0-10	28	16	12		85	CL	A-6 (8)			0.14	670 @ 25.2%	8.1	0.0054			
F-16	2					97			7.1	95.8							
LC-1	0-5	27	15	12		77	CL	A-6 (7)			0.51	530 @ 19.6%	8.1	0.0334			
LC-1	12					84			28.5								
LC-1	20					50			29.5								



CLIENT City of Grand Junction

PROJECT NUMBER 599.37

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT LOCATION Grand Junction, Colorado

**SUMMARY OF PHYSICAL & CHEMICAL TEST RESULTS**  
PAGE 2 OF 2


Borehole	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	Swell Potential (%)	% <#200 Sieve	Classification		Water Content (%)	Dry Density (pcf)	Unconfined Compressive Strength (psi)	Sulfate (%)	Resistivity (ohm-cm)	pH	Chlorides (%)	Proctor	
							USCS	AASHTO								MDD	OMC S/M
LC-2	0-5	25	15	10		68	CL	A-4 (4)									
LC-2	10				-0.2	55			25.0	87.9							
LC-2	20					58			29.0		0.47						
LC-2	30	NP	NP	NP		8	SP-SM	A-1-a (0)	6.4								
LC-2	40					42			15.1								
LC-3	0-2					58											
LC-3	2-4	28	15	13		75	CL	A-6 (7)									
LC-3	5				-1.7				19.6	102.2							
LC-3	10	29	16	13		94	CL	A-6 (11)	26.6								
LC-3	20					84			34.4		0.19		8.1				
LC-3	30								6.2		0.15						
LC-3	40					53			14.8								

CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado



Specimen Identification	LL	PL	PI	Fines	Classification
● B-1 2.0-10.0	27	13	14	83.3	LEAN CLAY with SAND (CL) (A-6)
▣ B-2 0.0-7.0	28	13	15	68.9	SANDY LEAN CLAY (CL) (A-6)
▲ B-3 2.0-9.0	28	12	16	66.6	SANDY LEAN CLAY (CL) (A-6)
★ B-5 3.0-10.0	33	14	19	88.6	LEAN CLAY (CL) (A-6)
⊙ B-6 4.0-10.0	19	15	4	73.1	SILTY CLAY with SAND (CL-ML) (A-4)
⊕ F-1 0.0-5.0	38	19	19	88.8	LEAN CLAY (CL) (A-6)
○ F-2 0.0-6.0	37	19	18	92.3	LEAN CLAY (CL) (A-6)
△ F-3 0.0-4.0	33	18	15	92.2	LEAN CLAY (CL) (A-6)
⊗ F-4 0.0-5.0	37	21	16	72.2	LEAN CLAY with SAND (CL) (A-6)
⊕ F-5 2.0-10.0	27	14	13	81.3	LEAN CLAY with SAND (CL) (A-6)
□ F-6 0.0-7.0	32	18	14	79.9	LEAN CLAY with GRAVEL (CL) (A-6)
⊕ F-7 0.0-5.0	30	18	12	79.6	LEAN CLAY with SAND (CL) (A-6)
⊕ F-8 0.0-5.0	26	19	7	75.4	SILTY CLAY with SAND (CL-ML) (A-4)
★ F-9 0.0-3.0	33	18	15	89.5	LEAN CLAY (CL) (A-6)
⊗ F-10 0.0-5.0	30	20	10	79.1	LEAN CLAY with SAND (CL) (A-4)
■ F-16 0.0-10.0	28	16	12	84.7	LEAN CLAY with SAND (CL) (A-6)
◆ LC-1 0.0-5.0	27	15	12	76.6	LEAN CLAY with SAND (CL) (A-6)
◇ LC-2 0.0-5.0	25	15	10	68.2	SANDY LEAN CLAY (CL) (A-4)
× LC-2 30.0	NP	NP	NP	7.7	POORLY GRADED SAND with SILT and GRAVEL (SP-SM) (A-1-a)
■ LC-3 2.0-4.0	28	15	13	74.9	LEAN CLAY with SAND (CL) (A-6)

ATTERBERG LIMITS - STANDARD 599.37 CITY OF GJ PARKWAY PROJECT.GPJ ROCKSOL TEMPLATE.GDT 12/9/21








# GRAIN SIZE DISTRIBUTION

CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification	Classification		LL	PL	PI	Cc	Cu		
● B-1 2.0-10.0	LEAN CLAY with SAND (CL) (A-6)		27	13	14				
■ B-2 0.0-7.0	SANDY LEAN CLAY (CL) (A-6)		28	13	15				
▲ B-3 2.0-9.0	SANDY LEAN CLAY (CL) (A-6)		28	12	16				
★ B-5 3.0-10.0	LEAN CLAY (CL) (A-6)		33	14	19				
⊙ B-6 4.0-10.0	SILTY CLAY with SAND (CL-ML) (A-4)		19	15	4				
Specimen Identification	D100	D60	D30	D10	%Gravel	%Coarse Sand	%Fine Sand	%Silt	%Clay
● B-1 2.0-10.0	19				2.8	2.3	11.6		83.3
■ B-2 0.0-7.0	19				7.2	4.5	19.4		68.9
▲ B-3 2.0-9.0	12.5				8.1	7.6	17.7		66.6
★ B-5 3.0-10.0	12.5				2.4	2.2	6.8		88.6
⊙ B-6 4.0-10.0	19				4.5	2.5	19.9		73.1




# GRAIN SIZE DISTRIBUTION

CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification	Classification		LL	PL	PI	Cc	Cu
● F-1 0.0-5.0	LEAN CLAY (CL) (A-6)		38	19	19		
▣ F-2 0.0-6.0	LEAN CLAY (CL) (A-6)		37	19	18		
▲ F-3 0.0-4.0	LEAN CLAY (CL) (A-6)		33	18	15		
★ F-4 0.0-5.0	LEAN CLAY with SAND (CL) (A-6)		37	21	16		
◎ F-5 2.0-10.0	LEAN CLAY with SAND (CL) (A-6)		27	14	13		

Specimen Identification	D100	D60	D30	D10	%Gravel	%Coarse Sand	%Fine Sand	%Silt	%Clay
● F-1 0.0-5.0	9.5				0.9	1.2	9.1		88.8
▣ F-2 0.0-6.0	4.75				0.3	1.2	6.2		92.3
▲ F-3 0.0-4.0	9.5				0.6	1.0	6.2		92.2
★ F-4 0.0-5.0	25				7.2	4.8	15.7		72.2
◎ F-5 2.0-10.0	19				4.3	3.2	11.1		81.3




# GRAIN SIZE DISTRIBUTION

CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification	Classification		LL	PL	PI	Cc	Cu
● F-6 0.0-7.0	LEAN CLAY with GRAVEL (CL) (A-6)		32	18	14		
☒ F-7 0.0-5.0	LEAN CLAY with SAND (CL) (A-6)		30	18	12		
▲ F-7 3.0	LEAN CLAY with SAND (CL) (A-6)						
★ F-8 0.0-5.0	SILTY CLAY with SAND (CL-ML) (A-4)		26	19	7		
◎ F-8 5.0	SILTY CLAY with SAND (CL-ML) (A-4)						

Specimen Identification	D100	D60	D30	D10	%Gravel	%Coarse Sand	%Fine Sand	%Silt	%Clay
● F-6 0.0-7.0	25				12.5	1.8	5.8		79.9
☒ F-7 0.0-5.0	12.5				0.8	1.7	17.9		79.6
▲ F-7 3.0	0.075								73.7
★ F-8 0.0-5.0	19				1.8	2.7	20.1		75.4
◎ F-8 5.0	0.075								62.4




# GRAIN SIZE DISTRIBUTION

CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification	Classification	LL	PL	PI	Cc	Cu
● F-9 0.0-3.0	LEAN CLAY (CL) (A-6)	33	18	15		
☒ F-10 0.0-5.0	LEAN CLAY with SAND (CL) (A-4)	30	20	10		
▲ F-10 2.0	LEAN CLAY with SAND (CL) (A-4)					
★ F-16 0.0-10.0	LEAN CLAY with SAND (CL) (A-6)	28	16	12		
◎ F-16 2.0	LEAN CLAY with SAND (CL) (A-6)					

Specimen Identification	D100	D60	D30	D10	%Gravel	%Coarse Sand	%Fine Sand	%Silt	%Clay
● F-9 0.0-3.0	9.5				0.5	1.1	8.9		89.5
☒ F-10 0.0-5.0	4.75				0.8	2.7	17.4		79.1
▲ F-10 2.0	0.075								76.5
★ F-16 0.0-10.0	4.75				0.3	1.1	13.9		84.7
◎ F-16 2.0	0.075								96.5

# GRAIN SIZE DISTRIBUTION




RockSol Consulting Group, Inc.

CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification	Classification		LL	PL	PI	Cc	Cu		
● LC-1 0.0-5.0	LEAN CLAY with SAND (CL) (A-6)		27	15	12				
☒ LC-1 12.0	LEAN CLAY with SAND (CL) (A-6)								
▲ LC-1 20.0	LEAN CLAY with SAND (CL) (A-6)								
★ LC-2 0.0-5.0	SANDY LEAN CLAY (CL) (A-4)		25	15	10				
◎ LC-2 10.0	SANDY LEAN CLAY (CL) (A-4)								
Specimen Identification	D100	D60	D30	D10	%Gravel	%Coarse Sand	%Fine Sand	%Silt	%Clay
● LC-1 0.0-5.0	63				8.6	2.1	12.7		76.6
☒ LC-1 12.0	0.075								84.1
▲ LC-1 20.0	1.18	0.092			0.0	0.2	50.2		49.5
★ LC-2 0.0-5.0	50				15.9	3.1	12.8		68.2
◎ LC-2 10.0	0.075								55.1

GRADATION - STANDARD 599.37 - CITY OF GJ PARKWAY PROJECT.GPJ ROCKSOL TEMPLATE.GDT 12/9/21



# GRAIN SIZE DISTRIBUTION




RockSol Consulting Group, Inc.

CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification	Classification	LL	PL	PI	Cc	Cu			
● LC-2 20.0	<b>SANDY LEAN CLAY (CL) (A-4)</b>								
■ LC-2 30.0	<b>POORLY GRADED SAND with SILT and GRAVEL (SP-SM) (A-1-a)</b>	NP	NP	NP	0.33	57.77			
▲ LC-2 40.0	<b>POORLY GRADED SAND with SILT and GRAVEL</b>								
★ LC-3 0.0-2.0	<b>SANDY GRAVEL</b>								
◎ LC-3 2.0-4.0	<b>LEAN CLAY with SAND (CL) (A-6)</b>	28	15	13					
Specimen Identification	D100	D60	D30	D10	%Gravel	%Coarse Sand	%Fine Sand	%Silt	%Clay
● LC-2 20.0	0.075								58.4
■ LC-2 30.0	37.5	6.442	0.484	0.112	53.3	18.7	20.3		7.7
▲ LC-2 40.0	0.075								42.1
★ LC-3 0.0-2.0	37.5	0.093			23.8	5.7	12.4		58.1
◎ LC-3 2.0-4.0	19				10.4	3.8	10.9		74.9

GRADATION - STANDARD 599.37 - CITY OF GJ PARKWAY PROJECT.GPJ ROCKSOL TEMPLATE.GDT 12/9/21




# GRAIN SIZE DISTRIBUTION

CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado




COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification	Classification	LL	PL	PI	Cc	Cu
● LC-3 10.0	LEAN CLAY (CL) (A-6)	29	16	13		
☒ LC-3 20.0	LEAN CLAY					
▲ LC-3 40.0	LEAN CLAY					

Specimen Identification	D100	D60	D30	D10	%Gravel	%Coarse Sand	%Fine Sand	%Silt	%Clay
● LC-3 10.0	9.5				1.5	0.7	3.5	94.4	
☒ LC-3 20.0	0.075							83.7	
▲ LC-3 40.0	0.075							53.2	

**CLIENT** City of Grand Junction **PROJECT NAME** F.5 Road Parkway and 24.5 Road Widening  
**PROJECT NUMBER** 599.37 **PROJECT LOCATION** Grand Junction, Colorado



SWELL - STANDARD 599.37\_CITY OF GJ PARKWAY PROJECT.GPJ ROCKSOL TEMPLATE.GDT 12/9/21


Specimen Identification	Classification	Swell/Consol. (%)	$\gamma_d$ (pcf)	MC%
● F-1                      3	<b>CLAY</b>	<b>0.0</b>	<b>97.9</b>	<b>19.5</b>

CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado



SWELL - STANDARD 599.37\_CITY OF GJ PARKWAY PROJECT.GPJ ROCKSOL TEMPLATE.GDT 12/9/21


Specimen Identification	Classification	Swell/Consol. (%)	$\gamma_d$ (pcf)	MC%
● F-3                      4	CLAY		103.3	13.1

CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado



SWELL - STANDARD 599.37\_CITY OF GJ PARKWAY PROJECT.GPJ ROCKSOL TEMPLATE.GDT 12/9/21

Specimen Identification	Classification	Swell/Consol. (%)	$\gamma_d$ (pcf)	MC%
● LC-2      10	<b>SANDY LEAN CLAY (CL) (A-4)</b>	<b>-0.2</b>	<b>87.9</b>	<b>25.0</b>




CLIENT City of Grand Junction

PROJECT NAME F.5 Road Parkway and 24.5 Road Widening

PROJECT NUMBER 599.37

PROJECT LOCATION Grand Junction, Colorado



SWELL - STANDARD 599.37\_CITY OF GJ PARKWAY PROJECT.GPJ ROCKSOL TEMPLATE.GDT 12/9/21

Specimen Identification	Classification	Swell/Consol. (%)	$\gamma_d$ (pcf)	MC%
● LC-3                      5	<b>CLAY, with SAND</b>	<b>-1.7</b>	<b>102.2</b>	<b>19.6</b>

## **APPENDIX C**

### **20 and 30-YEAR FLEXIBLE ME-PAVEMENT DESIGN OUTPUT SHEETS F ½ ROAD**



# F.5 Road (Updated)



File Name: C:\Users\goldbaum\Documents\My PMED Designs\My ME Design\Projects\F.5 Road\F.5 Road (Updated).dgp

## Design Inputs

Design Life: **20 years**      Base construction: **May, 2022**      Climate Data **39.134, -108.538**  
 Design Type: **FLEXIBLE**      Pavement construction: **June, 2022**      Sources (Lat/Lon)  
 Traffic opening: **September, 2022**

### Design Structure

Layer type	Material Type	Thickness (in)
Flexible	R3 Level 1 SX(100) PG 64-28	2.0
Flexible	R2 Level 1 SX(100) PG 64-22	5.5
NonStabilized	Crushed gravel	8.0
NonStabilized	A-1-b	14.0
Subgrade	A-6 (R-Value = 5)	Semi-infinite

### Volumetric at Construction:

Effective binder content (%)	10.7
Air voids (%)	5.7

### Traffic

Age (year)	Heavy Trucks (cumulative)
2022 (initial)	2,100
2032 (10 years)	3,814,160
2042 (20 years)	8,555,580

## Design Outputs

### Distress Prediction Summary

Distress Type	Distress @ Specified Reliability		Reliability (%)		Criterion Satisfied?
	Target	Predicted	Target	Achieved	
Terminal IRI (in/mile)	200.00	174.46	90.00	97.78	Pass
Permanent deformation - total pavement (in)	0.80	0.68	90.00	98.99	Pass
AC bottom-up fatigue cracking (% lane area)	25.00	21.26	90.00	94.31	Pass
AC thermal cracking (ft/mile)	1500.00	151.56	90.00	100.00	Pass
AC top-down fatigue cracking (ft/mile)	3000.00	382.11	90.00	100.00	Pass
Permanent deformation - AC only (in)	0.65	0.49	90.00	99.70	Pass







# F.5 Road (Updated)



File Name: C:\Users\goldbaum\Documents\My PMED Designs\My ME Design\Projects\F.5 Road\F.5 Road (Updated).dgp

## Distress Charts



— Threshold Value   
 ..... @ Specified Reliability   
 --- @ 50% Reliability



# F.5 Road (Updated)

File Name: C:\Users\goldbaum\Documents\My PMED Designs\My ME Design\Projects\F.5 Road\F.5 Road (Updated).dgp







## Traffic Inputs

### Graphical Representation of Traffic Inputs

Initial two-way AADTT: **2,100**  
 Number of lanes in design direction: **2**

Percent of trucks in design direction (%): **50.0**  
 Percent of trucks in design lane (%): **90.0**  
 Operational speed (mph): **35.0**



### Traffic Volume Monthly Adjustment Factors







# F.5 Road (Updated)

File Name: C:\Users\goldbaum\Documents\My PMED Designs\My ME Design\Projects\F.5 Road\F.5 Road (Updated).dgp



## Tabular Representation of Traffic Inputs

### Volume Monthly Adjustment Factors

Level 3: Default MAF

Month	Vehicle Class									
	4	5	6	7	8	9	10	11	12	13
January	0.9	0.8	0.8	0.7	0.8	0.9	0.9	0.9	0.9	0.9
February	0.9	0.8	0.8	0.8	0.9	0.9	0.9	0.9	1.0	0.8
March	1.0	0.9	0.8	1.1	1.0	1.0	1.0	1.0	0.9	0.9
April	1.0	1.0	0.9	1.0	1.0	1.0	1.1	1.0	1.0	1.1
May	1.1	1.1	1.0	1.3	1.1	1.0	1.1	1.1	1.1	1.0
June	1.1	1.1	1.2	1.1	1.1	1.0	1.1	1.0	1.1	1.0
July	1.1	1.2	1.5	1.3	1.2	1.0	1.1	1.1	1.1	1.3
August	1.1	1.2	1.3	1.0	1.1	1.0	1.1	1.1	1.1	1.0
September	1.1	1.1	1.1	1.0	1.1	1.0	1.1	1.1	1.0	1.1
October	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0.9	1.1
November	0.9	0.9	0.9	0.9	0.9	1.0	1.0	1.0	1.0	1.0
December	0.9	0.8	0.8	0.8	0.8	0.9	0.8	0.9	0.9	0.9

### Distributions by Vehicle Class

Vehicle Class	AADTT Distribution (%) (Level 3)	Growth Factor	
		Rate (%)	Function
Class 4	2.1%	2.2%	Compound
Class 5	56.1%	2.2%	Compound
Class 6	4.4%	2.2%	Compound
Class 7	0.3%	2.2%	Compound
Class 8	14.2%	2.2%	Compound
Class 9	21.1%	2.2%	Compound
Class 10	0.7%	2.2%	Compound
Class 11	0.7%	2.2%	Compound
Class 12	0.2%	2.2%	Compound
Class 13	0.2%	2.2%	Compound

Truck Distribution by Hour does not apply

### Axle Configuration

Traffic Wander	
Mean wheel location (in)	18.0
Traffic wander standard deviation (in)	10.0
Design lane width (ft)	12.0

Axle Configuration	
Average axle width (ft)	8.5
Dual tire spacing (in)	12.0
Tire pressure (psi)	120.0

Average Axle Spacing	
Tandem axle spacing (in)	51.6
Tridem axle spacing (in)	49.2
Quad axle spacing (in)	49.2






Wheelbase does not apply

### Number of Axles per Truck

Vehicle Class	Single Axle	Tandem Axle	Tridem Axle	Quad Axle
Class 4	1.53	0.45	0	0
Class 5	2.02	0.16	0.02	0
Class 6	1.12	0.93	0	0
Class 7	1.19	0.07	0.45	0.02
Class 8	2.41	0.56	0.02	0
Class 9	1.16	1.88	0.01	0
Class 10	1.05	1.01	0.93	0.02
Class 11	4.35	0.13	0	0
Class 12	3.15	1.22	0.09	0
Class 13	2.77	1.4	0.51	0.04

## AADTT (Average Annual Daily Truck Traffic) Growth

\* Traffic cap is not enforced







# F.5 Road (Updated)



File Name: C:\Users\goldbaum\Documents\My PMED Designs\My ME Design\Projects\F.5 Road\F.5 Road (Updated).dgp


## Climate Inputs

### Climate Data Sources:

Climate Station Cities: Location (lat lon elevation(ft))  
**GRAND JUNCTION, CO** 39.13400 -108.53800 4839





### Annual Statistics:

Mean annual air temperature (°F) 53.75  
 Mean annual precipitation (in) 7.96  
 Freezing index (°F - days) 360.58  
 Average annual number of freeze/thaw cycles: 111.77



Water table depth (ft) 10.00

### Monthly Climate Summary:






# F.5 Road (Updated)



File Name: C:\Users\goldbaum\Documents\My PMED Designs\My ME Design\Projects\F.5 Road\F.5 Road (Updated).dgp

## Hourly Air Temperature Distribution by Month:





# F.5 Road (Updated)

File Name: C:\Users\goldbaum\Documents\My PMED Designs\My ME Design\Projects\F.5 Road\F.5 Road (Updated).dgp



## Design Properties

### HMA Design Properties

<b>Use Multilayer Rutting Model</b>	False
<b>Using G* based model (not nationally calibrated)</b>	False
<b>Is NCHRP 1-37A HMA Rutting Model Coefficients</b>	True
<b>Endurance Limit</b>	-
<b>Use Reflective Cracking</b>	True

<b>Structure - ICM Properties</b>	
AC surface shortwave absorptivity	0.85

Layer Name	Layer Type	Interface Friction
Layer 1 Flexible : R3 Level 1 SX (100) PG 64-28	Flexible (1)	1.00
Layer 2 Flexible : R2 Level 1 SX (100) PG 64-22	Flexible (1)	1.00
Layer 3 Non-stabilized Base : Crushed gravel	Non-stabilized Base (4)	1.00
Layer 4 Non-stabilized Base : A-1-b	Non-stabilized Base (4)	1.00
Layer 5 Subgrade : A-6 (R-Value = 5)	Subgrade (5)	-





# F.5 Road (Updated)


File Name: C:\Users\goldbaum\Documents\My PMED Designs\My ME Design\Projects\F.5 Road\F.5 Road (Updated).dgp



## Thermal Cracking (Input Level: 1)

Indirect tensile strength at 14 °F (psi)	519.00
<b>Thermal Contraction</b>	
Is thermal contraction calculated?	True
Mix coefficient of thermal contraction (in/in/°F)	-
Aggregate coefficient of thermal contraction (in/in/°F)	5.0e-006
Voids in Mineral Aggregate (%)	16.4

Loading time (sec)	Creep Compliance (1/psi)		
	-4 °F	14 °F	32 °F
1	3.61e-007	4.73e-007	7.12e-007
2	4.04e-007	5.74e-007	9.97e-007
5	4.51e-007	7.35e-007	1.52e-006
10	5.11e-007	8.78e-007	1.99e-006
20	5.67e-007	1.04e-006	2.59e-006
50	6.57e-007	1.37e-006	3.75e-006
100	7.68e-007	1.66e-006	4.66e-006








# F.5 Road (Updated)






File Name: C:\Users\goldbaum\Documents\My PMED Designs\My ME Design\Projects\F.5 Road\F.5 Road (Updated).dgp

## HMA Layer 1: Layer 1 Flexible : R3 Level 1 SX(100) PG 64-28



## HMA Layer 2: Layer 2 Flexible : R2 Level 1 SX(100) PG 64-22



## Analysis Output Charts

