



Purchasing Division

ADDENDUM NO. 1

DATE: January 8, 2025
FROM: City of Grand Junction Purchasing Division
TO: All Offerors
RE: 2025 Contract Street Maintenance Overlays IFB-5560-25-DD

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded, and supplemented as to this date as hereinafter described.

Please make note of the following questions/answers/clarifications:

- 1. Question:** What is the City's plan for the rough, uneven surface at the patch locations on South Pinon and South Cedar? Will these locations/streets be a full width mill to help smooth up the road?
Answer: South Pinon and South Cedar will be a full width mill.
- 2. Question:** What would the City like for all the core holes and dips on UnawEEP side streets, which have settled? Will the City add a Pre-Level quantity to the project tabulation?
Answer: Pre-level quantity as directed has been added as line item #16 (See revised Bid Specification Sheet attached)
- 3. Question:** Will the Cul-De-Sac on North Pine be overlaid? The plan sheet is cut off and not showing any work to continue through the Cul-De-Sac.
Answer: All North Pine will be overlaid, including the cul-de-sac bulb.
- 4. Question:** The assumption is all existing Asphalt, and concrete driveways shall be milled for tie-ins on the UnawEEP side streets. What transition is the City proposing without the full width milling taking place?
Answer: Line item #18 added to address tie ins to existing hard surfaces, as directed. (See revised Bid Specification Sheet attached)
- 5. Clarification:** A sheet showing the approximate quantities per street has been added for bidders' convenience. Please note that some line items are accounted for in bulk and may not be shown per street. (Attached)

The original solicitation for the project noted above is amended as noted. All other conditions of the subject remain the same.

Respectfully,

A handwritten signature in blue ink that reads "Dolly Daniels".

Dolly Daniels, Senior Buyer
City of Grand Junction, Colorado

Bid Schedule: 2025 Contract Street Maintenance Overlays Rev 1

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	202	Asphalt Removal (Planing)(1.5" Typical)	40,750.	SY	\$ _____	\$ _____
2	202	Asphalt Removal (Bevel Mill)(1.5" to 0" over 100 LF)	1,750.	SY	\$ _____	\$ _____
3	210	Adjust Valve Box (Price to Include adjustment of Survey Monument Boxes)	91.	EA	\$ _____	\$ _____
4	210	Adjust Manhole Ring and Cover (Sanitary and Storm Sewer)	74.	EA	\$ _____	\$ _____
5	304	Aggregate Base Course (Class 6) - Shoulder Edging Gravel for UnawEEP Sidestreets	200.	Tons	\$ _____	\$ _____
6	401	Hot Mix Asphalt (1.5" thick) (Grading SX, 75 Gyration, Binder Grade 64-22)	5,000.	Tons	\$ _____	\$ _____
7	620	Sanitary Facility	1.	LS	\$ _____	\$ _____
8	626	Mobilization	1.	LS	\$ _____	\$ _____
9	627-30405	Preformed Thermoplastic Pavement Marking (Right Turn Arrow)	5.	EA	\$ _____	\$ _____
10	627-30405	Preformed Thermoplastic Pavement Marking (Left Turn Arrow)	39.	EA	\$ _____	\$ _____
11	627-30405	Preformed Thermoplastic Pavement Marking (Bike Symbol)	30.	EA	\$ _____	\$ _____
12	627-30410	Preformed Plastic Pavement Marking (X-Walk Bar)	50.	EA	\$ _____	\$ _____
13	630	Traffic Control (Complete In Place)	1.	LS	\$ _____	\$ _____
14	630	Flagging	44.	Days	\$ _____	\$ _____
15	SPC	Preformed 1'6" Wayfinding Bike Route Marking (Ennis-Flint Item ID PM6001342, PM125WH/BK QV VG)	1.	EA	\$ _____	\$ _____
16	401	Hot Mix Asphalt (1" thick Pre-Level) (Grading ST, Binder Grade 64-22)(As Directed)	500.	Tons	\$ _____	\$ _____
17	202	City to Retain UnawEEP Ave Millings and Contractor to Deliver Millings to 2620 Legacy Way (Including Stockpile Management/End of Day Buck Up)	Lump Sum		---	\$ _____
18	202	Asphalt Removal (Taper along frontage)(Tie In Existing Asphalt or Concrete Driveways)(1.0" to 0.0" over 2 LF)(As Needed)	150.	LF	\$ _____	\$ _____
INC	401	Asphalt Incentive (Achievable Per Specification)	---	---	---	<u>\$ 25,000.00</u>
MCR		Minor Contract Revisions	---	---	---	<u>\$ 50,000.00</u>

Bid Amount: \$ _____

Bid Amount:

dollars

Table: 2025 Contract Street Maintenance Over

Item No.	CDOT, City Ref.	Description	UnawEEP Ave	Pinon St South	Pinon St North	Cedar St South	Cedar St North	Pine St South	Pine St North	27 1/4 Rd South	Holly Ln South	27 3/8 Road South	29 Road E to F
1	202	Asphalt Removal (Planing)(1.5" Typical)	11,353.6	2,432.3		2,722.5					1,500.		27,791.8
2	202	Asphalt Removal (Bevel Mill)(1.5" to 0" over 100 LF)			250.		250.	250.	250.	250.	250.	250.	
3	210	Adjust Valve Box (Price to Include adjustment of Survey Monument Boxes)	18.	2.	2.	2.	2.	6.	4.		4.		51.
4	210	Adjust Manhole Ring and Cover (Sanitary and Storm Sewer)	14.	2.		3.	1.	3.	3.	1.	4.	3.	40.
5	304	Aggregate Base Course (Class 6) - Shoulder Edging Gravel for UnawEEP Sidestreets											
6	401	Hot Mix Asphalt (1.5" thick) (Grading SX, 75 Gyraton, Binder Grade 64-22)	936.67	200.66	127.66	224.61	122.28	285.61	313.34	26.76	271.23	163.16	2,292.82
9	627-30405	Preformed Thermoplastic Pavement Marking (Right Turn Arrow)											5.
10	627-30405	Preformed Thermoplastic Pavement Marking (Left Turn Arrow)	14.										25.
11	627-30405	Preformed Thermoplastic Pavement Marking (Bike Symbol)	12.										18.
12	627-30410	Preformed Plastic Pavement Marking (X-Walk Bar)	7.										43.
13	630	Traffic Control (Complete In Place)											
14	630	Flagging	10.	3.	2.	3.	2.	3.	3.	2.	3.	3.	10.
15	SPC	Preformed 1'6" Wayfinding Bike Route Marking (Ennis-Flint Item ID PM6001342, PM125WH/BK QV VG)	1.										