



Purchasing Division

## ADDENDUM NO. 1

**DATE:** February 12, 2025  
**FROM:** City of Grand Junction Purchasing Division  
**TO:** All Offerors  
**RE:** Purchase and Installation of New Luxury Vinyl Tile Flooring at the Senior Center  
RFQ-5603-25-DD

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded, and supplemented as to this date as hereinafter described.

Please make note of the following questions/answers/clarifications:

- 1. Clarification:** We would like to match the existing LVT flooring or as closely as possible. Would like to stay in the Mohawk Group. The existing LVT flooring is:  
Mohawk Group Hot and Heavy Collection Grown Up luxury Vinyl Tile  
Color: 138 Kingsley  
Refer to the attached 'Grown Up\_Tear Sheet.pdf' for specifications.

The existing 4" rubber cove base to match as closely as possible:  
Johnsonite Brand 4" rubber cove base in Beige color (DC-49), or equivalent.

The original solicitation for the project noted above is amended as noted. All other conditions of the subject remain the same.

Respectfully,

A handwritten signature in blue ink that reads "Dolly Daniels".

Dolly Daniels, Senior Buyer  
City of Grand Junction, Colorado

# Hot & Heavy Collection

Grown Up loose lay LVT employs a registered emboss over high-definition wood visuals to create one of the most realistic wood textures in the industry today.



Grown Up | 758 Hermes & 958 Cole

## Selling Features

- Oversized 9" x 59" planks install over large areas quickly
- 5mm overall thickness and 20 mil commercial wear layer for superior durability
- M-Force™ Enhanced Urethane finish for stain and wear resistance
- Inherent acoustic properties, IIC rating of 57 with drop ceiling, without underlayment
- Twice as thick as traditional LVT for seamless transition with Mohawk Group carpet tiles
- Non-skid backing keeps plank in place
- Minimum of 8% bio-based rapidly renewable resource content by total product weight helps avoid harmful phthalates

Collection	Hot & Heavy Collection
Style Name / Number	Grown Up CO075
Brand	Mohawk Group Hard Surface
Product Type	Loose Lay Luxury Vinyl Tile



## DESIGN

Overall Gauge	.20" (5mm)
Wear Layer	20 mil (0.5mm)
Finish	M-Force™ Enhanced Urethane
Texture	Registered Emboss
Colors Available / Size	10 colors - 9" x 59" (nominal) (235mm x 1505mm)
Packaging	22.84 sf/ctn (2.12 m2/ctn); 6 pcs/ctn; 40.78 lbs/ctn (18.49 kg/ctn)
Installation	Perimeter Glue
Recommended Adhesive	Perimeter glue only with MS160 Spray. May also use M95.0 Resilient Flooring Adhesive



## PERFORMANCE

Construction	Commercial Grade Floating Luxury Vinyl Tile
Classification	ASTM F1700 - Class III, Type A - Smooth, Type B - Embossed
Squareness	ASTM F2055 - Passes - 0.010 in. max
Size and Tolerance	ASTM F2055 - Passes - ±0.016 in. per linear foot
Thickness	ASTM F386 - Passes - Nominal ±0.005 in.
Flexibility	ASTM F137 - Passes - ≤ 1.0 in., no cracks or breaks
Dimensional Stability	ASTM F2199 - Passes - ≤ 0.024 in. per linear foot
Static Load Limit	ASTM F970 - Passes, modified - 1000 psi
Residual Indentation	ASTM F1914 - Passes - Average less than 8%
Slip Resistance	ASTM D2047 - Passes - > 0.6 Wet, 0.6 Dry
Resistance to Chemicals	ASTM F925 - Passes - No Change or Slight Change
Resistance to Light	ASTM F1515 - Passes - ΔE ≤ 8
Resistance to Heat	ASTM F1514 - Passes - ΔE ≤ 8
Critical Radiant Flux	ASTM E648 - Passes - ≥ 0.45 watts/cm2, Class 1
IIC Rating	57 (over 6" concrete and drop ceiling)



## SUSTAINABILITY

Certification	FloorScore® Certified
Renewable Resource Content	Minimum of 8% bio-based rapid renewable resource content by total product weight helps avoid harmful phthalates



## SERVICE

Warranty	Limited 10 Year Commercial
----------	----------------------------

# Hot & Heavy Collection

## Colorways

### Grown Up



132 Vera



138 Kingsley



241 Knox



322 Finn




358 Jackson




628 Lenox



758 Hermes



851 Butler



853 Emerson



958 Cole


M-Force™ Enhanced Urethane Finish

Heavy Commercial Wear Layer

Decorative Print Film

Enhanced Acoustical Layer

Stabilizing Back Layer



Featuring a Non-Skid Backing

