

Bid Schedule: Grand View Commons

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
GRAND AVE & 28 1/4 RD						
1	201	Clearing and Grubbing		Lump Sum	---	\$ _____
2	202	Removal of Asphalt Mat (Full Depth) (Complete in Place)	1,834.	SY	\$ _____	\$ _____
3	202	Removal of Asphalt Mat (Planing) (2" Depth)	89.	SY	\$ _____	\$ _____
4	210	Remove and Reset Stop Sign	1.	EA	\$ _____	\$ _____
5	202	Remove Storm Manholes & Pipe (28-1/4 Road)		Lump Sum	---	\$ _____
6	210	Adjust Manhole Rims	7.	EA	\$ _____	\$ _____
7	210	Remove and Reset Fence and Gate Controller (2801 Grand Ave) (Includes Corner Fence)		Lump Sum	---	\$ _____
8	202	Remove Light and Wood Pole (2801 Grand Ave)		Lump Sum	---	\$ _____
9	202	Remove Concrete Barriers (Deliver to City Shops)		Lump Sum	---	\$ _____
10	203	Earthwork (Complete in Place)		Lump Sum	---	\$ _____
11	306	Reconditioning (12" Depth) (Complete in Place) (toe of slope to toe of slope)	24,850.	SY	\$ _____	\$ _____
12	306	Reconditioning (12" Depth) (Complete in Place) (2801 Grand Ave)	737.	SY	\$ _____	\$ _____
13	304	Subgrade Stabilization (Class 3 ABC) (30" Depth) (Complete in Place) (As Directed)	5,000.	SY	\$ _____	\$ _____
14	420	Geotextile (Mirafi 580i or Approved Equal) (Complete in Place) (As Directed)	5,000.	SY	\$ _____	\$ _____
15	208	Vehicle Tracking Pad		Lump Sum	---	\$ _____
16	208	Silt Berm		Lump Sum	---	\$ _____
17	208	Concrete Washout Structure		Lump Sum	---	\$ _____
18	208	Erosion Log	150.	LF	\$ _____	\$ _____
19	208	Storm Drain Inlet/Culvert Protection	3.	EA	\$ _____	\$ _____
20	208	Aggregate Bag	150.	LF	\$ _____	\$ _____
21	208	Erosion Control Management		Lump Sum	---	\$ _____
22	304	ABC (Class 3) (15" Thick) (Under Roadway and Concrete Areas Excluding Sidewalk)	12,643.	SY	\$ _____	\$ _____
23	304	3/4" Crushed Gravel - 1 ft depth (Not incl under sidewalk)	350.	CY	\$ _____	\$ _____
24	304	ABC (Class 6) (6" Thick) (Under Roadway and Concrete Areas Excluding Sidewalk)	12,643.	SY	\$ _____	\$ _____

Bid Schedule: Grand View Commons

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
25	304	ABC (Class 6) (6" Thick) (Under Sidewalk Areas)	3,023.	SY	\$ _____	\$ _____
26	304	ABC (Class 6) (10" Thick) (Under Parking Lot at 2801 Grand Ave)	737.	SY	\$ _____	\$ _____
27	401	HMA (5" Thick) (SX 75, PG 64-22)	3,025.	TON	\$ _____	\$ _____
28	401	HMA (3" Thick) (SX 75, PG 64-22) (2801 Grand Ave)	111.	TON	\$ _____	\$ _____
29	401	HMA (Patching) (5" Thick) (SX 75, PG 64-22) (Includes 6" Class 6 ABC and 15" Class 3 ABC and Reconditioning)	250.	SY	\$ _____	\$ _____
30	304	ABC (Class 6) (6" Thick) (Shoulder 4' Wide)	284.	SY	\$ _____	\$ _____
31	608	Concrete Curb and Gutter (2' Wide) (Complete in Place) (Excludes Base)	4,107.	LF	\$ _____	\$ _____
32	608	Concrete Curb and Gutter (2' Wide) (Complete in Place) (Excludes Base) (Parking Lot Area 2801 Grand Ave)	105.	LF	\$ _____	\$ _____
33	608	Concrete Sidewalk (5" Thick) (Complete in Place) (Excludes Base)	2,594.	SY	\$ _____	\$ _____
34	608	Concrete Driveway Section (8" Thick) (Complete in Place) (Excludes Base)	39.	SY	\$ _____	\$ _____
35	608	Concrete Intersection Fillet & Drainage Pan (Complete in Place) (Excludes Base)	321.	SY	\$ _____	\$ _____
36	608	Concrete Curb Ramp (Complete in Place) (Includes Detectable Warnings) (Excludes Base)	10.	EA	\$ _____	\$ _____
37	308	Concrete Chase Drain (Detention Pond)	30.	LF	\$ _____	\$ _____
38	614	Stop/Street/Speed limit Sign Panels (Includes posts)	4.	EA	\$ _____	\$ _____
39	614	End of Roadway Type III Barrier	100.	LF	\$ _____	\$ _____
40	627	Preformed Thermoplastic Pavement Marking (White Turn Arrow)	4.	EA	\$ _____	\$ _____
41	627	Preformed Thermoplastic Pavement Marking (Bike Lane Symbol)	7.	EA	\$ _____	\$ _____
42	627	Preformed Thermoplastic Pavement Marking (Pedestrian Crosswalk)	3.	EA	\$ _____	\$ _____
43	613	4" Electrical Conduit (Sch 40 PVC) (Utility Sleeve) (Grey)	1,000.	LF	\$ _____	\$ _____
44	102	Connect To Existing Main (8" Water) (Complete in Place) (Grand Ave)	Lump Sum		---	\$ _____
45	102	Connect To Existing Main (8" Water) (Complete in Place) (28 1/4 Road)	Lump Sum		---	\$ _____
46	102	8" Water Pipe (C-900 PVC) (Complete in Place)	2,425.	LF	\$ _____	\$ _____
47	102	8" Gate Valve	6.	EA	\$ _____	\$ _____

Bid Schedule: Grand View Commons

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
48	102	6" Gate Valve	5.	EA	\$ _____	\$ _____
49	102	8" x 8" Tee	2.	EA	\$ _____	\$ _____
50	102	8" x 6" Tee	5.	EA	\$ _____	\$ _____
51	102	Fire Hydrant (Includes 6" C-900 Extension)	5.	EA	\$ _____	\$ _____
52	102	2" Blow-off	2.	EA	\$ _____	\$ _____
53	102	2" Water Meter Service (Complete in Place)	1.	EA	\$ _____	\$ _____
54	102	12" Storm Drain Pipe	10.	LF	\$ _____	\$ _____
55	102	18" Storm Drain Pipe	676.	LF	\$ _____	\$ _____
56	102	24" Storm Drain Pipe	864.	LF	\$ _____	\$ _____
57	102	30" Storm Drain Pipe	998.	LF	\$ _____	\$ _____
58	102	36" Storm Drain Pipe	366.	LF	\$ _____	\$ _____
59	102	Single Storm Drain Inlet (Vertical Curb)	5.	EA	\$ _____	\$ _____
60	102	Double Storm Drain Inlet (Vertical Curb)	1.	EA	\$ _____	\$ _____
61	102	Storm Sewer Basic Manhole (5' I.D.)	8.	EA	\$ _____	\$ _____
62	102	Storm Sewer Basic Manhole (6' I.D.)	1.	EA	\$ _____	\$ _____
63	102	Conflict Storm Sewer Manhole C2 (6' I.D.) (Complete in Place)	1.	EA	\$ _____	\$ _____
64	102	Conflict Storm Sewer Manhole C3 (6' I.D.) (Complete in Place)	1.	EA	\$ _____	\$ _____
65	102	18" Culvert End Section (RCP) (Flared)	1.	EA	\$ _____	\$ _____
66	102	36" Culvert End Section(RCP) (Flared)	1.	EA	\$ _____	\$ _____
67	506	Riprap (8" D50) (Includes Mirafi 700X or Approved Equal)	Lump Sum		---	\$ _____
68	210	Adjust Double Inlet (A-2)	Lump Sum		---	\$ _____
69	102	Connect to Double Inlet (A-2) (Complete in Place)	Lump Sum		---	\$ _____
70	102	Connect to Existing Main (8" Sewer) (Complete in Place)	Lump Sum		---	\$ _____
71	102	8" Gravity Sewer Pipe	1,556.	LF	\$ _____	\$ _____
72	102	Sanitary Sewer Basic Manhole (4' I.D.)	11.	EA	\$ _____	\$ _____

Bid Schedule: Grand View Commons

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
73	623	Backflow Preventor - Febco 825YA - 1-1/2"	1.	EA	\$ _____	\$ _____
74	623	Imperial ICA-22-xx Controller Assembly with Solar	1.	EA	\$ _____	\$ _____
75	623	1-1/2" Wilkins Pressure Reducing Valve	1.	EA	\$ _____	\$ _____
76	623	Netafim Hydrometer Flow Sensor/Master Valve w/ER register	1.	EA	\$ _____	\$ _____
77	623	1-1/2" PVC SCH 40 Mainline	1,720.	LF	\$ _____	\$ _____
78	623	1" PVC CL 200 Laterals	1,341.	LF	\$ _____	\$ _____
79	623	Air Relief Valves	2.	LF	\$ _____	\$ _____
80	623	PEB-IVM Zone Valves - 1"	6.	EA	\$ _____	\$ _____
81	623	Isolation Valves	2.	EA	\$ _____	\$ _____
82	623	Manual Drain Valve	1.	EA	\$ _____	\$ _____
83	623	Quick Couplers	3.	EA	\$ _____	\$ _____
84	623	Emitters & 1/4" Distribution Tubing	334.	EA	\$ _____	\$ _____
85	623	3/4" Tubing	700.	LF	\$ _____	\$ _____
86	623	Pipe Transition Point above grade (PVC to Drip)	12.	EA	\$ _____	\$ _____
87	623	Flush Caps in 6" Round Box	12.	EA	\$ _____	\$ _____
88	623	1804 Spray Heads (for Lawn areas)	6.	LF	\$ _____	\$ _____
89	623	4" PVC Irrigation Sleeving, bury at cross section depth	20.	LF	\$ _____	\$ _____
90	623	5 Gallon Shrubs	54.	EA	\$ _____	\$ _____
91	623	2'X2'X3' Granite Boulders	122.	EA	\$ _____	\$ _____
92	623	1 Gallon Perennials/Ornamental Grasses	45.	EA	\$ _____	\$ _____
93	623	1-1/2" Granite, 3" depth -Sidewalk to Curb	145.	CY	\$ _____	\$ _____
94	623	Fine Grading	16,102.	SF	\$ _____	\$ _____
95	623	Steel Edger	124.	LF	\$ _____	\$ _____
96	623	Soil Amendment - 6cy/1k sf in planted areas; in plant pit elsewhere	3,600.	SF	\$ _____	\$ _____
97	623	Grass Hydroseed/Hydromulch	270.	SF	\$ _____	\$ _____
98	623	Backfill -Topsoil	130.	CY	\$ _____	\$ _____

Bid Schedule: Grand View Commons

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
99	623	Unclassified Backfill, Low Salt	190.	CY	\$ _____	\$ _____
100	623	Weed Fabric	35,761.	SF	\$ _____	\$ _____
101	623	4" Slotted HDPE Pipe (open trench)	781.	LF	\$ _____	\$ _____
102	623	4" Solid HDPE Pipe (open trench)	1,043.	LF	\$ _____	\$ _____
103	623	Flared End Section Assembly	1.	LF	\$ _____	\$ _____
104	625	Construction Surveying (Includes As-Built Drawings)	Lump	Sum	---	\$ _____
105	630	Traffic Control (Complete in Place)	Lump	Sum	---	\$ _____
106	630	Traffic Control Plan	Lump	Sum	---	\$ _____
107	626	Mobilization	Lump	Sum	---	\$ _____
108	620	Sanitary Facility	Lump	Sum	---	\$ _____
		Asphalt Paving Incentive	---	---	---	\$ 10,000.00
MCR		Minor Contract Revisions	---	---	---	\$ 150,000.00
DISC		Prompt Payment Discount				
Bid Amount:					\$ _____	

Bid Amount:

dollars

ADD Alternate 1 - 28 Road Widening

A1	202	Removal of Asphalt Mat (Planing) (2" Depth)	1,041.	SY	\$ _____	\$ _____
A2	203	Earthwork (Complete in Place)	Lump	Sum	---	\$ _____
A3	306	Reconditioning (12" Depth) (Complete in Place)(to toe of slope)	7,479.	SY	\$ _____	\$ _____
A4	304	ABC (Class 3) (15" Thick) (Under Roadway and Concrete Areas Excluding Sidewalk)	2,247.	SY	\$ _____	\$ _____
A5	304	Backfill -3/4" Crushed Gravel - 1 ft depth (Not incl under sidewalk)	460.	CY	\$ _____	\$ _____
A6	304	ABC (Class 6) (6" Thick) (Under Roadway and Concrete Areas Excluding Sidewalk)	2,247.	SY	\$ _____	\$ _____
A7	304	ABC (Class 6) (6" Thick) (Under Sidewalk Areas)	1,507.	SY	\$ _____	\$ _____
A8	401	HMA (3" Thick) (SX 75, PG 64-22) (28 Road Widening Area)	308.	TON	\$ _____	\$ _____
A9	401	HMA (2" Thick) (SX 75, PG 64-22) (28 Road Widening Area)	253.	TON	\$ _____	\$ _____

Bid Schedule: Grand View Commons

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
A10	401	HMA (Patching) (5" Thick) (SX 75, PG 64-22) (Includes 6" Class 6 ABC and 15" Class 3 ABC and Reconditioning)	33.	SY	\$ _____	\$ _____
A11	608	Concrete Curb and Gutter (2' Wide) (Complete in Place) (Excludes Base)	1,233.	LF	\$ _____	\$ _____
A12	608	Concrete Sidewalk (5" Thick) (Complete in Place) (Excludes Base)	1,418.	SY	\$ _____	\$ _____
A13	608	Concrete Curb Ramp (Complete in Place) (Includes Detectable Warnings) (Excludes Base)	1.	EA	\$ _____	\$ _____
A14	627	Preformed Thermoplastic Pavement Marking (White Turn Arrow)	4.	EA	\$ _____	\$ _____
A15	627	Preformed Thermoplastic Pavement Marking (Bike Lane Symbol)	2.	EA	\$ _____	\$ _____
A16	210	Adjust Curb Inlet (28 Road Near Grand Ave)	Lump Sum		---	\$ _____
A17	623	1-1/2" PVC SCH 40 Mainline	780.	LF	\$ _____	\$ _____
A18	623	1" PVC CL 200 Laterals	1,555.	LF	\$ _____	\$ _____
A19	623	1-1/2" PVC CL 200 Laterals	481.	LF	\$ _____	\$ _____
A20	623	Air Relief Valves	1.	LF	\$ _____	\$ _____
A21	623	PEB-IVM Zone Valves - 1"	2.	EA	\$ _____	\$ _____
A22	623	PEB-IVM Zone Valves - 1-1/2"	1.	EA	\$ _____	\$ _____
A23	623	Quick Couplers	3.	EA	\$ _____	\$ _____
A24	623	Emitters & 1/4" Distribution Tubing	116.	EA	\$ _____	\$ _____
A25	623	3/4" Tubing	130.	LF	\$ _____	\$ _____
A26	623	Pipe Transition Point above grade (PVC to Drip)	6.	EA	\$ _____	\$ _____
A27	623	Flush Caps in 6" Round Box	6.	EA	\$ _____	\$ _____
A28	623	PCN Bubblers; 3/tree _ 1804 Spray Head Body	27.	EA	\$ _____	\$ _____
A29	623	Swing Pipe	70.	LF	\$ _____	\$ _____
A30	623	4" PVC Irrigation Sleeving, bury at cross section depth	24.	LF	\$ _____	\$ _____
A31	623	1-1/2" Deciduous Trees - 28 Road	9.	EA	\$ _____	\$ _____
A32	623	5 Gallon Shrubs	30.	EA	\$ _____	\$ _____
A33	623	2'X2'X3' Granite Boulders	77.	EA	\$ _____	\$ _____

Bid Schedule: Grand View Commons

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
A34	623	1 Gallon Perennials/Ornamental Grasses	18.	EA	\$ _____	\$ _____
A35	623	1-1/2" Granite, 3" depth -Sidewalk to Curb	115.	CY	\$ _____	\$ _____
A36	623	Fine Grading	12,307.	SF	\$ _____	\$ _____
A37	623	Steel Edger	60.	LF	\$ _____	\$ _____
A38	623	Soil Amendment - 6cy/1k sf in planted areas; in plant pit elsewhere	2,700.	SF	\$ _____	\$ _____
A39	623	Backfill -Topsoil	140.	CY	\$ _____	\$ _____
A40	623	Unclassified Backfill, Low Salt	255.	CY	\$ _____	\$ _____
A41	623	Weed Fabric	40,151.	SF	\$ _____	\$ _____
A42	623	4" Slotted HDPE Pipe (open trench)	270.	LF	\$ _____	\$ _____
A43	623	4" Solid HDPE Pipe (open trench)	925.	LF	\$ _____	\$ _____
A44	623	Flared End Section Assembly	1.	LF	\$ _____	\$ _____
A45	625	Construction Surveying (Includes As-Built Drawings)	Lump Sum		---	\$ _____
A46	630	Traffic Control (Complete in Place)	Lump Sum		---	\$ _____
A47	630	Traffic Control Plan	Lump Sum		---	\$ _____
A48	626	Mobilization	Lump Sum		---	\$ _____

Bid Amount: \$ _____

Bid Amount:

dollars