



Purchasing Division

ADDENDUM NO. 2

DATE: June 24, 2025
FROM: City of Grand Junction Purchasing Division
TO: All Offerors
RE: Four Canyons Parkway Phase 2B IFB-5692-25-DD

This addendum shall be a part of the Contract Documents for the above project and is hereby made effective on the date shown above. All other terms and conditions of the contract documents not addressed in this addendum shall remain unchanged.

The bidder shall acknowledge receipt of this addendum in the space provided in the Bid Form. Failure to do so may subject the bidder to disqualification.

Please make note of the following questions/answers/clarifications:

1. **Question:** Will Insert-A-T fittings be allowed for the 4" irrigation services on the 18" ADS pipe instead of using a standard tee fitting and several reducers.

Answer: *Insert-A-T fittings shall not be allowed for the 4" irrigation services. Standard tee fittings are acceptable.*

2. **Question:** Several questions were received regarding fiber optic installation.

- Fiber Splicing
- Splice Cases
- Termination Panels
- Testing and Acceptance
- Material Ownership and Supply
- Fiber Slack Requirements
- Labeling and Documentation

Answer: Phase 2B of the Four Canyons Parkway project does not propose the installation of Fiber Optic cable. Only conduit and boxes are proposed to be installed and are noted in the construction plans. Bid Items #256 & 258 have been removed from the Final Bid Schedule.

3. **Question:** I would like to request clarification regarding Bid Item 145, which lists 800 LF of Reset Fence. I've been unable to locate the corresponding locations on the plans. I'm assuming this work pertains to 25 Road, where existing fences may need to be relocated to the new property line. Could you please confirm if this is correct or provide additional details? Additionally, regarding the chain link fence at 623 25 Road with the automatic gate opener, we would like to request that this be listed as a separate line item for clarity and accurate pricing.

Answer #3: Your assumption is correct that Bid Item #145 pertains to resetting existing fences for several properties along 25 Road, to the new adjusted property alignment. The quantity for fencing to be reset is approximate and could be adjusted depending on several factors of the existing fencing.

Fencing to be relocated for 623 25 Road, including the coordination for resetting the automatic gate opener shall be completed under separate contract, or change order. The existing fence for 623 25 Road accounts for approximately 450 LF. This amount shall be deducted from Bid Item #145 and will be reflected in the updated Final Bid Schedule.

4. **Question:** Looking at Bid Items 146 and 163, are these duplicates as that is the same address as the Gastroenterology building. Also, is the City aware that the bottom portion of the sign isn't working properly now due to some electronic issues. Is the contractor going to need to repair that portion of the sign or are we going to reset as-is?

Answer: Bid Items 146 & 163 are not duplicate items. Item 146 is the small sign at the 25 Road driveway; Item 163 is the large electronic sign at the intersection. The Contractor must coordinate with the property owner and inform them of the sign's non-functioning panel before relocation. The Contractor is only responsible for relocation, but coordination with the owner and City may be needed to determine if repair is required at that time.

ADDENDUM #2 CLARIFICATIONS:

1. Please see attached revised Final Bid Schedule, reflecting the clarifications to question #2, with the removal of Bid Items #256 & #258. A description of "N/A" now fills Bid Item #256 & #258.
2. Please see attached revised Final Bid Schedule, reflecting the quantity change for Bid Item #145. The 450 LF of existing fencing to be reset for 623 25 Rd shall be completed under separate permit or change order.
3. Please see attached revised Final Bid Schedule, reflecting the quantity change for Bid Item #310 & #311. The quantities for these Bid Items have been reverted to the quantities prior to Addendum #1 (17,173 LF).
4. The updated sheet E4 of the Electrical Plans included in Addendum #1, reflecting the quantity change to Bid Item(s) #310 & #311, is no longer valid. Sheet E4 of the Electrical Plans included in the original Bid Package is correct.

The original solicitation for the project noted above is amended as noted. All other conditions of the subject remain the same.

Respectfully,



Dolly Daniels, Senior Buyer
City of Grand Junction, Colorado

Bid Schedule: FOUR CANYONS PKWY PH2B ADDENDUM No. 2

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	108.2	6" Water Pipe (C-900 PVC)	800.	LF	\$ _____	\$ _____
2	108.2	8" Water Pipe (C-900 PVC)	1,500.	LF	\$ _____	\$ _____
3	108.2	12" Water Pipe (C-900 PVC)	3,110.	LF	\$ _____	\$ _____
4	108.3	2" Gate Valve	4.	EA	\$ _____	\$ _____
5	108.3	6" Gate Valve	11.	EA	\$ _____	\$ _____
6	108.3	8" Gate Valve	8.	EA	\$ _____	\$ _____
7	108.3	12" Gate Valve	6.	EA	\$ _____	\$ _____
8	108.3	6" x 2" Tee	1.	EA	\$ _____	\$ _____
9	108.3	6" x 6" Tee	2.	EA	\$ _____	\$ _____
10	108.3	8" x 2" Tee	1.	EA	\$ _____	\$ _____
11	108.3	8" x 6" Tee	5.	EA	\$ _____	\$ _____
12	108.3	8" x 8" Tee	2.	EA	\$ _____	\$ _____
13	108.3	12" x 6" Tee	6.	EA	\$ _____	\$ _____
14	108.3	12" x 8" Tee	3.	EA	\$ _____	\$ _____
15	108.3	12" x 12" Tee	1.	EA	\$ _____	\$ _____
16	108.3	6" 11 1/4 degree Elbow	1.	EA	\$ _____	\$ _____
17	108.3	6" 22 1/2 degree Elbow	5.	EA	\$ _____	\$ _____
18	108.3	6" 45 degree Elbow	2.	EA	\$ _____	\$ _____
19	108.3	8" 11 1/4 degree Elbow	6.	EA	\$ _____	\$ _____
20	108.3	8" 22 1/2 degree Elbow	20.	EA	\$ _____	\$ _____
21	108.3	8" 45 degree Elbow	13.	EA	\$ _____	\$ _____
22	108.3	8" x 12" Reducer	1.	EA	\$ _____	\$ _____
23	108.3	12" 11 1/4 degree Elbow	2.	EA	\$ _____	\$ _____
24	108.3	12" 22 1/2 degree Elbow	15.	EA	\$ _____	\$ _____
25	108.3	12" 45 degree Elbow	2.	EA	\$ _____	\$ _____
26	108.3	Fire Hydrant	8.	EA	\$ _____	\$ _____
27	108.4	6"x3/4" Tapping Saddle	1.	EA	\$ _____	\$ _____
28	108.4	8"x3/4" Tapping Saddle	4.	EA	\$ _____	\$ _____
29	108.4	12"x3/4" Tapping Saddle	10.	EA	\$ _____	\$ _____
30	108.4	12"x1" Tapping Saddle	1.	EA	\$ _____	\$ _____
31	108.4	12"x2" Tapping Saddle	2.	EA	\$ _____	\$ _____
32	108.4	3/4" Corporation Stop	15.	EA	\$ _____	\$ _____
33	108.4	1" Corporation Stop	1.	EA	\$ _____	\$ _____
34	108.4	2" Corporation Stop	2.	EA	\$ _____	\$ _____
35	108.4	Water Service Line (3/4") (Type K Copper)	430.	LF	\$ _____	\$ _____
36	108.4	Water Service Line (1") (Type K Copper)	30.	LF	\$ _____	\$ _____
37	108.4	Water Service Line (2") (Type K Copper)	135.	LF	\$ _____	\$ _____
38	108.4	3/4" Meter Setter (Install Only) (Ute Water to Provide)	10.	EA	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
39	108.4	1" Meter Setter (Install Only) (Ute Water to Provide)	1.	EA	\$ _____	\$ _____
40	108.4	2" Meter Setter (Install Only) (Ute Water to Provide)	1.	EA	\$ _____	\$ _____
41	108.4	Meter Pit (Install Only) (Ute Water to Provide)	12.	EA	\$ _____	\$ _____
42	104.4	Cap Top Half of Sewer in Concrete per City Standard Detail GU-04.	5.	EA	\$ _____	\$ _____
43	104.4	Fully Encase Sewer in Concrete per City Standard Detail GU-04.	5.	EA	\$ _____	\$ _____
44	108.2	Import Trench Backfill (Class 3) (Including haul and disposal of unsuitable excavated material) (Assumed Unit Weight = 133 lbs/cu.ft.)	1,235.	TON	\$ _____	\$ _____
45	108.7	Granular Stabilization Material (Type B)	740.	TON	\$ _____	\$ _____
46	108.2	Storm Drain Pipe - 30" Concrete Pipe	2,644.	LF	\$ _____	\$ _____
47	108.2	Storm Drain Pipe - 18" Concrete Pipe	2,160.	LF	\$ _____	\$ _____
48	108.2	Storm Drain Pipe - 12" Concrete Pipe	750.	LF	\$ _____	\$ _____
49	108.6	Storm Drain Manhole (90" ID)	1.	EA	\$ _____	\$ _____
50	108.6	Storm Drain Manhole (60" ID)	6.	EA	\$ _____	\$ _____
51	108.6	Storm Drain Manhole (48" ID)	7.	EA	\$ _____	\$ _____
52	108.6	WQ manhole. ADS stormwater treatment unit Barracuda S8 or engineer approved equal. Includes 96" concrete manhole supplied by manufacturer and connection of adjacent storm sewer lines, forming inverts and adjusting to final grade. (Complete in Place).	1.	EA	\$ _____	\$ _____
53	108.6	WQ manhole. ADS stormwater treatment unit Barracuda S6 or engineer approved equal. Includes 72" concrete manhole supplied by manufacturer and connection of adjacent storm sewer lines, forming inverts and adjusting to final grade. (Complete in Place).	1.	EA	\$ _____	\$ _____
54	108.6	WQ Manhole. ADS stormwater treatment unit Barracuda Max S3 or engineer approved equal. Includes 36" HP (36" ADS triple wall polypropylene barrel section) manhole with ductile iron flat top lid supplied by manufacturer and connection of adjacent storm sewer lines, forming inverts and adjusting to final grade. Complete in Place).	1.	EA	\$ _____	\$ _____
55	108.6	Single Storm Drain Inlet with drive over curb opening (24" x 36")	3.	EA	\$ _____	\$ _____
56	108.6	Storm Drain Inlet with vertical curb opening (24" x 36")	25.	EA	\$ _____	\$ _____
57	108.6	Storm Drain - Large Area Inlet (24"x36")	1.	EA	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
58	108.5	Storm Drain - Manhole Barrel Section (D>5')(90" I.D.)	4.3	VLF	\$ _____	\$ _____
59	108.5	Storm Drain - Manhole Barrel Section (D>5')(60" I.D.)	30.	VLF	\$ _____	\$ _____
60	108.5	Storm Drain - Manhole Barrel Section (D>5')(48" I.D.)	2.	VLF	\$ _____	\$ _____
61	108.5	Storm Drain - Inlet Box Section (D>5')(24"x36" I.D.)	5.	VLF	\$ _____	\$ _____
62	108.5	Connect to Existing Manhole or Pipe	1.	EA	\$ _____	\$ _____
63	108.2	Imported Trench Backfill (Class 3) (Including haul and disposal of unsuitable excavated material) (Assumed Unit Weight = 133 lbs/cu.ft.)(Storm Drain)	1,220.	TON	\$ _____	\$ _____
64	108.7	Granular Stabilization Material (Type B) (18" Thick Min.) (Includes haul and disposal of unsuitable excavated material) (Assumed Unit Weight = 138 lbs/cu.ft.)(Storm Drain)	950.	TON	\$ _____	\$ _____
65	108.3	2-way Sanitary Sewer Service Clean-Out (Std Detail SS-07) (For Rain Garden Underdrains)	6.	EA	\$ _____	\$ _____
66	108.2	4" Gravity Underdrain Pipe (Factory Slotted SDR 17 PVC)	250.	LF	\$ _____	\$ _____
67	420	Geotextile Separator (CL 2) (Mirafi 180N or EQ) (For Rain Garden Underdrain)	300.	SY	\$ _____	\$ _____
68	420	Geotextile Separator (CL 2) (Mirafi 1100N or EQ) (For Rain Garden Underdrain)	155.	SY	\$ _____	\$ _____
69	304	Drain Gravel (For Rain Garden Underdrains)	41.	TON	\$ _____	\$ _____
70	304	Filter Sand (ASTM C-33)(For Rain Garden Underdrains)	70.	TON	\$ _____	\$ _____
71	LSC	Bio-Retention Topsoil Media (12" Thick) (all designated areas within Rain Gardens, see Underdrain Plans & Landscape Detail Sheets for Bio-Retention Media Properties)	305.	SY	\$ _____	\$ _____
72	108.2	Irrigation Pipe - 8" SDR-35 PVC	70.	LF	\$ _____	\$ _____
73	108.2	Irrigation Pipe - 10" C-900 PVC	10.	LF	\$ _____	\$ _____
74	108.2	Irrigation Pipe - 12" SDR-35 PVC	22.	LF	\$ _____	\$ _____
75	108.2	Irrigation Pipe - 18" C-900 PVC	450.	LF	\$ _____	\$ _____
76	108.2	Irrigation Pipe - 12" Corrugated HDPE Pipe	60.	LF	\$ _____	\$ _____
77	108.2	Irrigation Pipe - 18" Corrugated HDPE Pipe	1,500.	LF	\$ _____	\$ _____
78	108.2	Irrigation Pipe - 24" Corrugated HDPE Pipe	10.	LF	\$ _____	\$ _____
79	108.5	Irrigation Connection (2494 Flat Top Ln)	1.	EA	\$ _____	\$ _____
80	108.5	Irrigation Connection (623 25 Rd)	1.	EA	\$ _____	\$ _____
81	108.5	Irrigation Connection (625 25 Rd)	1.	EA	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
82	108.5	Irrigation Connection (653 1/2 25 Rd)	1.	EA	\$ _____	\$ _____
83	108.5	Irrigation Connection (653 25 Rd)	1.	EA	\$ _____	\$ _____
84	108.5	Irrigation Connection (651 25 Rd)	1.	EA	\$ _____	\$ _____
85	108.5	Irrigation Connection (649 25 Rd)	1.	EA	\$ _____	\$ _____
86	108.5	Irrigation Manhole (36" I.D.)	9.	EA	\$ _____	\$ _____
87	108.5	Irrigation Manhole (48" I.D.) Structures (29),(28),&(27) per Details and Plan	3.	EA	\$ _____	\$ _____
88	108.5	Irrigation - Manhole Barrel Section (D>5')(36" I.D.)	21.	VLF	\$ _____	\$ _____
89	108.5	Irrigation - Manhole Barrel Section (D>5')(48" I.D.)	13.	VLF	\$ _____	\$ _____
90	108.2	Imported Trench Backfill (Class 3) (Including haul and disposal of unsuitable excavated material) (Assumed Unit Weight = 133 lbs/cu.ft.)(Irrigation)	700.	TON	\$ _____	\$ _____
91	108.7	Granular Stabilization Material (Type B) (18" Thick Min.) (Includes haul and disposal of unsuitable excavated material) (Assumed Unit Weight = 138 lbs/cu.ft.)(Irrigation)	365.	TON	\$ _____	\$ _____
92	202	Remove Asphalt Mat. Full Depth.	22,500.	SY	\$ _____	\$ _____
93	202	Remove Concrete	2,500.	SY	\$ _____	\$ _____
94	202	Abandon Pipe by Plugging End with Concrete	4.	EA	\$ _____	\$ _____
95	202	Remove Landscape Border	450.	LF	\$ _____	\$ _____
96	202	Remove Fire Hydrant and return to Ute Water	3.	EA	\$ _____	\$ _____
97	202	Remove Water Meter	8.	EA	\$ _____	\$ _____
98	202	Remove Water Valve	23.	EA	\$ _____	\$ _____
99	202	Remove Storm Drain Inlet	5.	EA	\$ _____	\$ _____
100	202	Remove Irrigation Manhole	6.	EA	\$ _____	\$ _____
101	202	Remove Storm Drain Manhole	10.	EA	\$ _____	\$ _____
102	202	Remove Light Pole	2.	EA	\$ _____	\$ _____
103	202	Remove Light Pole Base	2.	EA	\$ _____	\$ _____
104	202	Remove Post	7.	EA	\$ _____	\$ _____
105	202	Remove Delineator	13.	EA	\$ _____	\$ _____
106	202	Remove Ground Sign	27.	EA	\$ _____	\$ _____
107	202	Remove Sod.	5,056.	SY	\$ _____	\$ _____
108	202	Remove Tree	52.	EA	\$ _____	\$ _____
109	202	Remove Tree Stump	6.	EA	\$ _____	\$ _____
110	202	Remove Bush	56.	EA	\$ _____	\$ _____
111	202	Remove Property Pin (no reference or reset)	8.	EA	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
112	202	Remove Fence (includes all gates and associated appurtenances)	2,228.	LF	\$ _____	\$ _____
113	202	Remove Pipe as shown on Plans	4,500.	LF	\$ _____	\$ _____
114	202	Remove Mail Box	3.	EA	\$ _____	\$ _____
115	202	Remove Signal Pole Steel Template (base) and Return to City Traffic	1.	EA	\$ _____	\$ _____
116	202	Clearing and Grubbing	1.	LS	\$ _____	\$ _____
117	210	Adjust Sprinkler System (Heritage Estates HOA Detention Pond Area)	1.	EA	\$ _____	\$ _____
118	210	Adjust Sprinkler System (2508 Blichmann)	1.	EA	\$ _____	\$ _____
119	210	Adjust Sprinkler System (2501 Blichmann)	1.	EA	\$ _____	\$ _____
120	210	Adjust Sprinkler System (Heritage Heights HOA Tract on the West side of 25 Rd North of 625 25 Rd)	1.	EA	\$ _____	\$ _____
121	210	Adjust Sprinkler System (625 25 Rd)	1.	EA	\$ _____	\$ _____
122	210	Adjust Sprinkler System (623 25 Rd)	1.	EA	\$ _____	\$ _____
123	210	Adjust Sprinkler System (2502 Foresight) (includes old Foresight Cir Median)	1.	EA	\$ _____	\$ _____
124	210	Adjust Sprinkler System (2503 Foresight)	1.	EA	\$ _____	\$ _____
125	210	Adjust Sprinkler System (610 25 Rd)	1.	EA	\$ _____	\$ _____
126	210	Adjust Sprinkler System (604 25 Rd)	1.	EA	\$ _____	\$ _____
127	210	Adjust Sprinkler System (Copper Creek HOA at 25 Rd and Waite Ave)	1.	EA	\$ _____	\$ _____
128	210	Adjust Sprinkler System (Garrett Estates HOA Detention Pond Area at 25 Rd and F 1/2 Rd)	1.	EA	\$ _____	\$ _____
129	210	Adjust Sprinkler System (Herritage Estates HOA North Side of F 1/4 Rd West of 25 Rd)	1.	EA	\$ _____	\$ _____
130	210	Adjust Sprinkler System (2494 F 1/4 Rd)	1.	EA	\$ _____	\$ _____
131	210	Adjust Water Valve to Finished Grade	16.	EA	\$ _____	\$ _____
132	210	Adjust Water Meter to Finished Grade	5.	EA	\$ _____	\$ _____
133	210	Reset Water Meter	1.	EA	\$ _____	\$ _____
134	210	Reset Outet Structure for Heritage Estates Detention	1.	EA	\$ _____	\$ _____
135	210	Reset Outet Structure for Garrett Estates Detention	1.	EA	\$ _____	\$ _____
136	210	Adjust Manhole to Finished Grade	21.	EA	\$ _____	\$ _____
136A	210	Modify Manhole to Finished Grade	7.	EA	\$ _____	\$ _____
137	210	Reset Landscape Boulder	1.	EA	\$ _____	\$ _____
138	210	Trim Tree to clear walkway	6.	EA	\$ _____	\$ _____
139	210	Trim Bush to clear walkway	11.	EA	\$ _____	\$ _____
140	210	Reference/Reset Survey Monument	5.	EA	\$ _____	\$ _____
141	210	Reset Gate	2.	EA	\$ _____	\$ _____
142	210	Reset Mail Box (Coordinate with USPS)	7.	EA	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
143	210	Reset Landscape Border	40.	LF	\$ _____	\$ _____
144	210	Reset 2" PVC Irrigation Halls Estates Irrigation Tract adjacent to Hanna Ln	650.	LF	\$ _____	\$ _____
145	210	Reset Fence	350.	LF	\$ _____	\$ _____
146	210	Reset Commercial Sign for 604 25 Rd	1.	EA	\$ _____	\$ _____
147	210	Reset Landscape Ground Cover (Halls Est. HOA adjacent to Hanna Ln N side Four Canyons Pkwy 24 1/2 to 24 3/4)	11,000.	SF	\$ _____	\$ _____
148	210	Reset Landscape Ground Cover (Heritage Heights HOA South side of Four Canyons Pkwy from 24 1/2 Rd to 24 3/4 Rd)	4,350.	SF	\$ _____	\$ _____
149	210	Reset Landscape Ground Cover (Heritage Heights HOA South side of Four Canyons Pkwy from 24 3/4 Rd to 25 Rd)	8,100.	SF	\$ _____	\$ _____
150	210	Reset Landscape Ground Cover (2501 Blichmann)	120.	SF	\$ _____	\$ _____
151	210	Reset Landscape Ground Cover (610 25 Rd)	130.	SF	\$ _____	\$ _____
152	210	Reset Landscape Ground Cover (604 25 Rd)	60.	SF	\$ _____	\$ _____
153	210	Reset Landscape Ground Cover (661 Garrett Way)	200.	SF	\$ _____	\$ _____
154	210	Reset Landscape Ground Cover (663 Garrett Way)	350.	SF	\$ _____	\$ _____
155	210	Reset Landscape Ground Cover (665 Garrett Way)	250.	SF	\$ _____	\$ _____
156	210	Reset Landscape Ground Cover (667 Garrett Way)	250.	SF	\$ _____	\$ _____
157	210	Reset Landscape Ground Cover (669 Garrett Way)	250.	SF	\$ _____	\$ _____
158	210	Reset Landscape Ground Cover (Garrett Way HOA on Garrett Way)	50.	SF	\$ _____	\$ _____
159	210	Reset Landscape Ground Cover (671 Garrett Way)	350.	SF	\$ _____	\$ _____
160	210	Reset Landscape Ground Cover (25 Rd and Waite Ave intersection - Copper Creek entrance - in ROW)	50.	SF	\$ _____	\$ _____
161	210	Reset Landscape Ground Cover (2494 F 1/4 Rd)	200.	SF	\$ _____	\$ _____
162	210	Cap Existing Sanitary Sewer with Cap	75.	LF	\$ _____	\$ _____
163	210	Reset Sign (Gastroenterology Associates on Patterson)	1.	EA	\$ _____	\$ _____
164	210	Reset Sign	3.	EA	\$ _____	\$ _____
165	PH	POTHOLING	75.	EA	\$ _____	\$ _____
166	203	Unclassified Excavation	73,876.	CY	\$ _____	\$ _____
167	203	Unclassified Embankment	10,776.	CY	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
168	203	Haul Earthwork Material	61,600.	CY	\$ _____	\$ _____
169	207	Topsoil (12" Thick) (all planting areas within ROW) (Except areas designated without, see Landscape Plans)	3,000.	SY	\$ _____	\$ _____
170	203	(Roadway Subgrade Stabilization) Muck Excavation	10,000.	CY	\$ _____	\$ _____
171	304	(Roadway Subgrade Stabilization) Aggregate Base Course (Class 3) (24" Thick)	15,000.	SY	\$ _____	\$ _____
172	420	(Roadway Subgrade Stabilization) Geotextile Separator (CI 2)	15,000.	SY	\$ _____	\$ _____
173	420	(Roadway Subgrade Stabilization) Geogrid Reinforcement	15,000.	SY	\$ _____	\$ _____
174	208	Storm Drain Inlet Protection (Erosion Log filter at Drop Inlet)	12.	EA	\$ _____	\$ _____
175	208	Storm Drain Inlet Protection (Type II)	35.	EA	\$ _____	\$ _____
176	208	Erosion Log	1,350.	LF	\$ _____	\$ _____
177	208	Prefabricated Vehicle Tracking Pad	5.	EA	\$ _____	\$ _____
178	208	Prefabricated Concrete Washout Structure	5.	EA	\$ _____	\$ _____
179	209	Dust Abatement	500.	DAYS	\$ _____	\$ _____
180	212	Seeding - Native Seed Mix	0.7	ACRE	\$ _____	\$ _____
181	304	Aggregate Base Course (Class 2) (14" Thick) (Four Canyons Pkwy, 25 Rd from Blichmann to Patterson, F 1/2 Rd from 25 Rd to Crossing St)	40,500.	SY	\$ _____	\$ _____
182	304	Aggregate Base Course (Class 2) (10" Thick) (25 Rd from Four Canyons Pkwy to Waite Ave)	6,920.	SY	\$ _____	\$ _____
183	304	Aggregate Base Course (Class 2) (12" Thick) (25 Rd & Four Canyons Pkwy Intersection)	8,050.	SY	\$ _____	\$ _____
184	304	Aggregate Base Course (Class 2) (12" Thick) (24 3/4 Rd, 25 Rd Ct, Blichmann, F 1/4 Rd, and Foresight Cir)	10,100.	SY	\$ _____	\$ _____
185	304	Aggregate Base Course (Class 6) (12" Thick) (Driveway)	1,500.	SY	\$ _____	\$ _____
186	304	Aggregate Base Course (Class 6) (8" Thick) (Four Canyons Pkwy, 25 Rd from Blichmann to Patterson, and F 1/2 Rd from 25 Rd to Crossing St)	36,350.	SY	\$ _____	\$ _____
187	304	Aggregate Base Course (Class 6) (8" Thick) (25 Rd from Four Canyons Pkwy to Waite Ave)	6,250.	SY	\$ _____	\$ _____
188	304	Aggregate Base Course (Class 6) (8" Thick) (25 Road & Four Canyons Pkwy Intersection)	7,350.	SY	\$ _____	\$ _____
189	304	Aggregate Base Course (Class 6) (8" Thick) (24 3/4 Rd, 25 Rd Ct, Blichmann, F 1/4 Rd and Foresight Cir)	8,800.	SY	\$ _____	\$ _____
190	304	Aggregate Base Course (Class 6) (8" Thick) (Patterson Rt Turn)	500.	SY	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
191	304	Aggregate Base Course (Class 6) (8" Thick) (Road Shoulder)	225.	SY	\$ _____	\$ _____
192	304	Aggregate Base Course (Class 6) (4" Thick) (Gravel Driveways on Plan)	360.	SY	\$ _____	\$ _____
193	304	Washed Rock Surface Course (Driveways and on Properties as shown) (2" Thick)	1,750.	SY	\$ _____	\$ _____
194	306	Reconditioning (6" Deep) (Four Canyons Pkwy, 25 Rd from Blichmann to Patterson, and F 1/2 Rd from 25 Rd to Crossing St)	40,500.	SY	\$ _____	\$ _____
195	306	Reconditioning (6" Deep) (25 Road from Four Canyons Pkwy to Waite Ave)	6,920.	SY	\$ _____	\$ _____
196	306	Reconditioning (6" Deep) (25 Road & Four canyons Pkwy Intersection)	8,050.	SY	\$ _____	\$ _____
197	306	Reconditioning (6" Deep) (24 3/4 Rd, 25 Rd Ct, Blichmann, F 1/4 Rd and Foresight Cir)	10,100.	SY	\$ _____	\$ _____
198	306	Reconditioning (6" Deep) (Patterson Rt Turn)	500.	SY	\$ _____	\$ _____
199	306	Reconditioning (6" Deep) (Driveways)	1,500.	SY	\$ _____	\$ _____
200	329	Sod. (To repair & Match Existing)	53,000.	SF	\$ _____	\$ _____
201	401	Asphalt Millings (4" thick) (1 1/2" max particle size) (Temporary Drive Surfaces)	100.	TON	\$ _____	\$ _____
202	401	Hot Mix Asphalt (4" thick) (Grading SX 100, Binder Grade 64-22) (Driveway)	330.	TON	\$ _____	\$ _____
203	401	Hot Mix Asphalt (2" thick) (Grading SX 100, Binder Grade 64-28) (Four Canyons Pkwy, 25 Rd from Blichmann to Patterson, and F 1/2 Rd from 25 Rd to Waite Ave)	4,000.	TON	\$ _____	\$ _____
204	401	Hot Mix Asphalt (2" thick) (Grading SX 100, Binder Grade 64-28) (25 Road from Four Canyons Pkwy to Waite Ave)	700.	TON	\$ _____	\$ _____
205	401	Hot Mix Asphalt (2" thick) (Grading SX 100, Binder Grade 64-28) (25 Road & Four canyons Pkwy Intersection)	810.	TON	\$ _____	\$ _____
206	401	Hot Mix Asphalt (2" thick) (Grading SX 100, Binder Grade 64-28) (24 3/4 Rd, 25 Rd Ct, Blichmann Ave, F 1/4 Rd and Foresight Cir)	970.	TON	\$ _____	\$ _____
207	401	Hot Mix Asphalt (5 1/2" thick) (Grading SX 100, Binder Grade 64-22) (Four Canyons Pkwy, 25 Rd from Blichmann to Patterson, and F 1/2 Rd from 25 Rd to Crossing St)	11,000.	TON	\$ _____	\$ _____
208	401	Hot Mix Asphalt (5" thick) (Grading SX 100, Binder Grade 64-22) (25 Road from Four Canyons Pkwy to Waite Ave)	1,720.	TON	\$ _____	\$ _____
209	401	Hot Mix Asphalt (7" thick) (Grading SX 100, Binder Grade 64-22) (25 Road & Four canyons Pkwy Intersection)	2,850.	TON	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
210	401	Hot Mix Asphalt (4" thick) (Grading SX 75, Binder Grade 64-22) (24 3/4 Rd, 25 Rd Ct, Blichmann Ave, F 1/4 Rd and Foresight Cir)	1,940.	TON	\$ _____	\$ _____
211	401	Hot Mix Asphalt (2" thick) (Grading SX 75, Binder Grade 64-22) (T-Top on plan)	40.	TON	\$ _____	\$ _____
212	504	Precast Concrete Block Retaining Wall System (includes all necessary appurtenances, work, etc. to complete).	600.	FSF	\$ _____	\$ _____
213	504	Retaining Wall System (Keystone Legacy Stone or Engineer Approved Equal) (For Rain Gardens and adjacent to Landscaping at the Slate on 25 Apts.)	1,340.	FSF	\$ _____	\$ _____
214	608	Concrete Landscape Border (match existing in kind)	100.	LF	\$ _____	\$ _____
215	608	Concrete Pavement (Patterson Rt Turn Ln) (9" Thick) (CL-P)	500.	SY	\$ _____	\$ _____
216	608	Concrete Curb and Spill Gutter (1.5' Wide) (both Spill and Collector Gutter) to include Class 6 Aggregate Base Course per Typical Cross Section	9,070.	LF	\$ _____	\$ _____
217	608	Concrete Curb (6" Wide) (6" High) to include Class 6 Aggregate Base Course per Typical Cross Section	700.	LF	\$ _____	\$ _____
218	608	Concrete Curb and Gutter (2' Wide) (both collector and spill gutters) to include Class 6 Aggregate Base Course per Typical Cross Section	14,620.	LF	\$ _____	\$ _____
219	608	Concrete Drive Over Curb and Gutter 3' wide and both collector and spill gutter to include Class 6 Aggregate Base Course per Typical Cross Section	1,420.	LF	\$ _____	\$ _____
220	608	Concrete Sidewalk (6" Thick) to include 6" of Class 6 Aggregate Base Course.	12,250.	SY	\$ _____	\$ _____
221	608	Concrete Drainage Pan (2' Wide) to include 6" of Class 6 Aggregate Base Course.	300.	LF	\$ _____	\$ _____
222	608	Concrete Drainage Pan (3' Wide) to include 6" of Class 6 Aggregate Base Course.	260.	LF	\$ _____	\$ _____
223	608	Concrete Drainage Pan (6' Wide) to include 6" of Class 6 Aggregate Base Course.	110.	LF	\$ _____	\$ _____
224	608	Concrete Intersection Corner (8" thick) to include 6" of Class 6 Aggregate Base Course.	240.	SY	\$ _____	\$ _____
225	608	Concrete Median Island Nose (8" Thick) to include 6" of Class 6 Aggregate Base Course.	70.	SY	\$ _____	\$ _____
226	608	Concrete Curb Ramp to include 6" of Class 6 Aggregate Base Course.	400.	SY	\$ _____	\$ _____
227	608	Concrete Pavement (6" Thick) to include 6" of Class 6 Aggregate Base Course.	85.	SY	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
228	608	Concrete Driveway Section (8" Thick) (Commercial) to include 6" of Class 6 Aggregate Base Course.	810.	SY	\$ _____	\$ _____
229	608	Concrete Median Edging (1.5' Wide) (4" thick) (make sure not repeated landscape quantities)	6,205.	LF	\$ _____	\$ _____
230	608	Concrete Median Cover Material (6" Patterned Concrete) to include 6" of Class 6 Aggregate Base Course. (make sure not repeated landscape quantities)	460.	SY	\$ _____	\$ _____
231	608	Detectable Warning (Cast Iron, Wet Set) (2'x2)	145.	EA	\$ _____	\$ _____
232	614	Sign Panel (CL I)	704.	SF	\$ _____	\$ _____
233	614	Sign Panel (CL II)	12.	SF	\$ _____	\$ _____
234	614	3 LB. U SHAPE CHANNEL STEEL POST	88.	EA	\$ _____	\$ _____
235	614	Steel Sign Support (2 1/2" round NP-40) (Pole/Slipbase)	1.	EA	\$ _____	\$ _____
236	614	Safe Hit Flexible Delineator SH248GP3-WS 09 to include sleeve or Engineer Approved Equal	10.	EA	\$ _____	\$ _____
237	202	Remove Existing Signal (Includes pole, mast arm, foundation, associated pull box, and telemetry per plan)	1.	EA	\$ _____	\$ _____
238	503-00036	Drilled Caisson (36 Inch)	44.	LF	\$ _____	\$ _____
239	503-00042	Drilled Caisson (42 Inch)	34.	LF	\$ _____	\$ _____
240	613-07005	Type Five Pull Box (Traffic) (30x48x24)	5.	EA	\$ _____	\$ _____
241	614-70150	Pedestrian Signal Face (16) (Countdown)	6.	EA	\$ _____	\$ _____
242	614-70336	Traffic Signal Face (12-12-12) (With Backplate) (Patterson)	2.	EA	\$ _____	\$ _____
243	614-70336b	Traffic Signal Face (12-12-12) (With Backplate and Retroflective Border) ("T"shape for HAWKS)	8.	EA	\$ _____	\$ _____
244		Traffic Signal Face (12-12-12-12-12) (With Backplate) (Patterson)	3.	EA	\$ _____	\$ _____
245	614-72855	Traffic Signal Controller Cabinet	2.	EA	\$ _____	\$ _____
246	614-72863	Pedestrian Push Button Post Assembly	8.	EA	\$ _____	\$ _____
247	614-72886	Intersection Detection System (Camera)	1.	EA	\$ _____	\$ _____
248	614-72886	Intersection Detection System (Camera with Radar)	4.	EA	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
249	614-72886o	Intersection Detection System (Opticom)	1.	EA	\$ _____	\$ _____
250	614-81140	Traffic Signal-Light Pole Steel (1-40 Foot Mast Arm)	3.	EA	\$ _____	\$ _____
251	614-81150	Traffic Signal-Light Pole Steel (1-50 Foot Mast Arm)	2.	EA	\$ _____	\$ _____
252	614	Mount City Provided Sign on Mast Arm	1.	EA	\$ _____	\$ _____
253	614	Sign Panel (CL I)(See Signal Plans)	135.	SF	\$ _____	\$ _____
254	614	Sign Panel (CL II)(at HAWK Signal Poles, see Signal Plans)	48.	SF	\$ _____	\$ _____
255						
256		N/A				
257	614-87320	Closed Circuit Television (patterson)	1.	EA	\$ _____	\$ _____
258		N/A				
259	614	2" PVC Conduit	800.	LF	\$ _____	\$ _____
260	614	White Delineator (Break away reflector)	180.	EA	\$ _____	\$ _____
261	627	High Build Acrylic Waterborne Paint Pavement Marking (White)(2 Coats)	200.	Gal	\$ _____	\$ _____
262	627	High Build Acrylic Waterborne Paint Pavement Marking (Yellow)(2 Coats)	105.	Gal	\$ _____	\$ _____
263	627	Preformed Thermoplastic Pavement Marking (Word / Symbol) (Asphalt only)	1,332.	SF	\$ _____	\$ _____
264	627	Preformed Thermoplastic Pavement Marking (X-Walk & Stop Line) (Asphalt only)	3,262.	SF	\$ _____	\$ _____
265	627	4" Preformed Thermoplastic Pavement Marking (White) (Cross Hatch inside bike buffer) (125 Mil)	655.	SF	\$ _____	\$ _____
266	627	Preformed Thermoplastic Pavement Marking (Green Bikeway Ladder)	1,224.	SF	\$ _____	\$ _____
267	627	Preformed Thermoplastic Pavement Marking (4" White stripe on outside of Green Bikeway Ladder)	210.	SF	\$ _____	\$ _____
268	627	Preformed Thermoplastic Markings - Bike Rider w/ Helmet (Left) (White bike on green background)(6'6"x3'4" (90 Mil)	50.	EA	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
269	627	Preformed Thermoplastic Pavement Marking (Word / Symbol) (Concrete)(Inlaid)(includes balck contrast tape, 1.5" each side, total of 3") (Patterson Rt. Turn)	50.	SF	\$ _____	\$ _____
270	627	Preformed Thermoplastic Pavement Marking (X-Walk & Stop Line) (Concrete only, Inlaid)(includes balck contrast tape, 1.5" each side, total of 3") (Patterson Rt. Turn)	80.	SF	\$ _____	\$ _____
271	LSC	Soil Amendment (To be tilled)	82,985.	SF	\$ _____	\$ _____
272	LSC	1-1/2" Tan Granite (3" Depth)	78,542.	SF	\$ _____	\$ _____
273	LSC	1-1/2" Tan Granite (3" Depth), Plus 2-3" La Sal Purple Granite (scattered at 1 CF/100 SF)	42,147.	SF	\$ _____	\$ _____
274	LSC	2-3" La Sal Purple Granite (3" Depth)	4,443.	SF	\$ _____	\$ _____
275	LSC	Landscape Boulder - Small (2'x2'x3')	463.	EACH	\$ _____	\$ _____
276	LSC	Landscape Boulder - Large (3'x3'x4')	54.	EACH	\$ _____	\$ _____
277	LSC	Deciduous Tree (1-1/2 Inch Caliper)	66.	EACH	\$ _____	\$ _____
278	LSC	Deciduous Tree (2 Inch Caliper)	42.	EACH	\$ _____	\$ _____
279	LSC	Deciduous Shrub (5 Gallon Container)	591.	EACH	\$ _____	\$ _____
280	LSC	Evergreen Tree (6 Foot, B&B)	15.	EACH	\$ _____	\$ _____
281	LSC	Evergreen Shrubs (5 Gallon Container)	120.	EACH	\$ _____	\$ _____
282	LSC	Perennials (1 Gallon Container)	354.	EACH	\$ _____	\$ _____
283	LSC	Ornamental Grasses (1 Gallon Container)	351.	EACH	\$ _____	\$ _____
284	IRR	Irrigation Connection to Four Canyons Pkwy PH1	1.	EACH	\$ _____	\$ _____
285	IRR	4 Inch PVC Irrigation Sleeve, 18" bury under sidewalks	100.	LF	\$ _____	\$ _____
286	IRR	4 Inch PVC Irrigation Sleeve, 30" bury under roadways	730.	LF	\$ _____	\$ _____
287	IRR	6 Inch PVC Irrigation Sleeve, 18" bury under sidewalks	100.	LF	\$ _____	\$ _____
288	IRR	6 Inch PVC Irrigation Sleeve, 30" bury under roadways	940.	LF	\$ _____	\$ _____
289	IRR	4" HDPE Mainline	7,086.	LF	\$ _____	\$ _____
290	IRR	1 Inch PVC CL 160 Lateral Pipe	15,996.	LF	\$ _____	\$ _____
291	IRR	1-1/2 Inch PVC CL 160 Lateral Pipe	400.	LF	\$ _____	\$ _____
292	IRR	Tracer Wire for all Mainline and PVC Lateral Pipes	23,482.	LF	\$ _____	\$ _____
293	IRR	3/4 Inch Quick Coupler Valve	5.	EACH	\$ _____	\$ _____
294	IRR	1 Inch Automatic PES-B Scrubber Valves	6.	EACH	\$ _____	\$ _____
295	IRR	1.5 Inch Automatic PES-B Scrubber Valves	4.	EACH	\$ _____	\$ _____
296	IRR	2-wire Control Wire	4.	LF	\$ _____	\$ _____
297	IRR	2-wire Control, including decoders, grounding	Lump	SUM	---	\$ _____
298	IRR	Isolations Valves - For Mainline	5.	EACH	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
299	IRR	Isolations Valves - For Rain Garden Lateral Shutoff	5.	EACH	\$ _____	\$ _____
300	IRR	Manual Drain Valves	1.	EACH	\$ _____	\$ _____
301	IRR	Risers with Compression Tee transition to Tubing	191.	EACH	\$ _____	\$ _____
302	IRR	1/2" Drip Tubing (No Emitters and Not including Tree Ring Assemblies)	10,760.	LF	\$ _____	\$ _____
303	IRR	Netafim Drip Emitters (incl. 1/4" Distribution Tubing)	3,543.	EACH	\$ _____	\$ _____
304	IRR	Tree Ring Assembly	123.	EACH	\$ _____	\$ _____
305	IRR	Flush Caps in 6" Round Box	77.	EACH	\$ _____	\$ _____
306	IRR	Air Relief/Pressure Relief Assembly	1.	EACH	\$ _____	\$ _____
307	613	2" Schedule 80 PVC (for Franchise Utility crossing) (varies)	2,200.	LF	\$ _____	\$ _____
308	613	4" Schedule 80 PVC (for Franchise Utility crossing) (varies)	2,200.	LF	\$ _____	\$ _____
309	613	Large Splice Box (Quasite) (3' - 2 5/8" x 2'-2") Broadband Logo.	25.	EACH	\$ _____	\$ _____
310	613	2" Schedule 80 PVC (City Broadband Conduit)	17,173.	LF	\$ _____	\$ _____
311	613	2" Schedule 80 PVC (City Electrical Conduit)	17,173.	LF	\$ _____	\$ _____
312	ELEC	Type two Pull Box	154.	EACH	\$ _____	\$ _____
313	ELEC	Wiring	Lump	SUM	---	\$ _____
314	ELEC	Light Standard and Luminaire (Pedestrian)	138.	EACH	\$ _____	\$ _____
315	ELEC	Light Standard Foundation (Pedestrian)	138.	EACH	\$ _____	\$ _____
316	ELEC	Lighting Control Center PWR Pedestal (Special) (LCBP x1.74)	3.	EACH	\$ _____	\$ _____
317	ELEC	Trench - Site Lighting and Electrical/Fiber	Lump	SUM	---	\$ _____
318	620	Sanitary Facility	1.	EACH	\$ _____	\$ _____
319	625	Construction Surveying	Lump	SUM	---	\$ _____
320	626	Mobilization	Lump	SUM	---	\$ _____
321	630	Traffic Control (Complete In Place)	Lump	SUM	---	\$ _____
322	630	Traffic Control Plan	Lump	SUM	---	\$ _____
323	630	Construction Phasing Plan	Lump	SUM	---	\$ _____
324	630	Temporary Paving	2,000.	SY	\$ _____	\$ _____
325	FO	Field Office, Class 1	1.	EACH	\$ _____	\$ _____

Bid Schedule: FOUR CANYONS PKWY PH2B

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
F/A	700-70019	Asphalt Cement Cost Adjustment	---	---	---	\$ 400,000.00
MCR		Minor Contract Revisions	---	---	---	\$ 800,000.00

Bid Amount: \$ _____

Bid Amount: _____ dollars

Contractor Name:
Contractor Address:
Contractor Phone #: