




NOTES:

1. THE OVERALL FLUORESCENT BALLAST SHALL HAVE A TOTAL HARMONIC DISTORTION OF PLUS/MINUS 20% AND A BALLAST FACTOR EQUAL TO OR GREATER THAN 80%.
2. ALL LIGHTING FIXTURES EQUIPPED WITH "EM" OR HALF SHADED SHALL BE PROVIDED WITH AN ENGINEER APPROVED EMERGENCY BALLAST. FOR OPERATION OF TWO LAMPS IN A 4 LAMP FIXTURE AND 1 LAMP IN A 2 OR 3 LAMP FIXTURE. BALLAST SHALL BE CONNECT TO THE UNSWITCHED SIDE OF THE LIGHTING CIRCUIT.
3. GRID TROPPER TYPE LIGHTING FIXTURES SHALL NOT BE SUPPORTED FROM THE T-BAR CEILING GRID.
4. THE SYMBOL USED IN THE SCHEDULE IS A GENERIC SYMBOL, TO INDICATE AN EXIT LIGHT FIXTURE. REFER TO THE PLANS FOR THE NUMBER OF FACES REQUIRED AT EACH EXIT. INSTALL THE NUMBER OF FACES REQUIRED AT EACH EXIT. FIELD ADJUST THE LOCATION OF THE EXIT SIGNS FOR THE BEST VISIBILITY POSSIBLE.
5. THIS EXIT SIGN REQUIRES THE EXTRA BATTERY CAPACITY TO OPERATE THE REMOTELY LOCATED EMERGENCY HEAD FOR EGRESS AWAY FROM BUILDING.
6. FLUORESCENT LUMINAIRES DISCONNECTING MEANS; INDOOR LOCATIONS, OTHER THAN DWELLINGS AND ASSOCIATED ACCESSORY STRUCTURES, FLUORESCENT LUMINAIRES (FIXTURES) THAT UTILIZE DOUBLE-ENDED LAMPS AND CONTAIN BALLAST(S) THAT CAN BE SERVICED IN PLACE OR BALLASTED LUMINAIRES THAT ARE SUPPLIED FROM MULTI-WIRE BRANCH CIRCUITS AND CONTAIN BALLAST(S) THAT CAN BE SERVICED IN PLACE SHALL HAVE A DISCONNECTING MEANS EITHER INTERNAL OR EXTERNAL TO EACH LUMINAIRE (FIXTURE), TO DISCONNECT SIMULTANEOUSLY FROM THE SOURCE OF SUPPLY ALL CONDUCTORS OF THE BALLAST, INCLUDING THE GROUNDED CONDUCTOR IF ANY. THE TERMINALS OF THE DISCONNECTING MEANS SHALL BE GUARDED, THE DISCONNECTING MEANS SHALL BE LOCATED SO AS TO BE ACCESSIBLE TO QUALIFIED PERSONS BEFORE SERVICING OR MAINTAINING THE BALLAST. THIS REQUIREMENT SHALL BECOME EFFECTIVE JANUARY 1, 2008.

1. MOUNT FICTURE TYPE SA AT 18"-0" A.F.F. TO BOTTOM OF FIXTURE, CENTERED OVER OR OPENING. TYPICAL OF ALL TYPE SD FIXTURES. SET THE PHOTOCELL TO TURN THE LIGHTS ON AT DARK AND OFF AT DAWN. SLIGHT ADJUSTMENTS CAN BE MADE TO THE MOUNTING HEIGHT AS NECESSARY TO WORK WITH THE BUILDING STRUCTURE.
2. MOUNT FICTURE SUB AT 8'-4" A.F.F. TO BOTTOM OF FIXTURE CENTERED OVER MAN DOOR. PROVIDE AN EMERGENCY FUNCTION IN THIS FIXTURE FOR EGRESS AWAY FROM THE BUILDING. SLIGHT ADJUSTMENTS CAN BE MADE TO THE MOUNTING HEIGHT AS NECESSARY TO WORK WITH THE BUILDING STRUCTURE.



This is for documentation only, no response is required.