



Purchasing Division

ADDENDUM NO. 3

DATE: January 29, 2026
FROM: City of Grand Junction Purchasing Division
TO: All Offerors
RE: Crosby Avenue Improvements Project IFB-5805-26-DD

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded, and supplemented as to this date as hereinafter described.

Please make note of the following questions/answers/clarifications:

- 1. Revised Bid Schedule (attached), Plan Set and Pre-Bid Meeting Slide Presentation (links). Bidders must submit this Revised Bid Schedule with their bid.**

[Revised Plan Sets Crosby Ave](#)

[Pre-Bid Slide Presentation](#)

Clarifications:

1. The bid item code for bid item 5 has been corrected to 202-00032.
2. The bid item code for bid item 8 has been corrected to 202-00210.
3. The quantities for bid items 43 and 44 have been corrected on the bid schedule.
4. Bid items 37 and 38 are all-inclusive of the work required to relocate sanitary sewer manhole D2-252-026.
5. The bid item code for bid item 49 has been corrected to 214-00650.
6. Bid items 65 and 66 are for adjustments to the sanitary sewer alignment to accommodate the D2-252-026 manhole relocation.
7. Bid item 68 has been revised to highlight the inclusion of the irrigation bypass in this bid item per CDOT Standard Specifications Section 107.05.
8. The bid item code for bid item 75 has been corrected to 609-21110.
9. The bid item code for bid item 83 has been corrected to 613-07002.
10. A bid item for tree trimming (#134) has been added to the bid schedule for the trees hanging low over the sidewalk at 464 Base Rock St.
11. The revision date has been updated on the cover and title sheets (sheets 1-2).
12. The CDOT M Standard Plan index (sheet 3) has been revised to the current version.
13. The SAQ (sheets 15-20) have been revised to include the updated bid schedule.
14. A graphical error on the striping tabulation (sheet 31) has been corrected.
15. The rim elevations of manholes D3-252-076 and D3-252-075 have been updated to reflect the spring 2025 modifications (sheet 39). These manholes will still require adjustment / modification.
16. The missing contour labels have been added to the staking plans (sheets 70-95) as requested.
17. The quantities for the rock mulch on sheet L-9 (sheet 172) have been revised to match the plan quantities.

2. Question: In looking at this Crosby Avenue Improvements Project. It says "150' of Plastic Fence", but we aren't seeing any detail on that. I was hoping you could provide some info or drawing on type of fence, location etc.

Answer: This is temporary, orange plastic fencing as described in CDOT Standard Specifications for Road and Bridge Construction Section 607. The installation locations will be as directed by the engineer.

The original solicitation for the project noted above is amended as noted. All other conditions of the subject remain the same.

Respectfully,



Dolly Daniels, Senior Buyer
City of Grand Junction, Colorado

Final / Bid Schedule: 25359 - Crosby Avenue Multimodal Improvements

Item No.	CDOT Bid Item Code	Description	Quantity	Units	Unit Price	Total Price
1	201-00000	CLEARING AND GRUBBING	Lump Sum		---	\$ _____
2	202-00002	REMOVAL OF INLET TYPE R (SEE PLAN FOR DIMENSIONS)	1.	EA	\$ _____	\$ _____
3	202-00010	REMOVAL OF TREE	2.	EA	\$ _____	\$ _____
4	202-00019	REMOVAL OF INLET	2.	EA	\$ _____	\$ _____
5	202-00032	REMOVAL OF VALVE / CLEANOUT COVER AND BOX	2.	EA	\$ _____	\$ _____
6	202-00035	REMOVAL OF PIPE	107.	LF	\$ _____	\$ _____
7	202-00201	REMOVAL OF CURB	59.	LF	\$ _____	\$ _____
8	202-00210	REMOVAL OF CONCRETE PAVEMENT	51.	SY	\$ _____	\$ _____
9	202-00202	REMOVAL OF GUTTER	88.	LF	\$ _____	\$ _____
10	202-00203	REMOVAL OF CURB AND GUTTER	1,090.	LF	\$ _____	\$ _____
11	202-00204	REMOVAL OF CURB, GUTTER AND SIDEWALK	1,776.	LF	\$ _____	\$ _____
12	202-00206	REMOVAL OF CONCRETE CURB RAMP	67.	SY	\$ _____	\$ _____
13	202-00240	REMOVAL OF ASPHALT MAT (PLANING) (2 INCH DEPTH) (INCLUDES HAULING MILLINGS TO 2620 LEGACY WAY, GRAND JUNCTION, CO)	487.	SY	\$ _____	\$ _____
14	202-00240	REMOVAL OF ASPHALT MAT (PLANING) (FULL DEPTH) (INCLUDES HAULING MILLINGS TO 2620 LEGACY WAY, GRAND JUNCTION, CO)	10,042.	SY	\$ _____	\$ _____
15	202-04060	DUST ABATEMENT	Lump Sum		---	\$ _____
16	202-00810	REMOVAL OF GROUND SIGN	5.	EA	\$ _____	\$ _____
17	203-00010	UNCLASSIFIED EXCAVATION (COMPLETE IN PLACE)	14,189.	CY	\$ _____	\$ _____
18	203-00060	EMBANKMENT MATERIAL (COMPLETE IN PLACE)	1,005.	CY	\$ _____	\$ _____
19	203-00100	MUCK EXCAVATION	110.	CY	\$ _____	\$ _____
20	203-01597	POTHOLING	20.	HR	\$ _____	\$ _____
21	208-00046	PRE-FABRICATED CONCRETE WASHOUT STRUCTURE (TYPE 1)	1.	EA	\$ _____	\$ _____
22	208-00051	STORM DRAIN INLET PROTECTION (TYPE I)	60.	LF	\$ _____	\$ _____
23	208-00054	STORM DRAIN INLET PROTECTION (TYPE II)	2.	EA	\$ _____	\$ _____
24	208-00075	PRE-FABRICATED VEHICLE TRACKING PAD	2.	EA	\$ _____	\$ _____
25	208-00106	SWEEPING (SEDIMENT REMOVAL) (AS DIRECTED BY ENGINEER)	80.	HR	\$ _____	\$ _____
26	208-00107	REMOVAL OF TRASH (AS DIRECTED BY ENGINEER)	80.	HR	\$ _____	\$ _____
27	208-00207	EROSION CONTROL MANAGEMENT (ECM)	180.	DAY	\$ _____	\$ _____
28	208-00300	TEMPORARY BERM	150.	LF	\$ _____	\$ _____
29	210-00010	RESET MAILBOX STRUCTURE	1.	EA	\$ _____	\$ _____
30	210-00020	ADJUST CLEANOUT / PROVIDE VALVE BOX AND COVER	1.	EA	\$ _____	\$ _____
31	210-00035	RESET WATER METER	1.	EA	\$ _____	\$ _____
32	210-00036	ADJUST BACKFLOW PREVENTER ASSEMBLY / PROVIDE MANHOLE COVER	1.	EA	\$ _____	\$ _____
33	210-00064	RESET MONUMENT	4.	EA	\$ _____	\$ _____
34	210-00420	RESET TIMBERS (INCLUDES REPLACEMENT OF ROTTEN TIMBERS)	Lump Sum		---	\$ _____
35	210-00810	RESET GROUND SIGN	10.	EA	\$ _____	\$ _____
36	210-04010	ADJUST / MODIFY MANHOLE	24.	EA	\$ _____	\$ _____
37	210-04016	REMOVE AND REPLACE MANHOLE D2-252-026 IN-KIND (COMPLETE IN PLACE) (INCLUDES CONNECTION TO PIPES)	1.	EA	\$ _____	\$ _____
38	210-04017	TEMPORARY SANITARY SEWER BYPASS FOR MANHOLE D2-252-026 RELOCATION (COMPLETE IN PLACE)	5.	DAY	\$ _____	\$ _____
39	210-04050	ADJUST VALVE BOX	39.	EA	\$ _____	\$ _____

Final / Bid Schedule: 25359 - Crosby Avenue Multimodal Improvements

Item No.	CDOT Bid Item Code	Description	Quantity	Units	Unit Price	Total Price
40	211-03005	DEWATERING	21.	DAY	\$ _____	\$ _____
41	212-00090	COMPOST	0.4	AC	\$ _____	\$ _____
42	213-00065	ROCK MULCH (D, LA SAL PURPLE)	2.4	CY	\$ _____	\$ _____
43	213-00067	ROCK MULCH (A, 1-1/2" TAN GRANITE)	12,887.	SF	\$ _____	\$ _____
44	213-00068	ROCK MULCH (B, 1" TAN GRANITE)	3,101.	SF	\$ _____	\$ _____
45	213-00069	ROCK MULCH (C, 3/4" WASHED GRAY)	2,855.	SF	\$ _____	\$ _____
46	213-00705	LANDSCAPE BOULDER	66.	EA	\$ _____	\$ _____
47	214-00220	DECIDUOUS TREE (2 INCH CALIPER)	8.	EA	\$ _____	\$ _____
48	214-00350	DECIDUOUS SHRUBS (#5 CONTAINER)	92.	EA	\$ _____	\$ _____
49	214-00650	EVERGREEN SHRUBS (#5 CONTAINER)	26.	EA	\$ _____	\$ _____
50	214-01706	PERENNIALS/ORNAMENTAL GRASSES (#1 CONTAINER)	115.	EA	\$ _____	\$ _____
51	217-00000	HERBICIDE TREATMENT	2,210.	SY	\$ _____	\$ _____
52	240-00000	WILDLIFE BIOLOGIST	20.	HR	\$ _____	\$ _____
53	250-00010	ENVIRONMENTAL HEALTH AND SAFETY MANAGEMENT	Lump Sum		---	\$ _____
54	250-00050	MONITORING TECHNICIAN	20.	HR	\$ _____	\$ _____
55	250-00110	HEALTH AND SAFETY OFFICER	20.	HR	\$ _____	\$ _____
56	250-00224	HAZARDOUS WASTE DISPOSAL (RADIOACTIVE)	40.	CY	\$ _____	\$ _____
57	304-02000	AGGREGATE BASE COURSE (CLASS 2)	6,531.	TON	\$ _____	\$ _____
58	304-03000	AGGREGATE BASE COURSE (CLASS 3) (SUBGRADE STABILIZATION)	3,322.	TON	\$ _____	\$ _____
59	304-06000	AGGREGATE BASE COURSE (CLASS 6)	7,052.	TON	\$ _____	\$ _____
60	306-01000	RECONDITIONING (6")	17,630.	SY	\$ _____	\$ _____
61	403-34741	HOT MIX ASPHALT (GRADING SX) (75) (PG 64-22)	3,101.	TON	\$ _____	\$ _____
62	412-00900	CONCRETE PAVEMENT (CLASS P) (9 INCH)	287.	SY	\$ _____	\$ _____
63	420-00132	GEOTEXTILE (SEPARATOR) (CLASS 1) (WOVEN) (SUBGRADE STABILIZATION)	5,575.	SY	\$ _____	\$ _____
64	506-00207	RIP RAP (6 INCH)	4.	TON	\$ _____	\$ _____
65	603-01245	24 INCH REINFORCED CONCRETE PIPE (COMPLETE IN PLACE)	200.	LF	\$ _____	\$ _____
66	603-50026	24 INCH PLASTIC PIPE (COMPLETE IN PLACE)	20.	LF	\$ _____	\$ _____
67	604-19411	MODIFY INLET TYPE R (D3-252-084) (SPECIAL)	1.	EA	\$ _____	\$ _____
68	604-19415	INLET TYPE R (15 FOOT) (SPECIAL) (COMPLETE IN PLACE) (INCLUDES IRRIGATION DIVERSION PER 107.15)	1.	EA	\$ _____	\$ _____
69	607-11525	FENCE (PLASTIC)	150.	LF	\$ _____	\$ _____
70	608-00006	CONCRETE SIDEWALK (6" THICK)	1,677.	SY	\$ _____	\$ _____
71	608-00010	CONCRETE CURB RAMP	230.	SY	\$ _____	\$ _____
72	608-10000	SIDEWALK CHANNEL (SPECIAL)	10.	LF	\$ _____	\$ _____
73	609-20010	CURB TYPE 2 (SECTION B)	38.	LF	\$ _____	\$ _____
74	609-21013	CURB AND GUTTER TYPE 2 (SECTION IM) (SPECIAL)	40.	LF	\$ _____	\$ _____
75	609-21110	CURB AND GUTTER TYPE 2 (SECTION IB) (SPECIAL)	4,599.	LF	\$ _____	\$ _____
76	609-22030	MONOLITHIC CURB, GUTTER AND SIDEWALK TYPE 2 (SECTION IB) (WIDTH = 7 FEET)	94.	LF	\$ _____	\$ _____
77	609-22031	MONOLITHIC CURB, GUTTER AND SIDEWALK TYPE 2 (SECTION IB) (WIDTH = 9.5 FEET)	258.	LF	\$ _____	\$ _____
78	609-22032	MONOLITHIC CURB, GUTTER AND SIDEWALK TYPE 2 (SECTION IB) (WIDTH = 10 FEET)	748.	LF	\$ _____	\$ _____

Final / Bid Schedule: 25359 - Crosby Avenue Multimodal Improvements

Item No.	CDOT Bid Item Code	Description	Quantity	Units	Unit Price	Total Price
79	609-22033	MONOLITHIC CURB, GUTTER AND SIDEWALK TYPE 2 (SECTION IB) (WIDTH = 11.5 FEET)	284.	LF	\$ _____	\$ _____
80	609-22034	MONOLITHIC CURB, GUTTER AND SIDEWALK TYPE 2 (SECTION IB) (WIDTH =13.5 FEET)	64.	LF	\$ _____	\$ _____
81	609-24006	GUTTER TYPE 2 (SPECIAL)	104.	LF	\$ _____	\$ _____
82	613-01200	2 INCH ELECTRICAL CONDUIT (PLASTIC) (FOR ELECTRICAL) (INCLUDES SWEEPS AND FITTINGS)	3,707.	LF	\$ _____	\$ _____
83	613-07002	TYPE 2 PULL BOX (ELECTRICAL)	40.	EA	\$ _____	\$ _____
84	613-10000	WIRING	Lump Sum		---	\$ _____
85	613-30001	LIGHT STANDARD AND LUMINAIRE SINGLE (PEDESTRIAN) (INSTALL ONLY)	35.	EA	\$ _____	\$ _____
86	613-30002	LIGHT STANDARD AND LUMINAIRE SINGLE (WALL PACK, PEDESTRIAN) (INSTALL ONLY)	2.	EA	\$ _____	\$ _____
87	613-40012	LIGHT STANDARD FOUNDATION (PEDESTRIAN) (SPECIAL)	35.	EA	\$ _____	\$ _____
88	613-50106	LIGHTING CONTROL CENTER (SPECIAL)	2.	EA	\$ _____	\$ _____
89	614-00011	SIGN PANEL (CLASS I)	39.	SF	\$ _____	\$ _____
90	614-00201	STEEL SIGNPOST (3# / FOOT U-CHANNEL) (SPECIAL)	60.	LF	\$ _____	\$ _____
91	620-00020	SANITARY FACILITY	1.	EA	\$ _____	\$ _____
92	623-00090	PIPE TRANSITION POINT ABOVE GRADE (PVC TO DRIP)	12.	EA	\$ _____	\$ _____
93	623-00162	DRIP EMITTER TUBING (3/4")	1,580.	LF	\$ _____	\$ _____
94	623-00164	DRIP EMITTER (A)	457.	EA	\$ _____	\$ _____
95	623-00167	DRIP EMITTER (B)	74.	EA	\$ _____	\$ _____
96	623-00169	DRIP EMITTER (C) (TREE RING)	8.	EA	\$ _____	\$ _____
97	623-00186	3/4 INCH FLUSH UNIT	16.	EA	\$ _____	\$ _____
98	623-00600	1-1/2" PLASTIC PIPE (MAINLINE)	1,300.	LF	\$ _____	\$ _____
99	623-00601	1" PLASTIC PIPE (LATERALS)	1,540.	LF	\$ _____	\$ _____
100	623-00604	4" PLASTIC PIPE (IRRIGATION/SLEEVE)	160.	LF	\$ _____	\$ _____
101	623-01706	1-1/2 INCH BACKFLOW PREVENTER	1.	EA	\$ _____	\$ _____
102	623-02006	3/4 INCH DRAIN VALVE	1.	EA	\$ _____	\$ _____
103	623-03106	1 INCH AUTOMATIC CONTROL VALVE	3.	EA	\$ _____	\$ _____
104	623-04000	2 WIRE CONTROL WIRE	640.	LF	\$ _____	\$ _____
105	623-04001	DECODER	4.	EA	\$ _____	\$ _____
106	623-04002	POWER SOURCE WIRE	20.	LF	\$ _____	\$ _____
107	623-04003	SURGE PROTECTION DEVICE (2 WIRE PATH)	4.	EA	\$ _____	\$ _____
108	623-04006	3/4" QUICK COUPLER	5.	EA	\$ _____	\$ _____
109	623-05012	1-1/2 INCH GATE VALVE (ISOLATION VALVE)	2.	EA	\$ _____	\$ _____
110	623-07600	FLOW SENSOR - (NETAFIM HYDROMETER)	1.	EA	\$ _____	\$ _____
111	623-08160	60 STATION AUTOMATIC CONTROLLER	1.	EA	\$ _____	\$ _____
112	623-08210	AUTOMATIC CONTROLLER TRANSMITTER/RECEIVER UNIT	1.	EA	\$ _____	\$ _____
113	624-00001	CONNECTING BAND (COMPLETE IN PLACE)	3.	EA	\$ _____	\$ _____
114	624-29019	18 INCH DRAINAGE PIPE (CLASS 9) (COMPLETE IN PLACE)	20.	LF	\$ _____	\$ _____
115	624-29055	54 INCH DRAINAGE PIPE (CLASS 9) (COMPLETE IN PLACE)	120.	LF	\$ _____	\$ _____
116	624-90000	PIPE ENCASEMENT (SPECIAL)	100.	LF	\$ _____	\$ _____
117	625-00000	CONSTRUCTION SURVEYING	Lump Sum		---	\$ _____

Final / Bid Schedule: 25359 - Crosby Avenue Multimodal Improvements

Item No.	CDOT Bid Item Code	Description	Quantity	Units	Unit Price	Total Price
118	626-00000	MOBILIZATION	Lump Sum		- - -	\$ _____
119	627-00002	THERMOPLASTIC PAVEMENT MARKING (GREEN PAVEMENT MARKING) (INCLUDES WHITE LINE EDGES)	298.	SF	\$ _____	\$ _____
120	627-00013	PAVEMENT MARKING PAINT (HIGH BUILD) (TWO COATS)	137.	GAL	\$ _____	\$ _____
121	627-30407	THERMOPLASTIC PAVEMENT MARKING (WORD-SYMBOL) (SPECIAL)	104.	SF	\$ _____	\$ _____
122	627-30411	PREFORMED THERMOPLASTIC PAVEMENT MARKING (XWALK- STOP LINE) (SPECIAL)	162.	SF	\$ _____	\$ _____
123	630-00000	FLAGGING	40.	HR	\$ _____	\$ _____
124	630-00007	TRAFFIC CONTROL INSPECTION	50.	DAY	\$ _____	\$ _____
125	630-00012	TRAFFIC CONTROL MANAGEMENT	130.	DAY	\$ _____	\$ _____
126	630-00016	TRAFFIC CONTROL PLAN (SPECIAL)	Lump Sum		- - -	\$ _____
127	630-80336	BARRICADE (TYPE 3 M-B) (TEMPORARY)	11.	EA	\$ _____	\$ _____
128	630-80341	CONSTRUCTION TRAFFIC SIGN (PANEL SIZE A)	14.	EA	\$ _____	\$ _____
129	630-80355	PORTABLE MESSAGE SIGN PANEL	2.	EA	\$ _____	\$ _____
130	630-80360	DRUM CHANNELIZING DEVICE	12.	EA	\$ _____	\$ _____
131	630-80364	DRUM CHANNELIZING DEVICE (WITH LIGHT) (STEADY)	17.	EA	\$ _____	\$ _____
132	700-70010	F/A MINOR CONTRACT REVISIONS	1.	F A	\$ _____	\$ _____
133	700-70012	F/A ASPHALT PAVEMENT INCENTIVE	1.	F A	\$ _____	\$ _____
134	202-00009	TREE TRIMMING (464 BASE ROCK ST)	Lump Sum		- - -	\$ _____

Bid Amount: \$ _____

Bid Amount:

dollars