

Bid Schedule: Neighborhood Repairs

Item No.	CDOT, City Ref.	Description	Units	Haven Hill Court	Country Lane Court	Caprock Court	Kami Circle
1	108.2	Connect to Existing 24" RCP Pipe per Plans	EA		1.		
2	108.2	Storm Drain Pipe - 12" C-900 PVC Pipe	LF		6.		
3	108.6	Single Storm Drain Inlet (vertical Curb) (see City Of Grand Junction Standard Detail D-07).	EA		1.		
4	202	Remove Asphalt Mat. Full Depth.	SY	925.	5.	100.	75.
5	202	Remove Concrete Curb, Gutter, and Walk	LF	120.	20.	55.	45.
6	202	Remove Concrete Mail Box Pad	SY		1.		
7	208	Storm Drain Inlet Protection (CDOT Type II)	EA		1.		
8	210	Adjust MH to FG	EA	1.			
9	210	Reset Landscaping	LS				
10	203	Unclassified Excavation	CY	269.			
11	203	Unclassified Embankment	CY	17.			
12	203	Haul	CY	252.			
13	203	(Rdwy Subgrade Stabilization) Muck Excavation (If Needed, As Directed)	CY				
14	304	(Rdwy Subgrade Stabilization) Aggregate Base Course (Class 3) (24" Thick) (If Needed, As Directed)	SY				
15	420	Geotextile Separator (CI 2)	SY	925.			
16	420	(Rdwy Subgrade Stabilization) Geogrid Reinforcement (If Needed, As Directed)	SY				
17	208	Aggregate Bag at Curb and Gutter	EA	1.	1.	1.	1.
18	208	Vehicle Tracking Pad	EA				
19	208	Prefabricated Concrete Washout Structure	EA				
20	209	Dust Abatement	DAYS	14.	14.	7.	7.
21	304	Aggregate Base Course (Class 6) (8" Thick)	SY	925.	5.	100.	75.
22	329	Sod.	SF	80.		75.	60.
23	401	Hot Mix Asphalt (4" thick) (Grading SX 75, Binder Grade 64-22)	TON	205.	1.	25.	19.
24	608	Concrete Drive Over Curb, Gutter, and Sidewalk (6.5' Wide) to include 6" Class 6 Aggregate Base Course	LF	120.		55.	45.
25	608	Concrete Curb and Gutter (2' Wide) to include Class 6 Aggregate Base Course per Typical Cross Section	LF		20.		
26	608	Concrete Mail Box Pad (6" Thick) to include 6" of Class 6 Aggregate Base Course.	SY		1.		
27	620	Sanitary Facility	EA				

Bid Schedule: Neighborhood Repairs

Item No.	CDOT, City Ref.	Description	Units	Haven Hill Court	Country Lane Court	Caprock Court	Kami Circle
28	625	Construction Surveying	SUM				
29	626	Mobilization	SUM				
30	630	Traffic Control (Complete In Place)	SUM				
31	630	Traffic Control Plan	EA	1.	1.	1.	1.
MCR		Minor Contract Revisions	- - -				