



Purchasing Division

ADDENDUM NO. 5

DATE: February 20, 2018
FROM: City of Grand Junction Purchasing Division
TO: All Offerors
RE: Las Colonias Business Park Phase I and Phase IA IFB-4476-18-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

1. **The Responses Due date and time shall be extended to February 22, 2018 prior to 4:00pm.**
2. Line Item 96 has been removed from the Bid Schedule. The revised Addendum 5 Bid Schedule is attached. Contractor shall utilize the Addendum 5 Bid Schedule when submitting their bid response.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", written over a horizontal line.

Duane Hoff Jr., Senior Buyer
City of Grand Junction, Colorado

Bid Schedule: Las Colonias Business Park Phase I and IA

Contractor: _____

Addendum No. 5

| Item No. | CDOT, City Ref. | Description | Quantity | Units | Unit Price | Total Price |
|----------|-----------------|---|----------|-------|------------|-------------|
| 1 | 104.4 | Cap top half of sewer in concrete per City Standard Detail GU-04 | 3. | EA | \$ _____ | \$ _____ |
| 2 | 108.2 | 6" Irrigation Conduit (Schedule 80 PVC) | 445. | LF | \$ _____ | \$ _____ |
| 3 | 108.2 | 6" Water Pipe (C-900 PVC) | 359. | LF | \$ _____ | \$ _____ |
| 4 | 108.2 | 8" Water Pipe (C-900 PVC) | 105. | LF | \$ _____ | \$ _____ |
| 5 | 108.2 | 12" Water Pipe (C-900 PVC) | 3,100. | LF | \$ _____ | \$ _____ |
| 6 | 108.2 | 4" Sewer Service Pipe (SDR 35) | 65. | LF | \$ _____ | \$ _____ |
| 7 | 108.2 | 6" Sewer Service Pipe (SDR 35) | 246. | LF | \$ _____ | \$ _____ |
| 8 | 108.2 | 8" Gravity Sewer Pipe (SDR 35) | 2,132. | LF | \$ _____ | \$ _____ |
| 9 | 108.2 | 12" Storm Drain Pipe (RCP) | 325. | LF | \$ _____ | \$ _____ |
| 10 | 108.2 | 15" Storm Drain Pipe (RCP) | 420. | LF | \$ _____ | \$ _____ |
| 11 | 108.2 | 18" Storm Drain Pipe (RCP) | 775. | LF | \$ _____ | \$ _____ |
| 12 | 108.2 | 24" Storm Drain Pipe (RCP) | 587. | LF | \$ _____ | \$ _____ |
| 13 | 108.2 | 3' x 7' Reinforced Concrete Box Culvert - Cost to include connection to existing. See SP - 2. | 465. | LF | \$ _____ | \$ _____ |
| 14 | 108.2 | 24" Heavy Duty Flap Gate-HYDRO Gate or approved equal. | 1. | EA | \$ _____ | \$ _____ |
| 15 | 108.2 | Import Trench Backfill | 355. | CY | \$ _____ | \$ _____ |
| 16 | 108.3 | 6" Gate Valve | 14. | EA | \$ _____ | \$ _____ |
| 17 | 108.3 | 8" Gate Valve | 2. | EA | \$ _____ | \$ _____ |
| 18 | 108.3 | 12" Gate Valve | 6. | EA | \$ _____ | \$ _____ |
| 19 | 108.3 | 6" x 6" Tee | 1. | EA | \$ _____ | \$ _____ |
| 20 | 108.3 | 12" x 6" Tee | 14. | EA | \$ _____ | \$ _____ |
| 21 | 108.3 | 12" x 8" Tee | 2. | EA | \$ _____ | \$ _____ |
| 22 | 108.3 | 12" x 12" Cross | 1. | EA | \$ _____ | \$ _____ |
| 23 | 108.3 | 8", 11.25° Elbow | 1. | EA | \$ _____ | \$ _____ |
| 24 | 108.3 | 12", 11.25° Elbow | 2. | EA | \$ _____ | \$ _____ |
| 25 | 108.3 | 12", 22.5° Elbow | 4. | EA | \$ _____ | \$ _____ |
| 26 | 108.3 | 12", 45° Elbow | 2. | EA | \$ _____ | \$ _____ |
| 27 | 108.3 | 6" End Cap/Plug | 4. | EA | \$ _____ | \$ _____ |
| 28 | 108.3 | 8" End Cap/Plug | 2. | EA | \$ _____ | \$ _____ |
| 29 | 108.3 | 12" End Cap/Plug | 2. | EA | \$ _____ | \$ _____ |

| | | | | | | |
|----|-------|--|---------|------|----------|--------------|
| 30 | 108.3 | Fire Hydrant | 10. | EA | \$ _____ | \$ _____ |
| 31 | 108.3 | 12" x 8" Reducer | 1. | EA | \$ _____ | \$ _____ |
| 32 | 108.3 | 8" x 4" Sewer Service Tap | 2. | EA | \$ _____ | \$ _____ |
| 33 | 108.3 | Sanitary Sewer Cleanout (2-way) to include appurtenances per City Standard Detail SS - 07. | 6. | EA | \$ _____ | \$ _____ |
| 34 | 108.4 | 2" Water Service Line (HDPE) | 300. | LF | \$ _____ | \$ _____ |
| 35 | 108.4 | 2" Water Service Assembly | 6. | EA | \$ _____ | \$ _____ |
| 36 | 108.5 | Sanitary Sewer Basic Manhole (48" I.D.) | 8. | EA | \$ _____ | \$ _____ |
| 37 | 108.5 | Manhole Barrel Section (D>5')(48" I.D.) | 29. | VLF | \$ _____ | \$ _____ |
| 38 | 108.5 | Storm Sewer Basic Manhole (48" I.D.) | 5. | EA | \$ _____ | \$ _____ |
| 39 | 108.5 | Irrigation Basic Manhole (30" I.D.) | 1. | EA | \$ _____ | \$ _____ |
| 40 | 108.5 | Storm Sewer Basic Manhole (60" I.D.) | 2. | EA | \$ _____ | \$ _____ |
| 41 | 108.5 | Connect to Existing Manhole (8" Pipe) | 2. | EA | \$ _____ | \$ _____ |
| 42 | 108.6 | Outlet Structure - See "Water Quality Outlet Structure Pond 1" To include all appurtenances (complete in place). | 1. | EA | \$ _____ | \$ _____ |
| 43 | 108.6 | Single Storm Drain Inlet (Vertical Curb) | 3. | EA | \$ _____ | \$ _____ |
| 44 | 108.6 | Large Area Inlet | 8. | EA | \$ _____ | \$ _____ |
| 45 | 108.7 | Granular Stabilization Material (Type B) | 390. | TON | \$ _____ | \$ _____ |
| 46 | 203 | Excavation and Embankment - See SP - 4. | 24,618. | CY | \$ _____ | \$ _____ |
| 47 | 207 | Topsoil (6" Thick) | 7,780. | SY | \$ _____ | \$ _____ |
| 48 | 207 | Import Fill Material - Clean fill 12" Thick at water quality pond. See Phase IA, Sheet 43 for information. | 1,468. | SY | \$ _____ | \$ _____ |
| 49 | 208 | Erosion Control (Complete in Place) | Lump | SUM | | --- \$ _____ |
| 50 | 208 | Stabilized Construction Entrance | 2. | EA | \$ _____ | \$ _____ |
| 51 | 209 | Dust Abatement | 70. | DAYS | \$ _____ | \$ _____ |
| 52 | 304 | Aggregate - River Cobble 1" -3" (6" Thick) to include approved fill below. | 460. | SY | \$ _____ | \$ _____ |
| 53 | 304 | Subgrade Stabilization - Aggregate Base Course (Class 3) (12" Thick) | 2,125. | SY | \$ _____ | \$ _____ |

| | | | | | | |
|----|-----|--|---------|---------|----------|----------|
| 54 | 304 | Aggregate Base Course (Class 6) (13" Thick) | 8,500. | SY | \$ _____ | \$ _____ |
| 55 | 306 | Reconditioning (12" Deep) | 8,500. | SY | \$ _____ | \$ _____ |
| 56 | 401 | Hot Mix Asphalt (5" thick) (Grading SX 75, Binder Grade 64-22) | 2,362. | TON | \$ _____ | \$ _____ |
| 57 | 420 | Geosynthetics - Mirafi RS580i or approved equal | 2,125. | SY | \$ _____ | \$ _____ |
| 58 | 420 | Geotextile Fabric (Non-Woven) Underlayment at Pond Liner. | 11,000. | SQ. FT. | \$ _____ | \$ _____ |
| 59 | 503 | 20" Steel Casing - See Plan Sheet 16 (Phase I) for details. | 40. | LF | \$ _____ | \$ _____ |
| 60 | 504 | Concrete Wall (Class D) per M and S Standard M-601-20 (Wall Design Height 6'). Work shall include approximately 4,590 lbs. Reinforcing Steel (Epoxy Coated), Structural Concrete Coating (Exterior of wall), 200 cy Structural Backfill (Class 1) and any necessary appurtenances to complete work. Refer to Plan Sheet 20 for detail. | 106. | CY | \$ _____ | \$ _____ |
| 61 | 506 | Riprap (d50=12" to include geogrid) | 40. | SY | \$ _____ | \$ _____ |
| 62 | 608 | Concrete Curb (6" Wide, 14" High) to include 6" of Class 6 Aggregate Base Course. | 3,770. | LF | \$ _____ | \$ _____ |
| 63 | 608 | Concrete Curb and Gutter (2' Wide) to include 6" of Class 6 Aggregate Base Course. | 1,630. | LF | \$ _____ | \$ _____ |
| 64 | 608 | Concrete Curb and Spill Gutter (1.5' Wide) to include 6" of Class 6 Aggregate Base Course. | 355. | LF | \$ _____ | \$ _____ |
| 65 | 608 | Concrete Sidewalk (6" Thick) to include 6" of Class 6 Aggregate Base Course. | 3,200. | SY | \$ _____ | \$ _____ |
| 66 | 608 | Concrete Pavement (Parking) (8" Thick) to include 6" of Class 6 Aggregate Base Course. | 6,450. | SY | \$ _____ | \$ _____ |
| 67 | 608 | Concrete Pavement (Crosswalk) (8" Thick) to include 6" of Class 6 Aggregate Base Course. | 94. | SY | \$ _____ | \$ _____ |
| 68 | 608 | Concrete Drainage Pan (6' Wide) to include 6" of Class 6 Aggregate Base Course. | 130. | LF | \$ _____ | \$ _____ |

| | | | | | | |
|----|-----|--|---------|-----|----------|----------|
| 69 | 608 | Concrete Corner Fillet to include 6" of Class 6 Aggregate Base Course. | 195. | SY | \$ _____ | \$ _____ |
| 70 | 608 | Concrete Curb Ramp to include 6" of Class 6 Aggregate Base Course. | 275. | SY | \$ _____ | \$ _____ |
| 71 | 608 | Detectable Warning (Cast Iron, Wet Set)(2'x2' - 3 per Ramp) | 60. | EA | \$ _____ | \$ _____ |
| 72 | 613 | Joint Trench (Street Side) 2" Schedule 80 PVC. Refer to Utility Detail and SP - 8(Addendum No. 3) for details. | 11,510. | LF | \$ _____ | \$ _____ |
| 73 | 613 | Joint Trench (Street Side) 6" Schedule 80 PVC. Refer to Utility Detail and SP -8 (Addendum No. 3) for details. | 2,600. | LF | \$ _____ | \$ _____ |
| 74 | 613 | Joint Trench (Property Side) 6" C-900 Refer to Utility Detail and SP -8 (Addendum No. 3) for details. | 4,450. | LF | \$ _____ | \$ _____ |
| 75 | 613 | Joint Trench (Property Side) 4" Schedule 80 PVC. Refer to Utility Detail and SP -8 (Addendum No. 3) for details. | 2,555. | LF | \$ _____ | \$ _____ |
| 76 | 613 | Joint Trench (Property Side) 2" Schedule 80 PVC. Refer to Utility Detail and SP -8 (Addendum No. 3) for details. | 2,555. | LF | \$ _____ | \$ _____ |
| 77 | 613 | Large Splice Box (Quasite) (3' - 2 5/8" x 2'-2") See Plan Sheet 5 for details. | 11. | LF | \$ _____ | \$ _____ |
| 78 | 613 | Splice Box (Provided by Others-Century Link) | 8. | EA | \$ _____ | \$ _____ |
| 79 | 620 | Sanitary Facility | 1. | EA | \$ _____ | \$ _____ |
| 80 | 625 | Construction Surveying | Lump | SUM | --- | \$ _____ |
| 81 | 626 | Mobilization | Lump | SUM | --- | \$ _____ |
| 82 | 627 | Preformed Thermoplastic Pavement Marking (Left Turn) | Lump | SUM | --- | \$ _____ |
| 83 | 627 | Preformed Thermoplastic Pavement Marking (X-walk)(2' x 10' TYP.) | 320. | EA | \$ _____ | \$ _____ |
| 84 | 627 | Preformed Plastic Pavement Marking (8" White Solid) | 60. | LF | \$ _____ | \$ _____ |
| 85 | 627 | Preformed Thermoplastic Pavement Marking (4" White Solid) | 5,797. | LF | \$ _____ | \$ _____ |
| 86 | 627 | Preformed Plastic Pavement Marking (24" White Solid) | 26. | LF | \$ _____ | \$ _____ |

| | | | | | | |
|-----|------------|--|---------|---------|----------|----------------------|
| 87 | 630 | Traffic Control (Complete In Place) | 1. | LF | \$ _____ | \$ _____ |
| 88 | 630 | Traffic Control Plan | Lump | SUM | --- | \$ _____ |
| 89 | 712 | Geomembrane (40 Mil) - See SP - 9. | 11,000. | SQ. FT. | \$ _____ | \$ _____ |
| 90 | | DELETE | | | | |
| 91 | Electrical | Luminaire LED (Pedestrian) to include foundation. | 39. | EA | \$ _____ | \$ _____ |
| 92 | Electrical | Luminaire LED (Street) to include foundation. | 7. | EA | \$ _____ | \$ _____ |
| 93 | Electrical | Electrical Pull Box (Type I)(11" x 18" x 12") | 55. | EA | \$ _____ | \$ _____ |
| 94 | Electrical | 2 Plex Receptacle (Complete in Place) to include appurtenances. | 5. | EA | \$ _____ | \$ _____ |
| 95 | Electrical | Wiring (Complete in Place) to include disconnect at pump location. | Lump | SUM | --- | \$ _____ |
| 96 | | DELETE | | | | |
| MCR | | Minor Contract Revisions | --- | --- | --- | \$ <u>130,000.00</u> |

Bid Amount: \$ _____

Bid Amount: _____ **dollars**