



Purchasing Division

ADDENDUM NO. 1

DATE: August 23, 2018
FROM: City of Grand Junction Purchasing Division
TO: All Offerors
RE: 2018 Tiara Rado Cart Path – Asphalt Pavement Rehabilitation IFB-4557-18-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

1. Q. Can the area be closed around the clubhouse and cart barn for construction work?

A. It may be possible to close the back half of the course (area around the cart barn entrance) to assist in the construction phasing. The clubhouse and pro-shop will remain open however.

2. Q. Can we remove the bollards near the pro shop entrance accessed from the cart parking area and replace them?

A. Yes, bollards shall be removed by the contractor. The void shall be replaced with flow-fill, or other approved material, and paved over. The bollards will be replaced by others. Please see the updated bid schedule.

3. Shoulder gravel quantities have been updated in the revised Price Bid Schedule. See attached.

4. Contractor shall utilize the attached revised Price Bid Schedule when submitting their bid response. See attached.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", written over a white background.

Duane Hoff Jr., Senior Buyer
City of Grand Junction, Colorado

Bid Schedule: Addendum #1 - 2018 Tiara Rado Cart Path - Pavement Rehabilitation

Contractor: _____

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	202	Asphalt Removal (Planing)(Thickness Varies - Maximum 3")	470.	SY	\$ _____	\$ _____
2	202	Bollard Removal	3.	EA	\$ _____	\$ _____
3	304	Aggregate Base Course (Class 6) - Shoulder Edging Gravel	139.	Tons	\$ _____	\$ _____
4	401	Hot Mix Asphalt (3" thick Patch - includes 12" subgrade prep) (Grading SX, Binder Grade 58-28)	45.	Tons	\$ _____	\$ _____
5	401	Hot Mix Asphalt (2" thick) (Grading SX, Binder Grade 58-28)	85.	Tons	\$ _____	\$ _____
6	620	Sanitary Facility	Lump Sum		---	\$ _____
7	626	Mobilization	Lump Sum		---	\$ _____
8	630	Traffic Control (Complete In Place)	Lump Sum		---	\$ _____
9	630	Flagging	210.	HR	\$ _____	\$ _____
MCR		Minor Contract Revisions	---	---	---	\$ <u>5,000.00</u>

Bid Amount: \$ _____

Bid Amount: _____ dollars

BA1	BID ALT 1	Hot Mix Asphalt (3" thick Patch - includes 12" subgrade prep) (Grading SX, Binder Grade 58-28)	120.	Tons	\$ _____	\$ _____
-----	-----------	--	------	------	----------	----------

Alternate Bid Amount #1: \$ _____

Alternate Bid Amount #1 (Includes BA1): _____ dollars

BA2	BID ALT 2	Hot Mix Asphalt (3" thick Patch - includes 12" subgrade prep) (Grading SX, Binder Grade 58-28)	25.	Tons	\$ _____	\$ _____
-----	-----------	--	-----	------	----------	----------

Alternate Bid Amount #2: \$ _____

Alternate Bid Amount #2 (Includes BA2): _____ dollars