



Purchasing Division

## **ADDENDUM NO. 1**

**DATE:** August 29, 2018  
**FROM:** City of Grand Junction Purchasing Division  
**TO:** All Offerors  
**RE:** 7<sup>th</sup> to 8<sup>th</sup> Street, Main Street to Colorado Avenue Alley Reconstruction  
IFB-4560-18-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

1. See attached Pre-Bid Meeting Agenda.
2. Contractor shall utilize the attached revised Addendum 1 Price Bid Schedule when submitting their bid response.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", written in a cursive style.

Duane Hoff Jr., Senior Buyer  
City of Grand Junction, Colorado

# Bid Schedule: Alley Reconstruction 7th to 8th St, Main St. to Colorado Addendum No. 1

**Contractor:** \_\_\_\_\_

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	202	Asphalt Removal to Include Saw Cut	63.	SY	\$ _____	\$ _____
2	202	Concrete Removal to Include Saw Cut	412.	SY	\$ _____	\$ _____
3	203	Disposal of Radioactive Materials (Uranium Mill Tailings)	30.	CY	\$ _____	\$ _____
4	208	Erosion Control (Complete in Place)		Lump SUM	---	\$ _____
5	210	Reset Manhole Ring & Cover to Finish Grade	4.	EA	\$ _____	\$ _____
6	210	Reset Cleanout Ring & Cover to Finish Grade	7.	EA	\$ _____	\$ _____
7	210	Reset Monitoring Well Ring & Cover to Finish Grade	1.	EA	\$ _____	\$ _____
8	210	Reset Pull Box to Finish Grade	1.	EA	\$ _____	\$ _____
9	304	Aggregate Base Course (Class 6) (6" Thick)	50.	SY	\$ _____	\$ _____
10	304	Aggregate Base Course (Class 3) (12" Thick)	120.	SY	\$ _____	\$ _____
11	306	Reconditioning (12" Deep)	400.	SY	\$ _____	\$ _____
12	401	Hot Mix Asphalt (Patching)(4" thick) (Grading SX, Binder Grade 64-22)	63.	SY	\$ _____	\$ _____
13	401	Hot Mix Asphalt (Skin Patch)(Thickness Varies) (Grading SX, Binder Grade 64-22)	3.	Ton	\$ _____	\$ _____
14	420	Geosynthetics - Geogrid	120.	SY	\$ _____	\$ _____
15	608	Concrete Sidewalk (4" Thick)	21.	SY	\$ _____	\$ _____
16	608	Concrete Sidewalk (8" Thick)	28.	SY	\$ _____	\$ _____
17	608	Concrete Driveway Section (8" Thick)	39.	SY	\$ _____	\$ _____
18	608	Concrete Pavement (8" Thick) (Class P)	392.	SY	\$ _____	\$ _____
19	620	Sanitary Facility		Lump SUM	---	\$ _____
20	626	Mobilization		SUM		
21	630	Traffic Control (Complete In Place)		Lump SUM	---	\$ _____
22	630	Traffic Control Plan		Lump SUM	---	\$ _____
23	710	Set Fence Post (City Supplied) (4' Deep)	2.	EA	\$ _____	\$ _____
24	SP	4" Conduit (36" Depth)	70.	LF	\$ _____	\$ _____
MCR		Minor Contract Revisions	---	---	---	\$ 5,000.00

**Bid Amount:** \$ \_\_\_\_\_

**Bid Amount:** \_\_\_\_\_ dollars