



Purchasing Division

## ADDENDUM NO. 1

**DATE:** November 1, 2018  
**FROM:** City of Grand Junction Purchasing Division  
**TO:** All Bidders  
**RE:** 2018 Safe Route to Schools IFB-4577-18-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following:

1. Pre-Bid Attendance List (Sign-In Sheet) is attached as Exhibit A (one page).
2. Pre-Bid Meeting Agenda including minutes of questions and project comments is attached as Exhibit A (six pages).
3. Staging area for pipe, material and supplies is located at 333 West Avenue.
4. NOTE: Jerod Timothy will be transferred off this project. Section 3.3.3 in the original IFB document has been amended to read:  
**Project Manager:** The Project Manager for the Project is Eric Mocko, who can be reached at (970)256-4017. During Construction, all notices, letters, submittals, and other communications directed to the City shall be addressed and mailed or delivered to:  
City of Grand Junction  
Department of Public Works and Planning  
Attn: Eric Mocko, Project Manager  
250 North Fifth Street  
Grand Junction, CO 81501
5. HMA Availability:
  - Concrete (6" Thick) shall be substituted at back of walk at driveways.
  - Sparn Street – Asphalt millings (12" Thick) shall be substituted for HMA. The Contractor shall load and haul millings from City's stockpile.
6. A Revised Bid Schedule has been attached. City will be providing construction staking.

The original solicitation for the project referenced above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", written over a white background.

Duane Hoff Jr., Senior Buyer  
City of Grand Junction, Colorado

Solicitation Name:	2018 Safe Route To Schools
Solicitation #:	IFB-4577-18-DH
Date:	10/30/2018
Time:	10:00 A.M.

**SIGN-IN SHEET**



	Company Name	Representative Name	Phone	Email
1	WHITEWATER BLDG MAT	SCOTT BAUMBARDWAR	234-1843	scott@whitewater.construction
2	HUDDLESTON-BERRY ENG.	JASON COLLARD	623-2690	JCOLLARD@HUDDLESTONBERRY.COM
3	HUDDLESTON BERRY	CLARK ROSENCRANS	907.602.8457	
4	All concrete solutions <sup>LLC</sup>	Pablo Reyes	470-201-6870	ACS 846 @ gmail.com
5	MA Concrete	Andy Azcarraga	243-3221	andy.maconcrete@gmail.com
6	Agave Construction	Gabriel Gutierrez	245-1407	gabriel@agave-construction.com
7				
8				
9				
10				
11				
12				
13				
14				

## Bid Schedule Safe Route to School

### Addendum No. 1

Item No.	CDOT City Ref.	Description	Unit	Quantity	Unit Cost	Extended Cost
<b>BID SCHEDULE</b>						
1	108.2	18" Irrigation Pipe (ADS HP Storm Pipe) W/ Native Backfill. Includes type A Bedding, Haunching, initial backfill, and clay cutoff walls. (City Supplied Pipe)	L.F.	309	\$	\$
2	108.2	18" Irrigation Pipe (ADS HP Storm Pipe) W/ Flowfill. Includes type A Bedding, Haunching (City Supplied Pipe)	L.F.	263	\$	\$
3	108.2	Install 30" PVC (Nyloplast) Heavy Duty Drain Basin (City Supplied Drain Basin)	EA.	5	\$	\$
4	108.5	Concrete Irrigation Structure (see detail on sheet 4) (City Supplied Structure)	EA.	1	\$	\$
5	108.5	Concrete Irrigation Structure With Headgate (see detail on sheet 4)(City Supplied Structure)	EA.	2	\$	\$
6	108.5	Connect to existing pipes	EA.	2	\$	\$
7	201	Clearing and Grubbing	L.S.	1	\$	\$
8	202	Removal of Existing Irrigation System. Shall include the Removal of all Pipe, Concrete Ditch, and Appurtenances. Fill void with approved	L.F.	572	\$	\$
9	202	Removal of Asphalt Mat	S.Y.	162	\$	\$
10	202	Removal of Trees	EA.	12	\$	\$
11	202	Remove Metal Grates	Ea.	4	\$	\$
12	207	Topsoil	S.Y.	5	\$	\$
13	208	Erosion Control (Complete in Place)	LS.	1	\$	\$
14	210	Reset Structures (Mail Box)	EA.	2	\$	\$
15	210	Reset Structures (Sign Post)	EA.	2	\$	\$
16	210	Reset Structures (Wood Split Rail Fence)	L.F.	90	\$	\$
17	304	Aggregate Base Course (Class 6) (Unit Weight Used = 136lbs/cubic foot)	Ton	14	\$	\$
18	304	Driveway Gravel (Match Existing Gravel)	S.Y.	56	\$	\$
19	304	Asphalt Milling Path (6" Thick)	S.Y.	72	\$	\$
20	304	Asphalt Milling Path (12" Thick)(Sparrn Street)	S.Y.	30	\$	\$
21	608	Monolithic Vertical Curb, Gutter & Sidewalk	S.Y.	209	\$	\$
22	608	Concrete Driveway Section (6" Thick)	S.Y.	149	\$	\$
23	620	Sanitary Facility	Ea.	1	\$	\$
24	626	Mobilization	L.S.	1	\$	\$
25	626	Public Information Services	L.S.	1	\$	\$
26	629	Survey Monumentation	L.S.	1	\$	\$
27	630	Construction Zone Traffic Control (Special)	LS.	1	\$	\$
28	-	Force Account	L.S.	1	\$ 10,000.00	\$10,000.00
-						
<b>Total Bid</b>						\$