

Date Submitted: 5-8-91

Zone: PB

Tax Schedule: 2945-114-19-023

Permit #

Fee \$ 10<sup>00</sup>

Requires Building Department Permit

Type A SIGN  
see File 27-90

# SIGN PERMIT

## GRAND JUNCTION COMMUNITY DEVELOPMENT

BUSINESS NAME: TACO Bell CONTRACTOR: Grand Junction Signs  
 BUS. ADDRESS: 850 North Ave ADDRESS: 2915 Hill Ave  
 PROPERTY OWNER: JOHN MOSS TELEPHONE NO: 245-2950  
 OWNER ADDRESS: 2519 I Road LICENSE NO: 2900244

- 1. FLUSH WALL (2 square feet per linear foot of building facade)
- 2. ROOF (2 square feet per linear foot of building facade)
- 3. FREE-STANDING (2 traffic lanes .75 square feet. x street frontage)  
(4 or more traffic lanes 1.5 square feet x street frontage)
- 4. PROJECTING (.5 square feet per each linear foot of building facade)
- 5. OFF PREMISE (See #3 Spacing Requirements; 300 square feet < 15 square feet)

EXTERNALLY ILLUMINATED     INTERNALLY ILLUMINATED     NON-ILLUMINATED

(1-5) Area of Proposed Sign 97 Square Feet  
 (1,2,4) Building Facade \_\_\_\_\_ Square Feet  
 (1-4) Street Frontage 145.25 \_\_\_\_\_ Feet  
 (2,4) Height to top of Sign 40 Feet      Clearance to Grade 28' Feet  
 (1-5) Maximum Allowed Area 217 Square Feet.  
 (5) Distance From All Existing Off-Premise Signs within 600 Feet \_\_\_\_\_ Feet

### EXISTING SIGNAGE / TYPE:

\_\_\_\_\_ Square Feet  
 \_\_\_\_\_ Square Feet  
 \_\_\_\_\_ Square Feet  
 \_\_\_\_\_ Square Feet      **TOTAL EXISTING** \_\_\_\_\_ Square Feet

COMMENTS: This is part of the Taco Bell package

**NOTE:** No sign may exceed 300 square feet. A separate sign permit is required for each sign. Attach a sketch of proposed and existing signage including types, dimensions, lettering, abutting streets, property lines, and locations. Free standing signs over 25 feet high, all roof signs, and illuminated signs require a separate permit from the Building Department.


[Signature]  
 APPLICANT'S SIGNATURE

\_\_\_\_\_  
 DATE

[Signature]  
 APPROVED BY

5-8-91  
 DATE

# SIGN TYPE 'A' DETAIL



**P4 97 Square Feet  
12'-0" x 8'-1" DF C-P Logo Sign  
at 35' OAH**

**Electrical Specifications:**

Lamps: F60T12 H/O C.W. (2)  
F64T12 H/O C.W. (2)  
F84T12 H/O C.W. (8)  
Ballast: Jefferson 262-464 (2)  
Jefferson 262-484 (2)  
Jefferson 262-002 (8)  
Conn. Load: 13.1 AMPS  
Circuits: 20 AMP (1)  
Service sign by: Hinged Face  
Lifting Weight: 1205 lbs.  
Maximum Design  
Wind Load: 30 PSF

**Ground Mounted Logo Signs**

Double face sign with one-piece, prescreened logo faces of polycarbonate. Logo faces are pan embossed with white border. Appendage faces are one-piece, prescreened polycarbonate and are embossed with white border. Optional copy reading: DRIVE THRU or WELCOME.

Sign box is extruded aluminum. Electrical meets standards of National Electric Code and bears U.L. label.

**64" x 59" Drive Thru**

Polycarbonate, single face. Constructed of 1/4" gauge supported by one 3" x 3" aluminum base cover at the supporting column. wind load. Single door in for easy entry. Electrical Code and Underwriters label.

Menu copy, illustrative to be supplied by others.

Foundation supplied by ( ) Four 3/4" anchor bolts rec

**Electrical Specifications:**

Lamps: (4)  
Ballast: Jel  
Voltage: 120  
Total Conn. Load: 2.7  
Circuits: (1)

Service sign by: Hi

of

Lifting Weight: Cr

Un

**SIGN TYP**

**16" x 36 7/8" DF C-P An  
Mounted Directional Si**