



# SIGN PERMIT

Community Development Department  
250 North 5th Street  
Grand Junction, CO 81501  
(303) 244-1430

PERMIT NO. \_\_\_\_\_  
Date Submitted 5/1/95  
FEE \$ 5.00  
Tax Schedule 2945-123-25-018  
Zone C-1

BUSINESS NAME BASKIN ROBBINS  
STREET ADDRESS 1702 NORTH AVE  
PROPERTY OWNER SIM FLYNN  
OWNER ADDRESS \_\_\_\_\_

CONTRACTOR SGN GALLERY  
LICENSE NO 2950366  
ADDRESS 1048 FIVE AVENUE  
TELEPHONE NO 241-6400

- 1. FLUSH WALL 2 Square Feet per Linear Foot of Building Facade
- 2. ROOF 2 Square Feet per Linear Foot of Building Facade
- 3. FREE-STANDING 2 Traffic Lanes - 0.75 Square Feet x Street Frontage  
4 or more Traffic Lanes - 1.5 Square Feet x Street Frontage
- 4. PROJECTING 0.5 Square Feet per each Linear Foot of Building Facade
- 5. OFF-PREMISE See #3 Spacing Requirements; Not > 300 Square Feet or < 15 Square Feet

Externally Illuminated       Internally Illuminated       Non-Illuminated

- (1 - 5) Area of Proposed Sign 31 Square Feet
- (1,2,4) Building Facade 27 Linear Feet
- (1 - 4) Street Frontage 50 Linear Feet
- (2,4,5) Height to Top of Sign \_\_\_\_\_ Feet Clearance to Grade \_\_\_\_\_ Feet
- (5) Distance from all Existing Off-Premise Signs within 600 Feet \_\_\_\_\_ Feet

Existing Signage/Type

<u># 3</u>	<u>44</u>	Sq Ft
_____	_____	Sq Ft
_____	_____	Sq Ft
<b>Total Existing:</b>	<u>44</u>	Sq Ft

<b>FOR OFFICE USE ONLY:</b>		
<u>Signage Allowed on Parcel</u>		
Building	<u>54</u>	Sq Ft
Free-Standing	<u>75</u>	Sq Ft
<b>Total Allowed:</b>	<u>75</u>	Sq Ft

COMMENTS: \_\_\_\_\_


**NOTE:** No sign may exceed 300 square feet. A separate sign permit is required for each sign. Attach a sketch of proposed and existing signage including types, dimensions, lettering, abutting streets, alleys, easements, property lines, and locations. All signs require a separate permit from the Building Department.

[Signature]  
Applicant's Signature

5-1-95  
Date


[Signature]  
Approved By

5/1/95  
Date



BR-SF-5A

Flush wall




<b>Sign Cabinet</b>	Slate Gray	22 gauge sheet metal, primed and painted to match PMS 5405C Slate Gray
<b>Retainer</b>	Slate Gray	22 gauge sheet metal, primed and painted to match PMS 5405C Slate Gray
<b>Faces*</b>	White Bkgd	Plexiglas #7328
"Baskin Robbins"	White Copy	With Slate Gray Outline on a Pink #VT-2230 field. ("®" to be Slate Gray)
"31"	White Copy	No outline
"Ice Cream" "Yogurt"	Slate Gray	Slate Gray #VT-2231 copy
<b>Illumination</b>	Cool White	Interior illuminated by 800 M.A. high output, cool white fluorescent lamps

\* In high vandalism area faces will be Clear Lexan with second surface applied vinyl decor. Colors to remain as above.


~~ATTN: M... Durkin~~

Free standing



9 SQ. FT.

35 SQ. FT.





3 1/2'

agreement to  
cond. table

THIS DESIGN  
FOR GRAND JUNCTION  
STORE

10'

18'  
FROM GROUND



BR-612B

120



<b>Sign Cabinet</b>	Slate Gray	22 gauge sheet metal, primed and painted to match PMS 5405C Slate Gray
<b>Retainer</b>	Slate Gray	22 gauge sheet metal, primed and painted to match PMS 5405C Slate Gray
<b>Faces*</b>	White Bkgd	Plexiglas #7328
"Baskin Robbins"	White Copy	With Slate Gray Outline on a Pink #VT-2230 field. ("®" to be Slate Gray)
"31"	Pink Logo	Pink 3M Scotchcal Film #VT-2230. No outline.
<b>Secondary Copy</b>		
"Ice Cream & Yogurt"	Slate Gray	3M Graphics Scotchcal Film #VT-2231 Slate Gray, on a White field
<b>Illumination</b>	Cool White	Interior illuminated by 800 M.A. high output, cool white fluorescent lamps

\* In high vandalism area faces will be Clear Lexan with second surface applied vinyl decor. Colors to remain as above.