



HETZEL ANNEXATION



VICINITY MAP
N.T.S.

DESCRIPTION

A parcel of land situate in the NW 1/4 of the SE 1/4 and in the SW 1/4 of the NE 1/4 of Section 3, Township 1 South, Range 1 West of the Ute Meridian, County of Mesa, State of Colorado and being more particularly described as follows:

Beginning at the Northeast corner of the NW 1/4 SE 1/4 of said Section 3; thence N 00°01'29" W a distance of 30.00 feet to a point on the North right-of-way line for F 1/2 Road; thence along said North right-of-way line, which is 30.00 feet North of and parallel with the North line of said NW 1/4 SE 1/4 N 89°55'45" W a distance of 659.55 feet to the Southeast corner of Kay Subdivision; thence leaving said North right-of-way line S 00°02'28" W a distance of 30.00 feet to a point on the North line of said NW 1/4 SE 1/4; thence S 89°55'45" E along said North line a distance of 12.11 feet to the Northeast corner of a parcel of land as described in Book 1101 at Page 800 of the records of the Mesa County Clerk and Recorder; thence S 00°08'52" E along the East line of said parcel of land a distance of 225.00 feet to the Southeast corner of said parcel of land; thence N 89°55'45" W along the South line of said parcel of land a distance of 193.60 feet to the Southwest corner of said parcel of land; thence N 00°08'52" W along the West line of said parcel of land a distance of 2.25 feet to the Southeast corner of a parcel of land as described in Book 905 at Page 692 of the records of said Mesa County Clerk and Recorder; thence N 89°55'45" W along the South line of said parcel of land a distance of 148.50 feet to a point on the West line of the E 1/2 W 1/2 NW 1/4 SE 1/4; thence S 00°08'37" E along the West line of said E 1/2 W 1/2 NW 1/4 SE 1/4 a distance of 1088.28 feet to a point on the South line of the NW 1/4 SE 1/4 of said Section 3; thence S 89°55'41" E along said South line a distance of 989.81 feet to the Southeast corner of said NW 1/4 SE 1/4; thence N 00°09'22" W along the East line of said NW 1/4 SE 1/4 a distance of 1311.06 feet to the point of beginning.

The Description(s) contained herein have been derived from subdivision plats and deed descriptions as they appear in the office of the Mesa County Clerk and Recorder. This plat does not constitute a legal survey, and is not intended to be used as a means for establishing or verifying property boundary lines.

James L. Shanks
JAMES L. SHANKS DIRECTOR OF PUBLIC WORKS & UTILITIES

AREA OF ANNEXATION

ANNEXATION PERIMETER	4,690.16 FT.
CONTIGUOUS PERIMETER	1,926.33 FT.
AREA IN SQUARE FEET	1,240,642.86
AREA IN ACRES	28.48

LEGEND

- ANNEXATION BOUNDARY
- - - - - CONTIGUOUS BOUNDARY (EXISTING CITY LIMITS)

ORDINANCE NO.
3000

EFFECTIVE DATE
MAY 18, 1997

REVISION	DESCRIPTION	DATE	DRAWN BY	DATE
REVISION			SRP	03-07-96
REVISION			CHECKED BY	DATE
REVISION			APPROVED BY	DATE
REVISION			FIELD BOOK NO.	PAGE

SCALE
1" = 200'

DEPARTMENT OF PUBLIC WORKS AND UTILITIES
ENGINEERING DIVISION
CITY OF GRAND JUNCTION, COLORADO

HETZEL ANNEXATION

SHEET NO. 1
OF 1
FILE NO.
HETZEL.DWG