



CANTRELL ANNEXATION NO.1



LEGAL DESCRIPTION

A parcel of land situate in the SW 1/4 SE 1/4 and in the SE 1/4 SW 1/4 of Section 8, Township 1 South, Range 1 East of the Ute Meridian, County of Mesa, State of Colorado, being more particularly described as follows:

Beginning at the S 1/4 corner of said Section 8; thence N 89°53'09" W along the south line of the SE 1/4 SW 1/4 of said Section 8 a distance of 177.92 feet to a point; thence leaving said south line N 00° 06'51" E a distance of 30.00 feet to a point; thence N 89°53'09" W along a line 10.00 feet south of and parallel with the north right of way line for North Avenue (U.S. Highway 6) a distance of 486.06 feet to a point; thence N 00°06'51" E a distance of 10.00 feet to a point on the north right of way line for said North Avenue (U.S. Highway 6); thence S 89°53'09" E along said north right of way line a distance of 633.91 feet to a point on the west right of way line for 29 1/2 Road; thence N 00°00'00" E along the west right of way line for said 29 1/2 Road a distance of 9.92 feet to a point; thence crossing said 29 1/2 Road N 90°00'00" E a distance of 70.00 feet to a point on the east right of way line for said 29 1/2 Road (said point also being the southwest corner of Lot 7 of J and J Subdivision); thence S 89° 58'35" E along the north right of way line for said North Avenue (U.S. Highway 6) a distance of 50.10 feet to a point; thence leaving said north right of way line S 00°01'25" W a distance of 50.00 feet to a point on the south line of the SW 1/4 SE 1/4 of said Section 8; thence N 89°58'35" W along said south line a distance of 90.08 feet to the point of beginning.

The Description(s) contained herein have been derived from subdivision plats and deed descriptions as they appear in the office of the Mesa County Clerk and Recorder. This constitutes a legal survey, and is not intended to be a means for establishing or verifying property boundaries.

Stu R. Pace
SENIOR REAL ESTATE TECHNICIAN, PLS 22580


AREA OF ANNEXATION

ANNEXATION PERIMETER	1607.99 FT.
CONTIGUOUS PERIMETER	268.00 FT.
AREA IN SQUARE FEET	16778.56
AREA IN ACRES	0.38

LEGEND

ANNEXATION BOUNDARY	—————
EXISTING CITY LIMITS	- - - - -

GRAPHIC SCALE



ORDINANCE NO.
3339

EFFECTIVE DATE
MAY 20, 2001

DEPARTMENT OF PUBLIC WORKS AND UTILITIES
ENGINEERING AND TECHNICAL SERVICES DIVISIONS
CITY OF GRAND JUNCTION, COLORADO

CANTRELL ANNEXATION NO.1

CANTRELL.DWG

Drawn by SRP DATE 2-13-2001
Designed by _____ DATE _____
Checked by _____ DATE _____
Approved by _____ DATE _____

SCALE
1" = 100'

Notice: According to Colorado law you have 60 days from the effective date shown herein to file a complaint based upon any defect on this plat. If no complaint is filed within said 60 days then said plat stands despite all defects and errors.