



# ISRE ANNEXATION NO. 2

SITUATE IN THE EAST-HALF (E 1/2) OF SECTION 17, T1S, R1E, U.M.  
COUNTY OF MESA, STATE OF COLORADO



### LEGAL DESCRIPTION

A certain parcel of land lying in the East half (E 1/2) of Section 17, Township 1 South, Range 1 East of the Ute Principal Meridian, County of Mesa, State of Colorado, being more particularly described as follows:


**BEGINNING** at the Southwest Corner of the South Half of the Southeast Quarter of the Northeast Quarter (S 1/2 SE 1/4 NE 1/4) of said Section 17 and considering the South line of the S 1/2 SE 1/4 NE 1/4 of said Section 17 to bear N 89°59'59" W with all bearings contained herein being relative thereto; thence from said Point of Beginning, N 00°05'59" W along the West line of the S 1/2 SE 1/4 NE 1/4 of said Section 17, a distance of 659.70 feet, more or less, to a point being the Northwest Corner of the S 1/2 SE 1/4 NE 1/4 of said Section 17, also being the Southwest Corner of the Plat of Banner Industrial Park, as same is recorded in Plat Book 11, Page 362, Public Records of Mesa County, Colorado; thence S 89°59'39" E along the South line of the S 1/2 SE 1/4 NE 1/4 of said Section 17, a distance of 396.12 feet, more or less, to a point on the East line of the West 6.0 Acres of the S 1/2 SE 1/4 NE 1/4 of said Section 17; thence S 00°05'59" E, along said East line, a distance of 689.66 feet, more or less, to a point on a line 30.00 feet South of and parallel to, the South line of the S 1/2 SE 1/4 NE 1/4 of said Section 17; thence N 89°59'59" W, along said parallel line, a distance of 396.16 feet, more or less, to a point on the West line of the Northeast Quarter of the Southeast Quarter (NE 1/4 SE 1/4) of said Section 17; thence N 00°00'59" W, along said West line, a distance of 30.00 feet, more or less, to the Point of Beginning.

Containing 273,196.20 Square Feet or 6.272 Acres, more or less, as described.

### AREA OF ANNEXATION

ANNEXATION PERIMETER	2,171.64 FT
CONTIGUOUS PERIMETER	789.66 FT
AREA IN SQUARE FEET	273,196.20
AREA IN ACRES	6.272

ORDINANCE NO. 3464 EFFECTIVE DATE December 8th 2002



The Description(s) contained herein have been derived from subdivision plats and deed descriptions as they appear in the office of the Mesa County Clerk and Recorder. This plat does not constitute a legal survey, and is not intended to be used as a means for establishing or verifying boundary lines.

PETER T. KRICK, PLS No. 32824  
SENIOR REAL ESTATE TECHNICIAN  
CITY OF GRAND JUNCTION  
DATE: November 11, 2002

THIS IS NOT A BOUNDARY SURVEY

Notice: According to Colorado law you have 60 days from the effective date shown hereon to file a complaint based upon any defect on this plat. If no complaint is filed within said 60 days then said plat stands despite all defects and or errors.

DRAWN BY P.T.K.	DATE 8-30-2002
DESIGNED BY	DATE
CHECKED BY T.W.	DATE
APPROVED BY	DATE

SCALE 1" = 100'

DEPARTMENT OF PUBLIC WORKS AND UTILITIES  
ENGINEERING AND TECHNICAL SERVICES DIVISIONS  
CITY OF GRAND JUNCTION, COLORADO

ISRE ANNEXATION NO. 2