



CHURCH ON THE ROCK ANNEXATION



SITUATE IN THE EAST HALF OF SECTION 23, TWP 11S, RGE 101W, 6th PRINCIPAL MERIDIAN
COUNTY OF MESA, STATE OF COLORADO



VICINITY MAP (NOT TO SCALE)



EAST LINE OF SECTION 23, TWP 11S, RGE 101W, 6TH PRINCIPAL MERIDIAN



LEGEND

ANNEXATION BOUNDARY
EXISTING CITY LIMITS

Legal Description
CHUCH ON THE ROCK ANNEXATION

A certain parcel of land lying in the East Half (E 1/2) of Section 23, Township 11 South, Range 101 West of the 6th Principal Meridian, County of Mesa, State of Colorado, being more particularly described as follows:

BEGINNING at the point of intersection of the Northerly right of way for Colorado Highway 340 (Broadway), as same is depicted on plans by the Colorado State Highway Department, Federal and Secondary Project No. S 0143(1), and the East line of the 50' right of way for Rio Hondo Road, as same is recorded in Book 945, Page 602, Public Records of Mesa County, Colorado and depicted on the Plat of Monument Village Commercial Center, as same is recorded in Plat Book 17, Page 396, Public Records of Mesa County, Colorado, being the Southwest corner of that certain parcel of land, Parcel Control Number 2947-231-00-950, Mesa County, Colorado, and considering the East line of said Rio Hondo Road to bear N 05°01'52" E with all other bearings mentioned herein being relative thereto; thence from said Point of Beginning, N 59°01'04" W along the North line of said Colorado Highway 340 (Broadway) a distance of 55.61 feet to a point on the West right of way for said Rio Hondo Road; thence N 05°01'52" E along the West line of said Rio Hondo Road and the East line of said Monument Village Commercial Center, a distance of 403.74 feet; thence S 89°50'04" E a distance of 491.91 feet; thence S 33°53'56" W a distance of 75.24 feet; thence S 13°15'56" W a distance of 180.80 feet; thence S 06°19'04" E a distance of 229.00 feet; thence S 18°52'58" W a distance of 189.71 feet to a point on the Northerly right of way for Colorado Highway 340 (Broadway); thence N 59°01'04" W along said Northerly right of way, a distance of 419.90 feet, more or less, to the Point of Beginning.

CONTAINS 5.4946 Acres (239,346.95 Square Feet) more or less, as described.

The Description contained herein has been derived from subdivision plats and deed descriptions as they appear in the office of the Mesa County Clerk and Recorder. This plat does not constitute a legal survey, and is not intended to be used as a means for establishing or verifying property boundary lines.

Peter T. Krick
Peter T. Krick
Professional Land Surveyor No. 316-2824
Senior Real Estate Technician No. 11-6-03
City of Grand Junction
Date: November 6th, 2003

AREA OF ANNEXATION

ANNEXATION PERIMETER	2,045.90 FT.
CONTIGUOUS PERIMETER	475.51 FT.
AREA IN SQUARE FEET	239,346.95
AREA IN ACRES	5.4946***

***CONTAINS 0.4798 ACRES OF RIO HONDO RIGHT OF WAY

ORDINANCE NO.	EFFECTIVE DATE
3580	December 7 th , 2003

DRAWN BY PTK DATE 09-22-2003
DESIGNED BY PTK DATE _____
CHECKED BY TW DATE _____
APPROVED BY _____ DATE _____

SCALE
1" = 80'

THIS IS NOT A BOUNDARY SURVEY

DEPARTMENT OF PUBLIC WORKS AND UTILITIES
REAL ESTATE DIVISION
CITY OF GRAND JUNCTION, COLORADO

CHURCH ON THE ROCK ANNEXATION

Notice:
According to Colorado law you have 60 days from the effective date shown hereon to file a complaint based upon any defect on this plat. If no complaint is filed within said 60 days then said plat stands despite all defects and/or errors.