



# CAMECK ANNEXATION NO. 1

SITUATE IN THE SE 1/4 OF THE SE 1/4 OF THE NW 1/4 OF SECTION 16, T1S, R1E, U.M.  
 COUNTY OF MESA, STATE OF COLORADO



LOCATION MAP: NOT-TO-SCALE




## LEGAL DESCRIPTION

A certain parcel of land lying in the Southeast Quarter of the Southeast Quarter of the Northwest Quarter (SE 1/4 SE 1/4 NW 1/4) of Section 16, Township 1 South, Range 1 East of the Ute Principal Meridian, County of Mesa, State of Colorado and being more particularly described as follows:

**BEGINNING** at the Southeast corner of the Northwest Quarter of said Section 16 and assuming the South line of the Southeast Quarter of the Northwest Quarter (SE 1/4 NW 1/4) of said Section 16 bears S 89°54'19" W with all other bearings contained herein being in reference thereto; thence from said Point of Beginning, S 89°54'19" W along the South line of the SE 1/4 NW 1/4 of said Section 16, a distance of 165.00 feet, more or less, to its intersection with the West line of the East Quarter (E 1/4) of the SE 1/4 SE 1/4 NW 1/4 of said Section 16; thence N 00°00'54" W along said West line, a distance of 450.00 feet; thence S 89°59'09" E a distance of 50.00 feet; thence S 00°00'54" E a distance of 416.90 feet; thence N 89°54'19" E along a line 33.00 feet North of and parallel with, the South line of the SE 1/4 NW 1/4 of said Section 16, a distance of 115.02 feet to a point on the East line of the SE 1/4 SE 1/4 NW 1/4 of said Section 16; thence S 00°00'51" W along said East line, a distance of 33.00 feet, more or less, to the Point of Beginning.

ANNEXATION PERIMETER	1,229.92 FT
CONTIGUOUS PERIMETER	4231.00 FT.
AREA IN SQUARE FEET	26,292.89
AREA IN ACRES	0.6036

LEGEND	
ANNEXATION BOUNDARY	—————
EXISTING CITY LIMITS	-----



THIS IS NOT A BOUNDARY SURVEY

DRAWN BY P.T.K. DATE 04-02-2004  
 DESIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 CHECKED BY T.W. DATE \_\_\_\_\_  
 APPROVED BY \_\_\_\_\_ DATE \_\_\_\_\_

SCALE  
 1" = 60'



PUBLIC WORKS AND UTILITIES  
 REAL ESTATE DIVISION

CAMECK ANNEXATION NO. 1

The Description(s) contained herein have been derived from subdivision plats and deed descriptions as they appear in the office of the Mesa County Clerk and Recorder. This plat does not constitute a legal survey, and is not intended to be used as a means for establishing or verifying property boundary lines.

*Peter T. Krick*  
 PETER T. KRICK, PLS No. 32824  
 Professional Land Surveyor for the City of Grand Junction  
 DATE: June 3rd, 2004

