


KRONVALL ANNEXATION

SITUATE IN THE SE 1/4 OF SECTION 7, T1S, R1W, U.M.
COUNTY OF MESA, STATE OF COLORADO




LOCATION MAP: NOT-TO-SCALE

LEGAL DESCRIPTION


A certain parcel of land lying in the Southeast Quarter (SE 1/4) of Section 7, Township 1 South, Range 1 West of the Ute Principal Meridian, County of Mesa, State of Colorado, being all of Lot 2, Greenbelt Subdivision, as same is recorded in Book 3671, Page 249, Public Records of Mesa County, Colorado, together with a parcel of land shown and labeled within the Northeast portion of said Lot 2 having a Mesa County Parcel Number of 2945-074-00-002, all being more particularly described as follows:

BEGINNING at the Southeast corner of said Lot 2, Greenbelt Subdivision and assuming the North line of said Lot 2 bears S 82°26'11" E with all other bearings mentioned herein in reference thereto; thence from said Point of Beginning, N 73°00'10" W along the South line of said Lot 2, a distance of 151.23 feet; thence continuing along said South line, N 56°07'10" W a distance of 128.84 feet to a point being the Southeast corner of Lot 1, Kronvall Subdivision, as same is recorded in Book 3602, Page 477, Public Records of Mesa County, Colorado; thence N 16°45'36" E along the East line of said Lot 1, Kronvall Subdivision, a distance of 151.81 feet to a point being the Northeast corner of said Lot 1, Kronvall Subdivision; thence N 62°57'41" W a distance of 203.26 feet to a point being the Southeast corner of Lot 1 of said Greenbelt Subdivision; thence N 12°08'01" E along the East line of said Lot 1, Greenbelt Subdivision, a distance of 172.00 feet to a point being the Northwest corner of Lot 2, Greenbelt Subdivision; thence S 82°26'11" E along the North line of said Lot 2, Greenbelt Subdivision, a distance of 606.45 feet to a point being the Northeast corner of said Lot 2, Greenbelt Subdivision; thence S 36°48'00" W along the East line of said Lot 2, Greenbelt Subdivision, being the West right of way for the Redlands Parkway, a distance of 9.45 feet; thence S 35°34'34" W along said West right of way, a distance of 54.72 feet to a point being the Southeast corner of that certain parcel of land with Mesa County parcel control number of 2945-074-00-002; thence S 35°32'54" W along the West right of way for the Redlands Parkway, a distance of 71.68 feet; thence S 28°40'28" W along the East line of said Lot 2 and the West right of way for the Redlands Parkway, a distance of 284.08 feet; thence S 21°48'03" W along the East line of said Lot 2 and the West right of way for the Redlands Parkway, a distance of 88.85 feet, more or less, to the Point of Beginning.



The Description(s) contained herein have been derived from subdivision plats and deed descriptions as they appear in the office of the Mesa County Clerk and Recorder. This plat does not constitute a legal survey, and is not intended to be used as a means for establishing or verifying property boundary lines.

Peter T. Krick
 PETER T. KRICK, PLS No. 32824
 Professional Land Surveyor for the
 City of Grand Junction
 DATE: October 21st, 2004




AREA OF ANNEXATION

ANNEXATION PERIMETER	1,922.37 FT
CONTIGUOUS PERIMETER	508.78 FT.
AREA IN SQUARE FEET	186,189
AREA IN ACRES	4.274

LEGEND

ANNEXATION BOUNDARY	
EXISTING CITY LIMITS	



ORDINANCE NO.
3681

EFFECTIVE DATE
November 21, 2004

THIS IS NOT A BOUNDARY SURVEY

DRAWN BY	P.T.K.	DATE	08-05-2004
DESIGNED BY		DATE	
CHECKED BY	T.W.	DATE	
APPROVED BY		DATE	

SCALE

1" = 50'



PUBLIC WORKS
AND UTILITIES
REAL ESTATE DIVISION

KRONVALL ANNEXATION

N:\Cadd\Annex by PTK\Kronvall Annexation.dwg 10/21/2004 3:44:54 PM MDT