



FOX ANNEXATION

SITUATE IN THE SW 1/4 OF THE SW 1/4 SECTION 4 AND THE SE 1/4 SE 1/4 SECTION 5,
T1S, R1E, U.M. COUNTY OF MESA, STATE OF COLORADO



LEGAL DESCRIPTION

A certain parcel of land located in the Southwest Quarter of the Southwest Quarter (SW 1/4 SW 1/4) of Section 4, Township 1 South, Range 1 East of the Ute Principal Meridian, County of Mesa, State of Colorado and being more particularly described as follows:

COMMENCING at the Southwest corner of said Section 4, and assuming the West line of the SW 1/4 SW 1/4 of said Section 4 to bear N00°09'16"W with all bearings contained herein relative thereto; thence N00°09'16"W, along the West line of the SW 1/4 SW 1/4 of said Section 4, a distance of 350.05 feet to the POINT OF BEGINNING; thence S89°50'44"W, a distance of 40.00 feet to a point on the Westerly right of way of 30 Road; thence N00°09'16"W, along the Westerly right of way of 30 Road a distance of 150.12 feet; thence S89°55'10"E along the Southerly right of way and the Westerly projection of East Vista Drive as same is shown on the plat of Village East First Filing, as described in Plat Book 11, page 76 of the Mesa County, Colorado, Public Records a distance of 240.07 feet to the Northwest corner of Block One of said Village East First Filing; thence S00°09'16"E along the West line of Block One of said Village East First Filing, a distance of 450.00 feet to a point on the Northerly right of way of Patterson Road; thence N89°55'10"W, along the North right of way of Patterson Road, a distance of 135.00 feet; thence N45°02'11"W, along said right of way, a distance of 35.43 feet to a point on the Easterly right of way of said 30 Road; thence N00°09'16"W along the East right of way of said 30 Road a distance of 275.21 feet; thence S89°50'44"W a distance of 40.00 feet, more or less to the POINT OF BEGINNING.

ABBREVIATIONS

P.O.C.	POINT OF COMMENCEMENT
P.O.B.	POINT OF BEGINNING
R.O.W.	RIGHT OF WAY
SEC.	SECTION
T.	TOWNSHIP
R.	RANGE
U.M.	UTE MERIDIAN
NO.	NUMBER
SQ. FT.	SQUARE FEET

The Description(s) contained herein have been derived from subdivision plats and deed descriptions as they appear in the office of the Mesa County Clerk and Recorder. This plat does not constitute a legal survey, and is not intended to be used as a means for establishing or verifying property boundary lines.

Peter T. Krick
 PETER T. KRICK, PLS No. 32824
 Professional Land Surveyor for the
 City of Grand Junction
 DATE: June 8, 2006




AREA OF ANNEXATION

ANNEXATION PERIMETER	1365.83 FT.
CONTIGUOUS PERIMETER	525.64 FT.
AREA IN SQUARE FEET	83,689***
AREA IN ACRES	1.92

LEGEND

ANNEXATION BOUNDARY	———
EXISTING CITY LIMITS	- - - -



ORDINANCE NO.
3913

EFFECTIVE DATE
July 9, 2006

THIS IS NOT A BOUNDARY SURVEY



PUBLIC WORKS
AND UTILITIES
REAL ESTATE DIVISION

FOX ANNEXATION
13064000.tif

Notice:
According to Colorado law you must commence any legal action based upon any defect in this survey within three years after you first discover such defect. In no event may any action based upon any defect in this survey be commenced more than ten years from the date of the certification shown hereon.

DRAWN BY	CM	DATE	04-03-06
DESIGNED BY		DATE	
CHECKED BY	P.T.K.	DATE	
APPROVED BY		DATE	

SCALE
1" = 50'