



VODOPICH ANNEXATION

SITUATE IN THE NW 1/4 OF THE SW 1/4 OF SECTION 4, T1S, R1E, U.M.
COUNTY OF MESA, STATE OF COLORADO



LEGAL DESCRIPTION

A certain parcel of land located in the Northwest Quarter of the Southwest Quarter (NW1/4 SW1/4) of Section 4, Township 1 South, Range 1 East of the Ute Principal Meridian, County of Mesa, State of Colorado and being more particularly described as follows:

BEGINNING at the Northeast corner of the NW1/4 SW1/4 of said Section 4 and assuming the East line of the NW1/4 SW1/4 of said Section 4 bears S00°10'25"E with all other bearings contained herein being relative thereto; thence from said Point of Beginning, S00°10'25"E along the East line of the NW1/4 SW1/4 of said Section 4 a distance of 453.62 feet to the Price Ditch, as described in Book 2266, Page 760 of the Mesa County, Colorado Public Records; thence N62°01'59"W along said Price Ditch a distance of 461.46; thence N00°01'57"W a distance of 236.96 feet to a point on the North line of the NW1/4 SW1/4 of said Section 4; thence N89°57'52"E along the North line of the NW1/4 SW1/4 of said Section 4, a distance of 406.33, more or less to the POINT OF BEGINNING.

ABBREVIATIONS

P.O.C.	POINT OF COMMENCEMENT
P.O.B.	POINT OF BEGINNING
R.O.W.	RIGHT OF WAY
SEC.	SECTION
T.	TOWNSHIP
R.	RANGE
U.M.	UTE MERIDIAN
NO.	NUMBER
SQ. FT.	SQUARE FEET
Δ	CENTRAL ANGLE
RAD	RADIUS
L	ARC LENGTH
CH	CHORD LENGTH
CB	CHORD BEARING

The Description(s) contained herein have been derived from subdivision plats and deed descriptions as they appear in the office of the Mesa County Clerk and Recorder. This plat does not constitute a legal survey, and is not intended to be used as a means for establishing or verifying property boundary lines.

P.T.K.
PETER T. KRICK, PLS No. 32824
Professional Land Surveyor for the
City of Grand Junction
DATE: July 21, 2006




AREA OF ANNEXATION

ANNEXATION PERIMETER	1559.58 FT
CONTIGUOUS PERIMETER	406.33 FT.
AREA IN SQUARE FEET	140,707***
AREA IN ACRES	3.23

LEGEND

ANNEXATION BOUNDARY	---
EXISTING CITY LIMITS	---

GRAPHIC SCALE



ORDINANCE NO.
3932

EFFECTIVE DATE
AUGUST 20, 2006

THIS IS NOT A BOUNDARY SURVEY

Notice:
According to Colorado law you must commence any legal action based upon any defect in this survey within three years after you first discover such defect. In no event may any action based upon any defect in this survey be commenced more than ten years from the date of the certification shown hereon.

DRAWN BY	CM	DATE	04-25-06
DESIGNED BY		DATE	
CHECKED BY	P.T.K.	DATE	
APPROVED BY		DATE	

SCALE
1" = 100'



PUBLIC WORKS
AND UTILITIES
REAL ESTATE DIVISION

VODOPICH ANNEXATION

13064700.tif