



# PROMONTORY ANNEXATION NO. 3

SITUATE IN THE NE 1/4 OF THE NW 1/4 OF SECTION 36,  
TWP 1S, RGE 1W, U.M. COUNTY OF MESA, STATE OF COLORADO



### LEGAL DESCRIPTION

A certain parcel of land located in the Northeast Quarter of the Northwest Quarter (NE 1/4 NW 1/4) of Section 36, Township 1 South, Range 1 West of the Ute Principal Meridian, County of Mesa, State of Colorado and being more particularly described as follows:

BEGINNING at the Southeast corner of Lot 16 of Sierra Vista Subdivision, as same is recorded in Plat Book 12, Page 115, Public Records of Mesa County, Colorado, and assuming the East line of Block Three of said Sierra Vista Subdivision bears N00°01'46"W with all other bearings contained herein being relative thereto; thence N89°58'14"E a distance of 10.00 feet to a point on a line being 10.00 feet East of and parallel with said East line; thence N00°01'46"W along said parallel line a distance of 255.00 feet to a point on the North line of the NE 1/4 NW 1/4 of said Section 36; thence N89°58'14"E along said North line a distance of 15.00 feet; thence S00°01'46"E along a line being 25.00 feet East of and parallel with the East line of said Sierra Vista Subdivision a distance of 428.42 feet; thence 74.80 feet along the arc of a 45.00 foot radius curve concave Northeast, having a central angle of 95°14'19" and a chord bearing S47°38'56"E a distance of 66.48 feet; thence 73.91 feet along the arc of a 772.60 foot radius curve concave South, having a central angle of 05°28'59" and a chord bearing N87°28'31"E a distance of 73.88 feet to a point on the East line of said Sierra Vista Subdivision; thence S00°13'11"W along said East line a distance of 25.00 feet to a point on the South line of Sierra Vista Road; thence 71.51 feet along the arc of a 747.60 foot radius curve concave South, having a central angle of 05°28'51" and a chord bearing S87°28'29"W a distance of 71.49 feet; thence S84°44'04"W along said South line a distance of 76.71 feet; thence N00°01'46"W a distance of 250.13 feet, more or less, to the Point of Beginning.

**ABBREVIATIONS**


P.O.C.	POINT OF COMMENCEMENT
P.O.B.	POINT OF BEGINNING
R.O.W.	RIGHT OF WAY
SEC.	SECTION
TWP.	TOWNSHIP
RGE.	RANGE
U.M.	UTE MERIDIAN
NO.	NUMBER
SQ. FT.	SQUARE FEET
Δ	CENTRAL ANGLE
RAD	RADIUS
AL	ARC LENGTH
CHL	CHORD LENGTH
CHB	CHORD BEARING
BLK	BLOCK
PB	PLAT BOOK
BK	BOOK
PG	PAGE

**AREA OF ANNEXATION**

ANNEXATION PERIMETER	1,281.58 FT
CONTIGUOUS PERIMETER	265.00 FT.
AREA IN SQUARE FEET	13,666***
AREA IN ACRES	0.31

**LEGEND**

ANNEXATION BOUNDARY	———
EXISTING CITY LIMITS	- - - - -




**ORDINANCE NO.**  
4070

**EFFECTIVE DATE**  
MAY 20, 2007

THIS IS NOT A BOUNDARY SURVEY


The Description(s) contained herein have been derived from subdivision plats and deed descriptions as they appear in the office of the Mesa County Clerk and Recorder. This plat does not constitute a legal survey, and is not intended to be used as a means for establishing or verifying property boundary lines.



Notice:  
According to Colorado law you must commence any legal action based upon any defect in this survey within three years after you first discover such defect. In no event may any action based upon any defect in this survey be commenced more than ten years from the date of the certification shown hereon.

DRAWN BY	CM	DATE	12-8-06
DESIGNED BY		DATE	
CHECKED BY	P.T.K.	DATE	
APPROVED BY		DATE	

SCALE  
1" = 60'



PUBLIC WORKS  
AND UTILITIES  
REAL ESTATE DIVISION

PROMONTORY ANNEXATION NO. 3  
13071100.tif