



LANG INDUSTRIAL PARK ANNEXATION

SITUATE IN THE NW 1/4 NE 1/4 OF SECTION 24, T1S, R1W, U.M.
 COUNTY OF MESA, STATE OF COLORADO



LOCATION MAP: NOT-TO-SCALE



LEGAL DESCRIPTION

A certain parcel of land located in the Northwest Quarter of the Northeast Quarter (NW 1/4 NE 1/4) of Section 24, Township One South, Range One West of the Ute Principal Meridian, County of Mesa, State of Colorado and being more particularly described as follows:


Commencing at the Northeast corner of the Northwest Quarter of the Northeast Quarter (NW 1/4 NE 1/4) of said Section 24 and assuming the North line of the NW 1/4 NE 1/4 of said Section 24 to bear N89°59'19"W with all bearings contained herein relative thereto; thence N89°59'19"W a distance of 491.69 feet along the North line of the NW 1/4 NE 1/4 of said Section 24 to a point on the East line of Riverside Parkway Annexation No. 2, Ordinance No. 4319, City of Grand Junction; thence S00°01'58"W a distance of 1291.39 feet along the West line of Pine Industrial No. 1 Annexation No. 2, Ordinance No. 3943, City of Grand Junction to a point on the South line of the NW 1/4 NE 1/4 of said Section 24, said point also being on the Northerly line of Indian Road Industrial Subdivision, as same is recorded in Plat Book 12, Page 43, public records of Mesa County, Colorado; thence along Indian Road Industrial Subdivision Annexation, Ordinance No. 3677, City of Grand Junction the following two (2) courses: (1) N89°52'25"W a distance of 164.28 feet along said South line of the NW 1/4 NE 1/4 of said Section 24, said line also being the Northerly line of said Indian Road Industrial Subdivision; (2) N00°02'56"E a distance of 1291.06 feet along the Easterly line of said Indian Road Industrial Subdivision to the Southwest corner of said Riverside Parkway Annexation No. 2; thence S89°59'19"E a distance of 163.92 feet along a line being 30.00 feet South of and parallel with the North line of the NW 1/4 NE 1/4 of said Section 24, said line also being the South line of said Riverside Parkway Annexation No. 2 to the Point of Beginning.

ABBREVIATIONS

P.O.C.	POINT OF COMMENCEMENT
P.O.B.	POINT OF BEGINNING
R.O.W.	RIGHT OF WAY
SEC.	SECTION
TWP.	TOWNSHIP
RGE.	RANGE
U.M.	UTE MERIDIAN
NO.	NUMBER
SQ. FT.	SQUARE FEET
Δ=	CENTRAL ANGLE
R	RADIUS
L	ARC LENGTH
CHD LEN	CHORD LENGTH
CHD BRG	CHORD BEARING
BLK	BLOCK
FB	PLAT BOOK
BK	BOOK
PG	PAGE

The Description(s) contained herein have been derived from subdivision plats and deed descriptions as they appear in the office of the Mesa County Clerk and Recorder. This plat does not constitute a legal survey, and is not intended to be used as a means for establishing or verifying property boundary lines.

Peter T. Krick
 PETER T. KRICK, PLS No. 32824
 Professional Land Surveyor for the
 City of Grand Junction
 DATE: June 23rd, 2009




AREA OF ANNEXATION

ANNEXATION PERIMETER	2,910.65 FT
CONTIGUOUS PERIMETER	2,910.65 FT.
AREA IN SQUARE FEET	211,887.79
AREA IN ACRES	4.86

LEGEND

ANNEXATION BOUNDARY	—————
EXISTING CITY LIMITS	-----

GRAPHIC SCALE



ORDINANCE NO.

4361

EFFECTIVE DATE

July 17th, 2009

THIS IS NOT A BOUNDARY SURVEY

Notice:
 According to Colorado law you must commence any legal action based upon any defect in this survey within three years after you first discover such defect. In no event may any action based upon any defect in this survey be commenced more than ten years from the date of the certification shown hereon.

DRAWN BY J.K.T. DATE 3-31-2009
 DESIGNED BY _____ DATE _____
 CHECKED BY P.T.K. DATE _____
 APPROVED BY _____ DATE _____

SCALE

1" = 100'



PUBLIC WORKS
 AND PLANNING
 ENGINEERING DIVISION

LANG INDUSTRIAL PARK ANNEXATION