



**Purchasing Division**

## **ADDENDUM NO. 1**

**DATE: March 14, 2019**  
**FROM: City of Grand Junction Purchasing Division**  
**TO: All Offerors**  
**RE: 2019 Monument Road Bicycle Path Trail IFB-4618-19-DH**

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

1. Q. I see in the bid information for the trail there is an abutment for a steel pedestrian bridge. Can you tell me when the bid for the bridge will be available, and will you consider a composite bridge?

A. The Bid for the Monument Road Trail is currently open. This bid includes the pedestrian bridge carrying the trail over No Thoroughfare Creek. The City would accept alternative (and equal) pedestrian bridge manufacturers of composite, pultruded structures to bid as long as the following documentation is submitted by the manufacturer no less than seven (7) business days prior to bid opening:

- Verification that the design loads of the proposed 'equal' bridge are less than or equal to those shown in the contract drawings.
- Copy of Quality Assurance Programs.
- Splicing and erection procedures.
- The name and qualifications of the Manufacturer's representative designated to represent the Manufacturer for all pre-bid activities.
- The name and qualifications of the Technical Assistant that will conduct on-site assistance during field installation of the Bridge until secure and stable.
- A copy of the written warranty issued by the manufacturer that warrants against corrosion of the superstructure (other than bridge flooring) for a period of not less than 35 years.
- List ten (10) permanent steel bridges similar in size and configuration to the Bridge, which the applicant has manufactured in the preceding five (5) years, together with drawings, calculations, project details and contact information.
- Complete list of plant, equipment, employees and others to be used by the applicant to design and manufacture the Bridge including copies of all Professional Engineering licenses for designers.
- ISO 9001 Certification: The Manufacturer shall be an approved pultruded composite fiber section fabricator under the ISO 9001 Quality Management System Certification Program, for a period of at least five (5) continuous years immediately preceding the bid opening.

All other standards required in the Revision of Section 509 – Prefabricated Structural Steel Bridge shall be translated to the appropriate material standards for composite, pultruded structures based on ASTM, ISO and any other industry standards.

2. See attached updated Project Submittal Form.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", written in a cursive style.

Duane Hoff Jr., Senior Buyer  
City of Grand Junction, Colorado

## PROJECT SUBMITTAL FORM

PROJECT: **2019 Monument Road Trail**

CONTRACTOR:

PROJECT ENGINEER: Kirsten Armbruster

---

---

Description	Date Received	Resubmittal Requested	Resubmittal Received	Date Accepted
-------------	---------------	-----------------------	----------------------	---------------

### CONCRETE TRAIL & PEDESTRIAN BRIDGE CONSTRUCTION

Base course gradation, Proctor curves				
Concrete Mix Design				
Micropile Testing				

### EROSION CONTROL / STORMWATER MANAGEMENT

Vehicle Tracking Pad				
Concrete Washout				

### PERMITS, PLANS, OTHER

Traffic Control Plan				
Stormwater Management Plan				